

**THIRD AMENDED AND RESTATED**

**DEVELOPMENT AGREEMENT**

**BY AND BETWEEN**

**MINNESOTA SPORTS FACILITIES AUTHORITY**

**AND**

**MINNESOTA VIKINGS FOOTBALL STADIUM, LLC**

**AGREEMENT HISTORY**

**Original Effective Date: October 3, 2013**

**Amended and Restated Effective Date: October 3, 2013**

**Execution Date of Amended and Restated Development Agreement: November 22, 2013**

**First Amendment to Amended and Restated Development Agreement: February 10, 2014**

**AMENDMENT HISTORY (TO SECOND AMENDED AND RESTATED)**

**Second Amended and Restated Effective Date: August 22, 2014**

**Execution Date of Second Amended and Restated Development Agreement: August 22, 2014**

**AMENDMENT HISTORY (TO THIRD AMENDED AND RESTATED)**

**First Amendment to Second Amended and Restated Development Agreement Effective Date:  
March 27, 2015**

**Second Amendment to Second Amended and Restated Development Agreement Effective Date:  
February 19, 2016**

**Execution Date of Third Amended and Restated Development Agreement: February 19, 2016**

## TABLE OF CONTENTS

	Page
ARTICLE 1      DEFINITIONS, RULES OF CONSTRUCTION AND PRELIMINARY DEVELOPMENT AGREEMENT .....	3
Section 1.1      Defined Terms .....	3
Section 1.2      Construction of Terms .....	3
Section 1.3      Preliminary Development Agreement; Conflicting Terms .....	3
ARTICLE 2      STADIUM DESIGN AND CONSTRUCTION GROUP .....	4
Section 2.1      Collaborative Effort .....	4
Section 2.2      Role of Stadium Design and Construction Group .....	4
(a)      Composition of SDC Group.....	4
(b)      SDC Chair.....	4
(c)      Team Representatives .....	4
(d)      Authority Representatives.....	5
(e)      Responsibilities of SDC Group Prior to Certification of GMP .....	5
(f)      Responsibilities of SDC Group Following Certification of GMP .....	5
(g)      Right to Attend Meetings.....	7
(h)      Right to Communications and Obligation to Object.....	7
(i)      Decisions of the SDC Group.....	7
(j)      Project Representative .....	7
Section 2.3      GMP Alternatives and Construction Phase Disputes.....	8
(a)      GMP Alternatives .....	8
(b)      Approval of GMP Alternative .....	8
(c)      Construction Phase Disputes.....	9
ARTICLE 3      RETENTION OF ARCHITECT, CONSTRUCTION MANAGER, PROJECT CONSULTANTS AND CRITICAL DESIGN DECISIONS .....	9
Section 3.1      Retention of Architect and Construction Manager .....	9
(a)      Retention of Architect.....	9
(b)      Retention of Construction Manager.....	9
Section 3.2      Amendment of Agreements .....	9
Section 3.3      Solicitation and Selection Process Applicability .....	10
Section 3.4      Solicitation and Selection Process .....	10
Section 3.5      Conduct of Discussions and Data Privacy .....	10



## TABLE OF CONTENTS

(continued)

	<b>Page</b>
ARTICLE 4      PRELIMINARY PROGRAM AND DEVELOPMENT OF MASTER PROJECT PROGRAM.....	11
Section 4.1      Program Elements .....	11
Section 4.2      Development of Master Project Program .....	11
ARTICLE 5      ESTABLISHMENT OF MINIMUM DESIGN STANDARDS AND DESIGN DEVELOPMENT DOCUMENTS .....	11
Section 5.1      Minimum Design Standards .....	11
(a)      Establishment of Minimum Design Standards .....	11
(b)      Technology Design and Procurement .....	12
(c)      Site of Stadium and Stadium Infrastructure .....	14
(d)      Operable Feature .....	14
(e)      Cost Control .....	15
(f)      Team and Authority Approval of Amendment to Effective Date Minimum Design Standards .....	15
(g)      Costs Associated with Changes to Final Minimum Design Standards .....	15
(h)      LEED Certification and Environmental/Building Matters .....	15
(i)      Stadium Lighting Design and Procurement .....	15
(j)      Stadium Sponsored Signage Design and Procurement .....	17
(k)      Stadium Bowl Seating .....	19
(l)      Stadium Mechanized Pivoting Doors Design and Procurement .....	19
(m)      Stadium Scrim Signage Conflicts .....	22
(n)      East Event Level Locker Rooms .....	22
(o)      Concession Equipment .....	25
(p)      Stadium Plaza Design .....	27
(q)      Commemorative Bricks .....	31
(r)      WiFi Communications System .....	31
(s)      Additional Team Allocated Spaces .....	33
(t)      House Reduction Curtains .....	34
(u)      NFL Broadcast Requirements .....	34
(v)      Radio and Television Cabling Requirements .....	36
(w)      Magnetometer (FF&E) Acquisition .....	37

## TABLE OF CONTENTS

(continued)

	<b>Page</b>
(x) Catwalk Netting .....	37
(y) Field Turf Selection and Acquisition.....	38
Section 5.2 Design Documents .....	39
(a) Design Meetings .....	39
(b) Conceptual Design .....	40
(c) Schematic Design.....	40
(d) Design Development Documents .....	40
(e) Construction Manager to Provide Detailed Estimates .....	40
Section 5.3 Timing of Critical Design Decisions .....	40
Section 5.4 Notice of Design Impasse .....	41
Section 5.5 Notice of Issue with Final Minimum Design Standards .....	41
Section 5.6 City of Minneapolis Stadium Implementation Committee .....	41
(a) Alternative Process .....	41
(b) Minneapolis City Council Approval of Stadium Implementation Committee Recommendations .....	41
(c) De Novo Review .....	42
ARTICLE 6 CONSTRUCTION MATTERS .....	42
Section 6.1 Stadium Developer.....	42
(a) Role of Stadium Developer.....	42
(b) Team Assumption of Stadium Developer Duties .....	42
Section 6.2 Construction Administration.....	42
(a) Stadium Developer Oversight of Construction Manager.....	42
(b) Change Orders .....	43
(c) Right to Attend Meetings.....	44
(d) Value Engineering .....	44
Section 6.3 Construction Manager Subcontracting .....	44
Section 6.4 Lists of Contractors and Subcontractors .....	45
Section 6.5 Stadium Developer Responsibilities .....	45
(a) Administration Responsibilities.....	45
(b) Contract Negotiation and Third Party Beneficiary .....	45
(c) Project Accounting Services .....	45

## TABLE OF CONTENTS

(continued)

	<b>Page</b>
(d) Project Reporting .....	45
(e) Competitive Bidding.....	46
(f) Budget and Value Engineering .....	46
(g) Procedures for Payment of Project Costs.....	46
(h) Contract Legal Administration .....	46
(i) Punchlist and Warranty .....	46
(j) Transportation Plan .....	46
(k) Response to Requests.....	46
Section 6.6 Permits .....	46
Section 6.7 Project Labor Agreement.....	46
Section 6.8 Project Insurance.....	47
(a) Insurance .....	47
(b) Delay in Completion Date or Completion Deadline.....	47
(c) Risks of Damage or Destruction Prior to Completion .....	48
ARTICLE 7 SITE ACQUISITION .....	49
Section 7.1 Acquisition and Delivery of Stadium Site .....	49
(a) Acquisition of Stadium Site Property .....	49
(b) Title Evidence and Defects .....	49
(c) Registration of Title .....	50
(d) Notices of Violations .....	50
(e) Taxes .....	50
(f) Utilities.....	50
(g) Zoning .....	50
Section 7.2 Environmental Matters.....	50
(a) Environmental Assessments .....	50
(b) Project Cost.....	50
(c) EIS Report and Delivery .....	51
Section 7.3 Boundary Survey; Site Assessment; Response Actions .....	51
(a) Project Costs for Boundary and ALTA Surveys; Site Assessment; Response Actions.....	51
(b) Conditions Encountered – Reporting Obligations .....	51

## TABLE OF CONTENTS

(continued)

	<b>Page</b>
Section 7.4      Parking .....	52
ARTICLE 8      FINANCING OF THE PROJECT .....	52
Section 8.1      Master Project Budget and Project Expenses .....	52
(a)      Preliminary Project Budget and Master Project Budget .....	52
(b)      Development and Administration of the Master Project Budget .....	53
(c)      Allocation of Project Costs .....	55
(d)      Cost Savings .....	55
(e)      Allocation of Cost Savings .....	55
(f)      Allocation of Construction Services Agreement Cost Reductions, Release of Construction Manager Contingency and Construction Services Agreement Savings Share .....	59
(g)      Use of Owner's Contingency .....	60
(h)      SDC Group Contingency .....	60
Section 8.2      Team/Private Contribution and Authority Contribution .....	60
(a)      Team/Private Contribution .....	60
(b)      Authority Contribution .....	65
(c)      Interest Earnings .....	66
Section 8.3      Trust Agreement, Project Accounts and Termination of Project Accounts .....	66
(a)      Trust Agreement .....	66
(b)      Project Account Termination .....	67
(c)      Disposition of Project Accounts Upon Termination After Project Completion/Non-Completion .....	67
(d)      Effect of Disposition of Project Accounts .....	68
Section 8.4      Reimbursement of Payments to Team and Authority .....	68
(a)      Team Reimbursement – Payments Equal to \$50 Million or Less Upon Termination .....	68
(b)      Reimbursement of Team and Authority in Accordance with the Act – Payments Exceeding \$50 Million and Less Than \$100 Million .....	69
Section 8.5      Payment Procedures; Audit Rights .....	69
(a)      Payment Procedures .....	69
(b)      Disbursing Agreement and Agent .....	69

## TABLE OF CONTENTS

(continued)

	<b>Page</b>
(c) Development Requisitions .....	69
(d) Construction and Design Requisitions .....	70
(e) Right to Audit .....	70
Section 8.6 Construction Monitor .....	71
Section 8.7 Project Financing – Cooperation .....	71
(a) Facilitation of Financing .....	71
(b) Marketing and Sale of SBLs; SBL Purchase and Sale Facility .....	72
(c) Use of Private Contribution Proceeds .....	72
(d) Conditional Assignment of Construction-Related Agreements .....	73
(e) [RESERVED] .....	73
(f) Private Contribution Shortfall .....	73
Section 8.8 Cost Overruns .....	73
Section 8.9 Sales Tax Exemption .....	74
Section 8.10 Ownership of Project, Stadium Use Agreement and Team Tax Benefits .....	74
(a) Ownership of Project .....	74
(b) Team’s Stadium Property .....	74
(c) Team’s Stadium Property Schedule .....	75
(d) Team’s Right to Depreciation .....	75
Section 8.11 Team Right to Remit Project Costs in Excess of Obligation .....	75
Section 8.12 Team Use of Related Entities .....	76
ARTICLE 9 REPRESENTATIONS AND WARRANTIES OF AUTHORITY .....	76
Section 9.1 Organization .....	76
Section 9.2 Authorization, Validity and Enforceability .....	76
Section 9.3 No Conflicts .....	76
Section 9.4 No Violation of Applicable Laws .....	76
Section 9.5 Litigation .....	77
Section 9.6 Funding Sources Determination .....	77
ARTICLE 10 REPRESENTATIONS AND WARRANTIES OF TEAM .....	77
Section 10.1 Organization .....	77
Section 10.2 Authorization, Validity and Enforceability .....	77

## TABLE OF CONTENTS

(continued)

	<b>Page</b>
Section 10.3 Financial Position.....	77
Section 10.4 No Conflicts .....	78
Section 10.5 No Violations of Applicable Laws .....	78
Section 10.6 Litigation.....	78
ARTICLE 11 ADDITIONAL COVENANTS AND CONDITIONS .....	78
Section 11.1 Additional Covenants of the Parties .....	78
(a) [RESERVED] .....	78
(b) Expansion of Tailgating Areas.....	78
(c) Liquor Licenses.....	78
(d) Use of References and Logos in Offering Documents .....	79
(e) Operations Management Company for Stadium.....	79
(f) Access to Financial Information .....	79
(g) Existing Workers .....	79
(h) Commemorative Bricks .....	79
(i) Agreement to Play at TCF Bank Stadium.....	79
(j) Sports-Themed Lottery Games .....	79
(k) Site Signage .....	80
(l) Employment Assistance and Job Fair .....	80
(m) Apportionment of Liquidated Damages under Construction Services Agreement .....	80
Section 11.2 Execution of Documents.....	81
(a) Concurrent Documents .....	81
(b) Agreements to be Entered Into .....	82
(c) Effect of Not Entering Into Agreements .....	82
(d) Termination Reimbursement .....	82
Section 11.3 No Injunction .....	82
ARTICLE 12 DEFAULT AND REMEDIES.....	82
Section 12.1 Events of Default .....	82
(a) Covenant Default .....	82
(b) Representation Default.....	83
(c) Team Bankruptcy/Insolvency Default .....	83

## TABLE OF CONTENTS

(continued)

	<b>Page</b>
(d) Authority Bankruptcy/Insolvency Default.....	83
Section 12.2 Injunctive Relief; Specific Performance.....	83
Section 12.3 Remedies Cumulative .....	84
Section 12.4 Risk of Certain Losses; Force Majeure.....	84
Section 12.5 Limited Recourse Obligations of the Parties .....	84
Section 12.6 No Liability for Members, Directors, Officers, Etc.....	84
ARTICLE 13 DISPUTE RESOLUTION.....	85
Section 13.1 Arbitration.....	85
(a) Agreement to Arbitrate .....	85
(b) Initiation of Arbitration and Selection of Neutral.....	85
(c) Qualifications of Neutral.....	86
(d) Location and Conduct.....	86
(e) Discovery .....	87
(f) Cooperation/Duration .....	87
(g) Post-Hearing Mediation .....	87
(h) Decision of the Neutral .....	87
(i) Exclusive Remedy .....	87
(j) Strikes .....	88
Section 13.2 Other Disputes .....	88
ARTICLE 14 INDEMNIFICATION.....	88
Section 14.1 Indemnification and Payment of Damages by Team.....	88
Section 14.2 Indemnification and Payment of Damages by Authority .....	88
Section 14.3 Limitation of Liability and Indemnification Obligations.....	89
(a) Consequential Damages.....	89
(b) Team Stadium Contracts - Limitation of Liability for Third Party Contract Claims .....	89
(c) Authority Stadium Contracts - Limitation of Liability for Third Party Contract Claims .....	89
ARTICLE 15 TERM AND TERMINATION.....	90
Section 15.1 Term.....	90

## TABLE OF CONTENTS

(continued)

	<b>Page</b>
Section 15.2 Termination – Prior to Certification of GMP .....	90
(a) Termination by Either of the Parties .....	90
(b) Termination by the Authority .....	90
(c) Termination by the Team .....	91
Section 15.3 Termination – After Completion of Financing and Certification of GMP .....	91
Section 15.4 Consequences of Early Termination .....	91
(a) Effect of Notice of Termination .....	91
(b) Effect on Team and Authority Contributions and Authority Activities .....	91
(c) Project Wind-Up .....	91
(d) Authority Required Actions .....	92
(e) Continuing Obligations .....	92
Section 15.5 Survival .....	92
ARTICLE 16 MISCELLANEOUS .....	93
Section 16.1 Opinion Regarding Tax-Exempt Bonds .....	93
Section 16.2 Waiver .....	93
Section 16.3 Additional Documents and Approval .....	93
Section 16.4 Good Faith .....	93
Section 16.5 Notice of Matters .....	94
Section 16.6 Form of Notices; Addresses .....	94
Section 16.7 Calculation of Time .....	96
Section 16.8 Incorporation by Reference .....	96
Section 16.9 Entire Agreement .....	96
Section 16.10 Amendment .....	96
Section 16.11 Binding Effect; Assignment .....	96
Section 16.12 Headings .....	96
Section 16.13 No Presumption Against Drafter .....	96
Section 16.14 Severability .....	97
Section 16.15 Third Party Beneficiaries .....	97
Section 16.16 Governing Law .....	97



**TABLE OF CONTENTS**  
(continued)

	<b>Page</b>
Section 16.17      Execution in Counterparts and Delivery of Electronic Signatures.....	97
Section 16.18      Relationship of Parties .....	98
Section 16.19      No Waiver of Authority Immunity or Liability .....	98
Section 16.20      Conformity with the Act .....	98

**SCHEDULE AND EXHIBITS**

**SCHEDULE 1 – DEFINITIONS**

EXHIBIT A	SDC Group Rules and Procedures (Section 2.1)
EXHIBIT B-1	Preliminary Program (Section 4.1)
EXHIBIT B-2	Master Project Program (Section 4.2)
EXHIBIT C-1	Effective Date Minimum Design Standards (Section 5.1(a))
EXHIBIT C-2	Final Minimum Design Standards (Section 5.1(a))
EXHIBIT D-1-A	Effective Date Stadium Site (site plan) (Section 5.1(c))
EXHIBIT D-1-B	Effective Date Stadium Site (legal description) (Section 7.1(a))
EXHIBIT D-2	Final Stadium Site (Section 5.1(c))
EXHIBIT E	Minneapolis City Council Agenda (Section 5.6(b))
EXHIBIT F-1	Preliminary Project Budget (Section 8.1(a)(i))
EXHIBIT F-2	Master Project Budget (Section 8.1(a)(ii))
EXHIBIT G	Owner's Contingency Release Schedule (Section 8.1(b)(i)(A))
EXHIBIT H	Amended Allocation of Project Costs (Section 8.1(c))
EXHIBIT I-1	Authority Design Add Alternates (Section 8.1(e)(iii)(A))
EXHIBIT I-2	Team Design Add Alternates (Section 8.1(e)(iii)(B))
EXHIBIT I-3	Authority Project Cost Allocation Reductions (Section 8.1(e)(iii))
EXHIBIT I-4	Team Project Cost Allocation Reductions (Section 8.1(e)(iii))
EXHIBIT J	Irrevocable Letter of Credit (Section 8.2(a)(v)(A))
EXHIBIT K	Form of Bank Loan Commitment Acknowledgement (Section 8.2(a)(v)(C))
EXHIBIT L-1	Indemnification and Contribution Agreement (Section 8.7(a))
EXHIBIT L-2	Indemnification and Contribution Agreement (Section 8.7(a))
EXHIBIT M-1	Authority Stadium Builder License Program (Section 8.7(b))
EXHIBIT M-2	SBL Marketing and Sales Agreement (Section 8.7(b))
EXHIBIT N	SBL Purchase and Sale Agreement (Section 8.7(b))
EXHIBIT O-1	Conditional Assignment of Construction Services Agreement
EXHIBIT O-2	Conditional Assignment of Design Services Agreement and Plans
EXHIBIT P	Final Team's Stadium Property Schedule (Section 8.10(c))
EXHIBIT Q	Roster of Potential Neutrals (Section 13.1(b)(i))
EXHIBIT R-1	Preliminary Project Schedule (Schedule 1)
EXHIBIT R-2	Master Project Schedule (Schedule 1)
EXHIBIT S	Form of Construction Monitor Certification (Section 8.5(d))
EXHIBIT T	Contingency Letter of Credit (Section 8.1(a)(iii))
EXHIBIT U	East Event Level Locker Room Buildout (Section 5.1(n)(i))
EXHIBIT V	Cost List (Section 5.1(o)(iii)(D))
EXHIBIT W	Stadium Plaza Design Area (Section 5.1(p)(iii)(A))
EXHIBIT X	Plaza Area Depiction of Areas and Priorities (Section 5.1(p)(ii))
EXHIBIT Y	Tenting Plans Submitted to Hennepin County (Section 5.1(p)(ii))

**THIRD AMENDED AND RESTATED  
DEVELOPMENT AGREEMENT**

**THIS THIRD AMENDED AND RESTATED DEVELOPMENT AGREEMENT** (this “**Agreement**”) is executed and delivered on the 19<sup>th</sup> day of February, 2016 and made effective as of February 19, 2016, (the “**Effective Date**”) by and between Minnesota Sports Facilities Authority, a public body and political subdivision of the State of Minnesota (the “**Authority**”), and Minnesota Vikings Football Stadium, LLC, a Delaware limited liability company (the “**StadCo**”).

**RECITALS**

A. Minnesota Vikings Football, LLC, a Delaware limited liability company (the “**Team**”) holds, owns, and controls a professional football franchise which is a member of the National Football League.

B. In 2012, the Minnesota legislature, finding that the expenditure of public money for the construction, financing, operation, and long-term use of a multi-purpose stadium and related infrastructure as a venue primarily for the National Football League and a broad range of other civic, community, athletic, educational, cultural, and commercial activities serves a public purpose, enacted legislation (the “**Act**”) creating the Authority and authorizing the construction of a stadium and related stadium infrastructure in the City of Minneapolis, Minnesota.

C. The Minnesota legislature provided for the public financing of such stadium and related stadium infrastructure, with certain required private contributions and contributions by the Team, and for tax-exempt ownership of the stadium and related stadium infrastructure by the Authority.

D. The Team and the Authority previously entered into that certain Preliminary Development Agreement dated December 7, 2012 (the “**Preliminary Development Agreement**”), as the same may be amended, modified or supplemented from time to time, to allow the Authority and the Team to, among other things, commence the planning, design, development, and preconstruction of the Stadium and related Stadium Infrastructure.

E. Upon the effectiveness of the Original Agreement, the Preliminary Development Agreement automatically terminated in accordance with **Section 1.3** of the Original Agreement; **provided, however**, that the survival provisions set forth in the Preliminary Development Agreement remained in full force and effect and binding upon the Authority and the Team in accordance with **Section 1.3** of this Agreement.

F. On October 3, 2013, the Authority and the Team entered into that certain Development Agreement (the “**Original Agreement**”).

G. In connection with certain financing arrangements for the Stadium and Stadium Infrastructure, on November 22, 2013, the Team assigned the Original Agreement to StadCo pursuant to the certain Development Agreement Assignment and Assumption Agreement by and

between the Team and StadCo, which assignment became effective as of October 3, 2013, (the “**Development Agreement Assignment**”) and for all purposes the Development Agreement Assignment was made effective (i) prior to any amendment of the Original Agreement, and (ii) concurrently with the assignment of the Stadium Use Agreement (defined below).

H. In order to incorporate certain technical corrections and supplement the Original Agreement, the Authority and StadCo entered into that certain Amended and Restated Development Agreement dated November 22, 2013, to be effective October 3, 2013 (the “**First Amended and Restated Agreement**”) to amend and restate the Original Agreement and, in so doing, the Original Agreement was superseded in its entirety so that all of the terms and conditions contained in the First Amended and Restated Agreement superseded and replaced the terms of the Original Agreement. Upon execution and delivery of the First Amended and Restated Agreement, the Original Agreement had no further force and effect. The First Amendment and Restated Agreement in no way impacted the effectiveness or validity of the Development Agreement Assignment described above. The Team joined in the execution of the First Amended and Restated Agreement for the limited purposes of (i) providing its acknowledgment and agreement (A) to the amendment and restatement of the Original Agreement, and (B) that it would be bound to its continuing obligations under the provisions of the First Amended and Restated Agreement, and (ii) confirming and affirming its retained rights under the Development Agreement Assignment, which assignment was and is not affected or otherwise changed by the terms of the First Amended and Restated Agreement.

I. From and after the date of First Amended and Restated Agreement dated November 22, 2013, the Parties executed and delivered two (2) amendments to the First Amended and Restated Agreement, respectively dated February 10, 2014 and August 22, 2014, and pursuant to the last of these amendments the Parties executed the Second Amended and Restated Development Agreement on August 22, 2014 (the “**Second Amended and Restated Agreement**”).

J. From and after the date of the Second Amended and Restated Agreement dated August 22, 2014, the Parties executed and delivered one (1) amendment to the Second Amended and Restated Agreement dated March 27, 2015. This Agreement incorporates the March 27, 2015 amendment and contains further amendments to the Second Amended and Restated Agreement, each of which have been approved by the Parties for incorporation to this Agreement. The amendments to the Second Amended and Restated Agreement described in this Recital are collectively referred to herein as the “**Second Amended and Restated Agreement Amendments**.”

K. In furtherance of the purposes of the Act, the Authority and the Team concurrently entered into that certain Stadium Use Agreement dated October 3, 2013 (the “**Stadium Use Agreement**”), which was (i) assigned by the Team to StadCo on October 3, 2013, and (ii) was concurrently amended and restated on November 22, 2013, by the Authority and StadCo to be effective as of October 3, 2013 (after giving full effect to the Team Assignment of the Stadium Use Agreement to StadCo), concerning the use of the Stadium and Stadium Infrastructure. The Stadium Use Agreement has been further amended by the Authority and StadCo and any reference used herein to the Stadium Use Agreement shall be as amended and amended and restated.

L. In order to incorporate certain understandings regarding, among other things, financing sources and covenants of the Parties, the Authority and StadCo enter into this Agreement to amend and restate the Second Amended and Restated Agreement and, in so doing, (i) the provisions of the Second Amended and Restated Agreement Amendments as described in Recital J above will be fully incorporated to this Agreement to be effective from and after August 22, 2014, (ii) all other provisions that are added to this Agreement other than the Amendment provisions shall be effective from and after the Effective Date (sometimes referred to herein as the “**Third Amended Effective Date**”), and (iii) all provisions of the Second Amended and Restated Agreement shall be and remain unaffected, except to the extent modified by the Second Amended and Restated Agreement Amendments and the other amended provisions of this Agreement that were not set forth in the Second Amended and Restated Agreement, which provisions shall remain effective as set forth in the terms of each such amendments.

**NOW, THEREFORE**, in consideration of the foregoing Recitals, which are hereby incorporated into this Agreement, and the mutual promises, undertakings and covenants hereinafter set forth, and intending to be legally bound hereby, the Authority and the Team covenant and agree as follows:

## **AGREEMENT**

### **ARTICLE 1**

#### **DEFINITIONS, RULES OF CONSTRUCTION AND PRELIMINARY DEVELOPMENT AGREEMENT**

##### Section 1.1 Defined Terms.

Capitalized terms used in this Agreement shall have the meanings set forth in **Schedule 1.**

##### Section 1.2 Construction of Terms.

As the context of this Agreement may require, terms in the singular shall include the plural (and vice versa) and the use of feminine, masculine or neuter genders shall include each other. Wherever the word “including” or any variation thereof is used herein, it shall mean “including, without limitation” and shall be construed as a term of illustration, not a term of limitation. Where a consent or approval is required, it shall be deemed to also require that such consent to be in writing and provided prior to the action to be taken.

##### Section 1.3 Preliminary Development Agreement; Conflicting Terms.

The Parties hereby acknowledge and agree that this Agreement terminates the Preliminary Development Agreement; **provided, however**, that the rights and obligations of the Parties specified in Section 11.2 of the Preliminary Development Agreement survive its termination and remain in full force and effect and binding upon the Parties in accordance with Section 11.2 thereof. In the event of any conflict between the terms of this Agreement and the

Preliminary Development Agreement, the terms of this Agreement shall govern and control in all respects.

## ARTICLE 2 STADIUM DESIGN AND CONSTRUCTION GROUP

### Section 2.1 Collaborative Effort.

Pursuant to Section 2.1 of the Preliminary Development Agreement, the Team and Authority established the Stadium Design and Construction Group (the “**SDC Group**”) to facilitate the collaborative effort between the Authority and the Team for the design and preliminary construction planning of the Project. The SDC Group shall continue under this Agreement to manage the design of the Project and oversee the construction of the Project as described in this Agreement. The SDC Group will be administered in accordance with the rules and procedures set forth in **Exhibit A** to this Agreement.

### Section 2.2 Role of Stadium Design and Construction Group.

(a) Composition of SDC Group. The SDC Group shall be comprised of the two (2) Authority Representatives and the two (2) Team Representatives. The Authority Representatives and the Team Representatives shall serve as the lead representatives to the SDC Group for the Authority and the Team, respectively. Each Party has also designated Alternate Representatives with the authority to serve in place of, and with the authority of, such representatives if such representatives are not available to attend SDC Group meetings. Each Party may remove and replace its Representatives or Alternate Representatives (collectively, its “**Authorized Representatives**”) at any time, with or without cause and without the approval of any other Party, effective immediately upon written notice to the other Party. Each Party shall be responsible for the compensation and expenses of its Authorized Representatives. The SDC Group shall cause minutes of all SDC Group meetings to be prepared.

(b) SDC Chair. An Authority Representative appointed by the Authority will serve as chairperson of the SDC Group (“**SDC Chair**”). The role of the SDC Chair shall be administrative in nature so as to facilitate the scheduling, conducting and documenting of meetings. The SDC Chair shall actively participate in discussions on all issues before the SDC Group and shall have the same voting rights as all other members of the SDC Group.

(c) Team Representatives. The Team has designated the Team Representatives and the Team Alternate Representatives as its agents and representatives authorized to act on the Team’s behalf with respect to the Project. It is the responsibility of the Team Representatives to obtain timely, appropriate and adequate authority to act on the Team’s behalf, including obtaining authority from the Team’s governing body on issues described in this Agreement. The Team Representatives are the Team’s exclusive representatives insofar as the SDC Group is concerned. All communications and submittals from the Team to the Authority or the SDC Group with respect to matters arising from the SDC Group shall be issued or made through the Team Representatives, unless the Team or the Team Representatives shall otherwise direct in writing. Only the signature on any document of the Team Representative or a Team Alternate

Representative that is designated as the voting representative pursuant to this Agreement may be relied upon as having been authorized by all necessary action of the Team.

(d) Authority Representatives. The Authority has designated the Authority Representatives and the Authority Alternate Representatives as its agents and representatives authorized to act on the Authority's behalf with respect to the Project. It is the responsibility of the Authority Representatives to obtain timely, appropriate, and adequate authority to act on the Authority's behalf including obtaining authority from the Authority board as described in of this Agreement or as otherwise required by Applicable Law. The Authority Representatives are the Authority's exclusive representatives insofar as the SDC Group is concerned. All communications and submittals from the Authority to the Team or the SDC Group with respect to matters arising from the SDC Group shall be issued or made through the Authority Representatives, unless the Authority or the Authority Representatives shall otherwise direct in writing. Only the signature on any document of the Authority Representative or an Authority Alternate Representative that is designated as the voting representative pursuant to this Agreement may be relied upon as having been authorized by all necessary action of the Authority.

(e) Responsibilities of SDC Group Prior to Certification of GMP. Prior to the Certification of GMP (as defined in **Section 2.3(b)**), the SDC Group will manage the design and preconstruction of the Project and oversee the construction of the Project by performing the following responsibilities and finalizing applicable documents pursuant to this Agreement, including: (i) development of the Master Project Program; (ii) approval of commitments and expenditures under the Preliminary Project Budget; (iii) development of the Master Project Schedule; (iv) development of the Design Delivery Schedule under the Design Services Agreement; (v) development of the Master Project Budget and approval of commitments and expenditures under the Master Project Budget; (vi) recommendation of the boundaries of the Stadium Site; (vii) management and direction of the Architect in its preparation of the Conceptual Design Documents, Schematic Design Documents and Design Development Documents and delivery of other services pursuant to the Design Services Agreement; (viii) management and direction of the Construction Manager in its delivery of preconstruction and construction services pursuant to the Construction Services Agreement; (ix) development of the Final Minimum Design Standards; (x) review and management of any claims under the Design Services Agreement and the Construction Services Agreement; (xi) review and comment on regular Project reports from the Stadium Developer, the Project Representative and/or the Construction Manager; (xii) determine compliance with the Act, this Agreement, the Master Project Program, the Preliminary Project Budget, the Master Project Budget, the Master Project Schedule, the final boundaries of the Stadium Site, the Design Services Agreement, the Construction Services Agreement, the Effective Date Minimum Design Standards and the Final Minimum Design Standards, Project contracts and commitments, and Applicable Laws; and (xiii) undertaking any other aspects of the Project where SDC Group oversight or responsibility is given under this Agreement.

(f) Responsibilities of SDC Group Following Certification of GMP. After the Certification of GMP, the duties of the SDC Group under **Section 2.2(e)** shall end and shall be limited to the provisions of this **Section 2.2(f)**, regarding review and approval (disapproval),

before submittal to the Parties for approval, of any proposed revisions to the Final Minimum Design Standards, including Change Orders which effect the Final Minimum Design Standards. In addition, the SDC Group shall have the right to (i) review all Project reports from the Stadium Developer, the Project Representative, the Architect, and/or the Construction Manager; (ii) approval of the Construction Manager's cast in place construction program pursuant to the Construction Services Agreement; and (iii) monitor compliance with the Act, this Agreement, the Master Project Program (as consistent with the Construction Services Agreement), the maximum amount of the Master Project Budget, the Completion Date of the Master Project Schedule, the final boundaries of the Stadium Site, the Design Services Agreement, the Construction Services Agreement, the Final Minimum Design Standards, Project contracts and commitments, and Applicable Laws. Further, the SDC Group shall have the right to perform the following oversight functions, including making a recommendation to the Stadium Developer on such matters, but if the SDC Group is unable to agree upon such recommendation, the Stadium Developer shall have the ultimate decision making authority on such matters: (A) subject to **Section 8.1(g)** of this Agreement with respect to use of Owner's Contingency, Change Orders that involve an expenditure from the Owner's Contingency; and (B) value engineering proposals, that involve an expenditure from the Owner's Contingency, that do not affect the Final Minimum Design Standards.

Notwithstanding the foregoing, after the Certification of GMP the duties and responsibilities of the SDC Group shall remain unchanged (as if Certification of GMP had not taken place), but only as specified in the Sections of this Agreement referenced in (1) through (27) of this paragraph, with respect to (1) the negotiation of and recommendation with respect to execution of the Park Use Agreement as defined in Section 3.9 of the Stadium Use Agreement, (2) matters related to the so-called Downtown East (DTE) acquisition and integration into the Project, including budgetary matters, (3) the Vendor Contract Technology set forth in **Section 5.1(b)**, (4) the Operable Feature as set forth in **Section 5.1(d)**, (5) Stadium Lighting set forth on **Section 5.1(i)**, (6) Stadium Sponsored Signage design and procurement matters set forth in **Sections 5.1(j)**, (7) Stadium bowl seating as set forth in **Section 5.1(k)**, (8) Stadium Mechanized Pivoting Doors as set forth in **Section 5.1(l)**, (9) Stadium Scrim Signage Positions as set forth in **Section 5.1(m)**, (10) East Event Level Locker Room Buildout as set forth in **Section 5.1(n)**, (11) Concession Equipment, including point of sale systems, as set forth in **Section 5.1(o)**, (12) Stadium Plaza design and improvements as set forth in **Section 5.1(p)**, (13) Commemorative Bricks design and procurement as set forth in **Section 5.1(q)**, and (14) WiFi design and procurement as set forth in **Section 5.1(r)**, (15) East Event Level Locker Room Buildout as set forth in **Section 5.1(s)**, (16) house reduction curtains as set forth in **Section 5.1(t)**, (17) NFL/broadcast requirements as set forth in **Section 5.1(u)**, (18) television, radio, and cabling costs as set forth in **Section 5.1(v)**, (19) design and procurement of magnetometers as set forth in **Section 5.1(w)**, (20) catwalk netting as set forth in **Section 5.1(x)**, (21) field turf selection as set forth in **Section 5.1(y)**, (22) review of and recommendation with respect to execution of contract(s) regarding development matters, including parking, with respect to the Ryan Construction development proposal, (23) signage and other unfinished matters with respect to the Stadium Implementation Committee, the Minneapolis Planning Commission and the Minneapolis City Council as generally described in **Section 5.6(b)**, (24) additional coverage of spray fireproofing in a manner consistent with the cost overrun and cost savings principles specified in the February 19, 2016 SDC Group Action, (25) additional



signage and removable turf rails in a manner consistent with the cost overrun and cost savings principles specified in the February 19, 2016 SDC Group Action, (26) miscellaneous contract claims for data room delivery in a manner consistent with the cost overrun and cost savings principles specified in the February 19, 2016 SDC Group Action, and (27) matters related to the February 2016 Sources and Uses Statement attached to the SDC Group approval action dated February 19, 2016 (the “**February 19, 2016 SDC Group Action**”), as set forth in the February 19, 2016 SDC Group Action.

(g) Right to Attend Meetings. The Authorized Representatives shall receive notice of and have the right to attend (with the methods of allowable attendance specified in **Section 2** of **Exhibit A**) all meetings of the SDC Group. Prior to the Certification of GMP, such Persons shall (i) have the right to attend all Project meetings in person, by telephone or video conference call, or by other means that permit each Party to be verified and to hear and be heard by the others; and (ii) shall receive all Project documents provided to the Authority or the Team under all Project related agreements at the same time they are provided to the other Party. Following the Certification of GMP, such Persons shall (A) have the right to attend all SDC Group meetings in person, by telephone or video conference call, or by other means that permit each Party to be verified and to hear and be heard by the others; and (B) shall receive Project documents for the SDC Group to review any issues presented to or requested by any member of the SDC Group. All SDC Group meetings shall be held in Hennepin County, Minnesota unless otherwise agreed by the Parties and shall be scheduled at a regular time that generally allows the Authorized Representatives and their respective staff and consultants to attend.

(h) Right to Communications and Obligation to Object. The Authorized Representatives shall receive copies of all communications, documents, and reports that are received by the Authority or the Team from the Architect, Construction Manager, Project Representative and all Project Consultants, in all matters arising from, in connection with or incident to the Project. The Authorized Representatives shall have the right to communicate with, but not direct, the Project Representative in all matters arising from, in connection with or incident to the Project. With respect to any document or report delivered to the Authorized Representatives and the Parties after Certification of GMP, the Stadium Developer shall be required to specifically highlight and specify, to the actual knowledge of the Stadium Developer, the Final Minimum Design Standards that may be affected. If a Party has any objection based on a deviation from the Final Minimum Design Standards to any such delivered document or report, such objection shall be timely made, consistent with **Section 16.5** hereof.

(i) Decisions of the SDC Group. The decisions of the SDC Group shall be effective only when made by the affirmative vote of each of the designated voting Authorized Representatives of the Authority and the Team. If such decision is a Critical Design Decision as defined in **Section 5.3**, the dispute over the decision is a Critical Design Decision that is subject to the Design Impasse and Notice of Design Impasse provisions of **Sections 5.4** and **13.1(b)** hereof.

(j) Project Representative. As of the date of this Agreement, each Party has retained its own third party owner’s representative to respectively represent each Party’s interest in the Project. The Stadium Developer’s owner’s representative (the “**Project Representative**”) shall be a non-voting member of the SDC Group. The Project Representative shall be the entity

serving as the owner's representative to the Stadium Developer. The Stadium Developer is the Party having Cost Overrun responsibility for the Project consistent with the Act. The initial Stadium Developer is the Authority, subject to the Team's right to request that it become the Stadium Developer and assume management of the construction under Minnesota Statutes section 473J.11, subd. 1(f) and **Section 6.1** of this Agreement. If desired by the Party that is not the Stadium Developer, its owner's representative shall continue to have the right to participate in the construction of the Project after the Certification of GMP.

Section 2.3 GMP Alternatives and Construction Phase Disputes.

(a) GMP Alternatives. In accordance with the Construction Services Agreement and Minnesota Statutes section 473J.11, subd. 1(c), the Construction Services Agreement may be a construction manager at-risk GMP contract or a design-build GMP contract. The Construction Services Agreement has been entered into as a Construction Manager at-risk GMP contract with an option on the part of the Authority to convert to a design-build GMP contract consistent with **Section 2.3(b)** hereof.

(b) Approval of GMP Alternative. As set forth in Article 5 of the Construction Services Agreement, and upon written approval of the SDC Group, the Authority shall cause the Construction Manager to submit a proposed Construction Management Plan for review and written approval by the Authority and Team, including the Construction Manager's proposed GMP and date of Substantial Completion to be certified by the Construction Manager. If the Construction Manager's proposed Construction Management Plan is acceptable to the Authority then, upon recommendation of the SDC Group and receipt of the separate written approval of the Team, the Construction Management Plan shall be executed by the Authority and the Construction Manager and incorporated into the Construction Services Agreement as a contract revision in the form of a completed "Exhibit 3" thereto (the "**Certification of GMP**"). The GMP cannot be approved pursuant to the above, and there cannot be Certification of GMP, unless the Final Minimum Design Standards, the Master Project Program, the Master Project Budget and the Master Project Schedule have been developed, finalized and approved by the SDC Group and the GMP is consistent with the foregoing. As a condition of Certification of GMP, the Authority and the Team will agree at the time of Certification of GMP that the Design Documents (as defined in the Design Services Agreement) then existing meet and satisfy the Final Minimum Design Standards attached as **Exhibit C-2**, or as otherwise agreed between the Parties. If the Construction Manager's proposed Construction Management Plan is not acceptable to both the Authority and Team, in their respective sole discretion, then (i) the Construction Manager may submit a new proposed Construction Management Plan for review and approval by the Authority and Team, or (ii) the Authority, with the written consent of the Team, may terminate the Construction Services Agreement. The Construction Management Plan proposed by the Construction Manager can be either a construction manager at risk proposal or a design-build proposal. The Authority and Team can ask for an alternative proposal in either format. If the Construction Manager's proposed Construction Management Plan is not acceptable to the Authority and Team, then the Authority, with the Team's written approval, may request the Construction Manager to submit a new proposal to complete the Project under either a design-build contract or a construction manager at risk contract which contains a Construction Manager-certified GMP and the date of Substantial Completion. If the Authority and Team are

unable to reach agreement with the Construction Manager under any form of Construction Manager proposal, then the Authority, with the Team's written approval, shall terminate the Construction Services Agreement and solicit proposals to complete the Project from other qualified contractors as authorized by the Act.

(c) Construction Phase Disputes. After the Certification of GMP, as between the SDC Group and the Stadium Developer, the Stadium Developer will have the right to interpret the provisions of the Design Services Agreement and the Construction Services Agreement; **provided, however,** that without the written approval of each of the Authority and the Team there can be no deviation from the Final Minimum Design Standards, the maximum amount of the Master Project Budget, the Completion Date under the Master Project Schedule, and the Certification of GMP, consistent with the provisions of this Agreement and the Construction Services Agreement.

### ARTICLE 3

#### RETENTION OF ARCHITECT, CONSTRUCTION MANAGER, PROJECT CONSULTANTS AND CRITICAL DESIGN DECISIONS

##### Section 3.1 Retention of Architect and Construction Manager.

(a) Retention of Architect. The Parties previously selected HKS, Inc. as the architect for the Project (the "**Architect**"). The Parties previously reviewed and approved the Design Services Agreement. The Parties have previously amended the Design Services Agreement. Other than a Change Order pursuant to Section 6.2(b) of this Agreement, no amendment shall be made to the Design Services Agreement other than as provided for in the Design Services Agreement. The Architect shall be directed in accordance with the Design Services Agreement.

(b) Retention of Construction Manager. The Parties previously selected M.A. Mortenson Company as the construction manager for the Project (the "**Construction Manager**"), which Construction Manager may be replaced in a manner set forth in Section 2.3(b). The Parties have previously amended the Construction Services Agreement. No further amendment shall be made to the Construction Services Agreement other than as provided for in the Construction Services Agreement and pursuant to Section 2.3, Section 3.2 or Section 6.2(b) of this Agreement.

##### Section 3.2 Amendment of Agreements.

Except as provided in Section 3.1(a) and (b), the Authority and the Team shall each approve or disapprove any amendment to the Design Services Agreement, the Construction Services Agreement and any other Project Consultant agreement, subject to the Change Order provisions set forth herein and in the foregoing agreements. No such amendment to the foregoing agreements shall be effective without the written consent of the Authority and the Team, subject to the Change Order provisions set forth herein and in the foregoing agreements. Upon Certification of GMP, and subject to Sections 2.2(f), 2.3 and 6.2(b) hereof, the SDC Group shall have the authority to approve or disapprove for recommendation to the Parties with respect to the foregoing agreements (i) only those amendments that deviate from or change the Final Minimum Design Standards; or (ii) would cause the Project Costs to exceed the Master

Project Budget as set forth in the Certification of GMP. The Authority or the Stadium Developer, as applicable, shall submit to the SDC Group for review and approval any such amendment. The SDC Group shall act within ten (10) Business Days of receipt to approve or disapprove such change. Approvals shall not be unreasonably withheld or conditioned. If the SDC Group shall fail to act within ten (10) Business Days, any such amendment shall be deemed to have been approved; **provided, however,** upon written request by the Authority, the SDC Group shall in writing to the Authority state the reasons for any disapproval; **provided, further,** that no such approval by the SDC Group with respect to the Final Minimum Design Standards or the Master Project Budget shall bind either the Authority or the Team, it being acknowledged and understood that any such amendment shall be solely within the exclusive right of the Parties to approve or disapprove of such matters.

Section 3.3 Solicitation and Selection Process Applicability.

Prior to Certification of GMP, the SDC Group shall use the solicitation and selection process set forth in this **Article 3** to recommend any consultants, subconsultants, trade contractors or vendors (“**Project Consultants**”) relating to the design, preconstruction and Construction Phases of the Project. The terms of the written agreement under which a Project Consultant will provide such goods or services is subject to the prior written approval of the Team and the Authority. The fees and expenses of the Architect, the Construction Manager(s) and such other Project Consultants recommended by the SDC Group, and separately approved by the Team and the Authority, shall be Project Costs. Following Certification of GMP, the selection and related fees and expenses of any Project Consultants engaged by the Stadium Developer that are reasonably required to complete the Project shall be Project Costs. Following Certification of GMP, the fees and expenses of any Project Consultant engaged by the Authority with the approval of the Team or engaged by the Team with the approval of the Authority, except as preapproved for expenditure under the allocations of Project Costs as set forth in **Section 8.1(c)**, shall be Project Costs.

Section 3.4 Solicitation and Selection Process.

Prior to Certification of GMP, the SDC Group shall prepare a request for proposals for issuance by the Authority for the applicable function and such request shall be published as required by Applicable Law. The Authority and the Team may, but are not required to, prequalify offerors by issuing a request for qualifications in advance of the request for proposals, and may select a short list of responsible offerors prior to the SDC Group’s discussions and evaluations.

Section 3.5 Conduct of Discussions and Data Privacy.

As provided in the request for proposals, the SDC Group may conduct discussions and negotiations with responsible offerors to determine which proposal is most advantageous to the Authority and the Team and to negotiate the terms of an agreement. In conducting discussions, there shall be no disclosure of any information derived from proposals submitted by competing offerors and the content of all proposals is nonpublic data under Minnesota Statutes Chapter 13 until such time as a notice to award a contract is given by the Authority or by the Stadium Developer (if the Stadium Developer is not the Authority).

## ARTICLE 4 PRELIMINARY PROGRAM AND DEVELOPMENT OF MASTER PROJECT PROGRAM

### Section 4.1 Program Elements.

Pursuant to Section 4.1 of the Preliminary Development Agreement, the Team and the Authority developed a basic description of the Project which the Parties agreed were the preliminary program basic program elements for the design and construction of the Project, as the same may be amended, modified or supplemented from time to time (the “**Preliminary Program**”). The Preliminary Program is attached hereto as **Exhibit B-1**. The Preliminary Program as set forth herein is the starting point for the development of the Master Project Program.

### Section 4.2 Development of Master Project Program.

The Parties agree that a master project program and the associated reconciliation table attached thereto (“**Master Project Program**”) must be developed and recommended by the SDC Group and consented to in writing by both Parties. Notwithstanding the foregoing, the Master Project Program as developed and recommended by the SDC Group shall not significantly deviate from the historical use and programming of the Metrodome as generally represented by the Preliminary Program. The Master Project Program is attached hereto as **Exhibit B-2**; **provided, however**, that if the Master Project Program has not been completed by the Effective Date of this Agreement, the Master Project Program will be attached and incorporated by reference to this Agreement on the date that it is approved by the SDC Group and approved in writing by each of the Parties. Any change, modification or amendment to Master Project Program shall only be in accordance with this Agreement and shall be considered final upon the Certification of GMP; **provided, however**, the Stadium Developer or SDC Group, as applicable, may make changes to the Design Documents (as defined in the Design Services Agreement) consistent with the terms of this Agreement, including specifically **Section 2.2(f)**.

## ARTICLE 5 ESTABLISHMENT OF MINIMUM DESIGN STANDARDS AND DESIGN DEVELOPMENT DOCUMENTS

### Section 5.1 Minimum Design Standards.

(a) Establishment of Minimum Design Standards. The Parties have agreed upon the Effective Date to minimum design standards as set forth in the attached **Exhibit C-1** (the “**Effective Date Minimum Design Standards**”). The final minimum design standards (the “**Final Minimum Design Standards**”) are hereby approved by the Parties and set forth as **Exhibit C-2**. After Certification of GMP, and notwithstanding any contrary provision of this Agreement other than the provisions of **Section 5.1(b)**, any change to the Final Minimum Design Standards shall require the written approval of both the Authority and the Team. The Stadium must be designed in conformance with all local and State requirements and be sufficient to allow NFL games and associated events to occur.

(b) Technology Design and Procurement.

(i) Vendor Contract Technology. The Authority and Team each acknowledge that the design and procurement of certain equipment and technology systems within the Project (including, without limitation, scoreboards, integration services, video boards and control room equipment and systems) will not occur until after Certification of GMP and, further, that the foregoing equipment and technology systems will not be included in the Construction Manager's scope of work at Certification of GMP but will be procured from and installed by other contractors or vendors unless later contracted for with the Construction Manager. The foregoing equipment and technology systems are referred to herein individually and collectively as "**Vendor Contract Technology.**" Vendor Contract Technology does not include the DAS or WiFi communications systems.

(ii) Vendor Contract Technology Budget. The Authority and Team will establish in the Master Project Budget a line item budget amount of Twenty-Eight Million One Hundred Thirty One Thousand One Hundred Five Dollars (\$28,131,105) for vendor contract technology ("**Vendor Contract Technology Budget**") inclusive of the amounts specified in the February 19, 2016 SDC Group Action. The Parties have agreed that a new Seven Hundred Thirty-Five Thousand Dollars (\$735,000) line item within the Vendor Contract Technology Budget will be allocated to Project management and consulting fees, with Two Hundred Thirty-Five Thousand Dollars (\$235,000) allocated for Project management and Five Hundred Thousand Dollars (\$500,000) allocated for consulting fees (which will be equally allocated to each of the Team and the Authority (Two Hundred Fifty Thousand Dollars (\$250,000) each)). This line item will be comprised of the transfer of Six Hundred Eight Thousand Dollars (\$608,000) reallocated from within the fiber network termination equipment line item in the Vendor Contract Technology Budget and an increase to the Vendor Contract Technology Budget in the amount of One Hundred Twenty Seven Thousand Dollars (\$127,000) in a manner consistent with the cost overrun and cost savings principles specified in the February 19, 2016 SDC Group Action. The Vendor Contract Technology Budget will not be reduced prior to completion of final design and procurement of Vendor Contract Technology unless agreed to by the SDC Group.

(iii) SDC Group Management of Vendor Contract Technology Design and Procurement Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of GMP the SDC Group will continue to manage the design and procurement of the Vendor Contract Technology (including the design and specifications, selection of contractors/vendors and approval of contract terms) and make recommendations to the Authority and Team for approval or disapproval. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The design and procurement of Vendor Contract Technology will be subject to the following requirements:

(A) Vendor Contract Technology Design Standard. Design and procurement of the Vendor Contract Technology will be consistent with and comparable to NFL facilities of similar design and age considering the Vendor

Contract Technology Budget, value engineering and add alternates agreed to by the Parties, but in no case shall Owner's Contingency be reduced or the Master Project Budget exceeded without Privately Financed Enhancements to satisfy Vendor Contract Technology design. The SDC Group will endeavor to develop a final design and specifications for the Vendor Contract Technology within the Vendor Contract Technology Budget. At the conclusion of the design process, the SDC Group's recommended design and specifications may include certain equipment and specifications estimated to exceed the Vendor Contract Technology Budget, provided such equipment and specifications are designated to be priced as alternates.

(B) Procurement of Vendor Contract Technology. Upon written approval by the Parties of the design and specifications for the Vendor Contract Technology, the SDC Group will solicit proposals for procurement of the Vendor Contract Technology consistent with the requirements of the Act and this Agreement. Following receipt of such proposals the SDC Group will timely recommend for approval by the Parties a procurement strategy, including recommended contractors, vendors and other considerations based on the responsive proposals received by the Authority and Team. In the event the approved design and specifications for the Vendor Contract Technology cannot be procured from the responsive bidders within the Vendor Contract Technology Budget, the SDC Group will evaluate value engineering options to align the design and specifications with the Vendor Contract Technology Budget for recommendation to the Authority and Team. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The Stadium Developer shall enter into and manage the contracts for Vendor Contract Technology. With respect to sponsorship agreements that provide for a trade exchange of Vendor Contract Technology, the Team may procure such Vendor Contract Technology and shall not be an element of the Vendor Contract Technology Budget. However, any proposed sponsorship trade exchange shall be coordinated with the Stadium Developer.

(C) Cost Overruns. At the sole election of either Party, the electing Party may choose to designate any design alternate or any equipment or specification recommended for deletion by the SDC Group during the value engineering process as a Design Add Alternate under **Section 8.1** hereof as if set forth on **Exhibit I-1** or **Exhibit I-2**, respectively, and the electing Party may choose to fund the procurement of the designated equipment or specification as a pre-approved Design Add Alternate consistent with the requirements of **Section 8.1** of this Agreement.

(D) Cost Underruns. In the event the total cost to procure the Vendor Contract Technology (exclusive of any equipment or specifications designated as a Design Add Alternate under **Section 5.1(b)(iii)(C)** above) is less than the Vendor Contract Technology Budget, the difference between the contracted

amount and the Vendor Contract Technology Budget shall be transferred to the Owner's Contingency pursuant to **Section 8.1(b)(i)(B)**.

(iv) **Vendor Contract Technology Design Impasse**. The Parties acknowledge and agree that maintaining the Master Project Schedule is essential for achieving the timely completion of the Project. In the event the SDC Group, or the Parties having received the SDC Group's recommendations, cannot reach agreement upon the design, specifications or procurement of the Vendor Contract Technology within the design and construction milestones to be established by the Parties in consultation with the Architect and Construction Manager, such impasse will be deemed a Design Impasse concerning a Critical Design Decision and either Party may provide a Notice of Design Impasse under **Section 5.4** hereof and the dispute shall be subject to Expedited ADR under **Article 13** of this Agreement.

(v) **Final Design And Specifications for Vendor Contract Technology to be Included in Final Minimum Design Standards**. The Authority and Team each acknowledge that the design and procurement of Vendor Contract Technology will not occur until after Certification of GMP and, therefore, final design and specifications for Vendor Contract Technology will not be included in the Effective Date Minimum Design Standards established under **Section 5.1** hereof. Upon completion of the design and procurement process, the final design and specifications for the Vendor Contract Technology, as approved in writing by each the Authority and Team, will be included in the Final Minimum Design Standards as if fully set forth on **Exhibit C-2**.

(c) **Site of Stadium and Stadium Infrastructure**. The SDC Group shall cause the Architect and, as applicable, its other Project Consultants to investigate a design that sites the Stadium as close to the far east on the Stadium Site as possible consistent with Applicable Laws for stadium design and construction, including full consideration of the increase or decrease to Project Costs, public health and safety, and other such issues, and to create a Stadium Plaza for game day and other year-round activities. The preliminary Stadium Site alternatives as of the Effective Date are set forth on **Exhibit D-1-A**, which is subject to change pending completion of the Stadium Site determination by the Authority (the "**Preliminary Stadium Site**"); **provided, however, Exhibit D-1-A** may be updated by the Parties at any time to supplement or replace **Exhibit D-1-A** to this Agreement. Upon completion of the Stadium Site determination by the Authority, such final Stadium Site, and the associated legal description, will be attached hereto by the Parties as **Exhibit D-2** (the "**Final Stadium Site**") and will be incorporated as a part of the Final Minimum Design Standards. From and after the Effective Date, the Authority shall work with the SDC Group to establish the Final Stadium Site.

(d) **Operable Feature**. The Parties acknowledge that the Effective Date Minimum Design Standards, and the Final Minimum Design Standards to be developed, will provide that the Stadium will have a fixed roof and will not have a retractable roof. The Parties further acknowledge that the Stadium will have an Operable Feature and that the cost of such Operable Feature is in the Master Project Budget and operating and maintenance costs attributable to the Operable Feature will be included as part of the Stadium operating and maintenance costs.



(e) Cost Control. The SDC Group shall work to control the Project Costs when considering changes to the Effective Date Minimum Design Standards for recommendation to the Authority and the Team. The SDC Group shall take into account operating and maintenance costs of the Stadium and Stadium Infrastructure when considering any amendments to the Effective Date Minimum Design Standards and the establishment of Final Minimum Design Standards, but such considerations may not change the quality requirements or attributes of the Stadium and Stadium Infrastructure as described in the Act.

(f) Team and Authority Approval of Amendment to Effective Date Minimum Design Standards. If either of the Authority or the Team does not approve an amendment to the Effective Date Minimum Design Standards recommended by the SDC Group prior to the Certification of GMP, the Effective Date Minimum Design Standards will remain unamended and the SDC Group shall continue with its efforts to amend the Effective Date Minimum Design Standards in a manner acceptable to the Authority and the Team. If either of the Authority or the Team does not approve an amendment to the proposed amendment to the Effective Date Minimum Design Standards, the objecting Party shall immediately provide to the SDC Group its specific written objections to such proposed amendment to the Effective Date Minimum Design Standards and such objection shall be deemed to be a Design Impasse. If the objection of a Party is decided by Expedited ADR Dispute in accordance with **Article 13** after further consideration by the SDC Group, then the Authority and the Team shall be bound by such decision by the Neutral and neither the Authority nor the Team shall have the right to withhold its approval of the amended Effective Date Minimum Design Standards.

(g) Costs Associated with Changes to Final Minimum Design Standards. Following the Certification of GMP, if either the Authority or the Team requests an amendment to the Final Minimum Design Standards, and such amendment is incorporated to the Final Minimum Design Standards pursuant to the written approval of each Party, any increase in the Master Project Budget or the GMP associated with such amendment shall be chargeable to the Party requesting such amendment unless approved in writing by the Authority and the Team. The Parties shall make reasonable commercial efforts to mitigate the negative impacts on the other previously agreed to Project elements. A request by one Party to amend the Final Minimum Design Standards after the Certification of GMP shall not be deemed an Expedited ADR Dispute subject to resolution by Expedited ADR pursuant to **Article 13**.

(h) LEED Certification and Environmental/Building Matters. To the extent practicable, the Stadium will be environmentally and energy efficient and the SDC Group shall cause the Architect to design the Stadium to receive Leadership in Energy and Environmental Design (LEED) certification or the Green Building Initiative Green Globes Certification for environmental design.

(i) Stadium Lighting Design and Procurement.

(i) Stadium Lighting. The Authority and Team each acknowledge that the design and procurement of the Stadium lighting package (“**Stadium Lighting**”) will not occur until after Certification of GMP and, further, that the estimated cost of the foregoing Stadium Lighting will be established as an allowance of Seven Million Eight

Hundred Seventy Two Thousand Two Hundred Twenty Dollars (\$7,872,220) (*i.e.*, Mortenson SC 2.4 Electrical).

(ii) Stadium Lighting Budget. Consistent with the allowance established at Certification of GMP, the Authority and Team acknowledge that the sum of Seven Million Eight Hundred Seventy Two Thousand Two Hundred Twenty Dollars (\$7,872,220) will be established for Stadium Lighting (the “**Stadium Lighting Budget**”). The Stadium Lighting Budget will not be reduced prior to completion of final design and procurement of Stadium Lighting unless agreed to by the SDC Group. With respect to sponsorship agreements that provide for a trade exchange of any component of the Stadium Lighting (*e.g.*, fixtures, products, equipment and labor), the Team may procure such Stadium Lighting components directly, and such components shall not be an element of the Stadium Lighting Budget. However, any proposed sponsorship trade exchange shall be coordinated with the Stadium Developer.

(iii) SDC Group Management of Stadium Lighting Design and Procurement Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of GMP the SDC Group will continue to manage the design and procurement of the Stadium Lighting (including the design and specifications for selecting product components in connection with trade exchanges described in **Section 5.1(i)(ii)** above and approval of contract terms) and make recommendations to the Authority and Team for approval or disapproval. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The design and procurement of Stadium Lighting will be subject to the following requirements:

(A) Stadium Lighting Design Standard. Design and procurement of the Stadium Lighting will be consistent with and comparable to NFL facilities of similar design and age considering the Stadium Lighting Budget, value engineering and add alternates agreed to by the Parties, but in no case shall Owner’s Contingency be reduced or the Master Project Budget exceeded without Privately Financed Enhancements to satisfy Stadium Lighting design. The SDC Group will endeavor to develop a final design and specifications for the Stadium Lighting within the Stadium Lighting Budget. At the conclusion of the design process, the SDC Group’s recommended design and specifications may include certain fixtures, products, equipment and specifications estimated to exceed the Stadium Lighting Budget, provided such fixtures, products, equipment and specifications are designated to be priced as alternates.

(B) Procurement of Stadium Lighting. In the event the approved design and specifications for the Stadium Lighting cannot be procured from the Construction Manager within the Stadium Lighting Budget, the SDC Group will evaluate value engineering options to align the design and specifications with the Stadium Lighting Budget for recommendation to the Authority and Team. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team.

(C) Cost Overruns. At the sole election of either Party, the electing Party may choose to designate any design alternate or any fixtures, products, equipment or specifications recommended for deletion by the SDC Group during the value engineering process as a Design Add Alternate under **Section 8.1** hereof as if set forth on **Exhibit I-1** or **Exhibit I-2**, respectively, and the electing Party may choose to fund the procurement of the designated equipment or specification as a pre-approved Design Add Alternate consistent with the requirements of **Section 8.1** of this Agreement.

(D) Cost Underruns. In the event the total cost to procure the Stadium Lighting (exclusive of any fixtures, products, equipment or specifications designated as a Design Add Alternate under **Section 5.1(i)(iii)(C)** above) is less than the Stadium Lighting Budget, the difference between the contracted amount and the Stadium Lighting Budget shall be transferred to the Owner's Contingency pursuant to **Section 8.1(b)(i)(B)**.

(iv) Stadium Lighting Design Impasse. The Parties acknowledge and agree that maintaining the Master Project Schedule is essential for achieving the timely completion of the Project. In the event the SDC Group, or the Parties having received the SDC Group's recommendations, cannot reach agreement upon the design, specifications or procurement of the Stadium Lighting within the design and construction milestones to be established by the Parties in consultation with the Architect and Construction Manager, such impasse will be deemed a Design Impasse concerning a Critical Design Decision and either Party may provide a Notice of Design Impasse under **Section 5.4** hereof and the dispute shall be subject to Expedited ADR under **Article 13** of this Agreement.

(j) Stadium Sponsored Signage Design and Procurement.

(i) Stadium Sponsored Signage. The Authority and Team each acknowledge that the design and procurement of the Stadium interior and exterior branding, sponsorship and naming rights signage ("**Stadium Sponsored Signage**") will not occur until after Certification of GMP and, further, that the estimated cost of the foregoing Stadium Sponsored Signage will be established as an allowance of One Million Dollars (\$1,000,000) (*i.e.*, Mortenson SC 4.18 Signage) at Certification of GMP.

(ii) Stadium Sponsored Signage Budget. Consistent with the allowance established at Certification of GMP, the Authority and Team acknowledge that the sum of One Million Dollars (\$1,000,000) will be established for Stadium Sponsored Signage (the "**Stadium Sponsored Signage Budget**"). The Stadium Sponsored Signage Budget will not be reduced prior to completion of final design and procurement of Stadium Sponsored Signage unless agreed to by the SDC Group. With respect to sponsorship agreements that provide for a trade exchange of any component of the Stadium Sponsored Signage, the Team may procure such Stadium Sponsored Signage directly, and such components shall not be an element of the Stadium Sponsored Signage Budget. However, any proposed sponsorship trade exchange shall be coordinated with the Stadium Developer.

(iii) SDC Group Management of Stadium Sponsored Signage Design and Procurement Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of GMP the SDC Group will continue to manage the design and procurement of the Stadium Sponsored Signage (including the design and specifications, selection of contractors/vendors and approval of contract terms) and make recommendations to the Authority and Team for approval or disapproval. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The design and procurement of Stadium Sponsored Signage will be subject to the following requirements:

(A) Stadium Sponsored Signage Design Standard. Design and procurement of the Stadium Sponsored Signage will be consistent with and comparable to NFL facilities of similar design and age considering the Stadium Sponsored Signage Budget, value engineering and add alternates agreed to by the Parties, but in no case shall Owner's Contingency be reduced or the Master Project Budget exceeded without Privately Financed Enhancements to satisfy Stadium Sponsored Signage design. The SDC Group will endeavor to develop a final design and specifications for the Stadium Sponsored Signage within the Stadium Sponsored Signage Budget. At the conclusion of the design process, the SDC Group's recommended design and specifications may include certain specifications estimated to exceed the Stadium Sponsored Signage Budget, provided such specifications are designated to be priced as alternates.

(B) Procurement of Sponsored Signage. In the event the approved design and specifications for the Stadium Sponsored Signage cannot be procured from the Construction Manager within the Stadium Sponsored Signage Budget, the SDC Group will evaluate value engineering options to align the design and specifications with the Stadium Sponsored Signage Budget for recommendation to the Authority and Team. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team.

(C) Cost Overruns. At the sole election of either Party, the electing Party may choose to designate any design alternates or specifications recommended for deletion by the SDC Group during the value engineering process as a Design Add Alternate under Section 8.1 hereof as if set forth on Exhibit I-1 or Exhibit I-2, respectively, and the electing Party may choose to fund the procurement of the designated equipment or specification as a pre-approved Design Add Alternate consistent with the requirements of Section 8.1 of this Agreement.

(D) Cost Underruns. In the event the total cost to procure the Stadium Sponsored Signage (exclusive of any specifications designated as a Design Add Alternate under Section 5.1(j)(iii)(C) above) is less than the Stadium Sponsored Signage Budget, the difference between the contracted amount and the Stadium Sponsored Signage Budget shall be allocated pursuant to Section 8.1(b).

(iv) Stadium Sponsored Signage Design Impasse. The Parties acknowledge and agree that maintaining the Master Project Schedule is essential for achieving the timely completion of the Project. In the event the SDC Group, or the Parties having received the SDC Group's recommendations, cannot reach agreement upon the design, specifications or procurement of the Stadium Sponsored Signage within the design and construction milestones to be established by the Parties in consultation with the Architect and Construction Manager, such impasse will be deemed a Design Impasse concerning a Critical Design Decision and either Party may provide a Notice of Design Impasse under **Section 5.4** hereof and the dispute shall be subject to Expedited ADR under **Article 13** of this Agreement.

(k) Stadium Bowl Seating.

(i) Fixed Bowl Seating. The Authority and Team each acknowledge that the budget for the fixed seating systems to be installed in the Stadium seating bowl ("**Fixed Bowl Seating**") will be Eight Million One-Hundred Thousand Dollars (\$8,100,000) (*i.e.*, Mortenson SC 3.21). At the sole election of either Party, the electing Party may choose to designate alternate fixtures, products, equipment or specifications for the Fixed Bowl Seating as a Design Add Alternate under **Section 8.1** hereof as if set forth on **Exhibit I-1** or **Exhibit I-2**, respectively, and the electing Party may choose to fund the procurement of the designated alternate fixtures, products, equipment or specification for the Fixed Bowl Seating as a pre-approved Design Add Alternate consistent with the requirements of **Section 8.1** of this Agreement.

(ii) Retractable Bowl Seating. The Authority and Team each acknowledge that the budget for the retractable seating systems to be installed in the Stadium seating bowl ("**Retractable Bowl Seating**") will be Five Million Eight-Hundred Fifty-Six Thousand Dollars (\$5,856,000) (*i.e.*, Mortenson SC 3.22). At the election of either Party, the electing Party may choose to designate alternate fixtures, products, equipment or specifications for the Retractable Bowl Seating (specifically including procurement of the Retractable Bowl Seating system identified on **Exhibit I-1** or **Exhibit I-2**) as a Design Add Alternate under **Section 8.1** hereof as if set forth on **Exhibit I-1** or **Exhibit I-2**, respectively, and the electing Party may, with the approval of the SDC Group, choose to fund the procurement of the designated alternate fixtures, products, equipment or specification for the Retractable Bowl Seating as a pre-approved Design Add Alternate consistent with the requirements of **Section 8.1** of this Agreement.

(l) Stadium Mechanized Pivoting Doors Design and Procurement.

(i) Stadium Mechanized Pivoting Doors. The Authority and Team each acknowledge that the design and procurement of the Stadium operable door package ("**Stadium Mechanized Pivoting Doors**") will not occur until after Certification of GMP and, further, that the estimated cost of the foregoing Stadium Mechanized Pivoting Doors will be established as an allowance of Thirteen Million Two Hundred Thirty Five Thousand Nine Hundred Sixty Eight Dollars (\$13,235,968) (*i.e.*, Mortenson SC3.11 Operable Wall Mechanization (including frames & glazing)).

(ii) Stadium Mechanized Pivoting Doors Budget. Consistent with the allowance established at Certification of GMP, the Authority and Team acknowledge that the value of the Stadium Mechanized Pivoting Doors Budget, as of the date of this Agreement, is Twelve Million Eight Hundred Thousand Nine Hundred Eighty Five Dollars (\$12,800,985), which is the value established in the Settlement Agreement (the “**Stadium Mechanized Pivoting Doors Budget**”). The Stadium Mechanized Pivoting Doors Budget will not be reduced prior to completion of final design and procurement of Stadium Mechanized Pivoting Doors unless agreed to by the SDC Group. In connection with the Settlement Agreement, the Authority and the Team have agreed to close out the allowance for the Stadium Mechanized Pivoting Doors Budget in the Construction Services Agreement (*i.e.*, Mortenson SC3.11 Operable Wall Mechanization (including frames & glazing) (as defined in the Settlement Agreement)) at the amount of Twelve Million Eight Hundred Thousand Nine Hundred Eighty Five Dollars (\$12,800,985) and, further, the Team has agreed that it will fund an additional Four Hundred Fifty-Three Thousand Dollars (\$453,000) of an anticipated Seven Hundred Twenty-Five Thousand Dollars (\$725,000) future risk associated with closeout of the Stadium Mechanized Pivoting Doors Budget with the Construction Manager. The Authority and the Team acknowledge the Nine Hundred Sixteen Thousand Dollars (\$916,000) disputed pipeline column cost (Construction Manager issue 1163) will be excluded from the Stadium Mechanized Pivoting Door allowance. If either the Construction Manager or the Authority rejects the settlement of claims pursuant to the terms of the Settlement Agreement, the Parties will be returned to the *status quo* set forth in the August 22, 2014, SDC Group action and (A) the Team’s additional funding of Four Hundred Fifty-Three Thousand Dollars (\$453,000) will be returned to the Team; (B) the Team will be responsible for cost overruns in connection with the Stadium Mechanized Pivoting Doors Budget; and (C) the Team will be entitled to dispute claims by the Construction Manager or the Authority for additional costs alleged to be associated with the Stadium Mechanized Pivoting Doors, including the Nine Hundred Sixteen Thousand Dollars (\$916,000) disputed pipeline column cost (Construction Manager issue 1163).

With respect to sponsorship agreements that provide for a trade exchange of any component of the Stadium Mechanized Pivoting Doors (*e.g.*, fixtures, products, equipment and labor), the Team may procure such Stadium Mechanized Pivoting Doors components directly, and such components shall not be an element of the Stadium Mechanized Pivoting Doors Budget. However, any proposed sponsorship trade exchange shall be coordinated with the Stadium Developer.

(iii) SDC Group Management of Stadium Mechanized Pivoting Doors Design and Procurement Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of GMP the SDC Group will continue to manage the design and procurement of the Stadium Mechanized Pivoting Doors (including the design and specifications for selecting product components in connection with trade exchanges described in **Section 5.1(l)(ii)** above and approval of contract terms) and make recommendations to the Authority and Team for approval or disapproval. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The design and

procurement of Stadium Mechanized Pivoting Doors will be subject to the following requirements:

(A) Stadium Mechanized Pivoting Doors Design Standard. Design and procurement of the Stadium Mechanized Pivoting Doors will be consistent with and comparable to NFL facilities of similar design and age considering the Stadium Mechanized Pivoting Doors Budget, value engineering and add alternates agreed to by the Parties, but in no case shall Owner's Contingency be reduced or the Master Project Budget exceeded without Privately Financed Enhancements to satisfy Stadium Mechanized Pivoting Doors design. The SDC Group will endeavor to develop a final design and specifications for the Stadium Mechanized Pivoting Doors within the Stadium Mechanized Pivoting Doors Budget. At the conclusion of the design process, the SDC Group's recommended design and specifications may include certain fixtures, products, equipment and specifications estimated to exceed the Stadium Mechanized Pivoting Doors Budget, provided such fixtures, products, equipment and specifications are designated to be priced as alternates.

(B) Procurement of Stadium Mechanized Pivoting Doors. In the event the approved design and specifications for the Stadium Mechanized Pivoting Doors cannot be procured from the Construction Manager within the Stadium Mechanized Pivoting Doors Budget, the SDC Group will evaluate value engineering options to align the design and specifications with the Stadium Mechanized Pivoting Doors Budget for recommendation to the Authority and Team. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team.

(C) Cost Overruns. At the sole election of either Party, the electing Party may choose to designate any design alternate or any fixtures, products, equipment or specifications recommended for deletion by the SDC Group during the value engineering process as a Design Add Alternate under **Section 8.1** hereof as if set forth on **Exhibit I-1** or **Exhibit I-2**, respectively, and the electing Party may choose to fund the procurement of the designated equipment or specification as a pre-approved Design Add Alternate consistent with the requirements of **Section 8.1** of this Agreement.

(D) Cost Underruns. In the event the total cost to procure the Stadium Mechanized Pivoting Doors (exclusive of any fixtures, products, equipment or specifications designated as a Design Add Alternate under **Section 5.1(i)(iii)(C)** above) is less than the Stadium Mechanized Pivoting Doors Budget, the difference between the contracted amount and the Stadium Mechanized Pivoting Doors Budget shall be allocated pursuant to **Section 8.1(b)**.

(iv) Stadium Mechanized Pivoting Doors Design Impasse. The Parties acknowledge and agree that maintaining the Master Project Schedule is essential for achieving the timely completion of the Project. In the event the SDC Group, or the Parties having received the SDC Group's recommendations, cannot reach agreement

upon the design, specifications or procurement of the Stadium Mechanized Pivoting Doors within the design and construction milestones to be established by the Parties in consultation with the Architect and Construction Manager, such impasse will be deemed a Design Impasse concerning a Critical Design Decision and either Party may provide a Notice of Design Impasse under **Section 5.4** hereof and the dispute shall be subject to Expedited ADR under **Article 13** of this Agreement.

(m) Stadium Scrim Signage Conflicts.

(i) Stadium Scrim Signage Positions. The Authority and Team each acknowledge that the design of the Stadium includes three (3) signage positions at the upper valance scrims near the roof of the Stadium ("**Stadium Scrim Signage Positions**") and as identified in item numbers 20, 30 and 32 of the Sponsorship Manifest as shown on Exhibit G-1 or Exhibit G-2 to the Stadium Use Agreement. Each Party further acknowledges that the Stadium design as of February 13, 2015, locates certain ductwork or other mechanical equipment or fixtures in position to block sightlines and inhibit Stadium visitors from viewing the entire surface of the Stadium Scrim Signage Positions. The Authority and Team therefore mutually desire to relocate the ductwork and/or other mechanical equipment and fixtures or otherwise modify the design to mitigate the impact of the ductwork/mechanicals on the sightlines/view of the Stadium Scrim Signage Positions.

(ii) SDC Group Management of Design Revisions to Mitigate Conflict with Stadium Scrim Signage Positions Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of GMP the SDC Group will continue to manage the design process and revisions necessary to relocate the ductwork and/or other mechanical equipment and fixtures or otherwise modify the design (including the design and specifications) to mitigate the impact of the ductwork/mechanicals on the sightlines/view of the Stadium Scrim Signage Positions and make recommendations to the Authority and Team for approval or disapproval of such design revisions. The final design recommendations of the SDC Group must be approved in writing by both the Authority and Team. Costs necessary to implement the mutually approved design revisions will be paid as Project Costs up to One Hundred Thousand Dollars (\$100,000). In the event that such costs exceed One Hundred Thousand Dollars (\$100,000), the Authority and Team will work in good faith to agree on an appropriate funding resolution.

(n) East Event Level Locker Rooms.

(i) East Event Level Locker Room Buildout. The Authority and Team mutually desire to buildout and finish approximately 7,500 square feet of locker room area in the east event level of the Stadium in accordance with the concept design set forth in as generally depicted in attached **Exhibit U**, including bathroom and locker facilities to be included in the final design (the "**East Event Level Locker Room Buildout**"), including approximately 2,500 square feet of locker room space that may be used exclusively by the Team pursuant to Article 14 of the Stadium Use Agreement in the



event the Team is awarded an MLS soccer franchise to operate a Team-Owned MLS Franchise (as that term is defined in the Stadium Use Agreement).

(ii) East Event Level Locker Rooms Budget. The Authority and Team acknowledge that the sum of Two Million Dollars (\$2,000,000) is established as the budget for the construction of the East Event Level Locker Room Buildout ("**East Event Level Locker Rooms Budget**"). The Team will fund the approved East Event Level Locker Room Buildout as a Privately Financed Enhancement. The East Event Level Locker Rooms Budget will not be reduced or increased prior to completion of final design and procurement of the East Event Level Locker Room Buildout unless agreed to by the SDC Group. In the event the Team is awarded an MLS soccer franchise to operate a Team-Owned MLS Franchise (as that term is defined in the Stadium Use Agreement), it will be responsible for any additional design and construction costs required to further finish the approximately 2,500 square feet of East Event Level Locker Room Buildout area to be used exclusively by the Team for MLS soccer operations.

(iii) SDC Group Management of East Event Level Locker Room Buildout Design and Procurement Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of GMP the SDC Group will continue to manage the design and procurement of the East Event Level Locker Room Buildout in accordance with the concept design set forth in **Exhibit U** (including the design and specifications, selection of contractors/vendors and approval of contract terms) and make recommendations to the Authority and Team for approval or disapproval. The Authority and Team acknowledge and agree that design services for the East Event Level Locker Room Buildout may be provided by a vendor other than the Architect currently under contract in the Design Services Agreement. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The design and procurement of the East Event Level Locker Room Buildout will be subject to the following requirements:

(A) East Event Level Locker Room Buildout Design Standard. Design and procurement of the East Event Level Locker Room Buildout will be consistent with and comparable to NFL facilities of similar design and age considering the East Event Level Locker Rooms Budget, value engineering and add alternates agreed to by the Parties, but in no case shall Owner's Contingency be reduced or the Master Project Budget exceeded without Privately Financed Enhancements to satisfy East Event Level Locker Room Buildout design. The SDC Group will endeavor to develop a final design and specifications for the East Event Level Locker Room Buildout within the East Event Level Locker Rooms Budget. At the conclusion of the design process, the SDC Group's recommended design and specifications may include certain equipment and specifications estimated to exceed the East Event Level Locker Rooms Budget, provided such equipment and specifications are designated to be priced as alternates.

(B) Procurement of East Event Level Locker Room Buildout. In the event the approved design and specifications for the East Event Level Locker Room Buildout cannot be procured within the East Event Level Locker Rooms

Budget, the SDC Group will evaluate value engineering options to align the design and specifications with the East Event Level Locker Rooms Budget for recommendation to the Authority and Team. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The Stadium Developer shall enter into and manage the contracts for the East Event Level Locker Room Buildout. With respect to sponsorship agreements that provide for a trade exchange in connection with the East Event Level Locker Room Buildout, the Team may procure such goods or services and such goods or services shall not be an element of the East Event Level Locker Rooms Budget. However, any proposed sponsorship trade exchange shall be coordinated with the Stadium Developer.

(C) Cost Overruns. At the sole election of either Party, the electing Party may choose to designate any design alternate or any equipment or specification recommended for deletion by the SDC Group during the value engineering process as a Design Add Alternate under **Section 8.1** hereof as if set forth on **Exhibit I-1** or **Exhibit I-2**, respectively, and the electing Party may choose to fund the procurement of the designated equipment or specification as a pre-approved Design Add Alternate consistent with the requirements of **Section 8.1** of this Agreement. Any cost overruns incurred during construction of the East Event Level Locker Room Buildout that would cause the East Event Level Locker Rooms Budget to be exceeded will be paid for by the Team except those cost overruns incurred as a direct result of the construction of a Design Add Alternate, in which case such cost overrun will be the responsibility of the Party that elected to fund the Design Add Alternate.

(D) Cost Underruns. In the event the total cost to procure the East Event Level Locker Room Buildout (exclusive of any equipment or specifications designated as a Design Add Alternate under **Section 5.1(n)(iii)(C)** above) is less than the East Event Level Locker Rooms Budget, the difference between the contracted amount and the East Event Level Locker Rooms Budget shall be allocated to the Team such that the Team will not be required to fund the amount of cost underrun or, if the Team has already funded such amount, the excess will be refunded to the Team.

(iv) East Event Level Locker Room Buildout Design Impasse. The Parties acknowledge and agree that maintaining the Master Project Schedule is essential for achieving the timely completion of the Project. In the event the SDC Group, or the Parties having received the SDC Group's recommendations, cannot reach agreement upon the design, specifications or procurement of the East Event Level Locker Room Buildout within the design and construction milestones to be established by the Parties in consultation with the Architect and Construction Manager, such impasse will be deemed a Design Impasse concerning a Critical Design Decision and either Party may provide a Notice of Design Impasse under **Section 5.4** hereof and the dispute shall be subject to Expedited ADR under **Article 13** of this Agreement.

(v) Final Design And Specifications for the East Event Level Locker Room Buildout to be Included in Final Minimum Design Standards. The Authority and Team each acknowledge that the design and procurement of the East Event Level Locker Room Buildout will not occur until after Certification of GMP and, therefore, final design and specifications for the East Event Level Locker Room Buildout will not be included in the Effective Date Minimum Design Standards established under **Section 5.1** hereof. Upon completion of the design and procurement process, the final design and specifications for the East Event Level Locker Room Buildout, as approved in writing by each of the Authority and Team, will be included in the Final Minimum Design Standards as if fully set forth on **Exhibit C-2**.

(o) Concession Equipment.

(i) Concession Equipment. The Authority and Team each acknowledge that the design and procurement of certain food service equipment, fixtures, furnishings, technology and smallwares within the Project (collectively, the "**Concession Equipment**") will not occur until after Certification of GMP and, further, that the foregoing Concession Equipment will not be included in the Construction Manager's scope of work at Certification of GMP but will be procured from and installed by other contractors or vendors unless later contracted for with the Construction Manager.

(ii) Concession Equipment Budget. The Authority and Team will establish in the Master Project Budget a line item budget amount of Twenty-Five Million Eight-Hundred Fifty Thousand Dollars (\$25,850,000) for Concession Equipment ("**Concession Equipment Budget**"). The Authority and Team each acknowledge that Two Million Six-Hundred Thousand Dollars (\$2,600,000) of the Concessions Equipment Budget will be funded by the Team as a Privately Financed Enhancement. The Authority and Team each acknowledge that this Concession Equipment Budget has been modified and allocated in separate line items consistent with the Master Project Budget as set forth in Schedule 1, including the transfer of \$175,000 from the point of sale system savings in the Food Service Equipment line item of the Master Project Budget to be applied to other costs as set forth in the February 19, 2016 SDC Group Action. In addition, the Authority and Team agree to allocate Two Hundred Thousand Dollars (\$200,000) from the point of sale system savings in the Food Service Equipment line item of the Master Project Budget to fund potential additional costs for the procurement of portable carts and smallwares in a manner consistent with the cost overrun and cost savings principles specified in the February 19, 2016 SDC Group Action. Any savings in this \$200,000 allocation realized from procurement of portable carts and smallwares will be first applied to cost overruns for the procurement of portable carts or smallwares and, if not covered by such savings or from excess sources or savings realized from other line items in the February 2016 Sources and Uses Statement attached to the February 19, 2016 SDC Group Action, then the overruns will be paid from the Owner's Contingency or from reductions to the Food Service Budget, as determined by the SDC Group. The Concession Equipment Budget will not be reduced prior to completion of final design and procurement of Concession Equipment unless agreed to by the SDC Group.

(iii) SDC Group Management of Concession Equipment Design and Procurement Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of GMP the SDC Group will continue to manage the design and procurement of the Concession Equipment (including the design and specifications, selection of contractors/vendors and approval of contract terms) and make recommendations to the Authority and Team for approval or disapproval. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The design and procurement of Concession Equipment will be subject to the following requirements:

(A) Concession Equipment Design Standard. Design and procurement of the Concession Equipment will be consistent with and comparable to NFL facilities of similar design and age considering the Concession Equipment Budget, value engineering and add alternates agreed to by the Parties, but in no case shall Owner's Contingency be reduced or the Master Project Budget exceeded without Privately Financed Enhancements to satisfy Concession Equipment design. The SDC Group will endeavor to develop a final design and specifications for the Concession Equipment within the Concession Equipment Budget. At the conclusion of the design process, the SDC Group's recommended design and specifications may include certain equipment and specifications estimated to exceed the Concession Equipment Budget, provided such equipment and specifications are designated to be priced as alternates.

(B) Procurement of Concession Equipment. In the event the approved design and specifications for the Concession Equipment cannot be procured within the Concession Equipment Budget, the SDC Group will evaluate value engineering options to align the design and specifications with the Concession Equipment Budget for recommendation to the Authority and Team. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The Stadium Developer shall enter into and manage the contracts for Concession Equipment. With respect to sponsorship agreements that provide for a trade exchange of Concession Equipment, the Team may procure such Concession Equipment and shall not be an element of the Concession Equipment Budget. However, any proposed sponsorship trade exchange shall be coordinated with the Stadium Developer.

(C) Cost Overruns. At the sole election of either Party, the electing Party may choose to designate any design alternate or any equipment or specification recommended for deletion by the SDC Group during the value engineering process as a Design Add Alternate under **Section 8.1** hereof as if set forth on **Exhibit I-1** or **Exhibit I-2**, respectively, and the electing Party may choose to fund the procurement of the designated equipment or specification as a pre-approved Design Add Alternate consistent with the requirements of **Section 8.1** of this Agreement. Any cost overruns incurred during construction or installation of the Concession Equipment that would cause the Concession Equipment Budget to be exceeded will be paid for from the Owner's Contingency

except those cost overruns incurred as a direct result of the construction or installation of a Design Add Alternate, in which case such cost overrun will be the responsibility of the Party that elected to fund the Design Add Alternate.

(D) Cost Underruns. In the event the total cost to procure the Concession Equipment (exclusive of any equipment or specifications designated as a Design Add Alternate under Section 5.1(o)(iii)(C) above) is less than the Concession Equipment Budget, the difference between the contracted amount and the Concessions Equipment Budget will be applied first to cover any cost overruns in connection with the specific items identified in Exhibit V and then any excess shall be transferred to the Owner's Contingency pursuant to Section 8.1(b)(i)(B).

(iv) Concession Equipment Design Impasse. The Parties acknowledge and agree that maintaining the Master Project Schedule is essential for achieving the timely completion of the Project. In the event the SDC Group, or the Parties having received the SDC Group's recommendations, cannot reach agreement upon the design, specifications or procurement of the Concession Equipment within the design and construction milestones to be established by the Parties in consultation with the Architect and Construction Manager, such impasse will be deemed a Design Impasse concerning a Critical Design Decision and either Party may provide a Notice of Design Impasse under Section 5.4 hereof and the dispute shall be subject to Expedited ADR under Article 13 of this Agreement.

(v) Final Design And Specifications for Concession Equipment to be Included in Final Minimum Design Standards. The Authority and Team each acknowledge that the design and procurement of Concession Equipment will not occur until after Certification of GMP and, therefore, final design and specifications for Concession Equipment will not be included in the Effective Date Minimum Design Standards established under Section 5.1 hereof. Upon completion of the design and procurement process, the final design and specifications for the Concession Equipment, as approved in writing by each of the Authority and Team, will be included in the Final Minimum Design Standards as if fully set forth on Exhibit C-2.

(p) Stadium Plaza Design.

(i) Stadium Plaza Improvements. The Authority and Team each acknowledge that the complete design and procurement of improvements to the Stadium Plaza, including Stadium Plaza lighting and technology (collectively, the "**Stadium Plaza Improvements**"), will not occur until after Certification of GMP and, further, that the comprehensive scope of improvements to the Stadium Plaza will not be included in the Construction Manager's scope of work at Certification of GMP but, rather, that some portion of such scope of work will be procured from and installed by other contractors or vendors unless later contracted for with the Construction Manager.

(ii) Stadium Plaza Improvements Budget. The Authority and Team acknowledge that the sum of Nine Million Nine Hundred Seventy Five Thousand Dollars (\$9,975,000) is established as the budget for Stadium Plaza Improvements, including Stadium Plaza lighting and technology ("**Stadium Plaza Improvements Budget**"), but excluding specific elements to be agreed to by the Team and the Authority, which elements will include the Vikings ship, sponsorship signage beyond the existing budgeted amount in the Master Project Budget or the Metropolitan Council pedestrian bridge as exclusions. The Authority and Team each acknowledge that Two Million Dollars (\$2,000,000) of the Stadium Plaza Improvements Budget will be funded by the Team as a Privately Financed Enhancement. The Stadium Plaza Improvements Budget will not be increased or reduced prior to the Commencement Date unless agreed to by the SDC Group; **provided, however**, that if the Authority or Team are unable to secure use rights through a lease to a mutually-approved portion of the real property bordered by South 5<sup>th</sup> Street, South 6<sup>th</sup> Street, Chicago Avenue South and Park Avenue South, all in Minneapolis, Minnesota (the "**Hennepin County Medical Examiner Parcel**"), then the Stadium Plaza Improvements Budget will be automatically reduced by Two Million Dollars (\$2,000,000) without further action of either party and the Team shall have no obligation to fund such Two Million Dollars (\$2,000,000) as a Privately Financed Enhancement; and, **provided, further**, that if the Authority and Team agree to acquire fee title or other ownership interest to all or a mutually-approved portion of the Hennepin County Medical Examiner Parcel, the cost of acquisition and improvements to that parcel will be shared equally.

One Million Six Hundred Seventy Five Thousand Dollars (\$1,675,000) of the Stadium Plaza Improvements Budget shall be prioritized to fund improvements to the area described as "ADD ALT. C" as set forth on **Exhibit X** (Plaza Area Depiction of Areas and Priorities) and reasonable distributed power (A) on the Plaza west of Chicago Avenue (excluding any power related to the Vikings ship, the Plaza east of Chicago Avenue and the Metropolitan Council pedestrian bridge) for providing power to the temporary tents related to event-day needs for Team games and Authority events consistent with that certain Ground Lease, dated as of November 20, 2015, by and between Hennepin County and the Authority, a memorandum of which is recorded with the Hennepin County Office of the Registrar of Titles, as document number T05321892. and (B) future reasonable distributed power requirements on the Plaza west of Chicago Avenue as depicted on **Exhibit X**. To the extent that the power requirements referenced in (A) and (B) immediately preceding have a cost exceeding Three Hundred Thousand Dollars (\$300,000), the Team will be responsible for all costs related to item (B) in excess of Three Hundred Thousand Dollars (\$300,000) if item (B) is the cause of the costs exceeding Three Hundred Thousand Dollars (\$300,000), or the Team may elect not to go forward with construction. The second priority within the \$1,675,000 of the Stadium Plaza Improvements Budget will be the areas described as "ADD ALT. D" and "ADD ALT. E" (as set forth on **Exhibit X**), the concessions stand, and Chicago Avenue street improvement area described as "ADD ALT. B" (as depicted on **Exhibit X** hereto). Any Cost Savings within the Stadium Plaza Improvements Budget will be used for other Plaza improvements as determined by the SDC Group.

(iii) SDC Group Management of Stadium Plaza Improvements Design and Procurement Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of GMP the SDC Group will continue to manage the design and procurement of the Stadium Plaza Improvements (including the design and specifications, selection of contractors/vendors and approval of contract terms) and make recommendations to the Authority and Team for approval or disapproval. The Authority and Team acknowledge and agree that design services for the Stadium Plaza Improvements may be provided by a vendor other than the Architect currently under contract in the Design Services Agreement. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The design and procurement of Stadium Plaza Improvements will be subject to the following requirements:

(A) Stadium Plaza Improvements Design Standard. Design and procurement of the Stadium Plaza Improvements will be consistent with and comparable to NFL facilities of similar design and age considering the Stadium Plaza Improvements Budget, value engineering and add alternates agreed to by the Parties, but in no case shall Owner's Contingency be reduced or the Master Project Budget exceeded without Privately Financed Enhancements to satisfy Stadium Plaza Improvements design. The SDC Group will endeavor to develop a final design and specifications for the Stadium Plaza Improvements within the Stadium Plaza Improvements Budget. For purposes of this **Section 5.1(p)**, the design of the Stadium Plaza will encompass, at a minimum, (x) the real property lying to the east of Chicago Avenue and located within the boundaries of the Stadium Site; (y) the real property bordered by South 4th Street, South 5th Street, Chicago Avenue South and Park Avenue South, all in Minneapolis, Minnesota (the "**Downtown East Parcel**"); and (z) that portion of the Hennepin County Medical Examiner Parcel for which the Authority or Team acquired mutually-approved title or use rights (collectively, the "**Stadium Plaza Design Area**") as generally depicted in attached **Exhibit W**. At the conclusion of the design process, the SDC Group's recommended design and specifications may include certain equipment and specifications estimated to exceed the Stadium Plaza Improvement Budget, provided such equipment and specifications are designated to be priced as alternates.

(B) Procurement of Stadium Plaza Improvements. In the event the approved design and specifications for the Stadium Plaza Improvements cannot be procured within the Stadium Plaza Improvements Budget, the SDC Group will evaluate value engineering options to align the design and specifications with the Stadium Plaza Improvements Budget for recommendation to the Authority and Team. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The Stadium Developer shall enter into and manage the contracts for the Stadium Plaza Improvements. With respect to sponsorship agreements that provide for a trade exchange of Stadium Plaza Improvements, the Team may procure such Stadium Plaza Improvements and shall not be an element of the Stadium Plaza

Improvements Budget. However, any proposed sponsorship trade exchange shall be coordinated with the Stadium Developer.

(C) Cost Overruns. At the sole election of either Party, the electing Party may choose to designate any design alternate or any equipment or specification recommended for deletion by the SDC Group during the value engineering process as a Design Add Alternate under **Section 8.1** hereof as if set forth on **Exhibit I-1** or **Exhibit I-2**, respectively, and the electing Party may choose to fund the procurement of the designated equipment or specification as a pre-approved Design Add Alternate consistent with the requirements of **Section 8.1** of this Agreement. Any cost overruns incurred during construction or installation of the Stadium Plaza Improvements that would cause the Stadium Plaza Improvements Budget to be exceeded will be paid for from the Owner's Contingency except those cost overruns incurred as a direct result of the construction or installation of a Design Add Alternate, in which case such cost overrun will be the responsibility of the Party that elected to fund the Design Add Alternate.

(D) Cost Underruns. In the event the total cost to procure the Stadium Plaza Improvements (exclusive of any equipment or specifications designated as a Design Add Alternate under **Section 5.1(p)(iii)(C)** above) is less than the Stadium Plaza Improvements Budget, the difference between the contracted amount and the Stadium Plaza Improvements Budget shall be transferred to the Owner's Contingency pursuant to **Section 8.1(b)(i)(B)**.

(iv) Stadium Plaza Improvements Design Impasse. The Parties acknowledge and agree that maintaining the Master Project Schedule is essential for achieving the timely completion of the Project. In the event the SDC Group, or the Parties having received the SDC Group's recommendations, cannot reach agreement upon the design, specifications or procurement of the Stadium Plaza Improvements within the design and construction milestones to be established by the Parties in consultation with the Architect and Construction Manager, such impasse will be deemed a Design Impasse concerning a Critical Design Decision and either Party may provide a Notice of Design Impasse under **Section 5.4** hereof and the dispute shall be subject to Expedited ADR under **Article 13** of this Agreement.

(v) Final Design And Specifications for Stadium Plaza Improvements to be Included in Final Minimum Design Standards. The Authority and Team each acknowledge that the design and procurement of Stadium Plaza Improvements will not occur until after Certification of GMP and, therefore, final design and specifications for Stadium Plaza Improvements will not be included in the Effective Date Minimum Design Standards established under **Section 5.1** hereof. Upon completion of the design and procurement process, the final design and specifications for the Stadium Plaza Improvements, as approved in writing by each of the Authority and Team, will be included in the Final Minimum Design Standards as if fully set forth on **Exhibit C-2**.



(q) Commemorative Bricks.

(i) Commemorative Bricks. The Authority and Team each acknowledge that the Act provides that the Authority shall sell commemorative bricks to be displayed at a prominent location at the Stadium for an amount to be determined by the Authority ("**Commemorative Bricks**").

(ii) Commemorative Bricks Budget and Sale Proceeds. All costs for the design and installation of the Commemorative Bricks and display area will be funded from proceeds of the sale of such Commemorative Bricks. The first One Million Three-Hundred Thousand Dollars (\$1,300,000) of net proceeds from the sale of Commemorative Bricks will be applied to Project Costs for Stadium Plaza Improvements. Any net proceeds from the sale of Commemorative Bricks in excess of One Million Three-Hundred Thousand Dollars (\$1,300,000) will be allocated to the Stadium Plaza Improvements Budget pursuant to Section 5.1(p) hereof but in no event shall net proceeds from the sale of Commemorative Bricks be used for anything other than improvements to the Stadium Plaza.

(iii) SDC Group Management of Commemorative Bricks Design and Procurement Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of GMP the SDC Group will continue to manage the design and procurement of the Commemorative Bricks and display area (including the design and specifications, selection of contractors/vendors and approval of contract terms) and make recommendations to the Authority and Team for approval or disapproval. The Authority and Team will work collaboratively to locate the Commemorative Bricks display area near the Viking ship to be located on the Stadium Plaza. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team.

(r) WiFi Communications System.

(i) WiFi. The Authority and Team each acknowledge that the design and procurement of a WiFi Communications System (the "**WiFi Communications System**") within the Project will not occur until after Certification of GMP and, further, that the foregoing WiFi Communications System will not be included in the Construction Manager's scope of work at Certification of GMP but will be procured from and installed by other contractors or vendors unless later contracted for with the Construction Manager.

(ii) WiFi Budget. The Authority and Team acknowledge that the sum of Four Million Seven Hundred Fifty Five Thousand Dollars (\$4,755,000) is established as the budget for the initial installation and activation of the WiFi Communications System ("**WiFi Budget**"). The Team will fund the initial design, installation and activation of the WiFi Communications System as a Privately Financed Enhancement. The WiFi Budget will not be reduced or increased prior to completion of final design and procurement of the WiFi Communications System unless agreed to by the SDC Group.

(iii) SDC Group Management of WiFi Design and Procurement Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of GMP the SDC Group will continue to manage the design and procurement of the WiFi Communications System (including the design and specifications, selection of contractors/vendors and approval of contract terms) and make recommendations to the Authority and Team for approval or disapproval. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The design and procurement of the WiFi Communications System will be subject to the following requirements:

(A) WiFi Design Standard. Design and procurement of the WiFi Communications System will be consistent with and comparable to NFL facilities of similar design and age considering the WiFi Budget, value engineering and add alternates agreed to by the Parties, but in no case shall Owner's Contingency be reduced or the Master Project Budget exceeded without Privately Financed Enhancements to satisfy WiFi design. The SDC Group will endeavor to develop a final design and specifications for the WiFi Communications System within the WiFi Budget. At the conclusion of the design process, the SDC Group's recommended design and specifications may include certain equipment and specifications estimated to exceed the WiFi Budget, provided such equipment and specifications are designated to be priced as alternates.

(B) Procurement of WiFi. In the event the approved design and specifications for the WiFi Communications System cannot be procured within the WiFi Budget, the SDC Group will evaluate value engineering options to align the design and specifications with the WiFi Budget for recommendation to the Authority and Team. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and Team. The Stadium Developer shall enter into and manage the contract(s) for the WiFi Communications System. With respect to sponsorship agreements that provide for a trade exchange in connection with the WiFi Communications System, the Team may procure such goods or services and such goods or services shall not be an element of the WiFi Budget. However, any proposed sponsorship trade exchange shall be coordinated with the Stadium Developer.

(C) Cost Overruns. At the sole election of either Party, the electing Party may choose to designate any design alternate or any equipment or specification recommended for deletion by the SDC Group during the value engineering process as a Design Add Alternate under **Section 8.1** hereof as if set forth on **Exhibit I-1** or **Exhibit I-2**, respectively, and the electing Party may choose to fund the procurement of the designated equipment or specification as a pre-approved Design Add Alternate consistent with the requirements of **Section 8.1** of this Agreement. Any cost overruns incurred during initial installation and activation of the WiFi Communications System that would cause the WiFi Budget to be exceeded will be paid for by the Team except those cost overruns incurred as a direct result of the construction of a Design Add Alternate,

in which case such cost overrun will be the responsibility of the Party that elected to fund the Design Add Alternate.

(D) Cost Underruns. In the event the total cost to procure the WiFi Communications System (exclusive of any equipment or specifications designated as a Design Add Alternate under Section 5.1(r)(iii)(C) above) is less than the WiFi Budget, the difference between the contracted amount and the WiFi Budget shall be allocated to the Team such that the Team will not be required to fund the amount of such cost underrun or, if the Team has already funded such amount, the excess will be refunded to the Team.

(iv) WiFi Design Impasse. The Parties acknowledge and agree that maintaining the Master Project Schedule is essential for achieving the timely completion of the Project. In the event the SDC Group, or the Parties having received the SDC Group's recommendations, cannot reach agreement upon the design, specifications or procurement of the WiFi Communications System within the design and construction milestones to be established by the Parties in consultation with the Architect and Construction Manager, such impasse will be deemed a Design Impasse concerning a Critical Design Decision and either Party may provide a Notice of Design Impasse under Section 5.4 hereof and the dispute shall be subject to Expedited ADR under Article 13 of this Agreement.

(v) Final Design And Specifications for WiFi Communications System to be Included in Final Minimum Design Standards. The Authority and Team each acknowledge that the design and procurement of the WiFi Communications System will not occur until after Certification of GMP and, therefore, final design and specifications for the WiFi Communications System will not be included in the Effective Date Minimum Design Standards established under Section 5.1 hereof. Upon completion of the design and procurement process, the final design and specifications for the WiFi Communications System, as approved in writing by each of the Authority and Team, will be included in the Final Minimum Design Standards as if fully set forth on Exhibit C-2.

(s) Additional Team Allocated Spaces. The Authority and Team mutually desire to relocate certain spaces depicted in the Stadium design as of February 13, 2015. To implement such desired relocations (x) the Team will relocate its designated office space to an off-site location; (y) the Authority will relocate a portion of its designated office space to the location of the Team's previously designated offices; and (z) the Team will be allocated a minimum of 4,000 square feet of additional Team Allocated Spaces (as that term is defined in the Stadium Use Agreement) adjacent to the Team Restaurant as depicted on Exhibit M (Team Allocated Spaces) to the Stadium Use Agreement and as mutually agreed to by the Authority and Team. In consideration for the relocation of Team and Authority office space and the designation of additional Team Allocated Spaces in this Section 5.1(s), and in further consideration of the designation of approximately 2,500 square feet of the East Event Level Locker Room Buildout space (designated as "Multipurpose" space on Exhibit U) for exclusive Team use as set forth in Section 5.1(n) hereof, the Team will fund, as a Privately Financed Enhancement, an additional Three Million Five Hundred Thousand Dollars (\$3,500,000) of mutually-approved Project Costs as set forth on Exhibit V; provided, however, that if the Team is not awarded an MLS soccer

franchise to operate a Team-Owned MLS Franchise (as that term is defined in the Stadium Use Agreement), or if such award is delayed, the Authority will refund One Million Five Hundred Thousand Dollars (\$1,500,000) to the Team within sixty (60) days of the Team providing written notice to the Authority of its request for such refund but in no case earlier than February 1, 2018; and, **provided, further,** that upon the Team's delivery of such written notice of request for refund to the Authority, the Team will relinquish any and all rights to the exclusive use of approximately 2,500 square feet of the East Event Level Locker Room Buildout space (designated as "Multipurpose" space on **Exhibit U**) as contemplated in **Section 5.1(n)** hereof. In the event the Team provides notice and request for refund under this **Section 5.1(s)** the approximately 2,500 square feet of the East Event Level Locker Room Buildout space (designated as "Multipurpose" space on **Exhibit U**) will then be built-out as shared space consistent with the design recommended by the SDC Group and approved by the Authority and Team under **Section 5.1(n)** of this Agreement; **provided, however,** if the Team subsequently is awarded an MLS Soccer Franchise to operate a Team-Owned MLS Franchise pursuant to Section 3.8 of the Stadium Use Agreement and the Team provides notice to the Authority of the Team's desire to have exclusive use of approximately 2,500 square feet of the East Event Level Locker Room Buildout space (designated as "Multipurpose" space on **Exhibit U**), the Team will reimburse for such refund.

(t) **House Reduction Curtains.** The Authority acknowledges and agrees that the Team may elect to have an optional house reduction system installed in the Stadium, including various curtains and coverings as conceptually depicted in Exhibit G-1 of the Stadium Use Agreement (collectively, the "House Reduction Curtains" as that term is defined in the Stadium Use Agreement) to be paid for by the Team as a Privately Financed Enhancement if the Team elects, in its sole discretion, to proceed with the installation of such optional House Reduction Curtains. The conditions upon which the Team may elect to have the House Reduction Curtains installed in the Stadium are as follows: (i) the SDC Group will continue to review design and specification options for recommendation to the Authority and Team; and (ii) the final design and specifications for the House Reduction Curtains must be approved in writing by both the Authority and Team. The Parties acknowledge and agree that maintaining the Master Project Schedule is essential for achieving the timely completion of the Project. In the event the SDC Group, or the Parties having received the SDC Group's recommendations, cannot reach agreement upon the design, specifications or procurement of the House Reduction Curtains within the design and construction milestones to be established by the Parties in consultation with the Architect and Construction Manager, such impasse will be deemed a Design Impasse concerning a Critical Design Decision and either Party may provide a Notice of Design Impasse under **Section 5.4** hereof and the dispute shall be subject to Expedited ADR under **Article 13** of this Agreement.

(u) **NFL Broadcast Requirements.**

(i) **NFL Broadcast Requirements.** The Authority and the Team each acknowledge that the Stadium will conform to certain NFL broadcast requirements as such requirements exist as of the date of this Agreement as specifically set forth in a request for proposals for Broadcast Infrastructure, dated December 1, 2015 and shall be determined pursuant to that request for proposals, including all addenda thereto, HKS

Architect ASR 124 for associated work and CCD 340 (the “**NFL Broadcast Requirements**”). If the proposals received in response to the request for proposals do not exceed the NFL Broadcast Requirements Budget, the scope of work for the NFL Broadcast Requirements will be completed as designed. If the proposals received for the NFL Broadcast Requirements work exceed the NFL Broadcast Requirements Budget, then the scope of work for the NFL Broadcast Requirements will be determined by the SDC Group. The NFL Broadcast Requirements within the Project will not occur until after Certification of GMP, but will be funded as part of the Project and may be included in the Construction Manager’s scope of work subsequent to such certification. Construction work for the NFL Broadcast Requirements shall be completed either by the Construction Manager or by other contractors or vendors mutually agreed-upon by the Authority and the Team.

(ii) NFL Broadcast Requirements Budget. The Authority and the Team acknowledge that the sum of One Million One Hundred Thousand Dollars (\$1,100,000) is established as the budget for the initial installation and activation of the NFL Broadcast Requirements (the “**NFL Broadcast Requirements Budget**”). The Authority and the Team acknowledge and agree that the NFL Broadcast Requirements Budget and Radio and Television Cabling Requirements Budget will be combined for purposes of procuring the scopes of work for the NFL Broadcast Requirements and Radio and Television Cabling Requirements. The net savings realized within the combined NFL Broadcast Requirements Budget and Radio and Television Cabling Requirements Budget will be dedicated solely to fund costs, if any, to (A) de-watering/flooding issues, (B) ETFE roof snow shedding/ice damming, and (C) the Stadium exterior/gutter issues, with priority of the use of such funds determined by the SDC Group. If remaining savings realized within the combined NFL Broadcast Requirements Budget and Radio and Television Cabling Requirements Budget exist after funding costs related to (A), (B), and (C) above, the remaining funds will be split equally (50/50) between the Authority and the Team to be used for (x) Authority-selected Project costs or to fund Owner’s Contingency (but not to be used for Authority reserves), and (y) Team-selected Project costs, respectively. The NFL Broadcast Requirements Budget will not be reduced or increased at any time unless agreed to by the SDC Group.

(iii) SDC Group Management of the NFL Broadcast Requirements Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, the following Certification of the GMP, the SDC Group will manage the design and procurement of the NFL Broadcast Requirements (including the design and specifications, selection of contractors/vendors and approval of contract terms) but only to the extent that the NFL Broadcast Requirements Budget is not exceeded, unless agreed to by the SDC Group and done so in a manner consistent with the cost overrun and cost savings principles specified in the February 19, 2016 SDC Group Action and make recommendations to the Authority and the Team for approval or disapproval. The Final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and the Team.

(v) Radio and Television Cabling Requirements.

(i) Radio and Television Cabling Requirements. The Authority and the Team each acknowledge that the Stadium will conform to certain radio and television cabling requirements as such requirements exist as of the date of this Agreement as specifically set forth in a request for proposals for Broadcast Infrastructure, dated December 1, 2015, and shall be determined pursuant to that request for proposals, including all addenda thereto, and CCD 329 (the “**Radio and Television Cabling Requirements**”). If the proposals received in response to the request for proposals do not exceed the Radio and Television Cabling Requirements Budget, then the scope of work for the Radio and Television Cabling Requirements will be completed as designed. If the proposals for the Radio and Television Cabling Requirements work exceed the Radio and Television Cabling Requirements Budget, then the scope of work for the Radio and Television Cabling Requirements will be determined by the SDC Group. The Radio and Television Cabling Requirements within the Project will not occur until after Certification of GMP, but will be funded as part of the Project and may be included in the Construction Manager’s scope of work subsequent to such certification. Construction work for the Radio and Television Cabling Requirements shall be completed either by the Construction Manager or by other contractors or vendors mutually agreed-upon by the Authority and the Team.

(ii) Radio and Television Cabling Requirements Budget. The Authority and the Team acknowledge that the sum of One Million One Hundred Thousand Dollars (\$1,100,000) is established as the budget for the initial installation and activation of the Radio and Television Cabling Requirements (the “**Radio and Television Cabling Requirements Budget**”). The Authority and the Team acknowledge and agree that the NFL Broadcast Requirements Budget and Radio and Television Cabling Requirements Budget will be combined for purposes of procuring the scopes of work for the NFL Broadcast Requirements and Radio and Television Cabling Requirements. The net savings realized within the combined NFL Broadcast Requirements Budget and Radio and Television Cabling Requirements Budget will be dedicated solely to fund costs, if any, to (A) de-watering/flooding issues, (B) ETFE roof snow shedding/ice damming, and (C) the Stadium exterior/gutter issues, with priority of the use of such funds determined by the SDC Group. If remaining savings realized within the combined NFL Broadcast Requirements Budget and Radio and Television Cabling Requirements Budget exist after funding costs related to (A), (B), and (C) above, the remaining funds will be split equally (50/50) between the Authority and the Team to be used for (x) Authority-selected Project costs or to fund Owner’s Contingency (but not to be used for Authority reserves), and (y) Team-selected Project costs, respectively. The Radio and Television Cabling Requirements Budget will not be reduced or increased at any time unless agreed to by the SDC Group.

(iii) SDC Group Management of the Radio and Television Cabling Requirements Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of the GMP, the SDC Group will manage the design and procurement of the Radio and Television Cabling Requirements (including

the design and specifications, selection of contractors/vendors and approval of contract terms) but only to the extent that the Radio and Television Cabling Requirements Budget is not exceeded, unless agreed to by the SDC Group and done so in a manner consistent with the cost overrun and cost savings principles specified in the February 19, 2016 SDC Group Action and make recommendations to the Authority and the Team for approval or disapproval. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and the Team.

(w) Magnetometer (FF&E) Acquisition.

(i) Magnetometer Acquisition Requirements. The Authority and the Team each acknowledge that the Authority has issued a request for proposals, dated February 8, 2016 (the “**Magnetometer RFP**”) for the acquisition of magnetometers for the Stadium. The magnetometers and associated equipment will conform to the standards established in the Magnetometer RFP. The magnetometer acquisition within the Project will not occur until after Certification of GMP, but will be funded as part of the Project.

(ii) Magnetometer Budget. The Authority and the Team acknowledge that the sum of Six Hundred and Fifty Thousand Dollars (\$650,000) is established as the budget for the acquisition of the magnetometers (the “**Magnetometer Acquisition Budget**”). The Magnetometer Acquisition Budget will not be reduced or increased prior to final design (i.e., establishment of specifications) and procurement of the magnetometers unless agreed to by the SDC Group. With respect to the Magnetometer Acquisition Budget (e.g., fixtures, products, equipment and labor), the Team may procure such components directly, and such components shall not be an element of the Magnetometer Acquisition Budget. Any such acquisition shall be subject to approval by the Stadium Developer, including cancellation by the Stadium Developer of any corresponding RFPs or rejection of any proposals and funding by the Team of the amounts in the Magnetometer Acquisition Budget as a Privately Financed Enhancement.

(iii) SDC Group Management of the Magnetometer Acquisition Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of the GMP, the SDC Group will manage the design and procurement of the magnetometer acquisition (including the design and specifications, selection of contractors/vendors and approval of contract terms) but only to the extent that the Magnetometer Acquisition Budget is not exceeded, unless agreed to by the SDC Group and done so in a manner consistent with the cost overrun and cost savings principles specified in the February 19, 2016 SDC Group Action and make recommendations to the Authority and the Team for approval or disapproval. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and the Team.

(x) Catwalk Netting.

(i) Catwalk Netting Requirements. The Authority will issue a request for proposals for the materials and installation for catwalk netting, with and for mutually agreed-upon areas of the Stadium. The catwalk netting design and associated installation,

equipment, materials, and supplies will conform to the standards established by the SDC Group in the request for proposals. The catwalk netting acquisition and installation work within the Project will not occur until after Certification of GMP, but will be funded as part of the Project. Design and installation work for the Catwalk Netting shall be completed either by the Construction Manager or by other designers, contractors or vendors mutually agreed-upon by the Authority and the Team.

(ii) Catwalk Netting Budget. The Authority and the Team acknowledge that the sum of Two Hundred and Fifty Thousand Dollars (\$250,000) is established as the budget for the acquisition and installation of catwalk netting in the Stadium (the “**Catwalk Netting Budget**”). The Catwalk Netting Budget will not be reduced or increased at any time unless agreed to by the SDC Group.

(iii) SDC Group Management of the Catwalk Netting Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of the GMP, the SDC Group will manage the design, procurement, and installation of the catwalk netting (including the design and specifications, selection of contractors/vendors and approval of contract terms) but only to the extent that the Catwalk Netting Budget is not exceeded, unless agreed to by the SDC Group and done so in a manner consistent with the cost overrun and cost savings principles specified in the February 19, 2016 SDC Group Action and make recommendations to the Authority and the Team for approval or disapproval. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and the Team.

(y) Field Turf Selection and Acquisition.

(i) Field Turf Selection and Acquisition Requirements. The Authority and the Team each acknowledge that the Parties have jointly selected turf Option 2 consistent with Schedule 4 to the Authority’s request for proposals issued on December 12, 2015. The Authority has issued a request for proposals as set forth above for the materials and installation for the field turf. The field turf selection and associated equipment and supplies will conform to the standards established by the Team and the Authority in the request for proposals. The field turf acquisition and installation work within the Project will not occur until after Certification of GMP, but will be funded as part of the Project. The field turf supply and installation shall be completed either by the Construction Manager or by other contractors or vendors mutually agreed-upon by the Authority and the Team.

(ii) Field Turf Budget. The Authority and the Team acknowledge that the sum of One Million Five Hundred Eleven Thousand Eight Hundred and Twenty Six Dollars (\$1,511,826) is established as the budget for the acquisition and installation of the field turf system for the Stadium (the “**Field Turf Budget**”). Any cost of the field turf for the Stadium that exceeds the Field Turf Budget is to be funded from (A) excess sources or savings realized from other line items in the February 2016 Sources and Uses Statement attached to the February 19, 2016 SDC Group Action as determined by the SDC Group, or (B) fifty percent (50%) from Owner Contingency and fifty percent (50%)



by the Team as a Privately Financed Enhancement if no such excess sources or savings are available. The Field Turf Budget will not be reduced or increased at any time unless agreed to by the SDC Group.

(iii) SDC Group Management of the Field Turf Acquisition and Installation Following Certification of GMP. Notwithstanding anything to the contrary in this Agreement, following Certification of the GMP, the SDC Group will manage the design, procurement, and installation of the field turf procurement and installation (including the design and specifications, selection of contractors/vendors and approval of contract terms) but only to the extent that the Field Turf Budget is not exceeded, unless agreed to by the SDC Group and done so in a manner consistent with the cost overrun and cost savings principles specified in the February 19, 2016 SDC Group Action and make recommendations to the Authority and the Team for approval or disapproval. The final design and procurement recommendations of the SDC Group must be approved in writing by both the Authority and the Team.

Section 5.2 Design Documents.

(a) Design Meetings.

(i) Members of the SDC Group, the Parties' designated representatives, consultants, or others as the Parties may designate, may attend meetings with the Design Team or portions thereof for the purpose of the Design Team developing the design during the preconstruction and Construction Phases and creating the design documents referenced in the Design Services Agreement ("**Design Meetings**"). Each Authorized Representative and each Party shall receive notice of all such meetings. Prior to the Certification of GMP, Critical Design Decisions in the preconstruction and Construction Phases shall only be made by the SDC Group, and such decisions shall be reflected in SDC Group minutes or other approved written actions of the SDC Group. Following the Certification of GMP, the SDC Group shall approve or disapprove any amendments to the Final Minimum Design Standards requiring any SDC Group decision under **Section 2.2(f)**, and such decisions shall be reflected in SDC Group minutes or other approved written actions of the SDC Group. Any recommendation of the SDC Group regarding an amendment to the Final Minimum Design Standards after Certification of GMP is subject to the written approval of both the Authority and the Team.

(ii) Prior to Certification of GMP, the Parties acknowledge and agree that design direction and decisions will only be made by the SDC Group, and such decisions shall be reflected in SDC Group minutes or other written actions of the SDC Group. The voting representative of each of the Parties' Authorized Representatives shall attend the Design Meetings.

(iii) Prior to Certification of GMP, if the SDC Group is unable to reach a design decision with respect to a Critical Design Decision discussed at a Design Meeting, the voting Authorized Representative of each Party shall within two (2) Business Days after the applicable Design Meeting provide written notice to the other voting Authorized Representatives of the Critical Design Decision that was not reached, the specific nature

of the dispute regarding the Critical Design Decision, and the position of the voting Authorized Representative with respect to the Critical Design Decision.

(iv) Prior to Certification of GMP, after timely notices of the dispute have been sent by each of the Parties' voting Authorized Representatives with respect to the disputed Critical Design Decision issue(s), the voting Authorized Representatives shall promptly attempt to achieve resolution of the disputed Critical Design Decision issue(s) by no later than the next SDC Group meeting. Failure to achieve resolution by the end of the next SDC Group meeting shall result in a Design Impasse on the unresolved Critical Design Decision issue(s) in question and shall be deemed subject to a Notice of Design Impasse for an Expedited ADR Dispute pursuant to **Section 5.4** and **Article 13**.

(v) All design decisions that are made by the SDC Group in Design Meetings shall be memorialized in minutes of the meeting prepared by either the Project Representative or the Architect (as designated by the SDC Group) and distributed to the Authorized Representatives within three (3) Business Days after the Design Meeting for review and approval by the Authorized Representatives at the next Design Meeting.

(b) Conceptual Design. The SDC Group previously reviewed the Conceptual Design Documents prepared and delivered by the Architect and provided timely review and input to the Conceptual Design Documents in accordance with the Design Delivery Schedule.

(c) Schematic Design. The SDC Group previously reviewed the Schematic Design Documents prepared and delivered by the Architect and provided timely review and input to the Schematic Design Documents in accordance with the Design Delivery Schedule.

(d) Design Development Documents. As a condition of execution of the Construction Manager's Construction Management Plan, the SDC Group must agree that the Design Development Documents, as qualified and amended within the GMP, comply with the Final Minimum Design Standards. Prior to Certification of GMP, the SDC Group shall reach agreement upon and approve Critical Design Decisions for the Design Development Documents within the timeframe set forth in the Task List and Design Delivery Schedule, or as otherwise determined by the SDC Group. Prior to the Certification of GMP, the Parties acknowledge and agree that the Design Development Documents may be subject to further value engineering and design/budgetary changes due to decisions of the SDC Group.

(e) Construction Manager to Provide Detailed Estimates. As required by the Construction Services Agreement, the Construction Manager shall provide a detailed estimate of the cost of construction of the Stadium and Stadium Infrastructure based upon the documents delivered to the SDC Group. The Construction Manager shall meet with the SDC Group as reasonably requested to provide information regarding the estimate and value engineering proposals.

### Section 5.3 Timing of Critical Design Decisions.

Prior to the Certification of GMP, pursuant to the Design Services Agreement, the Parties will jointly work with the Architect and Construction Manager to maintain the Design Delivery

Schedule and the Master Project Budget and to develop and maintain a construction schedule and the Master Project Schedule. The Architect, Construction Manager and/or Project Representative shall regularly update a task list (the “**Task List**”) which identifies critical design decisions necessary to maintain the Design Delivery Schedule, construction schedule and Master Project Schedule, and decisions with respect to the Effective Date Minimum Design Standards, the Preliminary Project Budget or the Master Project Budget (“**Critical Design Decisions**”) necessary for the design and construction of the Project to stay current with the Design Delivery Schedule, construction schedule and Master Project Schedule. The Parties acknowledge and agree that maintaining the Design Delivery Schedule, construction schedule and Master Project Schedule is essential for achieving the timely completion of the design, commencement of construction, and the completion of the Project within the Master Project Budget. The purpose of the Task List is to provide the timing and deadlines established by the Architect, Construction Manager and the Project Representatives for the Parties to make Critical Design Decisions so that the Parties and Architect, Construction Manager and Project Representative can adhere to the Design Delivery Schedule, construction schedule, the Master Project Schedule, and the Master Project Budget.

Section 5.4 Notice of Design Impasse.

Prior to Certification of GMP, if the SDC Group cannot reach agreement upon and approve a Critical Design Decisions matter as set forth in **Section 5.3** above, then such failure to reach agreement shall be a design impasse (“**Design Impasse**”) and either Party may provide a Notice of Design Impasse and such disagreement shall be deemed an Expedited ADR Dispute pursuant to **Article 13**.

Section 5.5 Notice of Issue with Final Minimum Design Standards.

If the Team has an objection with respect to a claimed deviation from the Final Minimum Design Standards and desires to raise its objection to a dispute under this Agreement, the Team may do so by timely asserting its objection pursuant to **Section 2.2(h)** and seeking remedies pursuant to the Expedited ADR procedures set forth in **Article 13**, and each Party agrees that the decision rendered by the Neutral shall be binding upon the Parties.

Section 5.6 City of Minneapolis Stadium Implementation Committee.

(a) Alternative Process. In order to accomplish the objectives of the Act within the required time frame, the Act established an alternative process for municipal land use and development review codified at Minnesota Statutes section 473J.17, subd. 6.

(b) Minneapolis City Council Approval of Stadium Implementation Committee Recommendations. Consistent with the procedures set forth in the Act, the City of Minneapolis Stadium Implementation Committee (“**Stadium Implementation Committee**”) issued its final recommendations in a report dated July 25, 2013. The recommendations of the Stadium Implementation Committee were then forwarded to the City of Minneapolis Planning Commission for an advisory recommendation, which was issued August 12, 2013. The Minneapolis City Council approved and adopted the final recommendations of the Stadium Implementation Committee and Minneapolis Planning Commission on August 30, 2013, subject

to the inclusion of two (2) additional recommendations as set forth in the Minneapolis City Council agenda attached hereto as **Exhibit E**. As set forth in the Minneapolis City Council's approval and adoption of the Stadium Implementation Committee's and Minneapolis Planning Commission's final recommendations, several land use and development approvals were deferred and delegated to various City of Minneapolis departments for further review and approval or denial upon submission of supplemental information from the Authority and Team. As of the Effective Date, the City of Minneapolis will not have taken final action on these various land use and development approvals. Accordingly, the Parties shall continue to work collaboratively to finalize and submit to the City of Minneapolis such supplemental information as may be required to secure approvals necessary for the Project.

(c) **De Novo Review**. The Authority may seek de novo expedited review in the district court for Hennepin County of any Minneapolis City Council action and appeal any decision of any court; **provided, however**, that before any such judicial review may be undertaken, the Authority must obtain the Team's written consent to initiate legal proceedings. The legal fees and costs associated with any such legal proceedings approved by the Authority and Team shall be deemed Project Costs.

## ARTICLE 6 CONSTRUCTION MATTERS

### Section 6.1 **Stadium Developer**.

(a) **Role of Stadium Developer**. Except as set forth in **Section 6.1(b)** below, the Authority shall serve as the Stadium Developer. The Stadium Developer will be responsible for, among other things, the stewardship of the Project Funds and the public interest therein, observing public bidding methods where required or practicable, coordinating regulatory approvals with applicable Governmental Authorities, providing the highest degree of transparency regarding all contractual and funding arrangements, complying with government data practices requirements, implementing and enforcing the Construction Services Agreement Equity Plan (as defined in the Construction Services Agreement), ensuring the Construction Manager's execution of an appropriate Project Labor Agreement, and cooperating with audit and oversight procedures of the Legislative Auditor and the Legislative Commission on Minnesota Sports Facilities.

(b) **Team Assumption of Stadium Developer Duties**. Prior to the Certification of GMP by the Construction Manager, the Team may request to become the Stadium Developer as provided in Minnesota Statutes section 473J.11, subd. 1(f). To become the Stadium Developer, the Team must agree to assume the roles and responsibilities of the Authority as the Stadium Developer for completion of construction in a manner consistent with the Effective Date Minimum Design Standards and, after Certification of GMP, the Final Minimum Design Standards and agreed upon Contract Documents, and any other applicable construction-related roles and responsibilities of the Authority as the Stadium Developer under the Act, including, without limitation, responsibility for Cost Overruns.

### Section 6.2 **Construction Administration**.

(a) Stadium Developer Oversight of Construction Manager. The Stadium Developer, in consultation with the other Party, as set forth in this Agreement, shall take action to enforce the obligations of the Construction Manager to provide the services required by the Construction Services Agreement.

(b) Change Orders.

(i) The Stadium Developer shall provide the other Party with a copy of all Change Order requests and final signed Change Orders and has the right to execute Change Orders subject to the terms of and other restrictions provided in this Agreement including those in Section 2.2(f) of this Agreement. The Stadium Developer shall promptly submit to the SDC Group all proposed Change Orders for review and recommendation as provided in Section 2.2(f). The applicable Representatives or SDC Group, as the case may be, shall review the Change Order the Representatives or SDC Group are entitled to review and act in an expeditious manner so that the Stadium Developer shall have sufficient time to respond within the period of time provided in the Construction Services Agreement for responding to Change Orders; **provided, however,** that Change Orders which modify or deviate from the Final Minimum Design Standards shall be subject to the approval of both the Authority and the Team. The failure of the applicable Representatives or SDC Group to respond within three (3) Business Days shall constitute a deemed approval and a recommendation of the SDC Group to the Parties. The SDC Group shall advise the Parties in writing of the recommendation with respect to changes to the Final Minimum Design Standards, and the Parties shall have three (3) Business Days from receipt to either approve or disapprove, and if approved the approval must be provided in writing, or will otherwise be deemed disapproved. If either Party disputes a disapproval by the other Party, such Party shall promptly initiate Expedited ADR in accordance with Article 13 hereof. The applicable Representatives or SDC Group, as the case may be, shall exercise good faith efforts to respond as diligently and expeditiously as possible to any requested Change Order. In the event that the applicable Representatives or SDC Group, as the case may be, disapproves or recommends disapproval of such Change Order, the applicable Representatives or SDC Group, as the case may be, shall state, with specificity, the reason for disapproval or recommendation of disapproval.

(ii) Either Party may submit to the other Party a request for a Change Order for a Privately Financed Enhancement, which Change Order shall be subject to the other Party's review and approval pursuant to the process and the time period set forth in Section 6.2(b)(i) above. In addition, the Authority Representatives shall review for approval, which approval shall not be unreasonably withheld or conditioned, a Team-requested Change Order for a Privately Financed Enhancement. Subject to the provisions of Section 8.1, if any Team-requested Change Order relates to a Privately Financed Enhancement or results in a Cost Overrun, then the Team, prior to the Stadium Developer executing the Change Order, shall deposit an amount equal to such Privately Financed Enhancement or Cost Overrun in the Project Accounts containing the Project Funds or otherwise demonstrate to the Authority the ability to fund such amount when payment is required, which demonstration the Team shall be deemed to have made if the Team

(A) provides a funding source that satisfies the requirements of **Section 8.2(a)(v)** with respect to a Team Source of Funds, (B) uses Cost Savings allocated to the Team to finance the same. If the Authority requests a Change Order that results in a Cost Overrun, then the Authority, prior to the Stadium Developer executing the Change Order, shall deposit an amount equal to such Cost Overrun in the Project Accounts containing the Project Funds or otherwise demonstrate to the Team the ability to fund such amount when payment is required. Any Change Order approved in accordance with the foregoing will be submitted to the Stadium Developer for implementation.

(iii) Unless the Team elects to hold the contract, Team Privately Financed Enhancements (*e.g.*, without limitation, the Team Store, Hall of Fame, East Event Level Locker Room Buildout, Viking Legacy Ship, Chairman's Lounge, and Lower Club Retail) are to be approved by the Authority for construction and installation under contracts to be held under the name of the Authority pursuant to terms and conditions acceptable to the Authority. Such contracts will be generally consistent with the Authority's current Trade Contracts. Team-held contracts will be consistent with the board approval of the Authority dated December 18, 2015. The cost of Team enhancements to be funded as Privately Financed Enhancements will be funded in accordance with **Section 8.1(e)(iv)**.

(c) **Right to Attend Meetings.** The Representatives and each Party's owner's representative or other designee shall receive from the Project Representative advance notice of all regularly scheduled Project meetings and all non-regularly scheduled Project meetings (to the extent notice can reasonably and practically be provided), and the Stadium Developer shall cause the Project Representative to provide such notice. The Representatives and each Party's owner's representative or other designee shall have the right to attend all of the Construction Team meetings, inspect the Project at all reasonable times and subject to all Stadium Site safety rules, and receive all written communications, reports and documents provided to the Stadium Developer at the same time as provided to the Stadium Developer. The Authority Representatives and the Team Representatives shall meet regularly in order to keep all Parties informed throughout the duration of the planning, design and construction of the Project.

(d) **Value Engineering.** If at any time during construction, the Stadium Developer reasonably believes that the Master Project Budget might be exceeded, then, following consultation with the other Party, the Stadium Developer shall be entitled to undertake such value engineering as may be reasonable and appropriate to attempt to cause the Master Project Budget not to be exceeded; **provided, however,** that any such value engineering shall be performed so that the revised design is in accordance with the Final Minimum Design Standards, or as otherwise approved by the Parties; **provided, further,** however, the Team shall have the right to initiate a Privately Financed Enhancement to avoid such value engineering modification, and the Stadium Developer shall implement such change in accordance with the provision of **Section 6.2(b)(ii)**.

### Section 6.3 **Construction Manager Subcontracting.**

The Construction Manager may contract for labor, materials, supplies, and equipment for the construction of the Project, including any work the Construction Manager proposes to self-

perform, as set forth in the Act and Construction Services Agreement and consistent with the requirements thereof. The Stadium Developer shall cause the Construction Manager to obtain SDC Group approval for each such contract under the Construction Services Agreement which has such requirement.

Section 6.4 Lists of Contractors and Subcontractors.

Upon the request of the either Party, the Stadium Developer shall promptly furnish the lists provided by the Construction Manager of all contractors and subcontractors employed in connection with the construction of the Project and true and correct copies of all executed contracts, subcontracts and purchase orders therefor.

Section 6.5 Stadium Developer Responsibilities.

(a) Administration Responsibilities. The Stadium Developer shall be responsible for the administration duties stated in the Design Services Agreement (unless and until assigned, if at all, to the Construction Manager) and the Stadium Developer shall be responsible for the duties of the Authority stated in the Construction Services Agreement, subject to the rights of the other Party as set forth herein. Upon and after Certification of GMP, except to the extent otherwise provided in this Agreement, the Stadium Developer will have the sole responsibility and obligation to provide direction and, as applicable, approvals to the Architect as contemplated in the tenth and twelfth “whereas” clause recitals contained in the Design Services Agreement. The Stadium Developer may provide such direction without the approval of the Team or the SDC Group.

(b) Contract Negotiation and Third Party Beneficiary. The Stadium Developer shall select and negotiate contracts with all consultants, professionals, trade contractors and vendors that shall comprise the Construction Team, subject to consultation with and final approval by the other Party, such approval not to be unreasonably withheld, delayed, or conditioned; with the other Party being named a third party beneficiary of such contracts.

(c) Project Accounting Services. The Stadium Developer shall provide accounting services for the Project, including records that reasonably detail Project Costs. The Authority and the Team have agreed upon the system for tracking and allocating such costs, which system shall at all times provide sufficient detail to allow the Team to track and allocate Team Contributions for tax purposes and incorporates the level of transparency commensurate with the public investment in the Project and will reflect the need for financial reporting and accountability to multiple Governmental Authorities.

(d) Project Reporting. The Stadium Developer, in collaboration with the Project Representative, shall furnish to the other Party monthly construction status and other progress reports, or more often if reasonably requested, containing, at a minimum: (i) the status of design planning; (ii) a comparison of the Master Project Budget to costs incurred through the date of the report, and an analysis of the reasons for variances; (iii) a narrative comparison of the Master Project Schedule to the work actually completed through the date of the report, and an analysis of the reasons for variances; (iv) any revision to the Master Project Schedule and/or Master Project Budget made during the period covered by the report; and (v) the status of any

governmental requirements and activities required to facilitate the approval of the Project. The Parties shall have the right to request from the Stadium Developer copies of any and all additional reports related to the Project as are reasonably requested by such Party.

(e) Competitive Bidding. The Stadium Developer, in cooperation with the other Party, shall develop such competitive bidding procedures and requirements as necessary to ensure compliance with the Act.

(f) Budget and Value Engineering. The Stadium Developer shall cause any consultants retained for the purposes of providing budgeting confirmations and value engineering services or identifying alternative cost reduction options to timely provide such information for consideration by the SDC Group.

(g) Procedures for Payment of Project Costs. The Stadium Developer shall, in coordination with the Construction Manager, the Architect, and the other Party, develop for the other Party's approval, procedures for reviewing and processing applications for payments by the Construction Manager, and procedures for payment of other Project Costs, including payments to other consultants, and such procedures shall be consistent with the provisions of **Section 8.5(d)**.

(h) Contract Legal Administration. The Stadium Developer shall take (i) all action reasonably required in the performance of its duties under the Construction Services Agreement to comply with all Legal Requirements and (ii) all reasonable action to enforce the obligations of the Architect, the Construction Manager, and all other agents and contractors engaged by, or acting on behalf of, the Stadium Developer to comply with all Legal Requirements.

(i) Punchlist and Warranty. The Stadium Developer shall take action to enforce the obligation of the Architect and Construction Manager to complete punchlist work and warranty work after the date of Substantial Completion of the Project pursuant to their respective duties under the Design Services Agreement and Construction Services Agreement.

(j) Transportation Plan. The Authority, with the cooperation of the Team, shall develop a transportation management plan for Stadium operations, including traffic control, street signage, street closures or diversions, public transportation issues, and parking meters, for any required City approval.

(k) Response to Requests. The Stadium Developer shall cause the Stadium Developer Representatives to promptly respond to requests from the other Party.

#### **Section 6.6 Permits.**

Except to the extent that the Stadium Developer is unable to do so due to the other Party's failure to perform its obligations under this Agreement, the Stadium Developer shall use its commercially reasonable efforts to obtain, comply with and keep in effect all Permits and other approvals obtained from any Governmental Authorities, regardless of the procurer of such Permits, that relate to the construction of the Project.



## Section 6.7 Project Labor Agreement.

The Stadium Developer shall enforce the obligation in the Construction Services Agreement requiring the Construction Manager to negotiate a no-strike project labor agreement (the “**Project Labor Agreement**”) with the applicable trade unions so as to prevent strikes or lockouts that would halt, delay or impede construction of the Project.

## Section 6.8 Project Insurance.

(a) Insurance. With the approval of the Team, the Authority has engaged Willis of Minnesota, Inc. to act as broker and administrator for the procurement and administration of the insurance program for the Project. At execution, the insurance program will not have been finally determined, brokered or placed. Accordingly, the Parties shall continue to work collaboratively to evaluate the Project’s insurance needs and to mutually agree on the policies of insurance and limits of coverage to be included within the insurance program. The Stadium Developer shall place and maintain insurance coverage for development and construction of the Stadium and Stadium Infrastructure in the form of insurance policies and limits of coverage as are mutually agreed by the Parties under this **Section 6.8(a)**, and the cost of such insurance shall be part of the Project Costs; **provided, however**, that the Stadium Developer shall be able to procure as a Project Cost supplemental insurance policies and increase limits of coverage that it considers in its reasonable discretion to be appropriate to protect itself, the Team, and the Project subject to the consent of the Team. The other Party acknowledges that the Stadium Developer will implement a “controlled insurance program,” either an “owner controlled insurance program” or a “contractor controlled insurance program.” The “owner controlled” insurance program shall, at a minimum, include the following coverages: general liability insurance, excess and umbrella liability insurance. The program shall cover the Parties, the Architect, the Construction Manager, enrolled subcontractors and enrolled consultants and trade contractors involved in the Project. The Stadium Developer shall administer such insurance programs. The Stadium Developer shall also place and maintain an owner protective professional indemnity policy or project-specific professional liability insurance policy consistent with the requirements set forth in the Construction Services Agreement, a railroad protective liability policy, an ocean cargo policy (including delay), a terrorism coverage or a separate policy covering terrorism, project-specific fixed site pollution liability policy and a contractors’ pollution liability policy. The Stadium Developer shall also place and maintain an all risk or “special form” policy of builder’s risk insurance for the Stadium and Stadium Infrastructure. The Authority and the Team shall cooperate with each other and jointly adjust and settle any loss insured under the builder’s risk insurance or to allocate any deductibles consistent with the builder’s risk insurance policy. The Authority shall take action to enforce the Architect’s contractual obligation to maintain professional liability insurance as set forth in the Design Services Agreement. Whichever of the Authority or the Team is not acting as the Stadium Developer shall at all times with respect to the Project be “additional named insureds” under each such policy of insurance (and StadCo will also be an “additional named insured”) and whichever of the Authority or the Team is acting as the Stadium Developer, as the case may be, will be the first named insured.

(b) Delay in Completion Date or Completion Deadline. The Parties acknowledge that, under various circumstances, the Stadium Developer may be entitled to payments from third parties as compensation for construction delays or payments to cover certain costs of

acceleration pursuant to the owner “controlled insurance program” if such is implemented by the Stadium Developer with respect to the Project or pursuant to other insurance policies that may be maintained by the Stadium Developer to cover the costs of delays in construction or construction acceleration costs. If the Stadium Developer is entitled to receive any such payments or damages, then all such payments or damages actually received by the Stadium Developer shall be allocated among the Parties as appropriately determined by the Stadium Developer as fiduciary of payment proceeds or as otherwise agreed by the Parties when placing or implementing such insurance.

(c) Risks of Damage or Destruction Prior to Completion. The Authority and the Team acknowledge that the Stadium Developer shall obtain, as a part of the Project Costs and subject to the Parties’ mutual approval, a builder’s risk policy of property insurance for the Project, which provides coverage for direct physical loss or damage resulting from an insured peril at the Project or the Stadium Site or to personal property that is at the Project or the Stadium Site, in storage or in transit. Payment of any deductible resulting from an insured peril under the insurance shall be a Project Cost. This coverage shall include sublimits for delay in completion (including gross earnings, extra expense and soft costs) and may include sublimits for flood coverage. The builder’s risk policy shall include separate sublimits for the Authority and Team for delay in completion (including gross earnings, extra expense and soft costs), separate deductibles and a specific loss payee endorsement naming the Team as a separate loss payee with respect to the delay in completion sublimits. The Authority and the Team shall decide whether to obtain such coverage for roads, streets and paving, and shall otherwise cooperate to assure that all improvements to be insured under the policy are identified and reported to the property insurer. The builder’s risk policy shall be an “all risk” or “special form” policy. With the exception of proceeds recovered in connection with the Team’s lost earnings and soft costs resulting from delay in completion, the Stadium Developer shall apply the proceeds of any recovery under such builder’s risk policy of property insurance (collectively, **“Insurance Proceeds”**) as fiduciary for the insureds consistent with their interests, toward restoration of the damage giving rise to such proceeds and to other costs directly related to the restoration of such damage. If a casualty or Condemnation shall occur with respect to all or any portion of the Project or the Stadium Site and such Insurance Proceeds or Condemnation award paid to the Stadium Developer or the estimated cost of the repair and restoration, either individually or in the aggregate, is greater than Five Million Dollars (\$5,000,000), the Stadium Developer shall, in accordance with all Applicable Laws, deposit the Insurance Proceeds or Condemnation award, as applicable, with an independent third party financial institution, which financial institution shall (i) have at least One Hundred Million Dollars (\$100,000,000) in assets or (ii) meet such threshold requirements specifically set by the Act, selected by the Authority and the Team to act as escrow agent. The funds held in escrow shall be administered and disbursed pursuant to the terms of an escrow agreement, which escrow agreement shall be consistent with the provisions of this Agreement (as applicable) and shall facilitate the application of such funds to fulfill the repair and/or restoration obligations set forth herein (as applicable). The Stadium Developer shall from time to time as requested by the Authority, the Team, its Affiliates, or any Leasehold Mortgagee (as defined in Section 23.3(a) of the Stadium Use Agreement), provide an accounting to such other party of such Insurance Proceeds or Condemnation award, as applicable, in detail and format reasonably satisfactory to such other party. Following completion of any repair or restoration, any remaining Insurance Proceeds or Condemnation

award, as applicable, shall be shared between the Authority, in proportion to the aggregate amount of the Authority Contribution and the Private Contribution, and the Team, in proportion to the amount of the Team Contribution. The funds received by the Authority and allocable to the Private Contribution will be distributed first to fund payments of refunds, if any, due to SBL Licensees and second to the purchaser under the SBL Purchase and Sale Facility.

Nothing in this **Section 6.8(c)** shall entitle a Leasehold Mortgagee to receive any award paid with respect to the Authority's interest in the Project and Stadium Site or this Agreement or proceeds of any insurance maintained by the Stadium Developer. The Stadium Developer shall not be liable or otherwise financially responsible for any loss or damage caused by actions or omissions of the other Party that are not covered by the builder's risk insurance. With the exception of proceeds recovered in connection with the Team's lost earnings and soft costs resulting from delay in completion, all such Insurance Proceeds shall be considered Project Funds and will be deposited in the appropriate Project Accounts in order to pay for the Project Costs. Whichever of the Authority and the Team is not acting as the Stadium Developer shall at all times with respect to the Project be an "additional named insured" under each such policy of insurance (and StadCo will also be an "additional named insured") and whichever of the Authority or the Team is acting as the Stadium Developer, as the case may be will be the first named insured.

## ARTICLE 7 SITE ACQUISITION

### Section 7.1 Acquisition and Delivery of Stadium Site.

(a) Acquisition of Stadium Site Property. Unless otherwise agreed to by the SDC Group and consistent with the Master Project Budget, the Authority shall (i) maintain or acquire good and marketable title to the real property legally identified on **Exhibit D-1-B**, which exhibit may be updated and supplemented by the Parties at any time to reflect the acquisition of real property and real property interests by the Authority, and (ii) maintain or acquire good and marketable title, enforceable real property interests, or other rights to use the entire Final Stadium Site and, in each case, free and clear of all encumbrances other than Permitted Encumbrances; **provided, however,** that with respect to Title Defects that impair the marketability of title or the validity or enforceability of easements identified by the Team in the manner provided below, the Authority shall have such time as is reasonably necessary following acquisition of title, or easements, as the case may be, to the Stadium Site to cure such Title Defects and the Authority hereby agrees to diligently undertake to effect such cure.

(b) Title Evidence and Defects. Following execution of this Agreement, the Authority shall provide to the Team title commitments and surveys covering the Stadium Site (the "**Title Evidence**"). Within twenty (20) days following receipt of all of the Title Evidence, the Team shall deliver to the Authority a list of Title Defects identified by the Team within the Title Evidence. Prior to acquiring title to each portion of the Stadium Site, the Authority shall give notice to the Team of (i) any Title Defects identified by the Team it does not intend to cure ("**Rejected Title Defects**"), provided that if the Team elects in writing to remove such Rejected Title Defect(s) from its list of Title Defects and accept title to the Stadium Site subject to the

Rejected Title Defect(s), the Authority shall be deemed to have withdrawn its notice of intent not to cure, and (ii) the anticipated schedule for curing the Title Defects.

(c) Registration of Title. The Authority will register title to the Stadium Site with the Hennepin County Registrar of Titles and will plat the Stadium Site (using a subdivision plat or a registered land survey) to conform to the as-built Stadium and Stadium Infrastructure. Upon such platting, the description of the Stadium Site will be modified to conform to the plat.

(d) Notices of Violations. If the Authority receives notice from any Governmental Authority with respect to the Stadium Site or any portion thereof or any buildings or improvements thereon that (i) relates to violations of any applicable Legal Requirements, (ii) claims any defect or deficiency with respect to any of the Stadium Site or any buildings or improvements thereon or (iii) requests the performance of any repairs, alterations or other work to or in any portion of the Stadium Site or in the streets bounding the same, then the Authority shall provide prompt written notice to the Team of such violations, defects or repairs and the proposed manner and timetable in which the Authority will address such violations, defects or repairs.

(e) Taxes. All special assessments of any kind (special, bond or otherwise) that are or have been levied against the Stadium Site, or any portion thereof, which are outstanding or unpaid shall be paid by the Authority.

(f) Utilities. The Stadium Infrastructure shall include within close proximity all public utilities (including water, gas, electric, storm and sanitary sewage and telephone utilities) required to operate the Stadium Site.

(g) Zoning. The Stadium Site shall have all necessary and required zoning approvals for the use and operation of the Stadium and Stadium Infrastructure in compliance therewith and under the Stadium Use Agreement.

## Section 7.2 Environmental Matters.

(a) Environmental Assessments. The Authority will obtain a Phase I environmental assessment of the Stadium Site addressed to the Parties, which assessment shall provide that each party can rely on such Phase I. If required, the Authority shall cause any Phase II environmental assessment to be performed as is determined to be reasonably necessary by the Authority.

(b) Project Cost. The cost of the Phase I (including the cost to prepare the Phase I) and the Phase II (including the cost to prepare any report of the results thereof, if any) shall be paid as part of the Project Costs. In the event the results of the Phase I or the Phase II indicate the presence of Contamination or if any Contamination is discovered during the course of construction that, pursuant to applicable Environmental Laws, requires the performance of a Response Action, the Authority shall prepare a Response Action plan sufficient to obtain from the Minnesota Pollution Control Agency (the “MPCA”) a “No Further Action” letter for soils at the Stadium Site and shall obtain approval of such plan by the MPCA. The Authority shall cause the Construction Manager or trade contractor to cause such Response Action to be performed in accordance with the approved plan as expeditiously as is reasonably possible and the

Construction Manager or trade contractor shall demonstrate that the costs for such Response Action are based upon competitive pricing. The costs of any Response Action shall be paid as a Project Cost. If any Contamination is discovered during the course of construction, then the Party discovering such Contamination shall notify the other Party immediately and before such Contamination is disturbed, but in no event later than five (5) days after either (i) the date the Party first observes the conditions or (ii) the date that such Contamination is reported to either of the Parties by the Construction Manager. The Parties shall explore in good faith the procurement of insurance coverage for any legal liability relating to Contamination at the Stadium Site other than as disclosed in the Phase I or Phase II and such insurance cost shall be a Project Cost.

(c) EIS Report and Delivery. The Authority, in collaboration with the Team, caused the Environmental Consultant to prepare and complete the final EIS on or before August 1, 2013. The Authority rendered its adequacy decision on the final EIS on August 23, 2013.

Section 7.3 Boundary Survey; Site Assessment; Response Actions.

(a) Project Costs for Boundary and ALTA Surveys; Site Assessment; Response Actions. The Project Costs shall include the cost of the following items:

(i) a boundary survey or other such legal description of the Stadium Site identifying new and existing confines of the Stadium Site. Such survey shall incorporate proposed road relocation and any proposed property and street vacation;

(ii) an ALTA survey prepared by a registered land surveyor in accordance with all Applicable Laws regulating surveying in the State and addressed to the Authority, the Team and such other parties as may be necessary or appropriate in connection with financing for the Project. Such ALTA survey shall comply with the "Minimum Standard Detail Requirements for ALTA/ACSM Land Title Surveys," jointly established and adopted by ALTA and NSPS in 2011, and shall include items from Table A thereof as the Authority or the Team may reasonably require;

(iii) a final report concerning the site-use assessment of historical and archaeological artifacts including any necessary surveys and investigations, together with clearance by the appropriate public agencies approving findings and recommendations identified in the final report; and

(iv) obtaining approval of any Response Action plan required under **Section 7.2(b)**, and obtaining a "No Further Action" letter covering soils at the Stadium Site and a "No-Association Determination," as appropriate, from the MPCA stating that any such Contamination discovered during the Phase II has been removed or remediated to the extent required by the MPCA, and that the Team and the Authority, and their respective successors and assigns and lenders, will not become associated with such Contamination as a result of acquiring title to the Stadium Site or constructing and operating the Stadium.

(b) Conditions Encountered – Reporting Obligations. If conditions are encountered at the Stadium Site that are subsurface structures, conditions or materials that differ substantially

from those indicated in the Geotechnical Report, then the Party discovering such condition shall notify the other Party immediately, and before such conditions are disturbed, but in no event later than five (5) days after either (i) the date the Party first observes the conditions or (ii) the date that such conditions are reported to either of the Parties by the Construction Manager. The Authority Representatives and Team Representatives shall promptly investigate such conditions. If such conditions cause an increase in the cost of, or time required for, performance of any part of the Project, such costs shall be a Project Cost.

Section 7.4 Parking.

Unless otherwise agreed to by the Parties, the Stadium Infrastructure shall include a minimum of two thousand (2,000) parking spaces within one (1) block of the Stadium, connected by skyway or tunnel to the Stadium, and five hundred (500) parking spaces within two (2) blocks of the Stadium, with a dedicated walkway on game days.

**ARTICLE 8**  
**FINANCING OF THE PROJECT**

Section 8.1 Master Project Budget and Project Expenses.

(a) Preliminary Project Budget and Master Project Budget.

(i) Preliminary Project Budget. The Preliminary Project Budget was established by the Parties pursuant to the execution and delivery of the Preliminary Development Agreement. Upon recommendation by the SDC Group, the Parties hereby approve the amendment to the Preliminary Project Budget as set forth on **Exhibit F-1** hereto (the “**Amended Preliminary Project Budget**”). Until the Master Project Budget is adopted and approved by the Parties, the Amended Preliminary Project Budget will serve as the Master Project Budget.

(ii) Master Project Budget. The Master Project Budget has been established and approved by the SDC Group and the Parties, respectively, and is attached hereto as **Exhibit F-2**. The Master Project Budget, as further supplemented by the February 19, 2016 SDC Group Action, (A) supersedes the Amended Preliminary Project Budget, (B) shall govern and control in all respects, and (C) the Master Project Budget, as it may be amended by the Parties from time to time, shall be incorporated into this Agreement. Only the Parties shall have the right to amend the total amount of the Master Project Budget.

(iii) Contingency Letter of Credit. The Team funding sources for the Project initially included that certain letter of credit (the “**Contingency Letter of Credit**”) issued by U.S. Bank National Association on behalf of the Team in the stated amount of \$26,447,957. The Authority consents to the amendment of the Contingency Letter of Credit, effective no earlier than the Second Amendment Effective Date, as set forth in **Exhibit T** attached hereto, and agrees that upon the effectiveness of such amendment, the Contingency Letter of Credit shall be deemed to be a Team Source of Funds that satisfies the requirements of **Section 8.2(a)(v)(A)** below.

(iv) DAS, WiFi and McClellan Block – Special Allocation Provision. The Team and the Authority acknowledge and agree that the Authority may enter into one (1) or more agreements with a third Person with respect to (A) the grant of license or other similar rights for DAS or WiFi at the Stadium, and (B) the grant of development rights in connection with the property referred to as the McClellan block adjacent to the Stadium. If the Authority enters into any such agreements and receives excess capital or proceeds (as described in Section 8.1(a)(iv)(A)(1) or (2) below) net of the reasonable costs and expenses associated with and incurred by the Authority in connection with the transaction(s) (broker commission, professional fees, etc.) (individually and collectively “**Proceeds**”), in connection with the license, grant, sale or other form of transaction with the third Person, then the amount of such Proceeds shall be treated as set forth in the following subsections:

(A) DAS, WiFi and McClellan Block Excess Proceeds. If (1) any capital is received by the Authority in excess of the capital requirements to install and activate the initial DAS or WiFi in connection with one or more DAS or WiFi transaction(s) or (2) any proceeds are received by the Authority in connection with the McClellan block transaction, the Authority will distribute to the Team such Proceeds from the initial DAS or WiFi transaction(s) or McClellan block transaction up to, but not exceeding, Twenty-Six Million Four-Hundred Forty-Seven Thousand Nine-Hundred Fifty-Seven Dollars (\$26,447,957). If the amount of Proceeds distributed to the Team equals or exceeds Twenty-Six Million Four-Hundred Forty-Seven Thousand Nine-Hundred Fifty-Seven Dollars (\$26,447,957), then any additional amount of the Proceeds from the transaction(s) after satisfaction of the foregoing shall be deemed Cost Savings and subject to the Cost Savings provisions set forth in Section 8.1(d) and Section 8.1(e) below.

(B) DAS, WiFi and McClellan Block Reconciliation of Excess Proceeds. Upon completion of the Project, to the extent that Cost Savings (as set forth in Section 8.1(d)) (excluding reduction by application of Proceeds) are less than Twenty-Six Million Four-Hundred Forty-Seven Thousand Nine-Hundred Fifty-Seven Dollars (\$26,447,957), the Team shall retain the Proceeds paid to the Team by the Authority up to, but not exceeding, the amount of such difference and will reimburse the Authority for the amount exceeding the difference equal to the Authority’s share of Cost Saving that the Authority would have received had the excess Proceeds not been distributed to the Team. To the extent that Cost Savings (as set forth in Section 8.1(d)) (excluding reduction by application of Proceeds) are greater than Twenty-Six Million Four-Hundred Forty-Seven Thousand Nine-Hundred Fifty-Seven Dollars (\$26,447,957), Proceeds paid to the Team by the Authority shall be reimbursed to the Authority in the amount of the difference between Twenty-Six Million Four-Hundred Forty-Seven Thousand Nine-Hundred Fifty-Seven Dollars (\$26,447,957) and the Proceeds paid by the Authority to the Team equal to the Authority’s share of Cost Saving that the Authority would have received had the Proceeds not been distributed to the Team.

(v) [RESERVED]

(b) Development and Administration of the Master Project Budget. The SDC Group (i) shall establish the details and total amount of the Master Project Budget, and (ii) document anticipated costs and cost reductions through value engineering in the course of developing the Final Minimum Design Standards and the Master Project Budget, which Master Project Budget shall include a Project contingency (the “**Owner’s Contingency**”) that will be agreed upon by the SDC Group. The SDC Group shall work in good faith such that the Master Project Budget shall concentrate spending on Project Costs and, to that end, as many program elements, amenities, and design features as are required for a first class multi-purpose stadium and related infrastructure. The Master Project Budget shall be finalized for recommendation and approval by the SDC Group and approval by the Parties prior to or concurrently with the Certification of GMP. At the time of Certification of GMP, the Construction Manager budget pursuant to the Certification of GMP shall be equal to the Construction Manager budget in the Master Project Budget. After Certification of GMP, the Stadium Developer may use underruns on any line item of the Master Project Budget for which the cost overrun risk is identified as the Owner’s Contingency in the Master Project Budget to pay for overruns on any line item of the Master Project Budget as long as the total amount of the Master Project Budget is not exceeded. Underruns in budget line items that identify the Team or the Authority as bearing the cost overrun risk shall be available to the respective Party to pay for overruns in any line item of the Master Project Budget for which that Party bears cost overrun risk; **provided, however**, that if the Party cannot apply the funds to a budget line item, then such excess shall be transferred to the Owner’s Contingency.

(i) Owner’s Contingency.

(A) As of the execution date of the Original Agreement, the Parties have established the Owner’s Contingency in the amount of Thirty Million Dollars (\$30,000,000). The Parties have established a schedule for the incremental release of specified amounts of unused Owner’s Contingency upon the occurrence of specific Project work milestones (the “**Owner’s Contingency Release Schedule**”), each as set forth in **Exhibit G** hereto. Any released Owner’s Contingency funds shall be deemed to be Cost Savings (as defined in **Section 8.1(d)**) and applied to Project Costs as set forth and allocated in accordance with **Sections 8.1(d)** and **8.1(e)**. Amounts from Owner’s Contingency that would otherwise be released in accordance with the Owner’s Contingency Release Schedule may be reserved and delayed for release pending the resolution of Change Orders or Claims of the Construction Manager that have been submitted to the Stadium Developer or can be reasonably estimated and determined by the Stadium Developer that there is a substantial likelihood of such a submittal based on existing facts and circumstances. Based on the foregoing, and notwithstanding any contrary provision in this Agreement, use of the Owner’s Contingency for use in the Project shall be assigned priority over all other uses of the Owner’s Contingency in the following order: (1) valid claims or Change Orders under the Construction Services Agreement or the Design Services Agreement (in the reasonable judgment of the Stadium Developer) for increases to the GMP or the Design Services Agreement contract amount (other than costs covered in (3) below), (2) Project Cost overruns, (3) valid claims or Change



Orders under the Construction Services Agreement or the Design Services Agreement (in the reasonable judgment of the Stadium Developer) for additional Project Costs incurred or to be incurred due to Master Project Schedule delay (including delay arising from damage or destruction of the Project), and (4) the release of Owner's Contingency as Cost Savings pursuant to **Section 8.1(d)**.

(B) The Owner's Contingency may be modified from time to time by (1) the difference between the budgeted and the actual cost incurred (accounting for rebates or other financial consideration) for any category of costs identified in the Master Project Budget, if such actual costs are more or less than the budgeted amount; (2) any amounts released from the Construction Manager Contingency, as that term is defined in the Construction Services Agreement, or amounts released from any other contractor contingencies established during the Project; **provided, however,** that any amounts paid to the State for transfer to the Authority for capital reserves consistent with Section 17.18 of the Construction Services Agreement ("**Construction Services Agreement Savings Share**") shall be allocated as set forth below in **Section 8.1(d)(ii)** hereof; (3) any amounts received due to reductions in cost under the Design Services Agreement; and (4) any release of collateral or other amounts received under a controlled insurance program (*i.e.*, an OCIP or CCIP).

(ii) **Limitation on Authority Funding.** Under no circumstances shall the Authority contribute more funds to the Master Project Budget other than authorized by the Act. Nothing in this Agreement shall limit or prevent the Team from funding amounts in excess of the Master Project Budget.

(c) **Allocation of Project Costs.** The Authority and the Team agree that the Project Costs shall be paid pursuant to this Agreement. Pursuant to the Preliminary Development Agreement, the SDC Group established and approved the allocation of Project Costs, which has been superseded and a copy of such allocation of Project Costs is attached as **Exhibit H** which sets forth the allocations of Project Costs that are binding upon the Parties (i) in the preparation of the Master Project Budget and (ii) for expenditures, costs and reimbursements that are deemed preapproved for payment as Project Costs, subject to the Cost Savings provisions set forth in **Section 8.1(d)** below.

(d) **Cost Savings.** "**Cost Savings**" shall mean any Project funds released from the Owner's Contingency pursuant to **Section 8.1(b)(i)**. Cost Savings are contingent upon use by the Stadium Developer to address Contract Revisions or Claims arising out of the Design Services Agreement or the Construction Services Agreement, and shall be further subject to the cost overrun and cost underrun provisions set forth in **Section 5.1(b)(iii)(C) and (D)**.

(e) **Allocation of Cost Savings.** Any Cost Savings, except as provided in **Section 8.1(f)** below, shall be used as follows:

(i) **Apportionment of Cost Savings.** Cost Savings shall be apportioned between the Authority and Team as follows:

(A) Cost Savings will first be allocated to fund the First Priority Joint Funded Design Add Alternates set forth in **Section 8.1(e)(ii)(E)** hereof;

(B) After the First Priority Joint Funded Design Add Alternates have been fully funded (including the reimbursement of any advances made by the Team as set forth in **Section 8.1(e)(ii)(E)**), or in the event Cost Savings become available after it is too late to add the First Priority Joint Funded Design Add Alternates to the Project, then the next Three Million Dollars (\$3,000,000) of excess or unused Cost Savings will be apportioned equally (50%/50%) on a dollar-for-dollar basis between the Authority and the Team;

(C) Any remaining Cost Savings in excess of the amounts apportioned and utilized as set forth above in **Sections 8.1(e)(i)(A) and (B)** will be allocated to the Team to be used as set forth in this Agreement.

(ii) **Use of Cost Savings.**

(A) **Authority Use of Cost Savings.** The Authority shall use all Cost Savings allocated to it under this Agreement to (1) fund Design Add Alternates set forth on **Exhibit I-1** and **Exhibit I-2**, (2) fund the restoration of Authority Project Cost Allocation Reductions set forth on **Exhibit I-3**, or (3) reimburse the Authority for costs incurred and/or paid by it to complete a Design Add Alternate prior to Cost Savings becoming available to the Authority to pay for such Design Add Alternate.

(B) **Team Use of Cost Savings.** The Team shall use all Cost Savings it receives under this Agreement to (1) fund Design Add Alternates set forth on **Exhibit I-1** and **Exhibit I-2**, (2) fund the restoration of Team Project Cost Allocation Reductions set forth on **Exhibit I-4**, (3) fund a Team Privately Financed Enhancement, (4) reimburse the Team for costs incurred and/or paid by it to complete a Design Add Alternate or a Team Privately Financed Enhancement prior to Cost Savings becoming available to the Team to pay for such Design Add Alternate or Team Privately Financed Enhancement, or (5) offset the Team's final ratable payment otherwise due pursuant to Section 8.2(a)(vi).

(C) **Restoration of Project Cost Allocation Reductions.** Neither Party shall be permitted to use Cost Savings to fund the restoration of Project Cost Allocation Reductions in amounts in excess of those set forth on **Exhibits I-3** and **I-4**.

(D) **Joint Funding of Design Add Alternates.** If the Authority and Team each agree to fund the same Design Add Alternate set forth on **Exhibit I-1** or **Exhibit I-2**, then each Party shall bear fifty-percent (50%) of the cost to complete that Design Add Alternate, which shall be paid with either Cost Savings available to the respective Party under this Agreement or with a financial contribution or a combination of both.

(E) First Priority Joint Funded Design Add Alternates. The Parties have each agreed that the first priority for use of Cost Savings shall be to add the following Design Add Alternates to the Project: (1) two (2) sets of escalators, (2) one (1) freight elevator, (3) laundry and hydro equipment, (4) the incremental allocation to the Retractable Bowl Seating System specified in **Exhibit I-1** and **Exhibit I-2**, (5) finish out two (2) auxiliary locker rooms, and (6) east relief louvers (collectively, the “**First Priority Joint Funded Design Add Alternates**”). The Parties therefore agree that the foregoing Design Add Alternates in this **Section 8.1(e)(ii)(E)** will be funded with the first available Cost Savings. The Authority further agrees that the Team may elect in its sole discretion to fund any or all of the foregoing First Priority Joint Funded Design Add Alternates with an additional financial contribution if Cost Savings are not available at the time, and the Construction Manager will be directed by the Stadium Developer to add the applicable foregoing First Priority Joint Funded Design Add Alternates. The Authority agrees that the Team will be fully reimbursed for such advanced costs from Costs Savings as such Cost Savings become available before any such Cost Savings will be apportioned and allocated to the Authority under **Section 8.1(e)(i)(B)** above.

(iii) Value Engineering and Budget Reconciliation. In connection with the value engineering process to reconcile the Effective Date Minimum Design Standards to the Amended Preliminary Project Budget, the Authority and Team compiled two (2) lists of design elements to be removed from the Project; **provided, however**, that such removed design elements will be maintained in the Project design as add alternates that may be reinstated to the Project in the future in the event funding becomes available in the form of Cost Savings or additional funding. The Architect has been, or shall be, directed to include these add alternates as alternate designs to be included within its design scope of work for immediate use upon the availability of Cost Savings at selection by either or both the Authority and/or the Team.

(A) Authority Design Add Alternates. The Authority’s list of design add alternates is referred to herein as the “**Authority Design Add Alternates**” and is attached as **Exhibit I-1**.

(B) Team Design Add Alternates. The Team’s list of design add alternates is referred to herein as the “**Team Design Add Alternates**” and is attached as **Exhibit I-2**.

Collectively the Authority Design Add Alternates and the Team Design Add Alternates are referred to herein as the “**Design Add Alternates**.” With respect to the Authority Design Add Alternates, the Authority identified priority items that the Authority desires to be included in the Project in the event Cost Savings or other funding becomes available. In addition, the Authority has identified Project Cost Allocation Reductions, attached as **Exhibit I-3**, that the Authority desires to restore in the event funding becomes available in the future (“**Authority Project Cost Allocation Reductions**”).

With respect to the Team Design Add Alternates set forth on **Exhibit I-2**, the Team identified priority items that the Team desires to be included in the Project in the event funding becomes available in the future. In addition, the Team identified Project Cost Allocation Reductions, attached as **Exhibit I-4**, that the Team desires to restore in the event funding becomes available in the future (“**Team Project Cost Allocation Reductions**”). Collectively the Authority Project Cost Allocation Reductions and the Team Project Cost Allocation Reductions are referred to herein as the “**Project Cost Allocation Reductions**.”

(iv) **Right to Fund a Design Add Alternate and Process to Contract for the Work.** Either Party shall have an absolute right to fund and cause a Change Order to be authorized and executed through the Stadium Developer, without the approval of the other Party, a Design Add Alternate set forth on **Exhibits I-1** and **I-2** with Cost Savings or additional financial contribution, provided that the Construction Manager agrees that the work can be timely completed without delaying the date of Substantial Completion, or the construction schedule can otherwise be maintained through Construction Manager’s acceleration, the costs of which will be allocated from such Party’s allocated Cost Savings or paid by the Party electing to fund the Design Add Alternate; **provided, however,** no Cost Savings or other Project Funds will be used to add a parking garage without the approval of the Authority. The Stadium Developer will, at the direction of either Party, submit a Change Order to the Construction Manager to add a Design Add Alternate and cause the Construction Manager to complete the requested work. Prior to the Stadium Developer executing the Change Order, the requesting Party shall either (A) deposit in the Project Account of the Stadium Developer an additional financial contribution in the amount equal to the cost of such Design Add Alternate, as negotiated with the Construction Manager, or otherwise demonstrate to the Stadium Developer the ability to fund such amount when payment is required, or (B) identify funds in an amount equal to the cost of such Design Add Alternate in the Project Account from Cost Savings, or (C) a combination of (A) or (B) above.

(A) **Use of Third-Party Contractors.** If the requested Design Add Alternate includes a scope of work that will be performed by a contractor or vendor other than the Construction Manager, the Stadium Developer shall contract with such other contractor or vendor selected by the requesting Party to complete the scope of work. Prior to Stadium Developer’s execution of the contract with the selected contractor or vendor, the requesting Party shall deposit an amount equal the cost of such Design Add Alternate, as negotiated with the contractor or vendor, in the Project Accounts containing the Project Funds or otherwise demonstrate to the Stadium Developer that the requesting Party has the ability to fully fund such amount when payment is required.

(B) **Cost Estimates for Design Add Alternates Shall not be Considered a Restriction.** The accuracy or underestimation of the estimated cost of the Design Add Alternates as set forth on **Exhibit I-1** or **Exhibit I-2** shall not be a limitation on either Party’s use of Cost Savings to fund any excess cost over estimate for the completion of the Design Add Alternates, or to reimburse the

applicable Party for the costs incurred to complete the Design Add Alternate prior to Cost Savings becoming available to pay for the Design Add Alternate.

(v) Right to Restore Project Cost Allocation Reductions. Either Party shall have an absolute right to fund the restoration of Project Cost Allocation Reductions as set forth on Exhibits I-3 and I-4 with its allocated and remaining Cost Savings or with a financial contribution, or a combination of both, in its sole discretion and without the approval of the other Party.

(vi) Use of Unused or Excess Cost Savings: Priority Application of Funds. If, after first applying Cost Savings to (A) fund the Design Add Alternates set forth on Exhibits I-1 and I-2, (B) fund the restoration of Project Cost Allocation Reductions, and (C) reimburse the respective Party for costs incurred to complete a Design Add Alternate prior to Cost Savings becoming available to that Party to pay for a Design Add Alternate, there are unused or excess Cost Savings, or in the event that it is not feasible to use Cost Savings to fund any remaining incomplete Design Add Alternates, then such unused or excess Cost Savings shall be used for other mutually-agreed capital improvements to the Stadium or to acquire and install mutually agreed furniture, fixtures and equipment (FF&E) or advanced electronic equipment or technological services at the Stadium or Stadium Plaza, or in the absence of such mutual agreement shall be transferred to the Authority's Capital Reserve Fund as defined in the Stadium Use Agreement.

(f) Allocation of Construction Services Agreement Cost Reductions, Release of Construction Manager Contingency and Construction Services Agreement Savings Share.

(i) Construction Services Agreement Cost Reductions and Release of Construction Manager Contingency. Notwithstanding anything to the contrary in this Agreement (specifically including the provisions of Section 8.1(b)(i)(B)) up to and including receipt of the first Fifteen Million One Hundred Twenty Nine Thousand Six Hundred Four Dollars (\$15,129,604) of cost reductions realized from (a) Authority and Team approval of alternative manufacturers of products and materials to those currently specified in the Contract Documents as that term is defined in the Construction Services Agreement; (b) a negotiated reduction in the amount of LeJeune Steel Company's claim and allowance as scheduled in the Construction Manager's Construction Management Report dated July 25, 2014; (c) a release of the Construction Manager Contingency (each of the forgoing potential cost reductions is described in Contract Revision No. 016 to the Construction Services Agreement dated August 22, 2014); and (d) a reduction in cost under the Design Services Agreement, will be apportioned equally (50%/50%) on a dollar-for-dollar basis between the Authority and the Team. The Authority's share of such cost reductions shall be applied to increase the amount of the Owner's Contingency or reimbursed to the Authority as may be agreed to by the Authority and the Team, and the Team's share of such cost reductions shall be used for the same purposes as the Team is permitted to use Cost Savings under Section 8.1(e)(ii)(B). Any cost reductions in excess of Fifteen Million One Hundred Twenty Nine Thousand Six Hundred Four Dollars (\$15,129,604) realized as a result of the foregoing matters will be applied to the Owner's Contingency as set forth in Section 8.1(b)(i)(B) of this Agreement.

(ii) Construction Services Agreement Savings Share. Any amounts paid to the State for transfer to the Authority for capital reserves consistent with Section 13 of Contract Revision 16 to the Construction Services Agreement, dated August 22, 2014 shall be allocated as follows: (i) seventy-five percent (75%) of the Construction Services Agreement Savings Share shall be apportioned in accordance with **Section 8.1(e)(i)**; and (ii) twenty-five percent (25%) of the Construction Services Agreement Savings Share shall be allocated to the Authority's Capital Reserve Fund as defined in the Stadium Use Agreement.

(g) Use of Owner's Contingency. The Stadium Developer shall not use Owner's Contingency to fund any work or item that is inconsistent with, or a significant deviation from, (i) the Construction Manager's approved scope of work set forth in the Construction Services Agreement or (ii) the budgeted items scheduled on the Master Project Budget.

(h) SDC Group Contingency. The Authority and Team will establish in the Master Project Budget a line item budget amount of Eight Million Dollars (\$8,000,000) to be used solely for the payment of disputed cost issues under the Construction Services Agreement, if any. For purposes of this **Section 8.1(h)**, such funds will not be deemed part of the Owner's Contingency established under **Section 8.1(b)** hereof and will not otherwise be subject to the terms and conditions applicable to the Owner's Contingency. Notwithstanding anything to the contrary in this Agreement, following Certification of GMP the SDC Group will be solely responsible for designating such disputed cost issues under the Construction Services Agreement to be paid from the funds governed by this **Section 8.1(h)** and managing the resolution of such disputed cost issues to be paid from the funds governed by this **Section 8.1(h)**, if any, and will make recommendations to the Authority and Team for approval or disapproval of such proposed resolutions based on the recommendations of the Authority's and Team's representatives, legal counsel and consultants. The final recommendations of the SDC Group and any distribution of funds governed by this **Section 8.1(h)** must be approved in writing by both the Authority and Team. Any funds remaining in the Master Project Budget line item established by this **Section 8.1(h)** as of January 1, 2016, will be transferred to the Authority's Capital Reserve Fund as defined in the Stadium Use Agreement.

## Section 8.2 Team/Private Contribution and Authority Contribution.

Subject to the terms and conditions of this Agreement, the Team and the Authority shall provide the following financing toward the Master Project Budget:

(a) Team/Private Contribution. The Team shall provide, and the Authority to the extent of net proceeds from each sale of SBLs to the public (each an "**SBL Public Sale**") and/or each sale of SBL Revenues in accordance with the provisions of **Section 8.7** below (each an "**SBL Revenue Sale**," and all SBL Revenue Sales and SBL Public Sales, collectively the "**SBL Sale**") shall provide payments for Project Costs pursuant to this Agreement as follows:

(i) As set forth in the Preliminary Development Agreement, the Team has previously provided the Authority with written evidence of Financial Security or other creditworthiness in the amount of Fifty Million Dollars (\$50,000,000), as required by Minnesota Statutes section 473J.15, subd. 2(b). The Authority hereby (A) re-

acknowledges receipt of such evidence from the Team and (B) advises the Team that such evidence is satisfactory to the Authority and that the statutory provisions of the Act requiring such evidence have been satisfied.

(ii) The Team's previous payments of Project Costs pursuant to the Preliminary Development Agreement and payments pursuant to this Agreement shall be credited against the Team/Private Contribution and shall be the source of the first funds used for Project Costs.

(iii) As provided in Minnesota Statutes section 473J.15, subd. 2(a), the team contribution and the private contribution amounts to the Project shall initially total Four Hundred Seventy Seven Million Dollars (\$477,000,000), and effective as of the Second Amendment Effective Date, shall total Five Hundred Twenty Five Million Six Hundred Fifty Thousand Dollars (\$525,650,000) (the "**Team/Private Contribution**"). The private share of the Team/Private Contribution, shall equal One Hundred Twenty Five Million Dollars (\$125,000,000) (the "**Private Contribution**") *less* the aggregate amount of all costs of finance related to the SBL Revenue Sales and SBL Related Costs and Expenses as of any date of determination (such amount, the "**Target Private Contribution Amount**"). Prior to or at the closing of the SBL Purchase and Sale Agreement, the Team and the Authority shall jointly determine the Target Private Contribution Amount, and the amount so determined shall thereafter be deemed the Target Private Contribution Amount. Within sixty (60) days after the last day of the first quarter of each calendar year thereafter, the Team and the Authority shall jointly determine the then-current aggregate amount of SBL Related Costs and Expenses previously incurred and estimated to be incurred, and the Target Private Contribution Amount shall be adjusted to reflect any change in the amount so determined from the amount previously determined. The Team shall guarantee the Private Contribution Shortfall in accordance with the provisions of **Section 8.7(f)**. The Team's share of the Team/Private Contribution (the "**Team Contribution**"), as of any date of determination, shall initially equal Four Hundred Seventy Seven Million Dollars (\$477,000,000), and effective as of the Second Amendment Effective Date, Five Hundred Twenty Five Million Six Hundred Fifty Thousand Dollars (\$525,650,000), *less* the Target Private Contribution Amount. The Team Initial Payment shall be the source of the first funds used for Project Costs and shall be credited against the Team Contribution.

(iv) Once the Team shall have deposited all of the Team Initial Payment into the Project Accounts and Fifty Million Dollars (\$50,000,000) of Project Costs shall have been paid from the Team Initial Payment, the next Fifty Million Dollars (\$50,000,000) of Project Costs shall be paid from a portion of the Authority Contribution as provided in **Section 8.2(b)** below.

(v) Prior to the initial deposit into the Project Accounts of any funds received by the Authority from the State representing any portion of the Authority Contribution, and at all times thereafter, the Team shall have provided Financial Security or financing commitment(s) (or a combination thereof) (each, a "**Team Source of Funds**"), reasonably satisfactory to the Authority in an aggregate Net Available Amount (defined below) at least equal to that portion of the Team Contribution not previously funded by

the Team to the Project Accounts or otherwise incurred, paid or expended for Project Costs. The net available amount of any Team Source of Funds shall be the aggregate undrawn or unfunded amount of such Team Source of Funds available to pay Project Costs, in each case net of costs of finance and other fees, costs, and expenses to be paid from such Team Source of Funds (the “**Net Available Amount**”). The Net Available Amount of each Team Source of Funds shall be periodically certified by the Team to the Authority, initially on or prior to the date of the closing of such Team Source of Funds and no less often than annually thereafter. Each Team Source of Funds for the Team Contribution shall be in form and substance reasonably acceptable to the Authority; provided, however, that the Authority acknowledges and agrees that the following Team Sources of Funds are and will be reasonably acceptable to the Authority:

(A) The issuance of one or more irrevocable letters of credit for the account of the Team, any of its direct or indirect equity owners, or any of their respective affiliates for the benefit of the construction funds trustee in substantially the form of **Exhibit J** attached hereto by any commercial bank that is organized under the laws of the United States, any state thereof or the District of Columbia, and (1) is “well capitalized” (as defined in the regulations of its primary federal banking regulators), and (2)(i) has a short-term debt rating of “P-2” (or higher) according to Moody’s, or a short-term debt rating of “A-2” (or higher) according to S&P, and (ii) has a long-term debt rating of “A3” (or higher) according to Moody’s, or a long-term debt rating of “A minus” or higher according to S&P;

(B) The execution by the Team and/or one or more entities affiliated with the Team, and by NFL Ventures, L.P. and/or one or more entities affiliated with the National Football League (the “**NFL Lenders**”) of definitive loan documentation relating to financing to be provided by the NFL Lenders to the Team and/or one or more of its affiliates (the “**NFL G-4 Facility**”) upon substantially the terms and conditions set forth in that certain 2013 Resolution JC-3 of NFL Ventures, Inc. (the “**NFL G-4 Resolution**”); and

(C) The execution by the Team, one or more of its affiliates and/or one or more statutory trusts or other entities formed to facilitate the provision of financing for the Team/Private Contribution and one or more banks or other financial institutions of definitive loan documentation relating to financing to be provided by such banks or other financial institutions to finance all or a portion of the Team/Private Contribution (the “**Bank Loan Facility**”) upon substantially the terms and conditions set forth in that certain bank loan commitment (the “**Bank Loan Commitment**”) made by and among StadCo, Minnesota Stadium Funding Trust, a bankruptcy remote special purpose Delaware statutory trust (“**FinCo**”), and the financial institutions party thereto (the “**Bank Loan Commitment Parties**”), and the lenders party thereto. Such approval shall extend to and include each sub-loan and sub-purchase facility contemplated by the Bank Loan Commitment. The Authority shall, on the date hereof, provide the Bank Loan



Commitment Parties with a written acknowledgement of its receipt and approval of the Bank Loan Commitment in the form of **Exhibit K** attached hereto.

The Team may from time to time request that the Authority approve one or more Team Sources of Funds (including one or more replacement or substitute Team Sources of Funds for any one or more previously approved Team Sources of Funds) by providing written notice of the same to the Authority (each, an “**Approval Request**”). Each Approval Request shall be accompanied by copies of the material definitive credit or other documents evidencing, securing or otherwise relating to such Team Source of Funds (collectively, with respect to each Approval Request, the “**Approval Documents**”); **provided, however**, that such Approval Documents need not be executed by the parties thereto if prospective approval is requested. The Authority shall, within ten (10) Business Days after receipt of any Approval Request, either approve or disapprove such Team Source of Funds by providing written notice of the same to the Team. Any notice of approval of a Team Source of Funds shall include a statement of the approved amount of such Team Source of Funds (which amount shall equal the maximum aggregate amount available to fund contributions to the Team/Private Contribution upon the terms and subject to satisfaction of the conditions set forth in the related Approval Documents), and may be conditioned upon the execution and delivery of the related Approval Documents by the parties thereto in substantially the form presented to the Authority within ninety (90) days after the date of approval. Any notice of disapproval of a Team Source of Funds shall include a reasonably detailed statement of the reasons for such disapproval and a reasonably detailed description of proposed modifications to such Team Source of Funds and/or the related Approval Documents that would cause the same to be reasonably acceptable to the Authority. The Authority agrees that the inclusion of usual, customary or otherwise commercially reasonable conditions precedent to any draw or other advance of funds in respect of any Team Funding Source set forth in the related Approval Documents shall not itself constitute a basis for disapproval by the Authority of such Approval Documents. The Team may from time to time thereafter submit an Approval Request with respect to any Team Source of Funds disapproved by the Authority, in which case the provisions of this **Section 8.2(a)(v)** shall apply. Upon approval of a Team Source of Funds as aforesaid, if the remaining Net Available Amount of Team Sources of Funds exceeds the remaining Team Contribution, at the request of the Team, the Authority shall release such excess Team Sources of Funds as the Team may designate, which may include reduction or termination of one or more of the letters of credit described in **Section 8.2(a)(v)(A)**. To so apply the release to such letter or letters of credit, the Team will execute and deliver to the Authority a letter of credit reduction certificate in the form provided by the Trust Agreement, and the Authority shall promptly provide the consent to such certificate provided on such form to deliver to the Trustee.

(vi) Once Project Costs in the aggregate amount of One Hundred Million Dollars (\$100,000,000) have been paid from the Project Accounts, the balance of the Team/Private Contribution and the balance of the Authority Contribution shall be ratably paid into the Project Accounts periodically in such amounts and at such times as may be required to timely pay the remaining Project Costs in the proportion of forty-eight and

eight-tenths percent (48.8%) Team/Private Contribution (the “**Team/Private Funding Percentage**”) (allocated ratably between the Team Contribution and the Private Contribution based on the aggregate amount thereof), and fifty-one and two-tenths percent (51.2%) Authority Contribution (the “**Authority Funding Percentage**”) until August 31, 2014; from and after which the Team/Private Funding Percentage shall be fifty-one and eighty-five one-hundredths percent (51.85%) and the Authority Funding Percentage shall be forty-eight and fifteen one-hundredths (48.15%). If total Project Costs equal or exceed Nine Hundred Seventy Five Million Dollars (\$975,000,000), the Authority shall cause the amount actually funded from the Authority Contribution to pay Project Costs to equal Four Hundred Ninety Eight Million Dollars (\$498,000,000), and the Authority hereby represents and warrants that there shall be no excess funds refundable to the Department of Minnesota Management and Budget pursuant to Section 2.13 of the Grant Agreement. Notwithstanding anything in this Section 8.2(a)(vi) to the contrary and subject to the Cost Savings provisions of Section 8.1(d) and (e) of this Agreement, if total Project Costs, as measured at the Completion Date, equal or exceed Nine Hundred Seventy Five Million Dollars (\$975,000,000) and the amount actually funded from the Authority Contribution as of the Completion Date is less than Four Hundred Ninety Eight Million Dollars (\$498,000,000), the Authority shall pay into the Authority Contribution Trust Account under the Trust Agreement, from the proceeds of advances under the Grant Agreement, the difference between the amount of the Authority Contribution (\$498,000,000) and the amount actually funded prior to the Completion Date from the Authority Contribution. Such payment shall be drawn in accordance with Section 6.02 of the Grant Agreement and applied to expenditures made for the purposes described in Section 2.03 of the Grant Agreement no later than the date which is sixty (60) days prior to the Outside Disbursement Date (as defined in the Grant Agreement). Amounts to be advanced from Team Sources of Funds to fund deposits to the Project Accounts may be allocated among such Team Sources of Funds as the Team may direct. Amounts to be advanced from or drawn under the SBL Purchase and Sale Agreement shall, unless otherwise agreed by the Team and the Authority, be advanced or drawn ratably, plus or minus five (5%), based on the proportion that (A) the maximum available undrawn amount of the SBL Purchase and Sale Agreement, *less* SBL Related Costs and Expenses expected to be (but not yet) incurred (the “Net Available Amount of the SBL Purchase and Sale Facility”), bears to (B) the sum of the Net Available Amount of the SBL Purchase and Sale Facility and the Net Available Amount of all Team Sources of Funds. The Team and Authority shall fund amounts required from the Team Contribution and the Authority Contribution, respectively, to the applicable Project Account for the payment of Project Costs on a monthly basis and paid within five (5) Business Days following the review and approval of any Development Requisition(s) by both the Team and the Authority pursuant to **Section 8.5(c)** for payments made prior to Certification of GMP, and of any Construction Requisition(s) by both the Construction Monitor and the Authority pursuant to **Section 8.5(d)** for payments made after Certification of GMP. In addition, the Authority shall fund amounts required for the Private Contribution, to the applicable Project Account for the payment of Project Costs on a monthly basis and paid within five (5) Business Days following the review and approval of any Development Requisition(s) by both the Team and the Authority pursuant to **Section 8.5(c)** for payments made prior to Certification of GMP, and of any

Construction Requisition(s) by both the Construction Monitor and the Authority pursuant to **Section 8.5(d)** for payments made after Certification of GMP, to the extent and only to the extent of net proceeds from the SBL Sale.

(vii) The Team Contribution is unconditional as to sources of payment and deposits made by the Team for payment of Project Costs pursuant to this Agreement shall earn interest on any funds deposited pending disbursement.

(viii) The Team Contribution under **Section 8.2(a)(vi)** shall be funded by wire transfer of federal funds pursuant to a draw certificate submitted by the Team for deposit with the Disbursing Agent or in one or more of the Project Accounts. As payments are received into the Project Accounts, that portion of the aggregate Net Available Amount of any Team Source of Funds in excess of the remaining Team Contribution shall, at the request of the Team, be released by the Authority to the Team. At its discretion, the Team may apply such release to reduction or termination of one or more of the letters of credit described in **Section 8.2(a)(v)(A)**. To so apply the release, the Team will execute and deliver to the Authority a letter of credit reduction certificate in the form provided by the Trust Agreement, and the Authority shall promptly provide the consent to such certificate provided on such form to deliver to the Trustee.

(ix) By way of clarification and limitation, the Team shall not be required under this Agreement to remit to the Project Accounts any amount exceeding the Team Contribution with respect to Project Costs which have been specifically approved pursuant to either **Section 8.1** or a properly approved Development Requisition.

(x) Regardless of the timing of the contribution and disbursement of the Project Funds, the Team and the Authority agree that legal and beneficial ownership of the Stadium shall be as set forth in **Section 8.10** hereof, but no such agreement as to legal and beneficial ownership shall affect the rights of a Party under this Agreement, including but not limited to design approval.

(b) **Authority Contribution.** The Authority shall provide payments for Project Costs pursuant to this Agreement as follows:

(i) The Authority Contribution has been granted to the Authority by the State pursuant to the Grant Agreement from legally available funds. Under Minnesota Statutes section 16A.965, the State has been authorized to issue appropriation bonds for public purposes as provided by Applicable Law, including, in particular, the financing of all or a portion of the acquisition, construction, improving, and equipping of the Stadium Project of the Authority as provided by Minnesota Statutes Chapter 473J, not to exceed Four Hundred Ninety-Eight Million Dollars (\$498,000,000) net of certain costs, payments and deposits as specified in Minnesota Statutes section 16A.965, subd. 2(b). The State anticipates issuing the bonds in several series within the discretion of the State as provided in the Grant Agreement; **provided, however,** that the Authority shall take such action consistent with the Grant Agreement to cause the State to issue such bonds and to grant the proceeds thereof to the Authority in a manner that allows the Authority to timely meet its obligations hereunder.

(ii) The Private Contribution shall be made from the net proceeds of the SBL Sale.

(iii) The State shall grant to the Authority and the Authority shall deposit into the Project Accounts in a timely manner, as described in Section 8.2(a)(iv) and (vi) above, legally available funds, totaling Four Hundred Ninety-Eight Million Dollars (\$498,000,000) towards the Authority Contribution, which contribution shall be made by wire transfer of federal funds for deposit into one or more of the Project established for deposit of the Authority Contribution. The Authority shall also deposit into the Project Accounts in a timely manner, the net proceeds from the SBL Sale as herein provided as the Private Contribution, which deposit shall be made by wire transfer of federal funds, ACH transfer, or other electronic means of deposit into one or more of the Project Accounts established for deposit of the Private Contribution.

(c) Interest Earnings. Interest earnings, if any, on amounts in the Project Accounts shall not be deemed a part of or credited against any part of the Team/Private Contribution. If this Agreement is terminated prior to the expenditure of all of the Team Initial Payment, the interest earnings on amounts in the Project Accounts shall be credited to the Team. If this Agreement is not terminated prior to the expenditure of all of the Team Initial Payment, the interest on amounts in the Project Accounts shall not be credited towards the Team Contribution or the Authority Contribution, but instead shall be paid to the Authority from time to time for deposit into the Capital Reserve Fund.

### Section 8.3 Trust Agreement, Project Accounts and Termination of Project Accounts.

#### (a) Trust Agreement.

(i) Pursuant to Section 8.4 of the Preliminary Development Agreement, the Parties established the Trust and Disbursement Agreement and a separate Trust and Disbursement Agreement was entered into for the remittance of Project Costs by the Team during the term of the Preliminary Development Agreement.

(ii) Prior to the initial deposit into the Project Accounts of any funds received by the Authority from the State representing any portion of the Authority Contribution, the SDC Group shall direct the Trustee under the Trust and Disbursement Agreement to: (A) pay from the applicable Project Accounts all outstanding invoices and payables authorized for payment by the SDC Group, and (B) transfer the Project Accounts and balances therein to a financial institution approved by the SDC Group in accordance with the RFQ/RFP requirements of the Act and this Agreement. Such financial institution that receives such Project Accounts will become the Trustee and hold such Project Accounts pursuant to a trust agreement (the “**Trust Agreement**”) established and approved by the SDC Group in accordance with this Agreement. The Project Accounts shall include separate accounts and subaccounts under the Trust Agreement (each a “**Trust Account**”) for the Team Contribution, the Authority Contribution and the Private Contribution, each of which accounts shall be managed or administered pursuant to the Trust Agreement with the Trustee. The Private Contribution, constituting all net proceeds of each SBL Sale received by the Authority, shall be promptly deposited to the Trust Account

established for the Private Contribution. The Trust Agreement shall contain terms and conditions relating to disbursement, certification and application of funds, disbursing procedures and requirements, reporting mechanisms and audit rights that will be made or provided to the Team and the Authority. The Trustee shall make cash payments to the Disbursing Agent. The funds therein shall not be commingled with any other Authority, State, City or Team funds. The Trust Agreement shall be administered and controlled by the Trustee in accordance with the terms of the Trust Agreement. The Trustee shall provide a copy of all monthly statements received in connection with the Trust Agreement to the Parties within a period of five (5) Business Days after receipt of such statements. Notwithstanding the foregoing, the SDC Group may extend the existing Trust and Disbursement Agreement until such time as the Team Initial Payment has been made and all outstanding invoices and payables authorized for payment by the SDC Group have been paid.

(b) Project Account Termination. Upon certification by the SDC Group in writing to the Trustee for the Project Accounts that any of one of the following has occurred: (i) all Project construction has been completed in accordance with this Agreement; or (ii) any Party has exercised its termination right under Section 9.2 hereof, and in all cases, all legally owing Project Costs have been fully paid, then the Project Accounts will be terminated in accordance with the further provisions of Section 8.3(c) hereof.

(c) Disposition of Project Accounts Upon Termination After Project Completion/Non-Completion. Subject to the occurrence of certain events set forth in Section 8.3(b) of this Agreement, the Project Accounts shall be terminated by the Trustee in the following manner:

(i) All remaining amounts in the Project Accounts (but not any Financial Security or financing commitment posted by the Team) shall be promptly liquidated.

(ii) If construction of the Project has been completed, then Project Account funds shall be distributed and released as follows:

(A) all remaining Authority Contribution then held in any Project Account and any remaining funds earned from investment of the Authority Contribution shall be paid from the Project Accounts to the Authority, which shall use such funds (1) to remit a refund to the State if and to the extent required by the Grant Agreement, and (2) to the extent any such amounts remain after application of clause (1), to fund the Capital Reserve Fund;

(B) all remaining Private Contribution then held in any Project Account and any remaining funds earned from investment of the Private Contribution shall be paid from the Project Accounts to the Authority, which shall use such funds to fund the Capital Reserve Fund;

(C) all remaining Team Contribution then held in any Project Account and any remaining funds earned from investment of such Team Contribution shall

be paid from the Project Accounts to the Authority to fund the Capital Reserve Fund; and

(D) any Financial Security or other pledged collateral shall be released and transferred to the owner thereof, in each case as directed in writing to the financial institution by such Party.

(iii) If construction of the Project has not been completed and this Agreement has been terminated, then:

(A) all remaining Authority Contribution then held in any Project Account not necessary to fund the Authority obligation to reimburse the Team for payment by Team of Project Costs on behalf of the Authority as set forth in Section 8.2(a)(vi) above, and any remaining funds earned from investment of Authority Contribution shall be paid from the Project Accounts to the Authority, which shall use such funds to make a refund to the State if and to the extent required by the Grant Agreement;

(B) all remaining Private Contribution then held in any Project Account and any remaining funds earned from investment of the Private Contribution shall be paid from the Project Accounts to the Authority;

(C) all remaining Team Contribution and any funds advanced by the Team then held in any Project Account and any remaining funds earned from investment of such Team Contribution or any funds advanced by the Team shall be paid from the Project Accounts to the Team; and

(D) any Financial Security or other pledged collateral shall be released and transferred to the owner thereof, in each case as directed in writing to the financial institution by such Party.

Notwithstanding clauses (A) and (B) of subsection (c)(iii) above, the Grant Agreement will provide that if the initial One Hundred Million Dollars (\$100,000,000) described in **Section 8.2(a)(iv)** has not been completely expended, then the Team shall be entitled to reimbursement in accordance with the Act in an amount equal to the difference between (1) the amount of the Team Initial Payment actually deposited into the Project Accounts, and (2) the product of the statutory percentage allowed by the Act for the aggregate amount expended for Project Costs.

(d) Effect of Disposition of Project Accounts. Disposition of amounts in the Project Accounts and interest as provided under this Agreement shall not satisfy, affect or resolve any Claims or rights held or asserted by any Party related to or arising in connection with duties, disputes or performance unrelated to such disposition, arising under this Agreement, the Grant Agreement or any other agreement.

Section 8.4 Reimbursement of Payments to Team and Authority.

(a) Team Reimbursement – Payments Equal to \$50 Million or Less Upon Termination. If this Agreement is terminated, and at the time of such termination the amount of Project Costs that have been paid or incurred is equal to or less than Fifty Million Dollars (\$50,000,000), the Team shall be reimbursed (i) in accordance with the Act, and (ii) by the Trustee and/or the Disbursing Agent of one-hundred percent (100%) of any amount remitted by the Team pursuant to this Agreement that remains in either the Project Accounts and/or any unexpended amounts that are held by the Disbursing Agent which are no longer required to satisfy Project Cost obligations. The Authority shall, following the termination of this Agreement and the Trustee's and Disbursing Agent's completion of their accounting for the Project Costs and disbursements, upon receipt of such funds from the State, remit the amount calculated to be due to the Team under this Section 8.4(a).

(b) Reimbursement of Team and Authority in Accordance with the Act – Payments Exceeding \$50 Million and Less Than \$100 Million. If this Agreement is terminated, and at the time of such termination the amount of the Project Costs that have been paid or incurred is greater than Fifty Million Dollars (\$50,000,000), but equal to or less than One Hundred Million Dollars (\$100,000,000), the Team and the Authority shall be reimbursed in accordance with the Act.

Section 8.5 Payment Procedures; Audit Rights.

(a) Payment Procedures. The SDC Group shall agree upon the payment procedures that shall be implemented in connection with payments to be made from the Project Accounts under the Trust Agreement and the form of Disbursement Request to be used in requesting payments from the Disbursing Agent.

(b) Disbursing Agreement and Agent. The SDC Group shall enter into an agreement with a disbursing agent (the “**Disbursing Agent**”) for the purpose of receiving funds from the Trust Agreement as remitted by the Trustee to pay for or reimburse for the payment of Project Costs (the “**Disbursing Agreement**”). The Disbursing Agent shall be selected in accordance with the RFQ/RFP requirements of the Act.

(c) Development Requisitions. Prior to Certification of GMP, the SDC Group shall have the right, from time to time, to submit to the Trustee, with copies to each of the Parties and the Disbursing Agent, and either Party shall have the right, from time to time, to submit to the Trustee, with copies to the other Party, the SDC Group and the Disbursing Agent, a withdrawal request in the form agreed upon in the Trust Agreement requesting that the Trustee distribute proceeds in the Project Accounts under the Trust Agreement to the Disbursing Agent to pay Project Costs incurred or due and payable in connection with the development of the Project (each, a “**Development Requisition**”). Each Development Requisition shall be accompanied by copies of invoices, cancelled checks or such other backup documentation substantiating such Project Costs incurred or due and payable as may be required by the Trust Agreement. Upon receipt of a Development Requisition from the SDC Group, the Trustee shall (i) review such requisition for compliance with the Trust Agreement, (ii) confirm with the Parties that there are no material defaults under this Agreement, the Contract Documents or the Disbursing Agreement

that would result in withholding any of the payments set forth in the applicable requisition, and (iii) promptly (and in any event, within five (5) Business Days) pay to the Disbursing Agent any undisputed amounts requested in the Development Requisition. A Party's Development Requisition shall be subject to the approval of the SDC Group, which approval shall not be unreasonably withheld. The objecting Party shall provide a specific written objection to the other Party within three (3) Business Days of its rejection of the invoice identifying the objectionable portion of the invoice and reason(s) for the objection. The SDC Group shall approve the non-objectionable portion of the invoice. The Parties shall endeavor to resolve the dispute, otherwise it shall be deemed to be an Expedited ADR Dispute subject to the provisions of **Article 13**.

(d) **Construction and Design Requisitions.** After Certification of GMP, and upon approval of the Authority and the Construction Monitor, the Stadium Developer shall have the right, from time to time, to submit to the Trustee, with a copy to the SDC Group, the other Party and the Disbursing Agent, a withdrawal request in the form to be agreed upon in the Trust Agreement or Disbursing Agreement requesting that the Trustee distribute funds in the Project Accounts under the Trust Agreement to the Disbursing Agent to pay Project Costs incurred or due and payable in connection with the design and construction of the Project (each, a "**Construction Requisition**"). Each Construction Requisition shall be accompanied by the approvals of the Authority and the Construction Monitor, copies of invoices, cancelled checks or such other backup documentation substantiating such Project Costs incurred or due and payable as may be required by the Trust Agreement. The sole basis for disapproval by the Construction Monitor of any Construction Requisition will be the criteria set forth in the form of certification attached as **Exhibit S**. Upon receipt of a Construction Requisition from the Stadium Developer, the Trustee shall (i) review such requisition for compliance with the Trust Agreement, (ii) confirm with the Parties that there are no material defaults under the Trust Agreement or the Disbursing Agreement and confirm with the Stadium Developer that there is no default under the Design Services Agreement or the Construction Services Agreement that would result in withholding any of the payments set forth in the applicable requisition, and (iii) promptly (and in any event, within three (3) Business Days) pay to the Disbursing Agent any amounts undisputed by the Stadium Developer requested in the Construction Requisition.

(e) **Right to Audit.** Each Party shall have the right to audit, upon reasonable notice and at its own expense, the Project Accounts and the Trust Agreement and all expenditures paid therefrom and pursuant to the Disbursing Agreement. The Parties shall reasonably cooperate with the assigned auditors (internal or external) in this regard, including by providing access to such auditors to all records in each of their possession and control directly relating to the Trust Agreement and the Disbursing Agreement. The Party conducting the audit shall provide a complete copy of the audit report to the other Party promptly following receipt of such report. For the avoidance of doubt, each Party shall bear the costs incurred by it in connection with the audit rights in this **Section 8.5(e)**, and such costs shall not be deemed to be Project Costs. Notwithstanding the foregoing, the Parties may agree to jointly retain external, independent auditors for the purpose of auditing the records arising from the Trust Agreement and the Disbursing Agreement and, if the Parties do so jointly retain an auditor, the cost of the joint auditor shall be a Project Cost. If the State legislative auditor undertakes its duty to audit the Project pursuant to the Act, such costs and expenses incurred shall be a Project Cost; **provided**,



**however**, such costs and expenses shall not include the costs and expenses of auditing the normal and recurring operations of the Authority (separate from the Project).

Section 8.6 Construction Monitor.

The Team and the Authority will cause FinCo to engage an independent engineering firm as the Construction Monitor. The Construction Monitor shall monitor the construction work from time to time throughout the Term of this Agreement. The Construction Monitor shall also serve as an independent engineer on behalf of FinCo for the purposes set forth in the definition of Construction Monitor contained in **Schedule 1** of this Agreement. The scope of the monitoring by the Construction Monitor as well as the scope of its services in its capacity as an independent engineer, including, without limitation, for review of progress of work, review of contracts and substantive budget reviews, review of payment and performance bonds, status of approvals and permits, review of proposed material Change Orders and Change Orders that involve an expenditure from the Owner's Contingency and the source of funds for the Project. The Construction Monitor will also serve in its capacity as the Construction Monitor under this Agreement with respect to the loan agreements relating to the Team Contribution.

Section 8.7 Project Financing – Cooperation.

(a) Facilitation of Financing. The Parties will cooperate with each other to facilitate the financing of the Project consistent with the Act. Such cooperation shall include, on the part of the Authority, the following:

(i) Collaboration with the Team for implementation of the Team financing strategy, including but not limited to the efficient and timely documentation and closing of (A) the Bank Loan Facility upon substantially the terms set forth in the Bank Loan Commitment, (B) the NFL G-4 Facility upon substantially the terms set forth in the NFL G-4 Commitment, (C) the SBL Purchase and Sale Facility as described in **Section 8.7(b)** below, and (D) each other Team Source of Funds from time to time approved by the Authority pursuant to **Section 8.2(a)** hereof.

(ii) Participation by the Authority in any commercially reasonable due diligence review of the Project, the Parties and matters reasonably related thereto conducted by the provider(s) of any proposed source of funds for Team/Private Contribution, all in accordance with such provider(s)' usual, customary and prudent underwriting practices.

(iii) The preparation, execution and delivery of such resolutions, certificates, legal opinions and other documents reasonably necessary or desirable to consummate the closing of and funding under any Team Source of Funds, all in accordance with usual and customary commercial financing practices, which documents shall include with respect to the Bank Loan Facility an opinion of legal counsel to the State with respect to the Grant Agreement in such form as the Bank Loan Commitment Parties may reasonably require.

(iv) The execution and delivery by the Authority of such documents, instruments and agreements, and taking such other actions, as the Team or any party to

any source of funds for Team/Private Contribution may reasonably request for the purpose of carrying out or evidencing any of the transactions contemplated by such source of funds for Team/Private Contribution, whether prior to, at or after the closing of such transactions.

Such cooperation shall not require the Authority to incur any material cost, or impose upon the Authority any material liability or potential liability; **provided, however**, that the foregoing limitation shall not apply to (A) any cost or liability in connection with the Authority Contribution, (B) overhead expenses, general and administrative expenses and other indirect costs incurred by the Authority in connection with such cooperation other than as can be properly segregated and allocated to the activities of the Authority related to the SBL Purchase and Sale Facility, (C) any cost or risk that is recourse only to revenue from the stadium builder licenses owned by the Authority, or that arises from any representation or warranty made by the Authority, and (D) indemnity, hold harmless and similar provisions relating to the Authority's participation in the SBL Purchase and Sale Facility consistent with those set forth in the SBL Purchase and Sale Agreement. The Authority agrees to execute and deliver to FinCo and StadCo, on the later of the date hereof or the date on which the Bank Loan Commitment is executed by the parties thereto, the Indemnification and Contribution Agreement in substantially the form attached as **Exhibit L-1** hereto. The Authority and the Team agree to execute, and the Team will cause StadCo to execute, on the later of the date hereof or the date on which the SBL Purchase and Sale Agreement is executed by the parties thereto, the Indemnification and Contribution Agreement in substantially the form attached as **Exhibit L-2** hereto.

(b) **Marketing and Sale of SBLs; SBL Purchase and Sale Facility.** The Authority shall own and retain the exclusive right to sell, and shall sell, SBLs in the Stadium pursuant to (i) the Authority Stadium Builder License Program attached as **Exhibit M-1** hereto (the "**Authority Stadium Builder License Program**") and (ii) the SBL Marketing and Sales Agreement attached as **Exhibit M-2** hereto (the "**SBL Marketing and Sales Agreement**"). The Authority shall retain the Team to act as the Authority's agent in marketing and selling such licenses pursuant to the SBL Marketing and Sales Agreement. The Authority further covenants and agrees that it shall establish a One Hundred Twenty Five Million Dollars (\$125,000,000) purchase and sale facility with respect to revenues associated with SBLs in the Stadium (the "**SBL Purchase and Sale Facility**") by executing and delivering to the appropriate parties an SBL Purchase and Sale Agreement in substantially the form attached as **Exhibit N** hereto (the "**SBL Purchase and Sale Agreement**") contemporaneously with the closing of the Bank Loan Facility, and by otherwise taking such action as may be reasonably required to consummate in a timely and efficient manner the transactions related to the SBL Purchase and Sale Agreement. Such cooperation action shall include delivery by legal counsel to the Authority of usual and customary legal opinions (including without limitation a so-called 'true-sale' opinion) in such form as the Bank Loan Commitment Parties may reasonably require.

(c) **Use of Private Contribution Proceeds.** The Authority shall consummate SBL Revenues Sales under the SBL Purchase and Sale Facility at such times and in such amounts as may be necessary to timely make each funding of the Private Contribution and to timely pay all SBL Related Costs and Expenses. All proceeds from the SBL Public Sale and/or SBL Revenue Sale constituting the Private Contribution, including without limitation all proceeds from any

sale of the SBL Revenues pursuant to the SBL Purchase and Sale Agreement, shall be deposited into the Project Account established for deposit of the Private Contribution as set forth in **Section 8.3(a)(ii)** or used to pay SBL Related Costs and Expenses. The Team shall have no ownership interest in proceeds generated from the Authority's sale of SBLs.

(d) **Conditional Assignment of Construction-Related Agreements.** The Authority shall conditionally assign all of its right, title and interest in and to the Development Agreement Documents (as defined in the Stadium Use Agreement), excluding this Agreement, but including without limitation the Construction Services Agreement and the Design Services Agreement, pursuant to a Conditional Assignment of Construction Services Agreement in substantially the form attached as **Exhibit O-1** hereto and a Conditional Assignment of Design Services Agreement and Plans in the form attached as **Exhibit O-2** hereto.

(e) **[RESERVED]**

(f) **Private Contribution Shortfall.** The Team hereby guarantees payment of any "Private Contribution Shortfall", defined for purposes of this Agreement to equal, as of any date of determination, (i) the Target Private Contribution Amount *plus* the amount of SBL Related Costs and Expenses not yet paid, *less* the aggregate amount of the Private Contribution previously deposited into the Project Accounts or otherwise used to pay Project Costs, *less* (ii) the aggregate remaining amount available to fund the Private Contribution and SBL Related Costs and Expenses under the SBL Purchase and Sale Facility or any similar facility established to purchase SBL Revenues; *provided*, that in no event shall the Private Contribution Shortfall be less than \$-0-. The Team shall guaranty the Private Contribution Shortfall, and at all times during which a Private Contribution Shortfall exists shall provide a Team Source of Funds in an amount at least equal to the amount of such Private Contribution Shortfall, which Team Source of Funds shall be reasonably acceptable to the Authority and shall be subject to approval by the Authority in accordance with the provisions of **Section 8.2(a)(v)**. The Team shall satisfy its obligation to guaranty any Private Contribution Shortfall under this **Section 8.7(f)** by making advances in respect of the Private Contribution on behalf of the Authority which advances shall reduce the obligation of the Authority with respect to the Private Contribution by the amount of such advances, at such times and in such amounts as the Private Contribution is required to be paid into the Project Accounts under **Section 8.2(a)(vi)** or is utilized to reimburse SBL Related Costs and Expenses pursuant to this Agreement or the SBL Marketing and Sales Agreement, which advances and related costs of financing shall be reimbursed by the Authority to the Team solely from SBL Revenues to which the Authority is or becomes entitled.

#### Section 8.8 **Cost Overruns.**

The Stadium Developer shall be responsible for payment of any Cost Overrun, which payment shall be made at such time as any portion thereof is legally required to be paid with respect to the Project; **provided, however**, that if the Stadium Developer is the Authority, the contract or contracts entered into by the Authority under **Article 6** hereof shall provide that any Cost Overruns are the responsibility of the Construction Manager, trade contractor or vendor, and not of the Authority or the State; and **provided, further**, in no event shall the State or the Authority be liable to contribute in excess of Four Hundred Ninety-Eight Million Dollars (\$498,000,000) for Project Costs. The Authority shall not accept responsibility for Cost

Overruns and shall not be responsible for Cost Overruns if the Authority has authorized the Team to become the Stadium Developer under Section 6.1, in which case the Team shall be responsible for Cost Overruns.

Section 8.9 Sales Tax Exemption.

As necessary, the State and the Authority shall cooperate with the Team to utilize the sales tax exemptions for materials and equipment under the Act. The State or the Authority (as applicable) shall execute and deliver all documents and certificates as necessary to assure that the Project and Construction Manager takes full advantage of sales tax exemptions for materials and equipment available under the Act, including, but not limited to, directing the Construction Manager to exercise all ordinary and necessary measures to qualify the transactions under the Stadium sales/use tax exemption to avoid or minimize sales/use tax costs of the Project. The management of the delivery and installation of such materials and equipment shall be the responsibility of the Construction Manager or trade contractor.

Section 8.10 Ownership of Project, Stadium Use Agreement and Team Tax Benefits.

(a) Ownership of Project. The Team acknowledges and agrees that the Stadium Site, together with all real and personal property constructed, installed and placed on the Stadium Site pursuant to this Agreement (with the exception of property funded through payments made by the Team pursuant to Section 5.6(e), Section 5.6(f), Section 5.6(g), and Section 5.6(h) of the Stadium Use Agreement), including the Stadium and Stadium Infrastructure, and all right, title and interest thereto and therein, shall be the property of and owned by the Authority, subject, however, to such use rights as are conferred on the Team pursuant to the Stadium Use Agreement. In furtherance thereof, the Team, at the request of the Authority, will execute and deliver a confirmatory quit claim deed or quit claim bill of sale in form and substance reasonably acceptable to the Authority (subject, however, to the rights of the Team under the Stadium Use Agreement). The Authority agrees that the Team shall retain all tax benefits with respect to the Team's Stadium Property and the Team's Beneficial Rights.

(b) Team's Stadium Property. The Parties acknowledge and agree that (i) portions of the Team Contribution and payments under Section 5.6(e), Section 5.6(f), Section 5.6(g), and Section 5.6(h) of the Stadium Use Agreement shall be used to construct or provide (or cause to be constructed or provided) certain specific improvements, fixtures, furnishings, equipment and other Internal Revenue Code Section 1245 personal property of a nature described in Exhibit D-1 of the Stadium Use Agreement to be placed in or upon the Stadium (including Team Year-Round Use Areas and Team Allocated Spaces as defined under the Stadium Use Agreement) and related property (collectively, the "**Team's Stadium Property**"), and (ii) the Team shall retain the sole legal and beneficial ownership of Team's Stadium Property to the extent that (A) the capital cost of such Team's Stadium Property is not included in the initial construction of the Stadium or Stadium Infrastructure or in any Capital Funding Plan as defined in the Stadium Use Agreement, (B) such capital cost is paid for by or otherwise a capital cost for which the Team is responsible hereunder, and (C) such Team's Stadium Property is not permanently affixed to the Stadium or Stadium Infrastructure. The Team will have the right to remove the Team's Stadium Property which is legally and beneficially owned by the Team at its discretion, subject to the Team's

responsibility to pay for the reasonable costs of removal and base-level repairs, if any, resulting from such removal.

(c) Team's Stadium Property Schedule. For purposes of identifying the Team's Stadium Property and the Team's Beneficial Rights (as defined below) therein, the Team shall prepare a schedule for the Authority's review and consent identifying the items constituting the Team's Stadium Property and allocating the Team's investment among the items forming the Team's Stadium Property as the Team shall elect (such schedule and allocation, the "**Team's Stadium Property Schedule**"). The Authority will have thirty (30) days after receipt to review and consent to the Team's Stadium Property Schedule, or to notify the Team in writing of any objections. If the Authority does not deliver a written objection and the basis thereof to the Team's Stadium Property Schedule within thirty (30) days of receipt of such Team's Stadium Property Schedule, then the Team's Stadium Property Schedule shall be deemed automatically consented to by the Authority and shall be final and binding on the Parties absent manifest error. If the Authority delivers to the Team a written objection and the basis thereof to the Team's Stadium Property Schedule within thirty (30) days of receipt by the Authority, then the Parties shall negotiate in good faith to resolve the disputes and, if the Parties are unable to resolve the disputes, either Party may seek any available remedy from a court of competent jurisdiction. The final and binding Team's Stadium Property Schedule shall be affixed to this Agreement as **Exhibit P.**

(d) Team's Right to Depreciation. The Parties acknowledge and agree that (i) the Team shall have the sole depreciable interest for income tax purposes in all of the Team's Stadium Property (whether or not such Team's Stadium Property is owned legally and beneficially by the Team), and (ii) for all income tax purposes, neither the Authority nor any other Person shall have the right to take depreciation deductions with respect to the Team's Stadium Property or claim any other right to tax benefits arising from the Team's Stadium Property, such depreciation deductions and tax benefits (the "**Team's Beneficial Rights**") being exclusively reserved to the Team unless assigned by the Team, in whole or in part, to one or more third Persons (including Affiliates). The Team shall have (A) a right, title and interest in the leasehold interest of the Team created by and arising from this Agreement and (B) a depreciable interest for tax purposes in, though no legal ownership of, all leasehold improvements paid for or otherwise funded by the Team. Neither the Team's ownership of, nor the Team's Beneficial Rights in, the Team's Stadium Property shall in any way affect, limit, modify or change in any way the rights, obligations and responsibilities of the Parties, as more particularly set forth in this Agreement; however, the Authority covenants and agrees to cooperate with the Team in the allocation of depreciable assets for the benefit of the Team with respect to the Team's Stadium Property, including in connection with the Team's Stadium Property Schedule, and the leasehold improvements to the Stadium and Stadium Infrastructure paid for or otherwise funded by the Team.

#### Section 8.11 Team Right to Remit Project Costs in Excess of Obligation.

Notwithstanding and prevailing over any contrary provision or implication of this Agreement, in addition to the Team Contribution, if the Project Costs exceed the Team/Private Contribution and Authority Contribution (plus any other funds or grants available for payment of the Project Costs), the Team shall have the right (but not the obligation), in its sole discretion, to

pay into the applicable Project Accounts any additional funds needed to pay the excess Project Costs.

**Section 8.12 Team Use of Related Entities.**

The Authority hereby acknowledges, agrees, and approves that (a) any of the obligations of the Team under this Agreement may be performed by the Team, a related entity of the Team, or a third party with common beneficial or equity ownership with the Team (including trusts or other entities established for the benefit of one or more members of the Team's ownership or one or more family members of the Team's ownership) and (b) the Team, a related entity of the Team or a third party with common beneficial or equity ownership with the Team (including trusts or other entities established for the benefit of one or more members of the Team's ownership or one or more family members of the Team's ownership) may receive revenues to which the Team is entitled under this Agreement or the Act; **provided, however,** the Team shall remain liable to the Authority for the failure of any such assignee to perform any duty, comply with any obligation or contractual requirement under this Agreement, or pay any liability that is assigned to a related entity of the Team or a third party as described above.

**ARTICLE 9  
REPRESENTATIONS AND WARRANTIES OF AUTHORITY**

The Authority hereby represents and warrants to the Team that, as of the date of execution of this Agreement:

**Section 9.1 Organization.**

The Authority is a political subdivision, duly organized, validly existing, and in good standing under the Applicable Laws of the State.

**Section 9.2 Authorization, Validity and Enforceability.**

The Authority has all requisite power and authority to enter into this Agreement and to carry out the actions contemplated hereby. The execution, delivery, and performance by the Authority of this Agreement have been duly authorized and approved by all necessary Authority action. This Agreement, when executed, shall constitute the valid and legally binding obligations of the Authority, enforceable against it in accordance with its terms.

**Section 9.3 No Conflicts.**

The execution, delivery and performance of this Agreement shall not result in a violation of, in any material respect, any provision of any other agreements, charters, instruments, contracts, judgments or decrees to which the Authority is a party, or by which the Authority or its assets may be bound or affected.

**Section 9.4 No Violation of Applicable Laws.**

The Authority has complied in all material respects with all Legal Requirements and is not in default with respect to any judgment, order, injunction or decree of any court,

administrative agency, or other Governmental Authority that is in any respect material to the transactions contemplated in and by this Agreement.

**Section 9.5    Litigation.**

To the actual knowledge of the Authority, there is no action, suit, proceeding or investigation at law or in equity or by or before any Governmental Authority now pending or threatened against the Authority seeking to restrain or prohibit, or seeking Damages or other relief in connection with, the execution of this Agreement and the performance of the transactions contemplated herein or the performance of the Authority hereunder.

**Section 9.6    Funding Sources Determination.**

The Authority has determined or will determine prior to Certification of GMP that all public and private funding sources for construction, operating expenses, and capital improvements and repairs, including funds adequate to design, construct, furnish, and equip the Project, pay projected operating expenses and the costs of capital improvements and repairs during the term of the Stadium Use Agreement, are included in written agreements, and have been made available (if legally required by the date in question) or are reasonably expected to be made timely available (when legally required).

**ARTICLE 10  
REPRESENTATIONS AND WARRANTIES OF TEAM**

The Team hereby represents and warrants to the Authority that, as of the date of execution of this Agreement:

**Section 10.1    Organization.**

The Team is a limited liability company duly organized, validly existing and in good standing under the Applicable Laws of State of Delaware and is the owner of the Minnesota Vikings NFL franchise.

**Section 10.2    Authorization, Validity and Enforceability.**

The Team has all requisite power and authority to enter into this Agreement and to carry out the actions contemplated hereby. The execution, delivery and performance of all obligations of the Team under this Agreement have been duly authorized and approved by all necessary Team action. All corporate action necessary for the authorization, execution, delivery and performance of all obligations of the Team under this Agreement has been taken. All consents and approvals of any Person required in connection with the execution of this Agreement have been obtained. This Agreement, when executed, shall constitute valid and legally binding obligations of the Team, enforceable against it in accordance with its terms.

**Section 10.3    Financial Position.**

The Team is able to pay its debts as they mature and possesses sufficient working capital to meet its financial obligations, as they become due, under this Agreement.

**Section 10.4 No Conflicts.**

The execution, delivery and performance of this Agreement shall not result in a violation of, in any material respect, any provision of any other agreements, charters, instruments, contracts, judgments or decrees to which the Team is a party or by which the Team or its assets may be bound or affected, including the constitution, by-laws, rules and regulations of the NFL, nor shall the execution, delivery and performance of this Agreement result in the breach of or constitute a default under any loan or credit agreement, or other agreement or instrument to which the Team is a party or by which the Team or its assets may be bound or affected.

**Section 10.5 No Violations of Applicable Laws.**

The Team has complied in all material respects with all Legal Requirements and is not in default with respect to any judgment, order, injunction or decree of any court, administrative agency, or other Governmental Authority that is in any respect material to the transactions contemplated in and by this Agreement.

**Section 10.6 Litigation.**

To the actual knowledge of the Team, there is no action, suit, proceeding or investigation at law or in equity or by or before any Governmental Authority now pending or threatened against the Team seeking to restrain or prohibit, or seeking Damages or other relief in connection with, the execution of this Agreement and the performance of the transactions contemplated herein or the performance of the Team hereunder.

**ARTICLE 11  
ADDITIONAL COVENANTS AND CONDITIONS**

**Section 11.1 Additional Covenants of the Parties.**

(a) [RESERVED].

(b) Expansion of Tailgating Areas. The Team will engage with the City, including entering into appropriate agreements, if any, to expand the current tailgating boundaries on surface parking lots generally east and south of the Stadium, recognizing that certain areas will not be practical for tailgating, and to amend Minneapolis Code of Ordinances, Title 13, Section 319.310 to include tailgating areas which have been identified and agreed upon. The Team and the City may also explore tailgating areas along current and future light rail transit lines. It is anticipated that any costs associated with tailgating on surface parking lots (for example, cleaning and trash removal) will be paid for by the owners of such lots.

(c) Liquor Licenses. The Authority shall seek and obtain from the City all intoxicating liquor licenses that are reasonably required for the Stadium and Stadium Infrastructure or other areas where the Authority has secured rights of use and the Authority deems appropriate for such licenses. These licenses are in addition to the number authorized by Applicable Law and such licenses shall be in the name of the Authority.



(d) Use of References and Logos in Offering Documents. The State, Authority and the Team shall permit references to their respective entities and organizations and the use of their respective trade names and logos, if any, in all offering documents of the State related to the issuance of the bonds.

(e) Operations Management Company for Stadium. The Authority and the Team will mutually agree on an experienced third party private management company or qualified individual to manage the Stadium on behalf of the Authority, and will also mutually agree on the food and beverage concessionaire. The Authority, with the approval of the Team, may enter into an agreement with a program manager for management of the Stadium, for a maximum of thirty (30) years. The Authority may negotiate a fixed-cost operating, management or employment agreement under which the third party manager or program manager assumes responsibility for Stadium operating costs and shortfalls.

(f) Access to Financial Information. The Team shall provide the Authority timely access to Team financial information or other information, which the Authority deems necessary for the determination to be made by the Authority under **Section 11.2(b)(vi)**. Any financial information obtained by the Authority under this provision is nonpublic data under Minnesota Statutes section 13.02, subd. 9. Team financial information and other information shall not include financial information of the NFL, NFL Ventures LP, the other NFL member clubs, and any of the Affiliates of the foregoing entities.

(g) Existing Workers. The Team and the Authority shall conclude necessary arrangements, including appropriate agreements, if any, to give food, beverage, retail and concession workers presently employed by the Team or the Authority or its vendors at the Metrodome the opportunity to continue their employment in comparable positions at the Stadium or Stadium Site. Workers who are presently represented under a collective bargaining agreement may seek to continue such representation in the Stadium or Stadium Site and designate such, or another collective bargaining unit, as their representative.

(h) Commemorative Bricks. The Authority shall sell commemorative bricks to be displayed at a prominent location in the Stadium, for an amount to be determined by the Authority. Funds raised through such sales are appropriated to the State for transfer to the Authority.

(i) Agreement to Play at TCF Bank Stadium. The Team has entered into an agreement with the University of Minnesota under which the Team will play games at TCF Bank Stadium when, by reason of construction of the Project, such games cannot be played at the Metrodome and Substantial Completion of the Project has not yet occurred.

(j) Sports-Themed Lottery Games. The Team will enter into arrangements, including appropriate agreements, if any, to reasonably cooperate with and assist the State Lottery in complying with NFL policies on use of trademarks, images and logos, and otherwise, in order for the State Lottery to carry out lottery games based on Stadium or professional sports themes provided for in Minnesota Statutes section 349A.20, should such games be conducted in accordance with the provisions of Minnesota Statutes section 16A.1524. Revenues from the games are appropriated to the general fund.

(k) Site Signage. The Parties shall determine as to whether the Project will have on-site signage describing the sources of funding and naming the responsible Governmental Authorities and private financing sources.

(l) Employment Assistance and Job Fair. The Authority will contract with an employment assistance firm (preferably owned by a minority, disabled individual or a woman) to create an employment program to recruit, hire and retain minorities for the Stadium in accordance with Minnesota Statutes section 473J.12, subd. 1. The Authority will hold a job fair and recruit and advertise at or with certain organizations specified in Minnesota Statutes section 473J.12, subd. 1. In addition, the Authority and Team intend to supplement the requirements of Minnesota Statutes section 473J.12, subd. 1 and the Authority will engage an employment assistance firm to identify, train and facilitate the hiring and utilization of minorities, women, and veterans by the Construction Manager and its subcontractors hired to construct the Project.

(m) Apportionment of Liquidated Damages under Construction Services Agreement. The Authority and Team acknowledge that for purposes of reducing to a liquidated sum the direct and consequential damages that each may incur in the event the Construction Manager fails to complete its work prior to certain specified deadlines, Article 4 of the Construction Services Agreement provides for the Construction Manager's payment of liquidated damages to the Authority. Absent gross negligence or willful misconduct in connection with the Authority's acts or omissions arising from its obligations hereunder the Authority shall not be liable for Losses to the Team arising from late completion of the Project pursuant to the July 1, 2016 completion date set forth in the Construction Services Agreement. Absent such gross negligence or willful misconduct, the Parties acknowledge and agree that their sole remedy for such late completion of the Project shall be limited to (i) the liquidated damages that are due from the Construction Manager under the Construction Services Agreement and shared by the Parties pursuant to **Section 11.1(m)** hereof, and (ii) the Losses the Parties may recover pursuant to the Design Services Agreement for damages due to late completion of the Project; **provided, however,** that the foregoing does not affect (A) the right of either Party to recover from insurance policies that may provide coverage for risk of late completion of the Project, or (B) the provisions of this Agreement or the Stadium Use Agreement with respect to the Team's payment obligations or abatement hereunder or thereunder. The Authority and Team hereby acknowledge and agree that any such liquidated damages recovered from the Construction Manager shall not constitute, and shall not be deemed, "costs savings" or "additional funds" obtained by the Authority or the Team for the Stadium or Stadium Infrastructure pursuant to Minnesota Statutes section 473J.11 as such funds are intended to compensate each Party for damages incurred due to Construction Manager's delay. The Authority and Team further acknowledge and agree that any such liquidated damages recovered from the Construction Manager shall be allocated between the Parties as follows:

(i) Per day liquidated damages: any liquidated damages assessed on a "per day" basis as provided for in Section 4.2.1 of the Construction Services Agreement, and which are recovered from the Construction Manager due to its failure to achieve Substantial Completion on or before July 1, 2016, shall be divided by the Authority and Team in equal shares.

(ii) Scheduled Event: any liquidated damages recovered from the Construction Manager due to its failure to complete the Project in time to host a Scheduled Event (as defined in Section 4.2.1 of the Construction Services Agreement) on or after August 1, 2016, shall be paid to the Authority.

(iii) NFL Games: any liquidated damages recovered from the Construction Manager due to its failure to complete the Project in time to host the first two scheduled NFL Games (as that term is used in Section 4.2.1 of the Construction Services Agreement) in the Stadium on or after August 1, 2016 shall be paid as follows: (A) to the Authority in an amount equal to its actual damages up to a cap of Two Hundred Fifty Thousand Dollars (\$250,000), but in no event more than five percent (5%) of the liquidated damages recovered from the Construction Manager, and (B) the entire balance of the liquidated damages recovered from the Construction Manager to the Team. Any liquidated damages recovered from the Construction Manager due to its failure to complete the Project in time to host the third scheduled NFL Game in the Stadium on or after August 1, 2016 shall be paid as follows: (1) to the Authority in an amount equal to its actual damages up to a cap of five percent (5%) of the liquidated damages recovered from the Construction Manager, and (2) the entire balance of the liquidated damages recovered from the Construction Manager to the Team.

For purposes of this **Section 11.1(m)**, liquidated damages recovered from the Construction Manager shall include any amounts withheld from the Construction Manager under a right of setoff or amounts otherwise withheld from the Construction Manager under the Construction Services Agreement if the setoff or withholding was implemented specifically for purposes of securing and satisfying the Construction Manager's obligations to pay liquidated damages under Article 4 of the Construction Services Agreement, and such amount withheld from the Construction Manager shall instead be paid to the Authority and/or Team as set forth in this **Section 11.1(m)**.

The Authority and Team further acknowledge and agree that any liquidated damages recovered from a Project Consultant under contract with the Stadium Developer shall be treated in the same manner as liquidated damages that may be recovered from the Construction Manager and that, for purposes of applying this **Section 11.1(m)** to liquidated damages recovered from any such Project Consultant, the term "Project Consultant" shall be deemed to be synonymous with the term "Construction Manager" and the agreement by and between the Stadium Developer and Project Consultant shall be deemed to be synonymous with the "Construction Services Agreement" (but without regard to specific dates and article or section number references that are set forth in this **Section 11.1(m)**).

## Section 11.2 Execution of Documents.

(a) Concurrent Documents. The Parties shall execute and deliver the following documents and agreements with this Agreement:

- (i) Stadium Use Agreement; and
- (ii) Football Playing Agreement.

(b) Agreements to be Entered Into. The Parties shall use their respective commercially reasonable efforts, as applicable, to cause the following to occur on or before the respective dates set forth below:

(i) the Team and the Authority shall have executed the Stadium Use Agreement on or before the Effective Date;

(ii) the State and the Authority shall have executed the Grant Agreement on or before November 1, 2013, subject to extension by mutual agreement of the Team and the Authority; and

(iii) the Authority shall have entered into a professional services agreement with an insurance consultant, broker and administrator on or before November 8, 2013, subject to extension by mutual agreement of the Team and the Authority.

(c) Effect of Not Entering Into Agreements. If any of the agreements listed in **Section 11.2(b)** have not been executed and delivered on or before the respective dates set forth therein, then any Party may terminate this Agreement by written notice to the other Party, unless the Parties have agreed, in their respective sole discretion, to extend any of the above dates. A notice to terminate is not subject to the cure periods set forth in **Section 12.1** hereof. A notice to terminate or a notice providing an extension of the termination date must be given on or before fifteen (15) days after the applicable date set forth above (as such date may be extended by agreement of the Parties) or the termination right granted under this **Section 11.2** relating to the particular event shall expire. Any Party may thereafter exercise any right or remedy available under **Section 12.1** hereof, not related solely to failure to deliver and execute the document, other than termination. Under no circumstance may this Agreement be terminated by either Party pursuant to **Section 11.2(c)** following the Certification of GMP.

(d) Termination Reimbursement. In the event the Agreement is terminated by a Party pursuant to **Section 11.2(c)**, the Parties shall be respectively entitled to reimbursement of expended funds only as provided under **Article 8**.

### Section 11.3 No Injunction.

There shall not be in effect any Applicable Law or any injunction or other order that prohibits the consummation or performance of this Agreement by either Party hereto.

## ARTICLE 12 DEFAULT AND REMEDIES

### Section 12.1 Events of Default.

Each of the following shall constitute an event of default ("**Event of Default**") under this Agreement:

(a) Covenant Default. A Party's violation or failure to perform or observe any material covenant or condition of this Agreement, which failure or violation shall continue for thirty (30) days after receipt of written notice to the non-performing Party by the other Party

identifying with particularity the failure or violation; **provided, however**, that so long as such failure or violation is susceptible to cure within a period of time that does not unreasonably cause risk to achieving the completion of the documents and actions set forth in **Article 8**, but is not reasonably capable of being cured within such thirty (30) day period, there shall exist no Event of Default if (i) the Event of Default is susceptible to cure and (ii) the non-performing Party promptly notifies the other Party of the non-performing Party's intention to duly institute all steps necessary to cure such default and the non-performing Party promptly commences cure of such failure or violation within such thirty (30) day period and diligently pursues such cure to completion;

(b) **Representation Default.** Any representation or warranty made by a Party herein shall prove to have been incorrect when made, in any material respect;

(c) **Team Bankruptcy/Insolvency Default.** (i) The Team shall institute voluntary proceedings in bankruptcy, (ii) involuntary proceedings in bankruptcy shall be instituted against the Team that are not discharged within ninety (90) days thereafter, (iii) any proceedings shall be instituted by or against the Team under any Applicable Law relating to insolvency or bankruptcy reorganization, and in the case of an involuntary proceeding, that is not discharged within ninety (90) days after filing, (iv) a trustee or receiver shall be appointed for the Team by any court of competent jurisdiction, or (v) the Team shall make a general assignment for the benefit of its creditors.

(d) **Authority Bankruptcy/Insolvency Default.** (i) The Authority shall institute voluntary proceedings in bankruptcy, (ii) involuntary proceedings in bankruptcy shall be instituted against the Authority that are not discharged within ninety (90) days thereafter, (iii) any proceedings shall be instituted by or against the Authority under any Applicable Law relating to insolvency or bankruptcy reorganization, and in the case of an involuntary proceeding, that is not discharged within ninety (90) days after filing, (iv) a trustee or receiver shall be appointed for the Authority by any court of competent jurisdiction, or (v) the Authority shall make a general assignment for the benefit of its creditors.

Notwithstanding the above, failure to reach agreement on Final Minimum Design Standards within the deadlines of the Task List and Design Delivery Schedule shall not be an Event of Default.

## Section 12.2 **Injunctive Relief; Specific Performance.**

The Parties acknowledge that the rights conveyed by this Agreement and the covenants of the Parties are of a unique and special nature, and that any violation of this Agreement shall result in immediate and irreparable harm to the Authority or the Team, as applicable, and that in the event of any actual or threatened breach or violation of any of the provisions of this Agreement, other than a monetary breach, each Party shall be entitled as a matter of right to seek injunctive relief or a decree of specific performance from any court of competent jurisdiction. The alleged breaching Party waives the right to assert the defense that such breach or violation can be compensated adequately in Damages in an action at law.

Section 12.3 Remedies Cumulative.

Subject to any terms to the contrary set forth in this Agreement, all rights and remedies which may be pursued at law, in equity, or as otherwise set forth in this Agreement, are cumulative. Nothing shall limit any Party's right to pursue rights and remedies at law or in equity, unless specifically set forth in and limited by this Agreement. A Party's exercise of any such rights or remedies shall not prevent the concurrent or subsequent exercise of any other right or remedy, and shall not preclude or waive the right to use any other remedy.

Section 12.4 Risk of Certain Losses; Force Majeure.

If the failure of a Party to act or omit to act under this Agreement, other than the payment of monies, is due to an occurrence of Force Majeure, and such inaction or omission occurs without the fault of the Party claiming an extension of time to perform, such Party shall be granted relief hereunder by an extension of time to perform as set forth herein. An extension of time for any such Force Majeure event shall be limited to the time period of delay arising from such Force Majeure event, which period shall be deemed to commence from the first date of the Force Majeure event; **provided, however**, that if notice by the Party claiming such extension is sent to the other Party more than thirty (30) days after the commencement of the Force Majeure event, the period shall be deemed to commence thirty (30) days prior to the giving of such notice. Times of performance under this Agreement also may be extended as mutually agreed upon in writing by the Authority and the Team. However, failure to agree to a proposed extension of time for performance shall not be deemed grounds for delay or failure to timely cure an Event of Default under this Agreement.

Section 12.5 Limited Recourse Obligations of the Parties.

Notwithstanding and prevailing over any contrary provision or implication of this Agreement, (a) any and all duties, liabilities and obligations of the Parties under this Agreement relating to the Project shall be required to be paid or performed by the Parties only to the extent that Project Funds, any funds relating to monetary recovery from third parties, insurance proceeds or other funds in the Project Accounts are available, and no duties, liabilities, or obligations of the Parties with respect to this Agreement relating to the Project shall be required to be satisfied from any other funds, revenues or reserves of the Parties (other than any Financial Security provided by the Team); **provided, however**, the foregoing shall not apply to the obligation to reimburse the Team under **Section 8.4**, and (b) neither Party will be liable to the other Party for any indirect, special or consequential Damages, or Damages for loss of profits, business interruption, or loss of goodwill arising from or relating to this Agreement, even if such Party is expressly advised of the possibility of such Damages; **provided, however**, subject to the limits imposed by Applicable Law, the foregoing shall not apply to third party Claims of indemnification. The foregoing limitations of liability and exclusion of certain Damages will apply regardless of the failure of the essential purpose of any remedies available to either Party.

Section 12.6 No Liability for Members, Directors, Officers, Etc.

All covenants, stipulations, promises, agreements and obligations of the Parties contained herein shall be deemed to be covenants, stipulations, promises, agreements and obligations of the

Party so making, and not of any member, director, officer, employee or agent of such Party in his or her individual capacity or any other entity or Governmental Authority, and no recourse shall be had for any Claim hereunder against any member, director, officer, employee or agent of the Parties or any other entity or Governmental Authority in such capacity.

## ARTICLE 13 DISPUTE RESOLUTION

### Section 13.1 Arbitration.

(a) Agreement to Arbitrate. All disputes between the Parties solely with respect to (i) Critical Design Decisions set forth in **Section 5.3**, (ii) Development Requisition invoices as set forth in **Section 8.5(c)**, (iii) decisions concerning establishment of and any deviation from the Final Minimum Design Standards, (iv) the Owner's Contingency as set forth in **Section 8.1(g)**, (v) use of Cost Savings, (vi) a Party's right to receive information, participate in meetings and offer comments as provided in this Agreement, (vii) the Park Use Agreement and the Urban Park, each as defined and described in Section 3.9 of the Stadium Use Agreement, (viii) matters related to the so-called Downtown East (DTE) acquisition, (ix) Vendor Contract Technology, Stadium Lighting, Stadium Mechanized Pivoting Doors, and Stadium Sponsored Signage design and procurement matters set forth in **Sections 5.1(b), (i) and (j)**, respectively, of this Agreement, (x) development matters, including parking, with respect to the Ryan Construction development proposal, and (xi) signage and other unfinished matters with respect to the Stadium Implementation Committee, the Minneapolis Planning Commission and the Minneapolis City Council as generally described in **Section 5.6(b)** are each subject to expedited arbitration (each, an "**Expedited ADR Dispute**") and shall be submitted to expedited alternative dispute resolution ("**Expedited ADR**") under this **Article 13**. One or more disputes over all of the above subject matter may be part of one (1) Expedited ADR Dispute. No other disputes between the Parties shall be subject to Expedited ADR, unless the Parties mutually agree to submit to Expedited ADR.

### (b) Initiation of Arbitration and Selection of Neutral.

(i) In order to initiate Expedited ADR, a Party shall simultaneously deliver a notice of design impasse ("**Notice of Design Impasse**") or a notice of Expedited ADR, as applicable with respect to the subject matter described in **Section 13.1(a)** above, to other Party and to the highest ranked eligible potential neutral on the roster (each such neutral a "**Potential Neutral**" and collectively, the "**Potential Neutrals**") attached as **Exhibit Q** to this Agreement ("**Roster of Potential Neutrals**"). The Potential Neutral receiving a Notice of Design Impasse or notice of Expedited ADR shall respond to the Parties within two (2) Business Days whether the Potential Neutral is available to serve. If the Potential Neutral is unavailable or otherwise unable to serve, or fails to respond within two (2) Business Days, either Party may deliver the Notice of Design Impasse or the notice of Expedited ADR to the next highest ranked Potential Neutral on the Roster of Potential Neutrals and may proceed in this same manner until a Potential Neutral is able to serve and accepts appointment as the Neutral ("**Neutral**") to hear and decide the dispute. If no Potential Neutral on the Roster of Potential Neutrals is able to serve, then either Party may request the Chief Judge of the United States District Court for the District of

Minnesota to appoint a Neutral, and the Parties agree to request such appointment as soon as practicable, but no later than five (5) calendar days after the Chief Judge receives such a request. The fees and costs of the Neutral shall be borne equally by the Parties.

(ii) After appointment of the Neutral, each Party shall have three (3) Business Days to prepare and deliver to the other Party and the Neutral a written statement outlining the nature of the impasse (each a “**Statement of Dispute**”).

(iii) The delivery of a Statement of Dispute by either Party to the Neutral shall initiate the Expedited ADR provisions of this Agreement and the matter covered by the Statement of Dispute shall be considered submitted to the Neutral for determination.

(iv) The timelines established for the expedited arbitration shall be strictly followed by the Neutral unless one of the Parties requests a continuance, in which case the Neutral may delay the applicable hearing if the Party requesting the continuance demonstrates good cause to extend the timelines stated in **Section 13.1(b)** or **Section 13.1(d)**, in which case the Neutral may grant a deadline extension and/or continue the Expedited ADR proceeding to an appropriate date with the understanding that the procedures stated in this **Section 13.1** are intended to be and must be expedited procedures to the extent possible.

(c) **Qualifications of Neutral.** The Parties shall obtain disclosures from each Potential Neutral and confirm that each Potential Neutral is independent of the Authority and Team (and their respective Affiliates) and holds no financial interest in, and has no material financial or material personal relationship with the Authority or Team (or their respective Affiliates). Each Potential Neutral shall be a resident of the State.

(d) **Location and Conduct.**

(i) The Expedited ADR proceeding shall be conducted by the Neutral at a time and location in Hennepin County, Minnesota selected by the Neutral. Subject to **Section 13.1(b)(iv)** hereof, the Neutral shall give the Authority and Team reasonable notice of the Expedited ADR proceeding, which shall be within two (2) Business Days after submission of the Statement of Dispute. The Neutral shall conduct the Expedited ADR proceeding in such manner as the Neutral deems appropriate, consistent with the provisions of this **Section 13.1**.

(ii) Each Party shall present its position with respect to the issue(s) to be determined in the Expedited ADR proceeding by an oral presentation to the Neutral. Each Party shall be given the opportunity to hear and orally respond to the other Party's presentation to the Neutral, and to present documents to the Neutral in support of such Party's position. The Neutral shall have the right to limit the time allowed for oral presentations and the documents presented to the Neutral to assure a prompt resolution of the issue(s) to be determined by the Neutral. Each Party may have its counsel and other consultants present at such Expedited ADR proceeding, but there shall be no examination or cross-examination of witnesses other than required or permitted by the Neutral. The Neutral may require the participation of the Architect, the Construction Manager and



other Project Consultants that have knowledge of the subject matter in the Statements of Dispute. At the conclusion of the Expedited ADR proceeding each Party shall submit its proposed written decision to the Neutral. A Party may propose alternate and multiple decisions from which the Neutral may select, but no Party shall submit more than three alternate proposed decisions.

(iii) The Authority and Team intend that the Neutral shall have the sole and exclusive authority and power to resolve Expedited ADR Disputes. In providing resolution to an Expedited ADR Dispute, the Neutral shall look to compliance with the Act, except to the extent that this Agreement diverges from the Act in a legally permitted manner, to this Agreement, to principles of law and equity, and to generally accepted principles in the appropriate area, such as design, construction, accounting or finance. The Neutral shall not have the power or authority to award any damages, require any payments, or issue any other form of award or relief other than as described in **Section 13.1(h)** hereof.

(e) Discovery. There shall be no discovery permitted with respect to any Expedited ADR proceeding other than that required by the Neutral.

(f) Cooperation/Duration. The Authority and Team shall cooperate in good faith to permit a conclusion of the Expedited ADR proceeding within five (5) Business Days following the submission of each Party's Statement of Dispute to the Neutral. The Expedited ADR proceeding shall last no longer than one (1) Business Day, unless the Neutral determines, in its sole discretion, that additional time is required to properly conduct the proceeding in a manner contemplated to provide sufficient information on which to form and issue an informed and fair decision.

(g) Post-Hearing Mediation. After the Expedited ADR proceeding concludes and after each Party submits its proposed written decision(s), but before the Neutral issues its written decision, the Neutral shall conduct a 180-minute mediation session and attempt to facilitate resolution of the issue(s) by settlement

(h) Decision of the Neutral. The Neutral shall render the arbitration decision within two (2) Business Days after the conclusion of the Expedited ADR proceeding, subject to the decision of the Neutral to expand such time for decision. The Neutral is empowered to render a written decision only pursuant to the following "baseball" arbitration principles. First, the Neutral must choose one (1) of the proposed written decision(s) submitted by the Parties. Second, the Neutral must prepare, at a minimum, a brief written memorandum with an explanation of the basis for the decision. Third, the Neutral's written memorandum and decision shall be addressed and simultaneously sent to each of the Parties as set forth in the notice provision of this Agreement. The decision of the Neutral shall be binding upon the Parties.

(i) Exclusive Remedy. The Authority and Team shall use Expedited ADR exclusively, rather than litigation, as a means of resolving all disputes that pursuant to the terms of this Agreement must be resolved by Expedited ADR. Subject to the provisions of Applicable Law, the written decision of the Neutral shall be the binding, final determination on the merits of the Expedited ADR Dispute, and shall preclude any subsequent litigation on such merits. The

Authority and Team agree that any disputes which arise out of such a written decision by a Neutral shall be resolved exclusively by Expedited ADR pursuant to this **Section 13.1**, provided that the Authority or Team may institute legal proceedings in a court of competent jurisdiction to enforce judgment upon the decision of a Neutral in accordance with Legal Requirements.

(j) Strikes. After a Neutral issues a written decision following an Expedited ADR proceeding, a Party may strike the Neutral from the Roster of Potential Neutrals. No Party shall be permitted to strike more than one Neutral. The stricken Neutral shall not thereafter be considered an eligible Potential Neutral and shall not be appointed as a Neutral, unless the Party that exercised its right to strike the Neutral subsequently agrees in writing to withdraw the strike.

Section 13.2 Other Disputes. Any other dispute or Claim between the Parties that is not expressly made an Expedited ADR Dispute in this Agreement shall be subject to the exclusive jurisdiction of the District Court of Hennepin County, Minnesota.

## ARTICLE 14 INDEMNIFICATION

### Section 14.1 Indemnification and Payment of Damages by Team.

The Team shall indemnify, defend and hold harmless the Authority Indemnified Persons for, and shall pay to the Authority Indemnified Persons, the amount of any Damages arising solely from a third party Claim arising from:

- (i) any breach of any representation or warranty made by the Team in this Agreement or in any schedule or exhibit attached hereto or any other certificate or document delivered by the Team to the Authority pursuant to this Agreement; and
- (ii) any breach by the Team of any covenant or obligation of the Team in this Agreement.

If the Team fails to make any payment of any sums payable by the Team to the Authority Indemnified Persons on the date due, which failure shall continue for thirty (30) days, then such payment shall bear interest at a rate of interest equal to the lesser of the “Wall Street Journal Prime Rate” published in the *Wall Street Journal*, (the “**Prime Rate**”) or the highest rate permitted by Applicable Law, payable from the date such payment was due to the date of payment thereof.

### Section 14.2 Indemnification and Payment of Damages by Authority.

Subject to the limits imposed by Applicable Law, Authority shall indemnify, defend and hold harmless the Team Indemnified Persons for, and shall pay to the Team Indemnified Persons the amount of Damages arising solely from a third party Claim arising from:

- (i) any breach of any representation or warranty made by the Authority in this Agreement or in any schedule or exhibit attached hereto or any other certificate or document delivered by the Authority to the Team pursuant to this Agreement; and

(ii) any breach by the Authority of any covenant or obligation of the Authority in this Agreement.

If the Authority fails to make any payment of any sums payable by the Authority to the Team Indemnified Persons on the date due, which failure shall continue for thirty (30) days, then such payment shall bear interest at a rate of interest equal to the lesser of the Prime Rate or the highest rate permitted by Applicable Law, payable from the date such payment was due to the date of payment thereof.

Section 14.3 Limitation of Liability and Indemnification Obligations.

(a) Consequential Damages. Neither Party will be liable for any indirect, special, exemplary, or consequential Damages of any kind or nature, including Damages for loss of profits, business interruption, or loss of goodwill arising from or relating to this Agreement, even if such Party is expressly advised of the possibility of such Damages, except in the case of gross negligence or willful misconduct; **the foregoing, however,** subject to the limits imposed by Applicable Law, will not apply to third party Claims asserted against an indemnified Party to this Agreement. Neither Party's elected officials, appointed officials, board members, members, shareholders and other owners, directors, officers, employees, agents and attorneys or other representatives shall be personally liable for any obligations or other matters arising under this Agreement. Subject to Minnesota Statutes section 473J.01, the foregoing limitations of liability and exclusion of certain Damages will apply regardless of the failure of the essential purpose of any remedies available to either Party.

(b) Team Stadium Contracts - Limitation of Liability for Third Party Contract Claims. If (i) the Team is a party to a contract related to the Stadium with a third Person, and (ii) such third Person asserts a Claim against the Team arising out of the contract related to the Stadium due to an alleged act or omission of the Authority under the Stadium Use Agreement or this Agreement, then (A) the Team or its Affiliates will not have any Claim of indemnification, contribution, or other cause of action against the Authority and (B) the Authority will not have a Claim of indemnification, contribution, or other cause of action against the Team or its Affiliates, each with respect to such third Person Claim. The foregoing shall not affect the subrogation rights of insurers of either the Authority or the Team against the insurers of the other Party.

(c) Authority Stadium Contracts - Limitation of Liability for Third Party Contract Claims. If (i) the Authority is a party to a contract related to the Stadium with a third Person, and (ii) such third Person asserts a Claim against the Authority arising out of the contract related to the Stadium due to an alleged act or omission of the Team under the Stadium Use Agreement or this Agreement, then (A) the Authority will not have any Claim of indemnification, contribution, or other cause of action against the Team; **provided, however,** that the Authority shall have a Claim of indemnification or contribution if the Team failed to include the exculpatory provision set forth in Section 7.2 of the Stadium Use Agreement in the contract with such third Person, and (B) the Team will not have a Claim of indemnification, contribution, or other cause of action against the Authority, in each case with respect to such third Person Claim. The foregoing shall not affect the subrogation rights of insurers of either the Authority or the Team against the insurers of the other Party.

**ARTICLE 15**  
**TERM AND TERMINATION**

Section 15.1 Term.

Unless the Parties agree otherwise in writing, the term of this Agreement (the “**Term**”) shall commence on the Effective Date and, unless earlier terminated in accordance with **Section 15.2**, shall continue until the Commencement Date (subject to the survival provisions of **Section 15.5**); **provided, however**, to become effective, this Agreement must be concurrently executed and delivered with the executed and delivered Stadium Use Agreement. Unless both this Agreement and the Stadium Use Agreement become concurrently binding upon and enforceable against each Party, this Agreement shall not become effective and no Effective Date will have occurred.

Section 15.2 Termination – Prior to Certification of GMP.

This Agreement may be terminated prior to the Certification of GMP in the manner set forth in this **Section 15.2**.

(a) Termination by Either of the Parties. This Agreement may be terminated prior to Certification of GMP by either Party:

(i) if any Legal Requirement or any injunction or other order prohibits either of the Parties from continuing, completing and/or otherwise consummating the Project, and such Legal Requirement, injunction or other order is not fully and finally overturned or otherwise vacated within sixty (60) days after its date of issuance;

(ii) if any amendment or modification of, or supplement to, the Act prohibits or materially and adversely affects the Project or both of the Parties’ ability to complete the Project as contemplated by this Agreement;

(iii) in accordance with the provisions of **Section 11.2(c)**;

(iv) there is an occurrence of Force Majeure that occurs prior to July 1, 2016 and it is reasonably determined to cause the Project to be delayed for a period by which the Commencement Date of the Project will not occur on or before July 1, 2017; or

(v) any material and adverse event or omission occurs that renders it improbable that the Project can be completed due to the lack of available funding to the Authority or the Team, including the funding mechanisms set forth in the Act.

(b) Termination by the Authority. This Agreement may be terminated prior to Certification of GMP by the Authority if:

(i) there is an Event of Default of the Team, and such Event of Default is not cured as set forth in **Section 12.1**; or

(ii) if any amendment or modification of, or supplement to, the Act prohibits or materially and adversely affects the Authority's ability to complete the Project as contemplated by this Agreement.

(c) Termination by the Team. This Agreement may be terminated prior to Certification of GMP by the Team if:

(i) there is an Event of Default of the Authority, and such Event of Default is not cured as set forth in **Section 12.1**; or

(ii) if any amendment or modification of, or supplement to, the Act prohibits or materially and adversely affects the Team's ability to complete the Project as contemplated by this Agreement.

**Section 15.3 Termination – After Completion of Financing and Certification of GMP.**

UPON AND AFTER INITIAL FUNDING OF THE TRANSACTIONS CONTEMPLATED UNDER THE BANK LOAN COMMITMENT, THE AUTHORITY RECEIPT OF THE GRANT AGREEMENT FROM THE STATE, AND CERTIFICATION OF GMP, EACH AND ALL, THIS AGREEMENT SHALL NOT BE SUBJECT TO TERMINATION AS A RESULT OF ANY BREACH OR EVENT OF DEFAULT OF EITHER PARTY, UNLESS SUCH BREACH OR EVENT OF DEFAULT, AS DETERMINED BY A COURT OF COMPETENT JURISDICTION, IS BASED UPON A MATERIAL ACT OF FRAUD OF THE OTHER PARTY.

**Section 15.4 Consequences of Early Termination.**

(a) Effect of Notice of Termination. Upon receipt of any notice of termination by either Party pursuant to **Sections 15.2** above, other than as set forth in **Section 15.4(b)**, (i) the Team shall no longer be required to make any further remittances with respect to Project Costs, and (ii) the Authority and the Team shall suspend all activities under this Agreement, including taking all actions necessary for the suspension of all agreements and contracts. During such thirty (30) day period either Party may rescind its termination notice and, if so rescinded, no termination shall occur.

(b) Effect on Team and Authority Contributions and Authority Activities. Upon receipt of any notice of termination by either Party under **Section 15.2**, (i) neither the Team nor the Authority shall be required to make any further remittances, respectively, of Team Contributions or the Authority Contribution, except to the extent to satisfy existing Project Costs incurred prior to the date of termination and the costs and expenses reasonably incurred in connection with Wind-Up Events, and (ii) the Authority shall suspend all activities under this Agreement, including suspension of all agreements and contracts.

(c) Project Wind-Up. In the event this Agreement is terminated pursuant to either of **Section 15.1** or **Section 15.2**, the Parties shall promptly wind-up the Project (the "**Wind-Up**"), which shall include (i) paying all accrued Project Costs incurred during the Term and costs associated with the Wind-Up (excluding any contractual early termination or minimum fee, if

any, contained in any contract, or otherwise asserted by any third party, contractor or consultant, including Hammes Company Sports Development, Inc., which Project Costs shall be the sole obligation of the Authority), (ii) terminating the agreements entered into prior to and during the Term, and (iii) performing any activities necessary to comply with Applicable Laws and that are otherwise prudent to retire the Project or to protect the Parties from liability (collectively, the “**Wind-Up Events**”). A termination of this Agreement shall not become effective until the provisions of this **Section 15.4(c)** are satisfied, including all Wind-Up Events. In addition, upon such termination, the Authority shall take the actions set forth in **Section 15.4(d)** below.

(d) **Authority Required Actions.** Promptly upon termination of this Agreement, the Authority shall take all actions necessary and proper to (i) confirm in writing the termination of this Agreement and the Project to the State through its proper reporting agency or agencies (anticipated to be the Department of Minnesota Management and Budget) to request and facilitate the reimbursement of the Team pursuant to the Act for the remaining balance of Project Costs, if any, expended by the Team in connection with the Project after set-off for any debts or contributions the Team may owe to the Authority or third parties arising out of or related to the Project, and (ii) properly authorize the Authority to take such necessary actions, including receipt and remittance of any amounts received by the Authority in connection with such reimbursement.

(e) **Continuing Obligations.** Following the termination of this Agreement, and after payment of the reimbursement obligations set forth in **Section 8.4**, if any, neither Party shall be liable to the other Party for Project Costs or other costs incurred during the Term by such other Party prior to the date of termination, except as may be allowed under **Sections 15.2** and **15.4**.

#### Section 15.5 **Survival.**

Notwithstanding termination of this Agreement, if any, the provisions of **Articles 1** (including **Schedule 1**) (Definitions, Rules of Construction and Preliminary Development Agreement), **12** (Default and Remedies), **14** (Indemnification), **15** (Term and Termination) and **16** (Miscellaneous), and **Sections 2.2(i)** (Decisions of the SDC Group), **3.1(a)** (Retention of Architect), **3.1(b)** (Retention of Construction Manager), **3.2** (Amendment of Agreements), **3.5** (Conduct of Discussions and Data Privacy), **6.1(a)** (Role of Stadium Developer), **6.2(a)** (Stadium Developer Oversight of Construction Manager), **6.5(a), (c), (d), (g), (h), (i) and (k)** (Stadium Developer Responsibilities), **6.8(a) – (c)** (Project Insurance), **7.1(e)** (Stadium Site – Taxes), **7.2(b)** (Environmental Reports – Project Costs), **8.1(a)(iii)** (Contingency Letter of Credit), **8.1(a)(iv)** (DAS, WiFi and McClellan Block – Special Allocation Provision), **8.1(c)** (Allocation of Project Costs), **8.1(g)** (Use of Owner’s Contingency), **8.2** (Team/Private Contribution and Authority Contribution), **8.3** (Trust Agreement, Project Accounts and Termination of Project Accounts), **8.4** (Reimbursement of Payments to Team and Authority), **8.5** (Payment Procedures; Audit Rights), **8.7(b)** (Marketing and Sale of SBLs; SBL Purchase Facility), **8.7(c)** (Use of Private Contribution Proceeds), **8.7(f)** (Private Contribution Shortfall), **8.8** (Cost Overruns), **8.9** (Sales Tax Exemption), **8.10** (Ownership of Project, Stadium Use Agreement and Team Tax Benefits), **8.12** (Team Use of Related Entities), **11.1(d)** (Use of References and Logos in Offering Documents), **11.1(f)** (Access to Financial Information), **11.1(m)** (Apportionment of Liquidated Damages under Construction Services Agreement) and **11.2(d)** (Termination Reimbursement) shall survive any termination of this Agreement. Notwithstanding any contrary

provision set forth in this or any other agreement, the representations, covenants, and obligations herein with respect to the SBL Purchase and Sale Agreement shall survive in accordance with the documents and instruments associated therewith.

**ARTICLE 16**  
**MISCELLANEOUS**

**Section 16.1 Opinion Regarding Tax-Exempt Bonds.**

If the Authority determines, based upon the written legal opinion of nationally recognized bond counsel, that any action under this Agreement creates a significant risk that interest on any tax-exempt bonds issued or proposed to be issued by the State for the Project will not be excludable from gross income for federal income tax purposes, the Parties shall negotiate in good faith to agree on alternative action to avoid such a result.

**Section 16.2 Waiver.**

No action taken pursuant to or related to this Agreement, including, without limitation, any investigation by or on behalf of a Party, shall be deemed to constitute a waiver by the Party taking such action of compliance with any representation, warranty, condition or agreement in this Agreement. A Party's exercise of or failure to exercise any such right or remedy shall not prevent the concurrent or subsequent exercise of any other right or remedy. A Party's delay or failure to exercise or enforce any rights or remedies shall not constitute a waiver of any such rights, remedies or obligations. No Party shall be deemed to have waived any default unless such waiver is expressly set forth in an instrument signed by such Party. If a Party waives in writing any default, then such waiver shall not be construed as a waiver of any covenant or condition set forth in this Agreement, except as to the specific circumstances described in such written waiver. Neither payment of a lesser amount than the sum due hereunder nor endorsement or statement on any check or letter accompanying such payment shall be deemed an accord and satisfaction, and the other Party may accept the same without prejudice to the right to recover the balance of such sum or to pursue any other remedy.

**Section 16.3 Additional Documents and Approval.**

The Parties, whenever and as often as each shall be reasonably requested to do so by the other Party, shall execute or cause to be executed any further documents and take any further actions as may be reasonably necessary or expedient and within their lawful obligation in order to consummate the transactions provided for in, and to carry out the purpose and intent of, this Agreement. Furthermore, the Authority shall take all ministerial actions and proceedings reasonably necessary or appropriate to remedy any apparent invalidity, lack or defect in authorization, or illegality, or to cure any other defect that has been asserted or threatened.

**Section 16.4 Good Faith.**

In exercising its rights and fulfilling its obligations under this Agreement, each of the Parties agrees to act in good faith. Each Party acknowledges that in each instance under this Agreement where a Party is obligated to exercise good faith or to use good faith, diligent or other

similar efforts, such Party shall not be required to, unless there is a specific obligation hereunder to do so, expend any funds, or grant any other consideration of any kind, in the performance of such undertaking. Each Party further acknowledges that the obligation of any Party to act in good faith, undertake good faith, act diligently or undertake other similar efforts does not constitute a warranty, representation or other guaranty that the result that the Parties are attempting to achieve shall be successfully achieved and no Party shall be liable for any failure to achieve the result or results intended so long as the Party has complied with its obligation to act in good faith, unless the achievement of the result or results intended are specifically required hereunder.

Section 16.5 Notice of Matters.

In the event that any Party receives knowledge about any matter that may constitute a breach of any of its warranties or covenants set forth in this Agreement that arises after the date of this Agreement, it shall promptly notify the other Parties of the same in writing.

Section 16.6 Form of Notices; Addresses.

All notices, requests, consents or other communications required under this Agreement shall be in writing and shall be deemed to have been properly given if served personally, or if sent by United States registered or certified mail, or overnight delivery service to the Parties as follows (or at such other address as a Party may from time to time designate by notice given pursuant to this **Section 16.6**):

**To the Team:** Minnesota Vikings Football, LLC  
9520 Viking Drive  
Eden Prairie, MN 55344  
Attn.: Kevin Warren  
Chief Operating Officer

**with copies to:** Briggs and Morgan, Professional Association  
2200 IDS Center  
80 South Eighth Street  
Minneapolis, MN 55402  
Attn.: Michael J. Grimes  
Steven J. Ryan  
Matthew A. Slaven



Minnesota Vikings Football, LLC  
9520 Viking Drive  
Eden Prairie, MN 55344  
Attn.: Lester Bagley  
Executive Vice President – Public Affairs &  
Stadium Development  
Attn.: Stephen LaCroix  
Executive Vice President &  
Chief Marketing Officer  
Attn.: Steven D. Poppen  
Executive Vice President &  
Chief Financial Officer

Garden Homes Development  
820 Morris Turnpike  
Short Hills, NJ 07078  
Attn.: Mark Wilf  
President  
Attn.: Donald Becker  
Stadium Project Executive

Proskauer Rose LLP  
Eleven Times Square  
80 South Eighth Street  
New York, NY 10036-8299  
Attn: Joseph M. Leccese  
Wayne D. Katz

**To the Authority:** Minnesota Sports Facilities Authority  
511 11<sup>th</sup> Avenue South, Suite 401  
Minneapolis, MN 55415  
Attn.: Michele Kelm-Helgen, Chair  
Attn.: Ted Mondale, CEO/Executive Director

**with copies to:** Dorsey & Whitney LLP  
50 South 6<sup>th</sup> Street, Suite 1500  
Minneapolis, MN 55402  
Attn.: Robert Hensley  
Attn.: Jay Lindgren

Fabyanske Westra Hart & Thomson PA  
800 LaSalle Avenue, Suite 1900  
Minneapolis, MN 55402  
Attn.: Mark W. Westra  
Attn.: Dean B. Thomson

Each notice shall be deemed given and received on the date delivered if served personally or by overnight delivery service or, if sent by United States registered or certified mail, then one (1) Business Day after its delivery to the address of the respective Party, as provided in this **Article 16**, except that with respect to the notices pertaining to matters that are to be accomplished within less than three (3) Business Days (e.g., requests for consent when the Person whose consent is sought has one (1) Business Day to respond in the granting or denying of such consent), notice shall be deemed given simultaneously with its delivery. Notices sent by a Party's counsel shall be deemed notices sent by such Party.

Section 16.7 Calculation of Time.

Unless otherwise stated, all references to "day" or "days" shall mean calendar days. If any time period set forth in this Agreement expires on other than a Business Day, such period shall be extended to and through the next succeeding Business Day.

Section 16.8 Incorporation by Reference.

All exhibits, schedules or other attachments referenced in this Agreement are hereby incorporated into this Agreement by such reference and are deemed to be an integral part of this Agreement.

Section 16.9 Entire Agreement.

Except as otherwise provided in this Agreement, this Agreement contains the sole and entire agreement between the Parties with respect to its subject matter and supersedes any and all other prior written or oral agreements between them with respect to such subject matter.

Section 16.10 Amendment.

No amendment modification or termination of this Agreement shall be valid unless in writing and duly executed by the Parties.

Section 16.11 Binding Effect; Assignment.

This Agreement shall be binding upon and shall inure to the benefit of the successors and assigns of the Parties hereof. Neither the Authority nor the Team shall assign its respective interests under this Agreement without the prior written consent of the other Party, except as contemplated with respect to the Team under **Section 8.12.**

Section 16.12 Headings.

The headings contained in this Agreement are for convenience of reference only, and shall not limit, extend or otherwise affect the meaning hereof.

Section 16.13 No Presumption Against Drafter.

This Agreement has been negotiated at arm's length and between Persons sophisticated and knowledgeable in the matters dealt with herein. In addition, each Party had been represented

by experienced and knowledgeable legal counsel. Accordingly, this Agreement shall be interpreted to achieve the intents and purposes of the Parties, without any presumption against the Party responsible for drafting any part of this Agreement.

**Section 16.14 Severability.**

If any term or provision of this Agreement or the application thereof to any Person or circumstance shall, to any extent, be inconsistent with, invalid or unenforceable under the Act, any Applicable Laws or Legal Requirements, the remainder of this Agreement, or the application of such term or provision to Persons or circumstances other than those as to which it was held invalid or unenforceable, shall not be affected thereby, and each term or provision of this Agreement shall be valid and enforceable to the fullest extent permitted by the Act, any Applicable Laws or Legal Requirements.

**Section 16.15 Third Party Beneficiaries.**

Nothing in this Agreement, express or implied, is intended to (a) confer upon any Person other than the Parties and their permitted successors and assigns any rights or remedies under or by reason of this Agreement as a third party beneficiary or otherwise except as specifically provided in this Agreement; or (b) authorize anyone not a Party to this Agreement to maintain an action pursuant to or based upon this Agreement. Notwithstanding the foregoing, (i) all Affiliates of the Team, including StadCo and (ii) the holder of any Leasehold Mortgage (as defined in Section 23.3 of the Stadium Use Agreement) are each intended direct third party beneficiaries of this Agreement with the right of direct enforcement of the provisions set forth herein. The Parties acknowledge and agree that the provisions of Section 23.1 (authorizing assignment of the Stadium Use Agreement and this Agreement to StadCo) and Sections 23.3(a)-(b) (authorizing the grant of a leasehold mortgage or other security interest to one or more Leasehold Mortgagees in the Stadium Use Agreement and this Agreement) of the Stadium Use Agreement are hereby incorporated by reference. Each Leasehold Mortgagee shall be entitled to all of the rights, privileges, and protections set forth in the Stadium Use Agreement with respect to this Agreement, including specifically Section 23.3(h) of the Stadium Use Agreement (notice and cure rights), as if such provisions were included in this Agreement.

**Section 16.16 Governing Law.**

This Agreement shall be governed by and construed in accordance with the laws of the State, notwithstanding its conflicts of law or choice of law provisions.

**Section 16.17 Execution in Counterparts and Delivery of Electronic Signatures.**

This Agreement may be executed in any number of counterparts. All such counterparts will be deemed to be originals and will together constitute but one and the same instrument. The executed counterparts of this Agreement may be delivered by electronic means, such as email and/or facsimile, and the receiving Party may rely on the receipt of such executed counterpart as if the original had been received.

Section 16.18 Relationship of Parties.

It is agreed that nothing contained in this Agreement shall be deemed or construed as creating a partnership or joint venture among the Parties.

Section 16.19 No Waiver of Authority Immunity or Liability.

Nothing contained in this Agreement, including but not limited to provisions regarding the Authority obtaining insurance or otherwise being insured, shall in any way affect or impair the Authority's immunity or the immunity of the Authority's employees or consultants or independent contractors, whether on account of official immunity, legislative immunity, statutory immunity, discretionary immunity or otherwise. Nothing contained in this Agreement, including but not limited to provisions regarding the Authority obtaining insurance or otherwise being insured, shall in any way affect or impair the limitations on the Authority's liability or the liability of the Authority's employees or consultants or independent contractors, set forth in Minnesota Statutes Chapter 466. By entering into this Agreement, the Authority does not waive any rights, protections or limitations provided for the Authority or its employees or consultants or independent contractors under the various rules of governmental immunity or under Minnesota Statutes Chapter 466.

Section 16.20 Conformity with the Act.

The Authority and the Team intend that this Agreement and all provisions in this Agreement conform to the Act and its requirements.


**[SIGNATURE PAGE FOLLOWS;  
REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]**

**EXECUTION COPY**

**IN WITNESS WHEREOF**, the Parties have executed this Agreement as of the date stated in the first paragraph of this Agreement.


**STADCO:**

**MINNESOTA VIKINGS FOOTBALL  
STADIUM, LLC,**  
a Delaware limited liability company

By:   
Mark Wilf, Owner/President

**Minnesota Vikings Football, LLC joins in  
this Agreement for the limited purposes  
described in Recital F of this Agreement:**

**MINNESOTA VIKINGS FOOTBALL,  
LLC**

By:   
Mark Wilf, Owner/President


**[SIGNATURE PAGE TO THIRD AMENDED AND RESTATED  
DEVELOPMENT AGREEMENT]**

**EXECUTION COPY**

**AUTHORITY:**

**MINNESOTA SPORTS FACILITIES  
AUTHORITY,**

a public body and political subdivision of the  
State of Minnesota

By:   
Michele Kelm-Helgen, Chair

By:   
Ted Mondale, CEO/Executive Director

**[SIGNATURE PAGE TO THIRD AMENDED AND RESTATED  
DEVELOPMENT AGREEMENT]**

**SCHEDULE 1**

**DEFINITIONS**

“**Act**” shall have the meaning set forth in the Recitals, as the same may be amended, modified or supplemented from time to time; **provided, however,** no such amendment, modification, or supplement of the Act shall change the rights, obligations, or covenants of the Parties hereto unless any such amendment, modification, or supplement is incorporated to this Agreement by written amendment executed and delivered by the Parties to the terms of this Agreement.

“**Affiliate**” of a specified Person shall mean any corporation, partnership, limited liability company, sole proprietorship or other Person that directly or indirectly, through one or more intermediaries controls, is controlled by, or is under common control with the Person specified. For purposes of this definition, the terms “controls,” “controlled by,” or “under common control” mean the possession, direct or indirect, of the power to direct or cause the direction of the management and policies of a Person.

“**Agreement**” shall have the meaning set forth in the preamble, as the same may be amended, modified or supplemented from time to time.

“**Alternate Representative**” or “**Alternate Representatives**” shall mean one (1) or more of the Authority Alternate Representatives or the Team Alternate Representatives.

“**Amended Preliminary Project Budget**” shall have the meaning set forth in **Section 8.1(a)(i)**.

“**Amendment**” shall have the meaning set forth in the Recitals.

“**Applicable Law**” or “**Applicable Laws**” shall mean any and all laws (including all statutory enactments and common law), ordinances, constitutions, regulations, treaties, rules, codes, standards, permits, requirements and orders that (i) have been adopted, enacted, implemented, promulgated, ordered, issued, entered or deemed applicable by or under the authority of any Governmental Authority or arbitrator having jurisdiction over a specified Person (or the properties or assets of such Person), and (ii) are applicable to this Agreement or the performance of the obligations of the Parties under this Agreement. For the avoidance of doubt, Environmental Laws are included in Applicable Laws.

“**Approval Documents**” shall have the meaning set forth in **Section 8.2(a)(v)**.

“**Approval Request**” shall have the meaning set forth in **Section 8.2(a)(v)**.

“**Architect**” shall have the meaning set forth in **Section 3.1(a)**.

“**Authority**” shall have the meaning set forth in the preamble.

“**Authority Alternate Representatives**” shall mean Steve Maki and Craig Skiem, the Persons designated as alternates to the Authority Representatives with the authority to serve in

place of, and with the authority of, the Authority Representatives, or any successor to the foregoing Persons designated in writing by the Authority by notice to the Team.

**“Authority Contribution”** shall mean Four Hundred Ninety-Eight Million Dollars (\$498,000,000), which amounts shall be granted to the Authority pursuant to the Grant Agreement.

**“Authority Design Add Alternates”** shall have the meaning set forth in **Section 8.1(e)(iii)(A).**

**“Authority Funding Percentage”** shall have the meaning set forth in **Section 8.2(a)(vi).**

**“Authority Indemnified Persons”** shall mean the Authority and its elected officials, appointed officials, board members, officers, employees, agents and attorneys.

**“Authority Project Cost Allocation Reductions”** shall have the meaning set forth in **Section 8.1(e)(iii).**

**“Authority Representatives”** shall mean Michele Kelm-Helgen and Ted Mondale or any successor to the foregoing Persons designated in writing by the Authority by notice to the Team.

**“Authority Stadium Builder License Program”** shall have the meaning set forth in **Section 8.7(b).**

**“Authorized Representatives”** shall have the meaning set forth in **Section 2.2(a).**

**“Bank Loan Commitment”** shall have the meaning set forth in **Section 8.2(a)(v)(C).**

**“Bank Loan Commitment Parties”** shall have the meaning set forth in **Section 8.2(a)(v)(C).**

**“Bank Loan Facility”** shall have the meaning set forth in **Section 8.2(a)(v)(C).**

**“Business Day”** shall mean any day other than a Saturday, Sunday or other day on which banks are required or authorized to close in Minneapolis, Minnesota.

**“Capital Reserve Fund”** shall mean the fund established by the Authority pursuant to Minnesota Statutes section 473J.13, subd. 4 to receive and reserve funds for payment of Capital Enhancements (as such term is defined in the Stadium Use Agreement) for the Stadium and Stadium Infrastructure.

**“Catwalk Netting Budget”** shall have the meaning set forth in **Section 5.1(x).**

**“Certification of GMP”** shall have the meaning set forth in **Section 2.3(b).**

**“Change Orders”** shall mean any change orders or change directives that are intended to implement changes in the Contract Documents to work or materials, contract time or milestone dates, or contract price. For purposes of this Agreement, the term Change Order shall have the



same meaning as the terms “Contract Revision” and “Construction Change Directive” as defined and utilized in the Construction Services Agreement and shall also mean the Stadium Developer’s written approval of the Construction Manager’s expenditure or utilization of the Construction Manager Contingency (as that term is defined and used in the Construction Services Agreement) as is authorized by the Construction Services Agreement.

“**City**” shall mean the City of Minneapolis, Minnesota.

“**Claim**” shall mean any claim, demand or dispute between or among the Parties relating to this Agreement or the Project, and may include incidental, consequential, exemplary, punitive and similar Damages when asserted in connection with a third party Claim.

“**Commemorative Bricks**” shall have the meaning set forth in Section 5.1(q)(i).

“**Commencement Date**” shall mean the date of Substantial Completion of the Stadium (i.e., the date that the Stadium is ready for opening to the general public and full occupancy or use by the Team), and a certificate of occupancy issued by the appropriate Governmental Authorities, if required, has been obtained.

“**Completion Date**” shall mean the date that is the earlier of (i) the date on which the Team has commenced occupancy of the Stadium pursuant to the Stadium Use Agreement, or (ii) the date on which the following have occurred: (a) the Architect has issued to the Stadium Developer a certificate of Substantial Completion certifying that the Project has been “substantially completed,” subject to the completion of minor punchlist items that do not materially affect the use or occupancy of the Stadium; and (b) a temporary certificate of occupancy has been issued by the City.

“**Conceptual Design Documents**” shall mean the preliminary project work plan, programming report, and pre-design document, concept sketches and renderings illustrating the scale and relationship of the Project components.

“**Concession Equipment**” shall have the meaning set forth in Section 5.1(o)(i).

“**Concession Equipment Budget**” shall have the meaning set forth in Section 5.1(o)(ii).

“**Condemnation**” shall mean any taking of property by exercise of the power of eminent domain, whether by formal condemnation proceedings or by purchase under the threat of the exercise of the power of eminent domain.

“**Conditional Assignments**” shall have the meaning set forth in Section 8.7(d).

“**Construction Change Directive**” shall have the meaning set forth in the definition of “Change Orders”.

“**Construction Management Plan**” shall mean the comprehensive document prepared by the Construction Manager, submitted pursuant to the procedures set forth in Article 5 of the Construction Services Agreement for review and approval by the Authority and Team, and setting forth in detail the Construction Manager’s planning, administrative and management

techniques to complete the Construction Manager's Work (as defined in the Construction Services Agreement).

**"Construction Manager"** shall have the meaning set forth in Section 3.1(b).

**"Construction Monitor"** shall mean an independent engineering firm selected for the purpose of reviewing the Development Agreement Documents (as defined in the Stadium Use Agreement), making inspections of the Stadium and Stadium Infrastructure during the Construction Phase and issuing reports that (i) detail the construction work completed to date, (ii) review and advise on all requisitions for disbursement of proceeds of all loans relating to the Team Contribution, (iii) provide an analysis of the adequacy of the source of funds to complete the Project and (iv) analyze and advise on all proposed material Change Orders and Change Orders that involve an expenditure from the Owner's Contingency.

**"Construction Phase"** shall mean the period of time commencing upon the Authority's written approval of the Construction Manager's Construction Management Plan and issuance of notice to proceed with the Construction Manager's "Construction Phase Services" (as defined in the Construction Services Agreement) and which period shall conclude upon Final Completion (as defined in the Construction Services Agreement).

**"Construction Requisition"** shall have the meaning set forth in Section 8.5(d).

**"Construction Services Agreement"** shall mean that certain Construction Services Agreement between the Authority and the Construction Manager dated February 15, 2013, as the same may be amended, modified or supplemented from time to time.

**"Construction Services Agreement Savings Share"** shall have the meaning set forth in Section 8.1(b)(i)(B).

**"Construction Team"** shall mean (i) the Stadium Developer's Representatives or his/her Alternate Representatives, (ii) the Construction Manager, (iii) the Architect, and (iv) any other consultants, such as an owner's representative, deemed necessary by the Authority and Team to assist in the design, construction or development of the Project.

**"Contamination"** shall mean the presence or release or threat of release of Regulated Substances in, on, under or emanating to or from the Stadium Site, which pursuant to Environmental Laws requires notification or reporting to any Governmental Authority, or which pursuant to Environmental Laws requires the identification, investigation, cleanup, removal, remediation, containment, control, abatement, monitoring of or other Response Action to such Regulated Substances, or which otherwise constitutes a violation of Environmental Laws.

**"Contingency Letter of Credit"** shall have the meaning set forth in Section 8.1(a)(iii).

**"Contract Documents"** shall mean this Agreement, the Construction Services Agreement, the Design Services Agreement and the other contracts and agreements described in the Design Services Agreement.

**“Contract Revision”** shall have the meaning set forth in the definition of “Change Orders”.

**“Cost Overrun”** shall mean any Project Costs in excess of the Master Project Budget.

**“Cost Savings”** shall have the meaning set forth in Section 8.1(d).

**“Critical Design Decisions”** shall have the meaning set forth in Section 5.3.

**“Damages”** shall mean any loss, liability, claim, damage, cost and expense, including costs of investigation and defense and reasonable attorneys’ fees, whether the action is for money damages, or for equitable or declaratory relief.

**“Design Add Alternates”** shall have the meaning set forth in Section 8.1(e)(iii).

**“Design Delivery Schedule”** shall mean the schedule covering design services to be performed by the Architect and the Architect’s consultants as set forth in Article 4 of the Design Services Agreement.

**“Design Development Documents”** shall mean the Drawings, Specifications and other documents prepared by the Architect that establish and describe the size and character of the Project as to architectural, civil, structural, landscape, mechanical and electrical systems, graphics and signage, and other elements, and which include typical construction details, equipment layouts and specifications that identify major materials and systems and as more specifically described in the Design Services Agreement.

**“Design Impasse”** shall have the meaning set forth in Section 5.4.

**“Design Meetings”** shall have the meaning set forth in Section 5.2(a)(i).

**“Design Services Agreement”** shall mean that certain Design Services Agreement between the Architect and the Authority dated September 28, 2012, as the same may be amended, modified or supplemented from time to time.

**“Design Team”** shall mean Architect and its sub-consultants.

**“Development Agreement Assignment”** shall have the meaning set forth in the Recitals.

**“Development Requisition”** shall have the meaning set forth in Section 8.5(c).

**“Disbursement Request”** shall mean the disbursement documents agreed upon pursuant to Section 8.5.

**“Disbursing Agent”** shall have the meaning set forth in Section 8.5(b).

**“Disbursing Agreement”** shall have the meaning set forth in Section 8.5(b), as the same may be amended, modified or supplemented from time to time.

**“Distributed Antenna System” or “DAS”** shall mean a network of spatially separated antenna nodes connected to a common source via a transport medium that increases the capacity and coverage of wireless services within the Stadium.

**“Downtown East Parcel”** shall have the meaning set forth in Section 5.1(p)(iii)(A).

**“Drawings”** shall mean graphic or pictorial portions of the Design Development Documents prepare by Architect, subconsultants, and consultants, wherever located and whenever issued, which show, among other things, the design, location and dimensions of the work, generally including plans, elevations, sections, details, schedules and diagrams.

**“East Event Level Locker Room Buildout”** shall have the meaning set forth in Section 5.1(n)(i).

**“East Event Level Locker Rooms Budget”** shall have the meaning set forth in Section 5.1(n)(ii).

**“Effective Date”** shall have the meaning set forth in the preamble; provided, however, for purposes of clarity, the “Effective Date” of the Original Agreement and the First Amended and Restated Agreement, and their respective remaining provisions is October 3, 2013 and the “Effective Date” of the provisions set forth in the Amendment which have been incorporated to this Agreement is February 10, 2014.

**“Effective Date Minimum Design Standards”** shall have the meaning set forth in Section 5.1(a) and are set forth in Exhibit C-1.

**“EIS”** shall mean the environmental impact statement, to be prepared by the Environmental Consultant, that contains all information, analysis and recommendations required by Minnesota Statutes Chapter 116D and related rules and regulations.

**“Environmental Consultant”** shall mean Kimley-Horn and Associates, Inc., a North Carolina corporation.

**“Environmental Law”** shall mean all Applicable Laws, including, without limitation, any consent decrees, settlement agreements, judgments, or orders, issued by or entered into with a Governmental Authority pertaining or relating to: (i) pollution or pollution control; (ii) protection of human health or the environment; (iii) the presence, use, management, generation, processing, treatment, recycling, transport, storage, collection, disposal or release or threat of release of Regulated Substances; (iv) the presence of Contamination; or (v) the protection of endangered or threatened species.

**“Event of Default”** shall have the meaning set forth in Section 12.1.

**“Expedited ADR”** shall have the meaning set forth in Section 13.1(a).

**“Expedited ADR Dispute”** shall have the meaning set forth in Section 13.1(a).

**“February 19, 2016 SDC Group Action”** shall have the meaning set forth in Section 2.2(f).

**“Field Turf Budget”** shall have the meaning set forth in Section 5.1(y).

**“Final Minimum Design Standards”** shall have the meaning set forth in Section 5.1(a) and are set forth in Exhibit C-2.

**“Final Stadium Site”** shall have the meaning set forth in Section 5.1(c).

**“Financial Security”** shall mean one or more letters of credit, cash, marketable debt or equity securities or other liquid collateral, or other security or creditworthiness satisfactory to the Authority, issued or pledged to or for the benefit of the Authority to assure that a portion or portions of the Team Contribution and any Private Contribution Shortfall shall be paid when required.

**“FinCo”** shall have the meaning set forth in Section 8.2(a)(v)(C).

**“First Amended and Restated Agreement”** shall have the meaning set forth in the Recitals.

**“First Priority Joint Funded Design Add Alternates”** shall have the meaning set forth in Section 8.1(e)(ii)(E).

**“Fixed Bowl Seating”** shall have the meaning set forth in Section 5.1(k)(i).

**“Football Playing Agreement”** shall mean that certain agreement between the Authority and the Team concurrently executed on the Effective Date.

**“Force Majeure”** shall mean acts of God, accidents, fire or other casualty, earthquake, hurricane, tornadoes, named storms, flood, war, riot, intervention by civil or military authorities of government, insurrection, or other civil commotion, governmental action (excluding any governmental action or inaction with respect to the granting or withholding of any governmental approvals or permits needed for the construction of the Project, acts or omissions of the Authority or the City, or the acquisition of the Stadium Site), material shortages, strikes, boycotts, lockouts or labor disputes (but not including player labor stoppages, whether attributable to strikes or lockouts), or any other similar or like event or occurrence beyond the reasonable control of a Party hereto, that causes such Party to be delayed or hindered in, or prevented from, the performance of any covenant or obligation hereunder.

**“Geotechnical Report”** shall mean, individually and collectively, the existing, updated or newly prepared reports issued by various Project Consultants, as each may be supplemented and updated.

**“GMP”** shall mean guaranteed maximum price, and all contractual services and obligations to be performed for that price, pursuant to the Construction Services Agreement, or any successor agreement, which is certified in the manner set forth in Section 2.3(b).

**“Governmental Authority”** shall mean any federal, state, county, city, local or other government or political subdivision or any agency, authority, board, bureau, commission, department or instrumentality thereof.

**“Grant Agreement”** shall mean that certain Grant Agreement dated November 1, 2013 (or such other date mutually agreed to by the parties thereto), by and between the State and the Authority.

**“Hennepin County Medical Examiner Parcel”** shall have the meaning set forth in **Section 5.1(p)(ii)**.

**“Insurance Proceeds”** shall have the meaning set forth in **Section 6.8(c)**.

**“Legal Requirements”** shall mean present and future Applicable Laws (including Environmental Laws) applicable to the design, development, construction, equipping, use, occupancy, possession, operation, maintenance and management of the Project, including all Applicable Laws relating to the issuance of any bonds or the exclusion of interest on such bonds from gross income for federal tax purposes, if such bonds are issued by any Governmental Authority in connection with the financing of the Project.

**“Losses”** shall mean all losses, liabilities, costs, charges, judgments, claims, damages, penalties, fines and expenses (including attorneys’ fees and expenses and costs of investigation and arbitration or litigation).

**“Magnetometer Acquisition Budget”** shall have the meaning set forth in **Section 5.1(w)**.

**“Master Project Budget”** shall mean the master project budget as developed by the SDC Group and approved in writing by the Authority and the Team, as updated, modified, supplemented, or amended from time to time in accordance with this Agreement. A copy of the Master Project Budget shall be attached as **Exhibit F-2** hereto as provided in **Section 8.1(a)(ii)**.

**“Master Project Program”** shall have the meaning set forth in **Section 4.2**.

**“Master Project Schedule”** shall mean the master project schedule as developed by the SDC Group and updated, modified, supplemented, or amended from time to time in accordance with this Agreement. A copy of the Master Project Schedule is attached as **Exhibit R-2** hereto.

**“Metrodome”** shall mean the Hubert H. Humphrey Metrodome and Mall of America Field at the Hubert H. Humphrey Metrodome.

**“Minnesota Multi-Purpose Stadium Construction Services Agreement Equity Plan”** shall mean the Minnesota Multi-Purpose Stadium Construction Services Agreement Equity Plan adopted by the Authority on February 8, 2013.

**“MPCA”** shall have the meaning set forth in **Section 7.2(b)**.

**“National Football League”** or **“NFL”** shall mean, collectively, the Office of the National Football League Commissioner, the National Football League Commissioner, the member clubs of the National Football League, the NFL owners, and/or any other Person appointed by any of the foregoing, or any successor substitute association or entity of which the Team is a member or joint owner and which engages in professional football in a manner comparable to the National Football League.

**“Net Available Amount”** shall have the meaning set forth in Section 8.2(a)(v).

**“Neutral”** shall have the meaning set forth in Section 13.1(b)(i).

**“NFL Broadcast Requirements”** shall have the meaning set forth in Section 5.1(u)(i).

**“NFL Broadcast Requirements Budget”** shall have the meaning set forth in Section 5.1(u)(ii).

**“NFL G-4 Facility”** shall have the meaning set forth in Section 8.2(a)(v)(B).

**“NFL G-4 Resolution”** shall have the meaning set forth in Section 8.2(a)(v)(B).

**“NFL Lenders”** shall have the meaning set forth in Section 8.2(a)(v)(B).

**“Notice of Design Impasse”** shall have the meaning set forth in Section 13.1(b)(i).

**“Operable Feature”** shall mean the large mechanized pivoting doors located at the main entrance to the Stadium as finally determined by SDC action.

**“Original Agreement”** shall have the meaning set forth in the Recitals.

**“Owner’s Contingency”** shall have the meaning set forth in Section 8.1(b).

**“Owner’s Contingency Release Schedule”** shall have the meaning set forth in Section 8.1(b)(i)(A).

**“Party”** or **“Parties”** shall mean either or both of the Authority and the Team.

**“Permits”** shall mean any permit, license or approval to be issued by any Person, including Required Environmental Permits, required permits for construction, demolition, installation, alteration or repair of any improvements related in any manner to the Project.

**“Permitted Encumbrances”** shall mean only the following liens and encumbrances on title to the Stadium Site: (i) this Agreement; (ii) the Stadium Use Agreement; (iii) liens for real estate taxes and installments of special assessments not yet due and payable; (iv) liens and encumbrances on the Team’s interest under Stadium Use Agreement granted or caused by the Team; (v) liens and encumbrances granted or caused by the Authority, with the consent of the Team; (vi) easements that do not materially restrict or interfere with the construction of the Project or the efficient operation of the Stadium in a manner consistent with a multi-purpose stadium and a first-class venue for the NFL; (vii) liens or encumbrances that have been

unconditionally subordinated in writing to the interests of the Authority as fee owner and the Team and its affiliates under the Stadium Use Agreement upon such terms as are satisfactory to the Team, in its sole and absolute discretion; and (viii) liens in favor of lenders providing financing for the Project as contemplated in this Agreement.

**“Person”** shall mean any natural person, sole proprietorship, corporation, partnership, trust, limited liability company, limited liability association, unincorporated association, joint venture, joint-stock company, Governmental Authority, or any other entity.

**“Phase I”** shall mean a Phase I Environmental Site Assessment Report to be prepared and issued by Braun Intertec within a reasonable time following the Execution Date.

**“Phase II”** shall mean any further environmental assessment required or contemplated by the Phase I to determine the extent and nature of any Contamination.

**“Potential Neutral”** or **“Potential Neutrals”** shall have the meaning set forth in **Section 13.1(b)(i)**.

**“Preliminary Development Agreement”** shall have the meaning set forth in the Recitals, as the same may be amended, modified or supplemented from time to time.

**“Preliminary Program”** shall have the meaning set forth in **Section 4.1**. A copy of the Preliminary Program is attached as **Exhibit B-1** hereto.

**“Preliminary Project Budget”** means the preliminary project budget contemplated by the Preliminary Development Agreement, agreed upon by the SDC Group and attached as **Exhibit F-1** hereto.

**“Preliminary Project Schedule”** means the preliminary schedule attached as Exhibit C to the Preliminary Development Agreement, a copy of which is attached to this Agreement as **Exhibit R-1**, and forms the basis of the Master Project Schedule to be developed and agreed upon pursuant to this Agreement.

**“Preliminary Stadium Site”** shall have the meaning set forth in **Section 5.1(c)**.

**“Prime Rate”** shall have the meaning set forth in **Section 14.1**.

**“Private Contribution Shortfall”** shall have the meaning set forth in **Section 8.2(a)(iii)**.

**“Private Contribution”** shall have the meaning set forth in **Section 8.2(a)(iii)**.

**“Privately Financed Enhancement”** shall mean additions or enhancements to the Project agreed upon by the Parties that are paid for solely by the Team or other private entity in amounts above the Preliminary Project Budget as set forth in **Exhibit F-1**.

**“Proceeds”** shall have the meaning set forth in **Section 8.1(a)(iv)**.



**“Project”** shall mean the Stadium and Stadium Infrastructure, including without limitation, all activities relating to the planning, development, design and construction of the Stadium and Stadium Infrastructure.

**“Project Accounts”** shall mean those accounts to be jointly established by the Authority and the Team to hold the Project Funds.

**“Project Consultants”** shall have the meaning set forth in **Section 3.3.**

**“Project Cost Allocation Reductions”** shall have the meaning set forth in **Section 8.1(e)(iii).**

**“Project Costs”** shall mean all eligible costs and expenses of the Project, including (i) the costs of acquiring the Stadium Site, (ii) the costs of the Stadium Infrastructure, and (iii) the costs of designing, constructing, equipping, and financing the Stadium, all as agreed upon by the SDC Group pursuant to this Agreement. Project Costs shall not include the costs otherwise arising out of negligent actions or omissions or breach of the Agreement on the part of the Party that is not serving as Stadium Developer.

**“Project Funds”** shall mean for the purposes of this Agreement the amounts remitted by the Team pursuant to this Agreement, which shall be considered part of the team/private contribution described in Minnesota Statutes section 473J.15, subd. 2(a).

**“Project Labor Agreement”** shall have the meaning set forth in **Section 6.7.**

**“Project Representative”** shall have the meaning set forth in **Section 2.2(j).**

**“Radio and Television Cabling Requirements”** shall have the meaning set forth in **Section 5.1(v)(i).**

**“Radio and Television Cabling Requirements Budget”** shall have the meaning set forth in **Section 5.1(v)(ii).**

**“Regulated Substances”** shall mean any substance, material or waste, regardless of its form or nature, defined under Environmental Laws as a “hazardous substance,” “hazardous waste,” “toxic substance,” “extremely hazardous substance,” “toxic chemical,” “toxic waste,” “solid waste,” “industrial waste,” “residual waste,” “municipal waste,” “special handling waste,” “mixed waste,” “infectious waste,” “chemotherapeutic waste,” “medical waste,” “regulated substance,” “pollutant” or “contaminant” or any other substance, material or waste, regardless of its form or nature that otherwise is regulated by Environmental Laws.

**“Rejected Title Defects”** shall have the meaning set forth in **Section 7.1(b).**

**“Representative”** or **“Representatives”** shall mean one (1) or more of the Authority Representatives or the Team Representatives. In the event of absence or inability to act of an Authority Representative or a Team Representative, “Representative” shall include an Authority Alternate Representative or a Team Alternate Representative, respectively.

**“Required Environmental Permits”** shall mean Permits, licenses, bonds, consents, programs, approvals or authorizations required under Environmental Laws for the construction of the Project, or required by the Team to conduct its operations, maintain or use the Stadium or construct, maintain, operate or use any alterations or improvements, regardless of whether such Permits are required to be or have been obtained by the Authority or the Team.

**“Response Action”** shall mean the investigation, cleanup, removal, remediation, containment, control, abatement, monitoring of or any other response action to the presence of Regulated Substances or Contamination in, on, at, under or emanating from the Stadium Site, including the correction or abatement of any violation required pursuant to Environmental Laws, Required Environmental Permits or by a Governmental Authority.

**“Retractable Bowl Seating”** shall have the meaning set forth in Section 5.1(k)(ii).

**“Roster of Potential Neutrals”** shall have the meaning set forth in Section 13.1(b)(i).

**“SBL”** means a stadium builders license that entitles the SBL Licensee to, among other things, buy season tickets to certain Team games and other Stadium events for a certain seat in the Stadium.

**“SBL Contract”** means the license agreement relating to an SBL.

**“SBL Licensee”** means the licensee under an SBL.

**“SBL Marketing and Sales Agreement”** shall have the meaning set forth in Section 8.7(b), as the same may be amended, modified or supplemented from time to time.

**“SBL Public Sale”** shall have the meaning set forth in Section 8.2(a).

**“SBL Purchase and Sale Agreement”** shall have the meaning set forth in Section 8.7(b).

**“SBL Purchase and Sale Facility”** shall have the meaning set forth in Section 8.7(b).

**“SBL Related Costs and Expenses”** shall mean the Authority’s fees, costs and expenses previously incurred or reasonably expected to be incurred under the SBL Marketing and Sales Agreement or the SBL Purchase and Sale Agreement or otherwise associated with the generation of the SBL Revenues (such as costs and expenses incurred in the structuring and documentation of the SBL program, and the marketing, sale, remarketing, and resale of SBLs), including without limitation all fees, costs, expenses and other amounts payable by the Authority to the Team, as agent, or any subagent or entity engaged to structure, develop, market and/or sell SBLs, provided that such fees, costs, and expenses shall be evidenced by supporting documentation.

**“SBL Revenue Sale”** shall have the meaning set forth in Section 8.2(a).

**“SBL Revenues”** means, collectively: (i) all payments, revenues, rents, royalties, issues, profits, fees, proceeds and other amounts paid or payable to the seller under or relating to an SBL Contract (including any replacement SBLs) sold, or caused to be sold, by the seller, including

any financing fees and interest relating to the financing of an SBL Contract, (ii) all other rights (but not any obligations) of the seller under the related SBL Contracts, (iii) any and all proceeds related to the foregoing, and (iv) all insurance or condemnation proceeds payable to the seller in the event of a casualty event with respect to all or any portion of the Stadium or in the event of a condemnation of all or any portion of the Stadium in accordance with this Agreement and the Stadium Use Agreement in each case as allocated to the Private Contribution; but only to the extent that (a) the items in clauses (i) to (iii) above are received and/or collected at any time prior to the tenth anniversary of the first home game of the Team played at the Stadium and (b) in the case of the item in clause (iv) above, the casualty or condemnation event occurs prior to the tenth anniversary of the first home game of the Team played at the Stadium.

“**SBL Sale**” shall have the meaning set forth in **Section 8.2(a)**.

“**Schematic Design Documents**” shall mean drawings prepared by the Architect that illustrate the scale and relationship of the various Project components and which also contain square footage and volume calculations for the building interior spaces, building exterior spaces, and major architectural and interior finishes.

“**SDC Chair**” shall have the meaning set forth in **Section 2.2(b)**.

“**SDC Group**” shall have the meaning set forth in **Section 2.1**.

“**Second Amended and Restated Agreement**” shall have the meaning set forth in the Recitals.

“**Second Amended and Restated Agreement Amendments**” shall have the meaning set forth in the Recitals.

“**Second Amendment Effective Date**” shall have the meaning set forth in the Recitals.

“**Settlement Agreement**” means that certain Settlement Agreement and Release by and among the Authority, Construction Manager and certain members of the Design Team dated February 10, 2016.

“**Specifications**” shall mean the written specifications prepared by Architect, subconsultants and consultants consisting of the written requirements for materials, equipment, technical requirements and construction systems, standards and workmanship for the work, and performance of related services.

“**StadCo**” shall have the meaning set forth in the preamble.

“**Stadium**” shall mean the stadium suitable for professional football to be designed, constructed, and financed under the Act, as more fully described in this Agreement.

“**Stadium Developer**” shall mean whichever of the Authority or the Team is acting in the role of the Stadium Developer as set forth in **Section 6.1** hereof.

**“Stadium Implementation Committee”** shall mean the Stadium Implementation Committee that has been established pursuant to the Act.

**“Stadium Infrastructure”** shall mean plazas, including the Stadium Plaza, parking structures, rights-of-way, connectors, skyways and tunnels, and other such property, facilities, and improvements, owned by the Authority or determined by the Authority to facilitate the use and development of the Stadium.

**“Stadium Lighting”** shall have the meaning set forth in Section 5.1(i)(i).

**“Stadium Lighting Budget”** shall have the meaning set forth in Section 5.1(i)(ii).

**“Stadium Mechanized Pivoting Doors”** shall have the meaning set forth in Section 5.1(l)(i).

**“Stadium Mechanized Pivoting Doors Budget”** shall have the meaning set forth in Section 5.1(l)(ii).

**“Stadium Plaza”** shall mean the open air portion of the Stadium Infrastructure immediately adjacent to the Stadium.

**“Stadium Plaza Design Area”** shall have the meaning set forth in Section 5.1(p)(iii)(A).

**“Stadium Plaza Improvements”** shall have the meaning set forth in Section 5.1(p)(i).

**“Stadium Plaza Improvements Budget”** shall have the meaning set forth in Section 5.1(p)(ii).

**“Stadium Scrim Signage Positions”** shall have the meaning set forth in Section 5.1(m)(i).

**“Stadium Site”** shall mean the real property, rights, easements, and access areas initially set forth on Exhibit D-1-B attached hereto as further determined by the Authority and agreed to by the Team upon the recommendation of the SDC Group pursuant to Section 2.2(e), and shall include the site of the Stadium and Stadium Infrastructure.

**“Stadium Sponsored Signage”** shall have the meaning set forth in Section 5.1(j)(i).

**“Stadium Sponsored Signage Budget”** shall have the meaning set forth in Section 5.1(j)(ii).

**“Stadium Use Agreement”** shall have the meaning set forth in the Recitals, as the same may be amended, modified or supplemented from time to time.

**“State”** shall mean the State of Minnesota.

**“Statement of Dispute”** shall have the meaning set forth in Section 13.1(b)(ii).

**“Substantial Completion”** or **“Substantially Complete”** shall mean the work (or separable units or phases as provided in the Contract Documents) is essentially and satisfactorily complete in accordance with the Contract Documents, such that the Project is ready for opening to the general public and full occupancy or use by Authority (it being understood that, without limitation of the foregoing, all suites, concessions and other income-generating areas and all areas serving the general public shall be ready for full operation without material inconvenience or discomfort). A minor amount of work, as determined by and at the discretion of Authority, such as installation of minor accessories or items, a minor amount of painting, minor replacement of defective work, minor adjustment of controls or sound systems, or completion or correction of minor exterior work that cannot be completed due to weather conditions, will not delay determination of Substantial Completion. For purposes of Substantial Completion, specified areas of the entire work or Project may be individually judged as Substantially Complete. In no event shall Substantial Completion be deemed to have occurred unless such certificates or licenses as required for opening of the Project to the general public have been issued to Authority.

**“Target Private Contribution Amount”** shall have the meaning set forth in Section 8.2(a)(iii).

**“Task List”** shall have the meaning set forth in Section 5.3.

**“Team”** shall have the meaning set forth in the Recitals.

**“Team Alternate Representatives”** shall mean Kevin Warren and Lester Bagley, the Persons designated as alternates to the Team Representatives with the authority to serve in place of, and with the authority of, the Team Representatives, or any successor to the foregoing Persons designated by the Team by notice to the Authority.

**“Team Contribution”** shall have the meaning set forth in Section 8.2(a)(iii).

**“Team Design Add Alternates”** shall have the meaning set forth in Section 8.1(e)(iii)(B).

**“Team Indemnified Persons”** shall mean the Team and its respective members, owners, partners, officers, directors, employees, affiliates, parents, subsidiaries, agents and attorneys.

**“Team Initial Payment”** shall mean Fifty Million Dollars (\$50,000,000).

**“Team/Private Funding Percentage”** shall have the meaning set forth in Section 8.2(a)(vi).

**“Team Project Cost Allocation Reductions”** shall have the meaning set forth in Section 8.1(e)(iii).

**“Team Representatives”** shall mean Donald Becker and Steven Poppen, or any successor to the foregoing Persons designated by the Team by notice to the Authority.

**“Team Source of Funds”** shall have the meaning set forth in Section 8.2(a)(v).

**“Team/Private Contribution”** shall have the meaning set forth in Section 8.2(a)(iii).

**“Team’s Beneficial Rights”** shall have the meaning set forth in Section 8.10(d).

**“Team’s Stadium Property”** shall have the meaning set forth in Section 8.10(b).

**“Team’s Stadium Property Schedule”** shall mean the schedule of the Team’s beneficial stadium property and allocation of the Team’s investment as set forth in Section 8.10(c).

**“Term”** shall have the meaning set forth in Section 15.1.

**“Third Amended Effective Date”** shall have the meaning set forth in the Recitals.

**“Title Defect”** shall mean any lien, encumbrance, easement, license, right-of-way, covenant, condition, restriction, or other title defect encumbering the Stadium Site that is not either a Permitted Encumbrance or caused by the acts of the Team or its agents, contractors, employees and tenants.

**“Title Evidence”** shall have the meaning set forth in Section 7.1(b).

**“Trust Account”** shall have the meaning set forth in Section 8.3(a)(ii).

**“Trust Agreement”** shall have the meaning set forth in Section 8.3(a)(ii).

**“Trust and Disbursement Agreement”** shall mean that certain Agreement and Declaration of Trust and Disbursement Agreement dated December 14, 2012, by and among the Team, the Authority and the Trustee, as the same may be amended, modified or supplemented from time to time.

**“Trustee”** shall mean U.S. Bank National Association, a national banking association, not individually but solely as trustee (together with its successors and assigns in such capacity).

**“Vendor Contract Technology”** shall have the meaning set forth in Section 5.1(b)(i).

**“Vendor Contract Technology Budget”** shall have the meaning set forth in Section 5.1(b)(ii).

**“WiFi”** shall mean a wireless local area network based on the Institute of Electrical and Electronics Engineers, Inc. 802.11 standards that uses radio waves to connect electronic devices to the Internet and promote connectivity within the Stadium.

**“WiFi Budget”** shall have the meaning set forth in Section 5.1(r)(ii).

**“WiFi Communications System”** shall have the meaning set forth in Section 5.1(r)(i).

**“Wind-Up”** shall have the meaning set forth in Section 15.4(c).

**“Wind-Up Events”** shall have the meaning set forth in Section 15.4(c).

**EXHIBIT A**

**SDC GROUP RULES AND PROCEDURES**

1. Meeting; Notice. Unless the Parties agree otherwise, the SDC Group shall meet (i) no less frequently than monthly, (ii) at special meetings called by either the Authority Representatives or the Team Representatives, and (iii) at special meetings called by any Party following two (2) Business Days' prior notice of such a special meeting to the other Party's Representatives. The SDC Chair of the SDC Group shall provide notice to the members of the SDC Group stating the place (or means if by telephone conference or other means), date and hour of each meeting of the SDC Group, together with a detailed agenda for the meeting, not less than one (1) Business Day before the date of the meeting (unless such notice is waived by an Authorized Representative of each Party either at the meeting or by written consent before or after the meeting). Any Party may submit an item for inclusion on the agenda of a SDC Group meeting. Attendance at a meeting of the SDC Group shall constitute a waiver of notification of the meeting.

2. Attendance. Each Party shall use commercially reasonable efforts to cause its Representatives or Alternate Representatives to attend each meeting of the SDC Group, and no Party shall withhold the presence or participation of its Representatives or Alternate Representatives to prevent, delay or forestall decisions on matters under consideration by the SDC Group. Other employees or agents of the Parties may attend meetings of the SDC Group. Meetings may be conducted in person, by telephone or video conference call, or by other means which permit the Representatives of each Party to be verified and to hear and be heard by the other Representatives and which are acceptable to the Representatives. Attendees who are not Representatives, or in the case that a Representative is not in attendance, who are not the applicable Alternate Representative, shall be identified at the commencement of such meeting and shall have no power to vote on any matters, but may participate in discussions in accordance with the SDC Group's rules of order, which may limit the amount of time that the employees or other agents may participate.

3. Rules. The SDC Group may adopt such rules of order, policy statements and directives as it considers necessary or appropriate for the conduct of its business and the exercise of its powers, none of which shall conflict with this Agreement.

4. Quorum. Meetings of the SDC Group shall require a quorum consisting of one (1) Representative or Alternate Representative of each Party.

5. Voting. Each Party shall have one (1) vote on any matter subject to the vote of the SDC Group, regardless of the number of that Party's Representatives in attendance at the meeting. Other than as provided in this Agreement, all decisions of the SDC Group shall require the affirmative vote of each Party. All decisions that are made in the SDC Group meetings shall be memorialized in minutes of the meeting prepared by the SDC Chair, subject to approval of the Authorized Representatives.

6. Action by Written Consent. Any action which may be taken by the SDC Group under this Agreement may be taken without a meeting if each Party's Representatives and Alternate Representatives is given prior notice in writing or by telephone or facsimile transmission and a copy of the proposed consent, and a consent setting forth the action taken is executed by a Representative of each Party.



**EXHIBIT B-1**

**PRELIMINARY PROGRAM**

See Attached

Exhibit B-1

# Minnesota Multipurpose Stadium

## Preliminary Program

**Prepared for**  
**Minnesota Sports Facilities Authority**

**And**

**Minnesota Vikings Football, LLC**

**Table of Contents**

- I. Project Summary
- II. Program Elements
- III. Food Service and Merchandising
- IV. Multipurpose Event Facilities
- V. Team Facilities
- VI. Media Facilities
- VII. Operations Staff Facilities
- VIII. Mechanical and Electrical Systems
- IX. Audio/Visual and Information Technology Systems
- X. Sponsorship Related Building Systems

**I. Project Summary**

**a. Project Description**

The project ("Project") means (1) the development, design, construction, outfitting and commissioning of a multipurpose stadium suitable for National Football League ("NFL") football and a broad range of other civic, community, athletic, educational, cultural, and commercial activities to be designed, constructed, and financed under the Stadium Legislation (the "Stadium"), (2) the open air plaza and event space adjacent to the Stadium (the "Stadium Plaza") and (3) such other plazas, parking structures, rights of way, connectors, skyways and tunnels, and other such property, facilities, and improvements, owned by the Authority or determined by the Authority, as reasonably necessary to facilitate the use and development of the Stadium as contemplated by the Stadium Legislation (the "Stadium Infrastructure").

**b. Location**

- Downtown Minneapolis, including all or portions of the current site of the existing stadium and adjacent areas, bounded generally by Park and Eleventh Avenues and Third and Sixth Streets.

**c. Uses**

- Multi-purpose venue capable of hosting NFL football games and a broad range of other civic, community, athletic, educational, cultural, and commercial activities.
- Primary tenant will be the Minnesota Vikings NFL franchise.
- The multipurpose design should include capability to be utilized for the following events:
  - NFL Super Bowl
  - NCAA Men's and Women's Basketball Championship
  - Professional and amateur soccer, including Major League Soccer ("MLS")
  - Motorsports events
  - Trade shows, community, or cultural events
  - Amateur and collegiate baseball and football
  - Other national and international events

**d. Stakeholders**

- State of Minnesota ("State")
- City of Minneapolis ("City")
- Hennepin County ("County")

- Minnesota Sports Facilities Authority (“Authority”)
- Minnesota Vikings Football, LLC (“Team”)

**e. Project Requirements**

The Stadium must be designed to meet or exceed all NFL rules and regulations, including the NFL Constitution, NFL By-Laws, the NFL Facility Guidelines and any other rules, guidelines, regulations or requirements of the Office of the Commissioner of the NFL and his appointees, that are generally applicable to NFL franchises, all as the same now exist or may be amended or adopted as part of the Minimum Design Standards. The Project must also meet or exceed the Minimum Design Standards to be established by the Authority and the Team, which shall include, without limitation, unless otherwise agreed by the Authority and the Team:

- The Stadium shall comprise approximately 1,500,000 square feet with approximately 65,000 seats, expandable to 72,000 seats
- The Stadium shall have approximately 150 suites and approximately 7,500 club seats or other such components as agreed to by the Authority and the Team
- To the extent practicable, the Authority and the Team will strive to make the stadium design architecturally significant
- To the extent practicable, the Authority and the Team will design and build a Stadium that is environmentally and energy efficient and will make an effort to build a Stadium that is eligible to receive the Leadership in Energy and Environmental Design (LEED) certification or the Green Building Initiative Green Globes certification for environmental design, and to the extent practicable. The stadium design must to the extent of having a payback of 30 years or less follow sustainable building guidelines established under Minnesota Statute 16B.325.
- A roof that is fixed or retractable.
- Space for NFL team museum and Hall of Fame.
- Patron parking, including 2,000 parking spaces within one block of the Stadium, connected by skyway or tunnel to the Stadium, and 500 parking spaces within two blocks of the Stadium, with a dedicated walkway on game days
- Elements sufficient to provide for community and civic uses as determined by the Authority

**II. Program Elements**

**a. Seating Bowl**

- Seating capacity of approximately 65,000 including general, club and suite seating

**b. General Seating**

- All fixed seating to be riser-mounted self-rising chairs including upper and lower bowl
- Aisle width per building code
- First row of seats no less than 4 feet 6 inches above field
- All seats to have cup holders
- Minimum tread depths:
  - Lower Bowl: Minimum 33 inches
  - Upper Bowl: 33 inches
- Minimum Seat Width:
  - Lower Bowl: 19 inches
  - Upper Bowl: 19 inches
- Typical number of seats per row will be even and no more than 24

**c. Accessible Seating**

- Accessible seating and companion seating to be provided in compliance with current ADA requirements

**d. Suites**

- Up to 150 suites as itemized below:
  - Private Suites: Sizes to vary (generally 12 to 24 individual seats, with some smaller suites having 6 to 8 seats) final number, capacities and amenities to be determined
  - Event Suites: To be determined
  - Bunker Suites: Approximately 14 (20 to 24 seat individual capacity). Preference for sideline locations with access to front row seating directly above.
  - NFL home team owner suite and visiting team owner suite
- Typical Suite:
  - Combination of fixed stadium seats and barstools
  - Minimum Seat Width: 22 inches, fully upholstered
  - Operable glass enclosure on field side to be operated by suite holder
  - Minimum amenities: full size refrigerator, under-counter ice maker, sink, two flat screen televisions, Toilet facilities generally not included within suites
- Loge Box Seating

- Depending on market demand, Stadium may include Loge Box Seats
  - Similar to opera box seating in a theater with 6 to 8 seats
  - Amenities may include a drink rail, food and beverage counter, refrigerator, and television monitor
  - May require access to club lounge

**e. Club Seating/Club Lounge**

- Seating
  - Seating to be located on sidelines in lower and mid seating bowls
  - Total capacity approximately 7,500 club seats based upon market study
  - Seats to be a minimum of 21 inches wide Tread depth minimum of 34 inches
  - Typical number of seats per row will be even and no more than 20 seats
- Club Lounge
  - Club lounges of sufficient number and size required to provide premium services to all club seating patrons
  - Include bars, concessions, pre-game buffet and toilets
  - Clubs must include facilities for in-seat service wait staff

**f. Concourses**

- Concourses to appropriately service patrons with toilets, concessions, merchandise stores, sponsor displays and audio/visual elements of game experience
- Adequate width and clear passage to allow proper circulation and include areas for promotional activities, gathering ,load in/out capabilities, and advertising
- Provide locations that can accommodate portable concessions

**g. Toilets**

- Toilets for men (50%) and women (50%) to be provided with proper distribution on every concourse level in compliance with local building codes
- Toilet Facilities to be designed to be comparable with other current NFL facilities

- General Seating Areas:
  - Lavatories: 1 per 150 Females; 1 per 200 Males
  - Water Closets: 1 per 60 Females; 1 per 350 Males
  - Urinals: 1 per 75 Males
  - Tempered Water
- Club Seating Areas:
  - Lavatories: 1 per 75 Females; 1 per 150 Males
  - Water Closets: 1 per 50 Females; 1 per 185 Males
  - Urinals: 1 per 55 Males
  - Hot and Cold Water Service
- Suite Levels:
  - Lavatories: 1 per 50 Females; 1 per 100 Males
  - Water Closets: 1 per 35 Females; 1 per 150 Males
  - Urinals: 1 per 40 Males
  - Hot and Cold Water Service
- Janitor's closet to be provided for every pair of public toilet rooms (on average)
- Family toilets
  - ADA accessible unisex toilet facilities to be provided for accessible or family use
  - Minimum of 1 Family Toilet for each quadrant on each level of general seating
  - Minimum 1 Family Toilet per Club

**h. Ingress/Egress**

- Stadium entries and exits should take advantage of existing points of interest and tie into existing transportation infrastructure
- Entries and exits must accommodate large crowds, ticket taking, and security
- Provision for major sponsorship opportunities to be considered

**i. Patron Vertical Transportation**

- Passenger Elevators
  - To be designed per code to optimally transport spectators to each level
  - Minimum size of 6 feet x 8 feet with minimum capacity of 3500 pounds
  - Elevators to be equipped with audio feeds to stadium broadcast
- Escalators
  - To be compliant with all current code requirements



- Minimum of 40 inches in width and must be reversible
- Designed to optimally transport spectators vertically to all levels of the stadium
- Stairs/Ramps
  - To be compliant with all current code requirements
  - Ramps to be designed to accommodate maintenance, and concession vehicles, and forklifts
    - a. Minimum width of 13 feet
    - b. Minimum Height of 10 feet
  - To be a mix of internal and external circulation, but all suite and club stairs should be interior only

**j. Ticketing**

- Central Ticketing office to be located at street level for easy public access
- Central Ticketing must accommodate minimum 22 ticket windows and office staff with four private offices, conference room, restrooms, break area, counting room, server room, vault, and settlement room with secure access to armored car pickup
- Day of game kiosks to be located near major entries
- Ticket will call to be located adjacent to Central Ticketing

**k. Guest Services**

- Information Stations at each public level provided to serve guest needs
- First Aid
  - Located on service level with convenient access to elevators and ambulance
  - Auxiliary first aid stations to be located throughout stadium
- Communications (, mobile charging stations)
- ATMs
- Drinking Fountains
  - Non-Refrigerated: to be provided on event level and all general concourses
  - Refrigerated: to be provided on all club concourses and suite levels
  - Must comply with local code and/or be at least two per concourse quadrant

**III. Food Service and Merchandising**

**a. Food/Beverage**

- Concessions – to be primarily designed by food service operator, however space must be designed to appropriately serve patrons from multiple locations throughout stadium with following minimum ratios:
  - General Seating: 1 POS per 175 spectators lower bowl; 1:200 POS upper bowl
  - Club Seating: 1 POS per 125 spectators
  - Fixed concessions must have sufficient MEP and food service infrastructure to support sales
  - Portable concessions to be placed throughout stadium with electrical and tel/data services provided
- Restaurant
  - A full service restaurant to be conveniently located to accommodate ticketed, game day patrons
  - Restaurant to be open for patrons from convention center and private events
  - Street access with dedicated elevator and stair access
  - Dedicated full service kitchen adjacent to the restaurant
  - Dedicated restrooms
- Bars
  - To be provided in Club Levels and Suite Level
- Club Lounges
  - Club lounges with sufficient food and beverage services to accommodate all club seating patrons
  - Include bars, concessions, pre-game buffet and toilets
  - Club lounges must include facilities for in-seat service wait staff

**b. Kitchens/Commissaries**

- Central Kitchen/Commissary
  - Located on event level convenient to loading dock and freight elevators
  - Equipped for preparation of food for concessions, clubs, suites, catering, and restaurants
  - Includes concession employee lockers, toilets, laundry, and offices also preferably at event level
  - Storage and staging for dry goods, frozen and refrigerated foods, pallets, alcoholic beverages and carts
- Vendor Commissaries
  - On all general concourse levels with a minimum of 15 square feet per vendor position
  - On premium seating levels, these areas will be for in-seat wait staff

- Pantries
    - On suite levels and each club lounge to provide support for in-suite catering and pre-game buffets in club lounges
    - One large pantry in each club lounge with supporting smaller club pantries
  - Empties Storage—recycling and waste facilities
  - Cart Storage and Wash Down Arenas
- c. Merchandising**
- Team Store
    - Central store on street level accessible on game days and non-game days
  - Merchandise Stands
    - Provided at fixed and mobile locations throughout stadium near major entries
    - One merchandise stand in each club lounge
  - Merchandise Storage on event level to accommodate team store and mobile merchandise

**IV. Multipurpose Event Facilities**

- a. Event Floor/Field**
- Accommodate multiple configurations for sports and conventions
  - Designed to accommodate all NFL, NCAA, MLS and Minnesota State High School League facility standards
  - Two entrances to accommodate large truck access to event floor
- b. Stage/Rigging**
- Designed to accommodate large touring concert and entertainment acts in end and center stage configurations
- c. Scoreboard/AV**
- State-of-the-art technology comparable to current stadiums
  - Consideration to be given to exterior video display capabilities especially visible from the stadium plaza.
- d. Control Rooms**
- Located on event level and press level to accommodate Scoreboard and AV control equipment
- e. Public Announcer Booth**

**V. Team Facilities**

- a. Home NFL Locker Room**

- Comparable to recent NFL stadiums with minimum 65 permanent lockers and 30 temporary lockers
- Shower, toilet and drying area with discreet access from press areas
- Elements to include:
  - Training Room
  - Head Athletic Trainer/Team Physician Room
  - Trainers' Changing Room
  - Hydrotherapy Room
  - Exam Room
  - Storage Supply and Equipment Storage
  - Stretching Room
  - Laundry
- Coaches Locker Rooms with work and lounge areas
- Staff Locker Room
- Offices for Head Coach and Equipment Manager
- Direct access to interview room and secure exit
- Access to truck loading

**b. Auxiliary Locker Rooms (2)**

- Two locker rooms with minimum 60 permanent lockers each sub dividable into locker rooms of 30 lockers each
- Shower, toilet and drying area (in both)
- Training Room (in both)
- Storage (in both)
- Coaches' lockers, showers and toilet (in both)

**c. Visitors NFL Locker Rooms**

- Comparable to recent NFL stadiums with 80 permanent lockers Design should allow for room to be divided into two locker rooms
- Shower, toilet and drying area with discreet access from press areas
- Elements to include:
  - Training Room
  - Exam Room
  - Staff Locker Room
  - Supply storage room and Equipment storage room
- Coaches Locker Rooms
- Office for Head Coach with dressing room
- Direct access to interview room
- Access to truck loading

**d. First Aid**

- First Aid/X-ray Room near team facility with compliance to NFL, NCAA, and MLS regulations
- e. Officials/Game Crew Locker Rooms**
  - Officials locker room to have minimum 10 lockers with shower and restroom facilities
  - Officials Meeting Room
  - Game Crew locker room to have 10 lockers with shower and restroom facilities
- f. Cheerleaders Locker Room**
  - 40 permanent lockers with space for make-up/hair and shower/restroom facilities
- g. Family Waiting Room for players' and coaches' families;** include separate child care room accessible to parking and family waiting room
- h. Owner's Lounge**
- i. Staging Area**
- j. Field Toilets with direct access to both bench areas**
- k. VIP/Team Parking**
- l. Coaches Booths (2)** convenient to Home NFL Locker Room
- m. Coaches Video Platforms**
- n. Video Replay Booth**
- o. Administrative Offices**
  - Year-round space for the Team administrative operations, sales, marketing and ticketing

**VI. Media Facilities**

- a. Press Box**
  - Located on the upper suite level
  - Writing press to include minimum 200 writing stations
  - Each station to include one electric and two tel/data outlets
- b. Broadcast Booths**
  - TV Broadcast Booths (one primary and one auxiliary) located at midfield
  - Six (6) Radio Broadcast Booths
- c. Broadcast Truck Facilities**
  - Minimum Four (4) broadcast TV tractor/trailer truck positions with two expandable to 16 foot trailer width
  - Parking for a minimum of three (3) TV satellite trucks with clear sightlines to southern sky
  - Parking for up to six (6) local TV microwave trucks (exterior)
  - Parking for TV crew

- Power and Broadcast Infrastructure per NFL and HD Specifications
- d. TV Host Locations**
  - 15x15 area to host three (3) cameras and four (4) talent positions
- e. Camera Positions**
  - In compliance with NFL, NCAA, and MLS network broadcast requirements
- f. Interview Rooms**
  - Home Team Interview Room adjacent to locker room to accommodate minimum 100 people seated or 150 standing
  - Coach/Player Interview Room
  - Visiting Team Interview Room to accommodate minimum 50 people seated and 75 standing
- g. Press Support**
  - Media Work Room
  - Press Dining Room and Lounge for minimum 150 people
  - Media Function Room
  - Photographers Work Room
  - TV Cable Connection Room
  - Broadcast Crew Room
  - Equipment Storage
  - Restrooms

**VII. Authority and Operations Staff Facilities**

- a. Offices**
  - Year round administrative offices for the Authority
  - Offices and cubicles for Stadium operations staff
  - Include conference room, break room, work room and storage
  - Food Service(s); main and fine dining
- b. Employee Locker rooms for men and women to accommodate minimum 100 staff**
- c. Gathering Rooms**
  - Employee Break Room
  - Ticket Taker and Usher Briefing Room
  - Event Security Briefing Room
- d. Storage**
  - Employee Uniform Storage and Laundry Facilities
  - Field Equipment Storage
  - Stage Storage and Support
  - General Storage



**e. Security Command Center**

- Two administrative offices
- One central game day office
- Restrooms
- Four (4) holding cells
- Roll-call room
- BMS Control Rooms
- Command Center to control access to loading dock and service tunnel
  - Stadium and Field Lighting Controls
  - Communications Systems
  - Fire Command Center
  - Public Address Systems
  - Monitors for Surveillance Camera Systems

**f. Janitorial/Maintenance Facilities**

- Four private offices and an open office area on event level for Maintenance
- Engineers Office adjacent to main BMS control room in the Command Center
- Maintenance shops for Machinery, Carpentry, Paint, Electrical and Plumbing
- Central Supply Room
- Janitors Closets on all levels near toilet facilities

**g. Trash Collection/Recycling**

- Main handling facility located near loading dock to accommodate separate treatment of trash and recyclable materials
- Trash container and recycling container storage/staging on each level

**h. Freight Elevators**

- Minimum one freight elevator on each side of stadium that must stop on all levels and accommodate 12,000 pounds minimum
- 10 feet wide by 20 feet deep

**i. On-field Observation Booths**

- Stadium Operations Booth
- Security Observation Booth

**j. Loading Dock**

- Convenient access to field level and service areas with easy street access
- Minimum of 6 truck bays with dock levelers and appropriate ventilation
- Additional two truck docks for central commissary
- Dedicated truck dock adjacent to NFL home team locker room

**VIII. Mechanical and Electrical Systems**

**a. Central Plant**

- b. HVAC Distribution System
- c. Plumbing System
- d. Fire Protection
- e. Electrical Power distribution
- f. Emergency Power System
- g. Lighting
- h. Fire Alarm and Detection Systems

**IX. Audio/Visual and Information Technology Systems**

The Project shall incorporate state-of-the-art audio and high definition video systems, including, without limitation, the following:

- a. Distributed Audio System
- b. MATV
- c. Broadcast Distribution and Camera
- d. Communication Systems/Information Management
- e. Security and Surveillance
- f. Scoreboard and Video Systems
- g. Hi density wifi and neutral host Distributed Antenna System
- h. Space for potential on site studio production

**X. Sponsorship Related Building Systems**

- a. Branding and Theming opportunities
- b. Integrated video and fixed signage opportunities to support all Sponsors
- c. Identify prominent locations for naming sponsor and major sponsors



**EXHIBIT B-2**

**MASTER PROJECT PROGRAM**

The Master Project Program is set forth in the MINNESOTA MULTIPURPOSE STADIUM FACILITIES PROGRAM issued by HKS, Inc., dated 12/10/13, which is incorporated by reference as if fully set forth herein, and as further supplemented and clarified by the document entitled “Review of DDSI20 #20 Scope Comparison” and attached hereto as **Exhibit B-2**.

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within GMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS
				TOTAL ESTIMATE OF ADDED COST FOR DDSI #20	\$ 8,477,363	\$ 2,098,526	REVISIONS from 11/6/13 Meeting
General Comments:							
	1	Electrical	Rejected / DD Drawings Govern	Add to humidity spaces - No Humidification in current design. Added (13) 68KW humidification unit connections, (2) 20A FCU connections at the trash room, (1) 20A FCU connection at the AV storage room, and (2) 20A FCU connections at the chiller distribution room	\$ 65,405		For all Vikings' Locker Room Areas - Pages 108 thru 126 of the 10/23/13 Program
	2	Electrical		Program note says "Investigate potential pre-action sprinkler systems or specialty dry chemical systems" Added the following scope: (27) rooms will have (1) smoke detector, (1) heat detector, and (1) preaction release module and (3) rooms will have (2) smoke detectors, (2) heat detectors, and (1) preaction release module.	\$ 58,202	\$ 58,202	Noted on pages 325, 332, 345, 347, 351, 371, 373, 439, 443, 445 of the 10/23/13 Program
	3	Fire Protection		Add dry chemical fire protection system in the following locations: Video Rack Room, Audio Control / PA Announcer, Sound System Amplifier Rooms, Primary/Secondary Telecom Service Entry Room	\$ 220,000	\$ 220,000	Added dry chemical system fire protection system for 345, 347, 373, & 435
	4	Electrical		Add (2) circuits to every suite for a total of 8 circuits per suite to cover additional amenities.	\$ 92,719	\$ 92,719	
	5	Mechanical	Rejected / DD Drawings Govern	Copper piping should be used on <u>all water piping 4" and smaller; above 4" it also needs to be copper</u> unless a water softener system is included.	\$ 462,000		Noted on Page 55, 56, 57 of the 10/23/13 Program. Spec calls for stainless steel for lines over 4"
	6	Mechanical	Rejected / DD Drawings Govern	Refrigeration System Condensing Units Room - notes relating to ReCirc Chilled Water Compressor and other Utilities. Notation to be similar to kitchen exhaust	\$ 92,950		Noted on Page 159 of the 10/23/13 Program
	7	Mechanical	Rejected / DD Drawings Govern	Food Service Bulk Storage - notes relating to ReCirc Chilled Water Compressor and other Utilities	\$ 96,800		Noted on Page 203 of the 10/23/13 Program
	8	Elevator Scope - AV Revisions	Rejected / DD Drawings Govern	Add cabling to support audio and video in (14) passenger elevators. This price presumes the speakers and TVs in the elevators are procured as part of the elevator purchase. Also traveling cable for both is by others. This includes cable and connections to the traveling cable in the elevator equipment rooms.	\$ 33,825		Noted on Page 465 of the 10/23/13 Program
	9	Catwalks - card readers	Rejected / DD Drawings Govern	Add Card Reader at catwalk entrances (unclear how many entrances there are, but presuming (8) locations.	\$ 20,566		Noted on Page 481 of the 10/23/13 Program
	10	Public Restrooms	Rejected / DD Drawings Govern	Add epoxy flooring at public restrooms	\$ 477,662		Noted on Page 56 of the 10/23/13 Program. RFC #1 Question #9 & RFC #2 calls these to be sealed concrete.
	11	Custodial Rooms	Rejected / DD Drawings Govern	Add built-in shelving (36 rooms x 10 ft) p-lam 3 row	\$ 45,934		Noted on Page 279 of the 10/23/13 Program
	12	Seating		Extra Seating to achieve 72,000 seating capacity is excluded from the GMP Proposal	NA		NOT INCLUDED IN GMP SCOPE
	13	Off Site Parking		Any off site parking is excluded from the GMP Proposal	NA		NOT INCLUDED IN GMP SCOPE
	14	Wall Types		All wall types are as noted in the GMP Proposal scope	NA		Types up scopes and quantities for all partition types
	15	Toilet Partitions - Spring Hinges	Rejected / DD Drawings Govern	Specifications call for "drop hinges" and not spring hinges	\$ 115,416		Noted on Page 55 of the 10/23/13 Program. Specs call for drop hinges.
	16	NFL Viking Locker Rooms, Vikings Locker Rooms		Add full height 2'x6' mirrors at NFL Locker Rooms	\$ 4,290	\$ 4,290	Noted on Page 57 of the 10/23/13 Program for Family Toilet rooms (Rejected at Family Toilet rooms)
01 - EVENT LEVEL	01.19.07	A/V			\$ -		
01 - EVENT LEVEL	01.02.07	AUDIO STORAGE			\$ -		
01 - EVENT LEVEL	01.27.03	AUX EQUIP RM 1			\$ -		
01 - EVENT LEVEL	01.25.09	AUX EQUIP RM 2			\$ -		
01 - EVENT LEVEL	01.25.08	AUX EQUIP RM 3			\$ -		
01 - EVENT LEVEL	01.23.08	AUX EQUIP RM 4			\$ -		
01 - EVENT LEVEL	01.27.02	AUX SHOWER 1			\$ -		
01 - EVENT LEVEL	01.25.06	AUX SHOWER 2			\$ -		
01 - EVENT LEVEL	01.24.08	AUX SHOWER 3			\$ -		
01 - EVENT LEVEL	01.23.04	AUX SHOWER 6			\$ -		
01 - EVENT LEVEL	01.26.04	AUX TRNG RM 1			\$ -		
01 - EVENT LEVEL	01.26.03	AUX TRNG RM 2			\$ -		
01 - EVENT LEVEL	01.24.07	AUX TRNG RM 3			\$ -		
01 - EVENT LEVEL	01.23.06	AUX TRNG RM 4			\$ -		
01 - EVENT LEVEL	01.27.04	AUX WET RM 1	Rejected / DD Drawings Govern	Area to be at 40% RH (relative humidity)	\$ 7,700		M-E engineers confirmed that the current mechanical system as designed will control humidity within these spaces
01 - EVENT LEVEL	01.25.05	AUX WET RM 2			\$ -		
01 - EVENT LEVEL	01.24.09	AUX WET RM 3			\$ -		
01 - EVENT LEVEL	01.23.05	AUX WET RM 4			\$ -		
01 - EVENT LEVEL	01.26.08	AUX COACH WET RM 1			\$ -		
01 - EVENT LEVEL	01.25.10	AUX COACH WET RM 2			\$ -		
01 - EVENT LEVEL	01.24.13	AUX COACH WET RM 3			\$ -		
01 - EVENT LEVEL	01.23.09	AUX COACH WET RM 4			\$ -		
01 - EVENT LEVEL	01.26.07	AUX COACH LOCK RM 1	Rejected / DD Drawings Govern	DDSI #17 called for 32" TV. DDSI #20 Program calls for 42" TV.	\$ 880		Calls for 42" TV
01 - EVENT LEVEL	01.25.11	AUX COACH LOCK RM 2	Rejected / DD Drawings Govern	DDSI #17 called for 32" TV. DDSI #20 Program calls for 42" TV.	\$ 880		Calls for 42" TV
01 - EVENT LEVEL	01.24.12	AUX COACH LOCK RM 3	Rejected / DD Drawings Govern	DDSI #17 called for 32" TV. DDSI #20 Program calls for 42" TV.	\$ 880		Calls for 42" TV
01 - EVENT LEVEL	01.23.10	AUX COACH LOCK RM 4	Rejected / DD Drawings Govern	DDSI #17 called for 32" TV. DDSI #20 Program calls for 42" TV.	\$ 880		Calls for 42" TV
01 - EVENT LEVEL	01.26.05	AUXILIARY LOCKER RM 1		The fit out of this space is now an alternate (Alt 11): Add proximity card reader	NA		Noted on Page 167 of the 10/23/13 Program
01 - EVENT LEVEL	01.25.07	AUXILIARY LOCKER RM 2		The fit out of this space is now an alternate (Alt 11): Add proximity card reader	NA		Noted on Page 167 of the 10/23/13 Program
01 - EVENT LEVEL	01.24.10	AUXILIARY LOCKER RM 3		Add proximity card readers	\$ 2,571	\$ 2,571	Noted on Page 167 of the 10/23/13 Program

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within RMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS
				TOTAL ESTIMATE OF ADDED COST FOR DDSI #20	\$ 8,477,363	\$ 2,098,526	REVISIONS from 11/6/13 Meeting
01 - EVENT LEVEL	01.23.07	AUXILIARY LOCKER RM 4		Add proximity card readers	\$ 2,571	\$ 2,571	Noted on Page 167 of the 10/23/13 Program
01 - EVENT LEVEL	01.29.01	BEV PUMP ROOM			\$ -		
01 - EVENT LEVEL	01.04.06	BEV PUMP ROOM			\$ -		
01 - EVENT LEVEL	01.15.08	BEV PUMP ROOM			\$ -		
01 - EVENT LEVEL	01.26.10	BEV PUMP ROOM			\$ -		
01 - EVENT LEVEL	01.06.04	BEVERAGE COOLER			\$ -		
01 - EVENT LEVEL	01.06.01	BEVERAGE STOR.			\$ -		
01 - EVENT LEVEL	01.02.04	BOH BREAK ROOM			\$ -		
01 - EVENT LEVEL	01.02.06	BOH OFFICE			\$ -		
01 - EVENT LEVEL	01.09.04	CART WASH	Misinterpretation - Rejected / DO Drawings Govern	Note in Program - provide natural gas at the cart wash area. Not picked up in DO documents	\$ 3,850		Noted on Page 193 of the 10/23/13 Program
01 - EVENT LEVEL	01.36.05	CHAIN CREW LOCKER ROOM	Rejected / DO Drawings Govern	Add PA System	\$ 9,203		Noted on Page 185 of the 10/23/13 Program
01 - EVENT LEVEL	01.08.10	CHEERLEADER STORAGE			\$ -		
01 - EVENT LEVEL	01.04.11	CHEM. STOR.			\$ -		
01 - EVENT LEVEL	01.07.15	CHEMICAL STOR.			\$ -		
01 - EVENT LEVEL	01.01.04	CLEANING GA - OFFICE		Automatic Lighting System Dimmable lighting, 2x2 indirect fluorescent fixtures	\$ 1,112	\$ 1,112	Noted on Page 291 of the 10/23/13 Program
01 - EVENT LEVEL	01.01.03	CLEANING GA - STORAGE ROOM			\$ -		
01 - EVENT LEVEL	01.02.03	CL FANING LOCKER CORR			\$ -		
01 - EVENT LEVEL	01.02.01	CLEANING PREMIUM - STORAGE ROOM	Rejected / DO Drawings Govern	Add to humidity spaces - No Humidification in current design	\$ 7,709		Noted on Page 283 of the 10/23/13 Program
01 - EVENT LEVEL	01.01.06	CLEANING SERVICES BREAKROOM	Rejected / DO Drawings Govern	Cleaning area break room bathroom vs. no dedicated bathrooms	\$ -		Noted on Page 293 of the 10/23/13 Program
01 - EVENT LEVEL	01.01.06	CLEANING SERVICES BREAKROOM	Rejected / DO Drawings Govern	Add sink for (5) water closets, (6) lavatories, and (2) urinals	\$ 3,031		Noted on Page 293 of the 10/23/13 Program
01 - EVENT LEVEL	01.01.06	CLEANING SERVICES BREAKROOM	Rejected / DO Drawings Govern	Add 42" TV	\$ 4,536		Noted on Page 293 of the 10/23/13 Program
01 - EVENT LEVEL	01.10.14	CD2 STORAGE		Note in Program added for General Exhaust, Natural Gas, Hot Water, Cold Water to this room.	\$ 10,450	\$ 10,450	Noted on Page 197 of the 10/23/13 Program
01 - EVENT LEVEL	01.08.07	COMM. STORAGE			\$ -		
01 - EVENT LEVEL	01.10.12	COMMAND CENTER	Rejected / DO Drawings Govern	Add Sound System tied into Event Broadcasting	\$ 10,265	\$ 10,265	Noted on Page 319 of the 10/23/13 Program
01 - EVENT LEVEL	01.07.04	COMMISSARY KITCHEN		Add (2) 2MP Security Cameras	\$ 3,080		Noted on Page 319 of the 10/23/13 Program
01 - EVENT LEVEL	01.08.08	COMMISSARY OFFICES	Rejected / DO Drawings Govern	DDSI #17 did not include a TV at this location. DDSI #20 Program calls for four (4) 42" TV's.	\$ 18,146		Concessionaire Offices - Calls for (4) 42" TV's
01 - EVENT LEVEL	01.08.08	COMMISSARY OFFICES		Add 208 base & upper cabinets for commissary offices (break/work room function)	\$ 18,050	\$ 18,050	Noted on Page 213 of the 10/23/13 Program
01 - EVENT LEVEL	01.15.03	CONC. RM			\$ -		
01 - EVENT LEVEL	01.05.05	CONCESS DAY OF GAME MEN UNIFORMS		Add 101F stainless steel service counter; 2 rolling shutters	\$ 6,207	\$ 6,207	Noted on Page 217 of the 10/23/13 Program
01 - EVENT LEVEL	01.05.04	CONCESS DAY OF GAME WOMEN UNIFORMS		Included in CONCESS DAY OF GAME MEN UNIFORMS	\$ -		Noted on Page 217 of the 10/23/13 Program
01 - EVENT LEVEL	01.31.01	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.08.06	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.12.06	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.19.05	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.37.02	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.22.05	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.14.12	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.07.01	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.12.02	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.24.04	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.15.04	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.26.06	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.24.11	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.15.09	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.14.22	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.16.08	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.21.01	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.14.10	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.01.08	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.07.06	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.03.03	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.37.05	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.10.16	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.08.11	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.23.16	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.26.09	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.13.12	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.26.14	CORRIDOR			\$ -		
01 - EVENT LEVEL	01.14.26	CROSS CONNECT			\$ -		
01 - EVENT LEVEL	01.38.01	DAS	Rejected / DO Drawings Govern	Program makes reference to Dedicated HVAC (with Redundancy). This is not currently reflected in the design.	\$ 51,700		Noted on Page 443 of the 10/23/13 Program
01 - EVENT LEVEL	01.38.02	DATA CENTER	Rejected / DO Drawings Govern	Program makes reference to Dedicated HVAC (with Redundancy). This is not currently reflected in the design.	\$ 91,300		Noted on Page 441 of the 10/23/13 Program

Review of DDSI #20 Scope Comparison								
LEVEL	Number	ROOM NAME	Status within GMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS	REVISIONS from 11/6/23 Meeting
				<b>TOTAL ESTIMATE OF ADDED COST FOR DDSI #20</b>	<b>\$ 8,477,363</b>	<b>\$ 2,098,526</b>		
01 - EVENT LEVEL	01.39.05	DEMARC	Rejected / DO Drawings Govern	Program makes reference to Dedicated HVAC (with Redundancy). This is not currently reflected in the design.	\$ 62,700		Noted on Page 439 of the 10/23/13 Program	MODL - YA to go to standard AHU - not a CRAC unit. Not a fully separate unit will be managed
01 - EVENT LEVEL	01.14.23	DEMARC			\$ -			
01 - EVENT LEVEL	01.07.10	DETERGENT STOR.			\$ -			
01 - EVENT LEVEL	01.07.09	DISH STORAGE			\$ -			
01 - EVENT LEVEL	01.07.07	DISH WASH			\$ -			
01 - EVENT LEVEL	01.10.11	DOCK STORAGE			\$ -			
01 - EVENT LEVEL	01.07.11	DRY STR.			\$ -			
01 - EVENT LEVEL	01.04.10	DRYER RM			\$ -			
01 - EVENT LEVEL	01.13.09	ELEC			\$ -			
01 - EVENT LEVEL	01.21.03	ELEV CNTRL RM			\$ -			
01 - EVENT LEVEL	01.03.03	ELEV MACH RM			\$ -			
01 - EVENT LEVEL	01.23.12	ELEV MACH RM			\$ -			
01 - EVENT LEVEL	01.13.12	ELEV MACH ROOM			\$ -			
01 - EVENT LEVEL	01.05.02	EM ELEC			\$ -			
01 - EVENT LEVEL	01.39.06	EM ELEC			\$ -			
01 - EVENT LEVEL	01.15.12	EM ELEC			\$ -			
01 - EVENT LEVEL	01.23.14	EM ELEC			\$ -			
01 - EVENT LEVEL	01.37.01	ERAZONE SUBSTATION RM		Add Subroof - deck and plumbing - 1,000 SF	\$ 39,600	\$ 39,600	Noted on Page 421 of the 10/23/13 Program	
01 - EVENT LEVEL	01.10.13	EVENT EMPLOYEE CHECKIN			\$ -			
01 - EVENT LEVEL	01.28.03	EVENT FND ZONE CONCOURSE			\$ -			
01 - EVENT LEVEL	01.18.07	EVENT PARKING			\$ -			
01 - EVENT LEVEL	01.34.02	FAM			\$ -			
01 - EVENT LEVEL	01.29.02	FAM			\$ -			
01 - EVENT LEVEL	01.22.04	FAMILY			\$ -			
01 - EVENT LEVEL	01.09.07	FAN ROOM - GOOD			\$ -			
01 - EVENT LEVEL	01.17.09	FAN ROOM - VIRINGS, TV CREW			\$ -			
01 - EVENT LEVEL	01.35.01	FIELD ACCESS NW			\$ -			
01 - EVENT LEVEL	01.28.01	FIELD ACCESS SW			\$ -			
01 - EVENT LEVEL	01.13.08	FIELD PHOTOGRAPHY	Rejected / DO Drawings Govern	DDSI #17 did not include a TV at this location. DDSI #20 Program calls for one (1) 50" TV.	\$ 4,536		Calls for (1) 50" TV	no changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.18.04	FIELD SIGELINE CLUB	Rejected / DO Drawings Govern	Program had a note for a 400A panelboard and 150KVA transformer	\$ 32,153		Noted on Page 207 of the 10/23/13 Program	The panel boards are not in the rooms, but in the adjacent rooms
		<b>FIELD SUITES</b>	Rejected / DO Drawings Govern	1. Segmented OH Glass Doors are noted in the program. "Airtight separation between Suite tub seats (seating bowl) and suite interior with operable sections" 2. Suite fronts are not "airtight" 3. Interior Glass Walls are not operable 4. Subroof needs to be added 5. No custom signage or "plaque" for the entrance of the suite 6. "Upgraded Hanger" for closet are a part of the FF&E Scope and not included in the GMP (proposal)			Noted on Page 23 of the 10/23/13 Program	
01 - EVENT LEVEL		Field Suites	Rejected / DO Drawings Govern	Add to provide AIR TIGHT Glass requires the system to be an exterior system	NA		Suite Fronts are not "airtight"	
01 - EVENT LEVEL		Field Suites	Rejected / DO Drawings Govern	Add to make INTERIOR GLASS WALLS OPERABLE	NA		Interior Walls Not Operable	
01 - EVENT LEVEL		Field Suites	Rejected / DO Drawings Govern	Add 12" deep, 42" tall stainless countertop at the front of the patio	No Change		Included as Itail Type E1 in the GMP	
01 - EVENT LEVEL		Field Suites	Refer to Add Alternate 23	Add Subroof - deck, tectum and plumbing - 26,300 SF	\$ 1,486,000		Was included in ADD ALTERNATE #23	
01 - EVENT LEVEL		Field Suites	Rejected / DO Drawings Govern	Add custom signage or "plaque"	\$ 29,231			Interior sign not required
01 - EVENT LEVEL		Field Suites	Rejected / DO Drawings Govern	Add individual suite controls	\$ 6,600	\$ 6,600		
01 - EVENT LEVEL		WIRE SUITES	Rejected / DO Drawings Govern	AUTO 204 LCLING LID	\$ 5,860			this is add alternate
01 - EVENT LEVEL	01.27.01	FIELD SUITE 01	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.26.01	FIELD SUITE 02	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.25.03	FIELD SUITE 03	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.25.02	FIELD SUITE 04	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.25.01	FIELD SUITE 05	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.24.03	FIELD SUITE 06	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.18.01	FIELD SUITE 15	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.17.03	FIELD SUITE 16	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.17.02	FIELD SUITE 17	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.17.01	FIELD SUITE 18	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.16.01	FIELD SUITE 19	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.15.01	FIELD SUITE 20	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.14.01	FIELD SUITE 21	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	No changes to TV's - TV's follow DDSI-17



Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within GMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS
				<b>TOTAL ESTIMATE OF ADDED COST FOR DDSI #20</b>	<b>\$ 8,477,363</b>	<b>\$ 2,098,526</b>	<b>REVISIONS from 11/6/13 Meeting</b>
01 - EVENT LEVEL	01.13.01	FIELD SUITE 22	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
01 - EVENT LEVEL	01.12.01	FIELD SUITE 23	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
01 - EVENT LEVEL	01.28.02	FIELD TLT			\$ -		No changes to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.12.03	FIELD TLT			\$ -		
01 - EVENT LEVEL	01.22.01	FINISHING KITCHEN			\$ -		
01 - EVENT LEVEL	01.09.06	FIRE/ DOMESTIC WATER ENTRY	Rejected / DO Drawings Govern	Add Subroof - deck and plumbing - 1,000 SF	\$ 39,600		Noted on Page 427 of the 10/23/13 Program
01 - EVENT LEVEL	01.11.12	FRYER WASTE OIL		Note in Program added for General Exhaust to this room.	\$ 1,650	\$ 1,650	Noted on Page 193 of the 10/23/13 Program
01 - EVENT LEVEL	01.36.01	GAME OFFICIALS LX MEN	Rejected / DO Drawings Govern	Add Sound System tied into Event Broadcasting	\$ 9,203		Noted on Page 183 of the 10/23/13 Program
01 - EVENT LEVEL	01.36.02	GAME OFFICIALS LX WOMEN	Rejected / DO Drawings Govern	Add Sound System tied into Event Broadcasting	\$ 9,203		Noted on Page 183 of the 10/23/13 Program
01 - EVENT LEVEL	01.36.04	GAME OFFICIALS MEETING ROOM			\$ -		Not required per 11/6/13 program review meeting
01 - EVENT LEVEL	01.06.02	GENERATOR			\$ -		
01 - EVENT LEVEL	01.13.07	HEAD COACH TOILET			\$ -		
01 - EVENT LEVEL	01.14.08	HOLDING CELL			\$ -		
01 - EVENT LEVEL	01.14.13	HOLDING CELL			\$ -		
01 - EVENT LEVEL	01.18.06	IDF			\$ -		
01 - EVENT LEVEL	01.36.01	IDF			\$ -		
01 - EVENT LEVEL	01.05.01	IDF			\$ -		
01 - EVENT LEVEL	01.05.08	IDF			\$ -		
01 - EVENT LEVEL	01.23.13	IDF			\$ -		
01 - EVENT LEVEL	01.13.10	IDF			\$ -		
01 - EVENT LEVEL	01.27.06	IDF			\$ -		
01 - EVENT LEVEL	01.10.15	IDF			\$ -		
01 - EVENT LEVEL	01.22.02	IDF			\$ -		
01 - EVENT LEVEL	01.38.05	IDF			\$ -		
01 - EVENT LEVEL	01.19.00	INTERVIEW - VIKINGS	Rejected / DO Drawings Govern	Add electrochromic glass at Vikings Interview	\$ 37,651		Noted on Page 357 of the 10/23/13 Program
01 - EVENT LEVEL	01.09.09	INTERVIEW - VISITING	Rejected / DO Drawings Govern	Add card access for Visitor Interview Room	\$ 2,571		Noted on Page 357 of the 10/23/13 Program
01 - EVENT LEVEL	01.20.03	JAN			\$ -		
01 - EVENT LEVEL	01.34.03	JAN			\$ -		
01 - EVENT LEVEL	01.29.01	JAN			\$ -		
01 - EVENT LEVEL	01.22.08	JAN			\$ -		
01 - EVENT LEVEL	01.07.08	JAN			\$ -		
01 - EVENT LEVEL	01.04.08	LAUNDRY RM			\$ -		
01 - EVENT LEVEL	01.16.17	LIQUOR STOR			\$ -		
01 - EVENT LEVEL	01.11.14	LOADING DOCK		Hose bibs at ramps and general loading dock area	\$ 4,400	\$ 4,400	Noted on Page 308 of the 10/23/13 Program
01 - EVENT LEVEL	01.11.14	LOADING DOCK		Added (11) 60A receptacles on loading dock wall, (5) 60A receptacles for misc truck power, (9) 30A receptacles for misc truck power, and (5) 20A receptacles for misc truck power	\$ 25,478	\$ 25,478	Noted on Page 308 of the 10/23/13 Program
01 - EVENT LEVEL	01.14.24	LOCAL TV ENG	Rejected / DO Drawings Govern	Program denotes a 24 Breaker Panel for Electronic Rack Power - Added 150A panelboard and 45kVA transformer	\$ 12,525		Noted on Page 367 of the 10/23/13 Program
01 - EVENT LEVEL	01.06.03	MAIN ELECTRICAL			\$ -		Panel is in separate room
01 - EVENT LEVEL	01.38.03	MAIN TELECOMM RM			\$ -		
01 - EVENT LEVEL	01.04.01	MAINTENANCE SHOP			\$ -		
01 - EVENT LEVEL	01.24.14	MICH PAN			\$ -		
01 - EVENT LEVEL	01.05.09	MICH PAN ROOM - LOCKER/ COMMISSARY			\$ -		
01 - EVENT LEVEL	01.15.05	MED. OFF.	Rejected / DO Drawings Govern	DDSI #17 Included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV.	No Change		Calls for 27" TV
01 - EVENT LEVEL	01.14.19	MEDIA PANTRY			\$ -		No change to TV's - TV's follow DDSI-17
01 - EVENT LEVEL	01.16.03	MEDICAL STAFF			\$ -		
01 - EVENT LEVEL	01.16.04	MEDICAL STAFF WET ROOM			\$ -		
01 - EVENT LEVEL	01.07.02	MEN	Rejected / DO Drawings Govern	Security Locking Hose bibs - add \$53,000	\$ 53,000		Not required for all family/single toilet rooms per NSFA/Vikings 11/6/13
01 - EVENT LEVEL	01.10.05	MEN			\$ -		
01 - EVENT LEVEL	01.13.02	MEN			\$ -		
01 - EVENT LEVEL	01.25.04	MEN			\$ -		
01 - EVENT LEVEL	01.20.02	MEN			\$ -		
01 - EVENT LEVEL	01.05.03	MEN			\$ -		
01 - EVENT LEVEL	01.04.03	MEN			\$ -		
01 - EVENT LEVEL	01.34.01	MEN			\$ -		
01 - EVENT LEVEL	01.29.03	MEN			\$ -		
01 - EVENT LEVEL	01.01.05	MEN RR			\$ -		
01 - EVENT LEVEL	01.36.07	NSFA STORAGE		Add to humidity spaces - No Humidification in current design	\$ 10,450	\$ 10,450	Noted on Page 277 of the 10/23/13 Program
01 - EVENT LEVEL	01.26.12	NSFA STORAGE		Add to humidity spaces - No Humidification in current design	\$ 10,450	\$ 10,450	Noted on Page 277 of the 10/23/13 Program
01 - EVENT LEVEL	01.04.05	NSFA UNIFORM MEN			\$ -		
01 - EVENT LEVEL	01.04.04	NSFA UNIFORM WOMEN			\$ -		
01 - EVENT LEVEL	01.11.04	NFL TESTING	Rejected / DO Drawings Govern	Add card reader at NFL Concussion Room	\$ 2,571		Noted on Page 131 of the 10/23/13 Program
01 - EVENT LEVEL	01.11.04	NFL TESTING		Provide one (1) private toilet room with 2 floor mounted SST water closets and 1 SST lavatory	\$ 8,250	\$ 8,250	Per Vikings - not required
01 - EVENT LEVEL	01.11.08	NFL VIS. AST. COACH DRY AREA			\$ -		
01 - EVENT LEVEL	01.11.06	NFL VIS. AST. COACH LKR. RM.			\$ -		
01 - EVENT LEVEL	01.11.17	NFL VIS. AST. COACH RESTROOM			\$ -		
01 - EVENT LEVEL	01.11.07	NFL VIS. AST. COACH WET RM.			\$ -		
01 - EVENT LEVEL	01.10.09	NFL VIS. HEAD COACH LKR. RM.			\$ -		

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within GMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS
				<b>TOTAL ESTIMATE OF ADDED COST FOR DDSI #20</b>	<b>\$ 8,477,363</b>	<b>\$ 2,098,526</b>	
01 - EVENT LEVEL	01.10.07	NFL VIS HEAD COACH LKR RM	Rejected / DO Drawings Govern	DDSI #17 included one (1) 42" TV. DDSI #20 Program calls for one (1) 27" TV.	No Change		Calls for 27" TV
01 - EVENT LEVEL	01.10.08	NFL VISITING LOCKER ROOMS	Rejected / DO Drawings Govern	Note regarding a Separate HVAC Monitoring system for the Viking Team Locker Room	\$ 10,450		Noted on Page 155 of the 10/23/13 Program
01 - EVENT LEVEL	01.11.09	NFL VISITING TEAM ENTRY			\$ -		
01 - EVENT LEVEL	01.11.10	NFL VISITING TEAM EQUIP RM			\$ -		
01 - EVENT LEVEL	01.09.05	NFL VISITING TRAINING RM	Rejected / DO Drawings Govern	Note regarding a Separate HVAC system from the one for the Locker Room	\$ 60,500		Noted on Page 163 of the 10/23/13 Program
01 - EVENT LEVEL	01.09.05	NFL VISITING TRAINING RM		Water and drain line for note related to providing an ice machine. Ice Machine is FF&E	\$ 1,650	\$ 1,650	Noted on Page 163 of the 10/23/13 Program
01 - EVENT LEVEL	01.10.09	NFL VISITING WET RM			\$ -		
01 - EVENT LEVEL	01.10.10	NFL VISITING WET RM	Rejected / DO Drawings Govern	Area to be at 40% RH (relative humidity)	\$ 7,700		Noted on Page 157 of the 10/23/13 Program
01 - EVENT LEVEL	01.16.13	NURSERY	Rejected / DO Drawings Govern	Water and drain line for under counter ice maker in NFL Family nursery. Ice Maker is FF&E	\$ 2,200		Noted on Page 151 of the 10/23/13 Program
01 - EVENT LEVEL	01.16.14	NURSERY TOILET			\$ -		
01 - EVENT LEVEL	01.07.13	OFFICE			\$ -		
01 - EVENT LEVEL	01.14.06	OWNER TOILET			\$ -		
01 - EVENT LEVEL	01.20.01	PAINTRY			\$ -		
01 - EVENT LEVEL	01.16.02	PAINTRY			\$ -		
01 - EVENT LEVEL	01.26.02	PAINTRY			\$ -		
01 - EVENT LEVEL	01.07.14	PAPER STOK			\$ -		
01 - EVENT LEVEL	03.04.10	PATIO			\$ -		
01 - EVENT LEVEL	03.04.11	PATIO			\$ -		
01 - EVENT LEVEL	03.04.12	PATIO			\$ -		
01 - EVENT LEVEL	03.04.13	PATIO			\$ -		
01 - EVENT LEVEL	03.04.14	PATIO			\$ -		
01 - EVENT LEVEL	03.04.15	PATIO			\$ -		
01 - EVENT LEVEL	03.04.16	PATIO			\$ -		
01 - EVENT LEVEL	03.04.17	PATIO			\$ -		
01 - EVENT LEVEL	03.04.18	PATIO			\$ -		
01 - EVENT LEVEL	03.04.19	PATIO			\$ -		
01 - EVENT LEVEL	03.04.20	PATIO			\$ -		
01 - EVENT LEVEL	03.04.21	PATIO			\$ -		
01 - EVENT LEVEL	03.04.22	PATIO			\$ -		
01 - EVENT LEVEL	03.04.23	PATIO			\$ -		
01 - EVENT LEVEL	03.04.24	PATIO			\$ -		
01 - EVENT LEVEL	03.04.25	PATIO			\$ -		
01 - EVENT LEVEL	03.04.26	PATIO			\$ -		
01 - EVENT LEVEL	03.04.27	PATIO			\$ -		
01 - EVENT LEVEL	03.04.28	PATIO			\$ -		
01 - EVENT LEVEL	03.04.29	PATIO			\$ -		
01 - EVENT LEVEL	03.04.30	PATIO			\$ -		
01 - EVENT LEVEL	03.04.31	PATIO			\$ -		
01 - EVENT LEVEL	03.04.32	PATIO			\$ -		
01 - EVENT LEVEL	01.01.01	PLAYING FIELD			\$ -		
01 - EVENT LEVEL	01.39.03	QUAD ELEC SUB	Rejected / DO Drawings Govern	Add Subroof - deck and plumbing - 5,400 SF (01.38.01 - DAS, 01.38.02 - Data Center, 01.38.03 - Main Telecom Room, 01.39.03 - NW Quad Elec Sub)	\$ 237,600	\$ 237,600	Noted on Page 421 of the 10/23/13 Program
01 - EVENT LEVEL	01.05.06	QUAD ELEC SUB			\$ -		
01 - EVENT LEVEL	01.15.11	QUAD ELEC SUB / ENDZONE SUB			\$ -		
01 - EVENT LEVEL	01.23.11	QUAD ELEC SUB / CHILLER SUB	Rejected / DO Drawings Govern	Add Subroof - deck and plumbing - 1,000 SF	\$ 39,600		Noted on Page 421 of the 10/23/13 Program
01 - EVENT LEVEL	01.08.08	RAMP-01			\$ -		
01 - EVENT LEVEL	01.01.02	SERVICE CORRIDOR			\$ -		
01 - EVENT LEVEL	01.40.03	SERVICE CORRIDOR			\$ -		
01 - EVENT LEVEL	01.23.03	SERVICE CORRIDOR			\$ -		
01 - EVENT LEVEL	01.11.03	SHOW POWER			\$ -		
01 - EVENT LEVEL	01.36.06	SHOW POWER	Rejected / DO Drawings Govern	Add Subroof - deck and plumbing - 500 SF	\$ 19,800	\$ 19,800	Noted on Page 433 of the 10/23/13 Program
01 - EVENT LEVEL	01.03.04	SND SYSTEM AMP RM	Rejected / DO Drawings Govern	4" conduit from show power to skyline; one conduit to the north and south skyline from both show power rooms	\$ 66,216		Noted on Page 52 of the 10/23/13 Program
01 - EVENT LEVEL	01.03.04	SND SYSTEM AMP RM	Rejected / DO Drawings Govern	Program denotes 300 kva power on separate K13 XFM Total for all rooms Added (6) 150A panelboards and (6) 45KVA K13 rated transformers	\$ 91,578		Noted on Page 373 of the 10/23/13 Program
01 - EVENT LEVEL	01.37.06	SND SYSTEM AMP RM	Rejected / DO Drawings Govern	Dedicated HVAC system for each room DX Split system for each room	\$ 23,100		Noted on Page 373 of the 10/23/13 Program
01 - EVENT LEVEL	01.23.15	SND SYSTEM AMP RM			\$ -		
01 - EVENT LEVEL	01.17.10	SND SYSTEM AMP RM			\$ -		
01 - EVENT LEVEL	01.16.10	STAFF FAMILY LOUNGE		Add Audio control - ability to select press, PA, radio and TV	\$ 13,692	\$ 13,692	Noted on Page 149 of the 10/23/13 Program
01 - EVENT LEVEL	01.16.10	STAFF FAMILY LOUNGE		Add beverage station and controls interface at Vikings Staff Family Lounge	\$ 3,300	\$ 3,300	Noted on Page 149 of the 10/23/13 Program
01 - EVENT LEVEL	01.04.09	STAIR-01			\$ -		
01 - EVENT LEVEL	01.07.06	STAIR-03			\$ -		
01 - EVENT LEVEL	01.13.11	STAIR-04			\$ -		
01 - EVENT LEVEL	01.15.10	STAIR-06			\$ -		
01 - EVENT LEVEL	01.22.06	STAIR-08			\$ -		
01 - EVENT LEVEL	01.26.13	STAIR-09			\$ -		
01 - EVENT LEVEL	01.38.04	STAIR-11			\$ -		
01 - EVENT LEVEL	01.33.02	STAIR-13			\$ -		
01 - EVENT LEVEL	01.14.25	STANDBY GENERATOR RM			\$ -		

B-2-6

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within BWP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS
				<b>TOTAL ESTIMATE OF ADDED COST FOR DDSI #20</b>	<b>\$ 8,477,363</b>	<b>\$ 2,098,526</b>	<b>REVISIONS from 11/6/13 Meeting</b>
01 - EVENT LEVEL	01.26.11	STEAM ENTRANCE	Rejected / DO Drawings Govern	Conditioned makeup air and exhaust required for the combined chilled water and steam entrance	\$ 29,700		Noted on Page 375 of the 10/23/13 Program
01 - EVENT LEVEL	01.40.01	STORAGE			\$ -		
01 - EVENT LEVEL	01.39.04	STORAGE			\$ -		
01 - EVENT LEVEL	01.02.05	STORAGE			\$ -		
01 - EVENT LEVEL	01.21.02	STORAGE			\$ -		
01 - EVENT LEVEL	01.07.12	STORAGE			\$ -		
01 - EVENT LEVEL	04.13.10	STORAGE			\$ -		
01 - EVENT LEVEL	01.03.02	SUITE/CLUB CLEANING STORAGE	Rejected / DO Drawings Govern	Add card reader	\$ 2,571		Noted on Page 285 of the 10/23/13 Program
01 - EVENT LEVEL	01.03.02	SUITE/CLUB CLEANING STORAGE	Rejected / DO Drawings Govern	Add to humidity spaces - No Humidification in current design	\$ 7,700		M-E engineers confirmed that the current mechanical system as designed will control humidity within these spaces
01 - EVENT LEVEL	01.17.08	SUMP PUMP		General exhaust note for these rooms denoted in program - not yet in design documents	\$ 11,770	\$ 11,770	Noted on Page 415 of the 10/23/13 Program
01 - EVENT LEVEL	01.25.12	SUMP PUMP			\$ -		
01 - EVENT LEVEL	01.04.07	SUMP PUMP			\$ -		
01 - EVENT LEVEL	01.39.02	SUMP PUMP			\$ -		
01 - EVENT LEVEL	01.14.02	THERMAL PLUNGE			\$ -		
01 - EVENT LEVEL	01.16.09	TLT			\$ -		
01 - EVENT LEVEL	01.16.15	TLT			\$ -		
01 - EVENT LEVEL	01.16.16	TLT			\$ -		
01 - EVENT LEVEL	01.16.11	TLT			\$ -		
01 - EVENT LEVEL	01.11.11	TOILET		Stainless steel water closets and lavs in field toilets vs. scheduled	\$ 6,600	\$ 6,600	Noted on Page 129 of the 10/23/13 Program
01 - EVENT LEVEL	01.14.21	TOILET			\$ -		
01 - EVENT LEVEL	01.14.20	TOILET			\$ -		
01 - EVENT LEVEL	01.02.8	TRAINER OFFICE			\$ -		
01 - EVENT LEVEL	01.11.15	TRASH AND RECYCLE ROOM		1 000 CFM exhaust with climate control to 55 degrees F - was exhaust as part of VA process	\$ 7,700	\$ 7,700	Noted on Page 313 of the 10/23/13 Program
		TRASH AND RECYCLE ROOM		Hot water hose bib provided for wash down	\$ 4,950	\$ 4,950	Noted on Page 313 of the 10/23/13 Program
01 - EVENT LEVEL	01.11.05	TUNNEL			\$ -		
01 - EVENT LEVEL	01.18.08	TURF STORAGE			\$ -		
01 - EVENT LEVEL	01.40.02	TURF STORAGE			\$ -		
01 - EVENT LEVEL	01.14.18	TV CREW MEDIA DINING	Rejected / DO Drawings Govern	Add sound system tied into Event broadcasting	\$ 12,397	\$ 12,397	Noted on Page 209 of the 10/23/13 Program
01 - EVENT LEVEL	01.14.18	TV CREW MEDIA DINING	Rejected / DO Drawings Govern	Note in Program added natural gas to this room.	\$ 6,650		Noted on Page 209 of the 10/23/13 Program
01 - EVENT LEVEL	01.14.09	USHER OPERATIONS ROOM			\$ -		
01 - EVENT LEVEL	01.14.11	USHER CONFERENCE ROOM	Rejected / DO Drawings Govern	Full down screen, video call equipment	\$ 40,785		Noted on Page 257 of the 10/23/13 Program
01 - EVENT LEVEL	01.14.16	USHER LOCKERS - MEN		Add PA System	\$ 9,203	\$ 9,203	Noted on Page 255 of the 10/23/13 Program
01 - EVENT LEVEL	01.14.15	USHER LOCKERS - WOMEN		Add PA System	\$ 9,203	\$ 9,203	Noted on Page 255 of the 10/23/13 Program
01 - EVENT LEVEL	01.14.17	USHER RESTROOMS - MEN			\$ -		
01 - EVENT LEVEL	01.14.14	USHER RESTROOMS - WOMEN			\$ -		
01 - EVENT LEVEL	01.09.01	V.C. - PREP AREA			\$ -		
01 - EVENT LEVEL	01.08.05	V.C. - RESTROOM			\$ -		
01 - EVENT LEVEL	01.09.03	V.C. - WET AREA			\$ -		
01 - EVENT LEVEL	01.15.06	VEST			\$ -		
01 - EVENT LEVEL	01.11.16	VEST			\$ -		
01 - EVENT LEVEL	01.02.02	VIDEO STORAGE			\$ -		
01 - EVENT LEVEL	01.12.08	VIRGUS AST. COACH DRY AREA			\$ -		
01 - EVENT LEVEL	01.12.09	VIRGUS AST. COACH DRY AREA			\$ -		
01 - EVENT LEVEL	01.13.04	VIRGUS AST. COACH LOCK. RM		Add a Kitchen Counter Sink	\$ 7,700	\$ 7,700	Noted on Page 147 of the 10/23/13 Program
01 - EVENT LEVEL	01.13.04	VIRGUS AST. COACH LOCK. RM		Premium Wood for Assistant Coaches Lockers (35 ea)	\$ 38,607	\$ 38,607	
01 - EVENT LEVEL	01.12.07	VIRGUS AST. COACH WET RM			\$ -		
01 - EVENT LEVEL	01.08.04	VIRGUS CHEERLEADERS			\$ -		
01 - EVENT LEVEL	01.08.04	VIRGUS CHEERLEADERS	Rejected / DO Drawings Govern	Area to be at 40% RH (relative humidity)	\$ 7,700		M-E engineers confirmed that the current mechanical system as designed will control humidity within these spaces
01 - EVENT LEVEL	01.16.06	VIRGUS DRYING AREA			\$ -		
01 - EVENT LEVEL	01.14.04	VIRGUS EQUIP. MAJOR OFF.			\$ -		
01 - EVENT LEVEL	01.14.05	VIRGUS EQUIP. RM			\$ -		
01 - EVENT LEVEL	01.16.12	VIRGUS FAMILY LOUNGE		Added a 8 strand fiber to telecom closet	\$ 2,365	\$ 2,365	Noted on Page 147 of the 10/23/13 Program
01 - EVENT LEVEL	01.16.12	VIRGUS FAMILY LOUNGE		Add Audio control - ability to select press, PA, radio and TV's and added iPad Charging Station	\$ 16,014	\$ 16,014	Noted on Page 147 of the 10/23/13 Program
01 - EVENT LEVEL	01.13.05	VIRGUS GM			\$ -		
01 - EVENT LEVEL	01.13.06	VIRGUS HEAD COACH	Rejected / DO Drawings Govern	DDSI #17 included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV.	No Change		Call for 27" TV
01 - EVENT LEVEL	01.13.06	VIRGUS HEAD COACH		Added (1) Connection for Projector as the program noted a ceiling mounted projector in this room	\$ 1,539		Noted on Page 111 of the 10/23/13 Program
01 - EVENT LEVEL	01.13.06	VIRGUS HEAD COACH	Rejected / DO Drawings Govern	Area to be at 40% RH (relative humidity)	\$ 7,700		M-E engineers confirmed that the current mechanical system as designed will control humidity within these spaces
01 - EVENT LEVEL	01.13.06	VIRGUS HEAD COACH		Premium Wood for Head Coaches Lockers (2 ea)	\$ 2,206	\$ 2,206	
01 - EVENT LEVEL	01.15.13	VIRGUS HYDRO. RM		Trench drains in hydrotherapy vs. floor drain	\$ 3,850	\$ 3,850	Noted on Page 107 of the 10/23/13 Program
01 - EVENT LEVEL	01.15.13	VIRGUS HYDRO. RM	Rejected / DO Drawings Govern	Area to be at 40% RH (relative humidity)	\$ 7,700		M-E engineers confirmed that the current mechanical system as designed will control humidity within these spaces
01 - EVENT LEVEL	01.15.13	VIRGUS HYDRO. RM		Area to be at 40% RH (relative humidity)	\$ 21,252	\$ 21,252	Follow up to program review meeting on 11/6/13 - Add FCU for dehumidification
01 - EVENT LEVEL	01.16.05	VIRGUS LOCKER ROOM		Added a 8 strand fiber to telecom closet	\$ 2,365	\$ 2,365	Noted on Page 107 of the 10/23/13 Program



Review of DDSI #20 Scope Comparison									
LEVEL	Number	ROOM NAME	Status within GMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS		
				<b>TOTAL ESTIMATE OF ADDED COST FOR DDSI #20</b>	<b>\$ 8,477,363</b>	<b>\$ 2,098,526</b>			
01 - EVENT LEVEL	01.16.05	VIKINGS LOCKER ROOM	Rejected / DO Drawings Govern	Added sub roof system over the Locker Room	\$ 1,103,044		Noted on Page 107 of the 10/23/13 Program		
01 - EVENT LEVEL	01.16.05	VIKINGS LOCKER ROOM		Area to be at 40% RH (relative humidity)	\$ 7,700		Noted on Page 107 of the 10/23/13 Program		
01 - EVENT LEVEL	01.16.05	VIKINGS LOCKER ROOM		Added 4 digit code locks at Minnesota Vikings Lockers	\$ 22,337	\$ 22,337	Noted on Page 107 of the 10/23/13 Program		
01 - EVENT LEVEL	01.17.04	VIKINGS MEETING RM 1		Added (1) Connection for Projector as the program noted a ceiling mounted projector in this room	\$ 1,539		Noted on Page 117 of the 10/23/13 Program		
			Rejected / DO Drawings Govern	Area to be at 40% RH (relative humidity)	\$ 3,850		Noted on Page 117 of the 10/23/13 Program		
01 - EVENT LEVEL	01.17.05	VIKINGS MEETING RM 2		Added (1) Connection for Projector as the program noted a ceiling mounted projector in this room	\$ 1,539		Noted on Page 117 of the 10/23/13 Program		
			Rejected / DO Drawings Govern	Area to be at 40% RH (relative humidity)	\$ 3,850		Noted on Page 117 of the 10/23/13 Program		
01 - EVENT LEVEL	01.14.03	VIKINGS OWNER'S RM		Audio Control - ability to select press, PA, radio, TV and a auxiliary, (2) ceiling speakers	\$ 9,203	\$ 9,203	Noted on Page 119 of the 10/23/13 Program		
01 - EVENT LEVEL	01.12.04	VIKINGS STAFF LVR RMS							
01 - EVENT LEVEL	01.37.03	VIKINGS STORAGE		Add to humidity spaces - No Humidification in current design	\$ 10,450	\$ 10,450	Noted on Page 277 of the 10/23/13 Program		
01 - EVENT LEVEL	01.37.04	VIKINGS STORAGE		Add to humidity spaces - No Humidification in current design	\$ 10,450	\$ 10,450	Noted on Page 277 of the 10/23/13 Program		
01 - EVENT LEVEL	01.18.05	VIKINGS STRETCHING RM		Added (1) Connection for Projector as the program noted a ceiling mounted projector in this room	\$ 1,539		Noted on Page 115 of the 10/23/13 Program		
01 - EVENT LEVEL	01.18.05	VIKINGS STRETCHING RM	Rejected / DO Drawings Govern	Area to be at 40% RH (relative humidity)	\$ 7,700		Noted on Page 115 of the 10/23/13 Program		
01 - EVENT LEVEL	01.17.07	VIKINGS TEAM STO.		Add to humidity spaces - No Humidification in current design	\$ 9,350	\$ 9,350	Noted on Page 261 of the 10/23/13 Program		
01 - EVENT LEVEL	01.16.19	VIKINGS TEAM STO.							
01 - EVENT LEVEL	01.16.07	VIKINGS TOILETS							
01 - EVENT LEVEL	01.13.03	VIKINGS TRAINING RM							
01 - EVENT LEVEL	01.17.06	VIKINGS VIDEO STO.							
01 - EVENT LEVEL	01.15.07	VIKINGS WET ROOM	Rejected / DO Drawings Govern	Area to be at 40% RH (relative humidity)	\$ 7,700		Noted on Page 109 of the 10/23/13 Program		
01 - EVENT LEVEL	01.15.07	VIKINGS WET ROOM		Added 6 hair dryers at the Wet Room Areas	\$ 7,656	\$ 7,656	Noted on Page 109 of the 10/23/13 Program		
01 - EVENT LEVEL	01.07.03	WOMEN		Security Locking Hove bibs - add \$53,000	See Pricing Above		Total price for all toilet rooms is \$53,000		
01 - EVENT LEVEL	01.10.04	WOMEN		- same note as above -					
01 - EVENT LEVEL	01.15.02	WOMEN		- same note as above -					
01 - EVENT LEVEL	01.24.05	WOMEN		- same note as above -					
01 - EVENT LEVEL	01.22.03	WOMEN		- same note as above -					
01 - EVENT LEVEL	01.05.02	WOMEN		- same note as above -					
01 - EVENT LEVEL	01.04.02	WOMEN		- same note as above -					
01 - EVENT LEVEL	01.30.01	WOMEN		- same note as above -					
01 - EVENT LEVEL	01.01.07	WOMEN		- same note as above -					
01 - EVENT LEVEL	01.33.01	WOMEN		- same note as above -					
01 - EVENT LEVEL	01.12.05	X-RAY RM	Rejected / DO Drawings Govern	DDSI #17 did not include a TV at this location. DDSI #20 Program calls for one (1) 27" TV.	\$ 3,986		Calls for 27" TV		
01 - EVENT LEVEL	01.12.05	X-RAY RM		Added Wall hung sink with faucet	\$ 3,850	\$ 3,850	Noted on Page 135 of the 10/23/13 Program		
		<b>01B - ENDZONE SUITES</b>		1. Segmented OH Glass Doors are noted in the program. 2. Suite fronts are not "airtight" "Airtight separation between Suite lab seats (seating bowl) and Suite Interior with operable sections" 3. Interior Walls are not operable. 4. There is on N" deep speed rail between the 1st and 2nd row of seats. 5. No 12" solid surface / stone countertops that run the length of the seats. 6. No custom signage or "plaque" for the entrance of the suite. 7. Subroof needs to be added. 8. "Upgraded Hangers" for closet are a part of the FF&E Scope and not included in the GMP proposal.			Noted on Page 261 of the 10/23/13 Program		
01 - EVENT LEVEL		Endzone Suites	Rejected / DO Drawings Govern	Add to provide AIR TIGHT Glass requires the system to be an exterior system	NA		Suite Fronts are not "airtight"		
01 - EVENT LEVEL		Endzone Suites	Rejected / DO Drawings Govern	Add for making interior walls operable	NA		Interior Walls Not Operable		
01 - EVENT LEVEL		Endzone Suites		Add for Speed Rail between 1st and 2nd Row	\$ 16,500	\$ 16,500	Adds roughly 100 LF of railing		
01 - EVENT LEVEL		Endzone Suites		Add for 12" surface running the length of the seats	\$ 27,500	\$ 27,500	Adds roughly 100 LF of railing		
01 - EVENT LEVEL		Endzone Suites		Add for Custom signage or plaque on interior of suite	\$ -		See total add for signage noted above		
01 - EVENT LEVEL		Endzone Suites	Alternate 23	Add Subroof - deck, ductum and plumbing - 6,300 SF	\$ 341,600		Was included on the ADD ALTERNATE Listing - Item #23		
01 - EVENT LEVEL		Endzone Suites		Add individual suite controls	\$ 6,600	\$ 6,600			
01B - ENDZONE SUITES	01.08.03	CORRIDOR							
01B - ENDZONE SUITES	01.11.02	FIELD SUITE 24	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub		
01B - ENDZONE SUITES	01.11.01	FIELD SUITE 25	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub		
01B - ENDZONE SUITES	01.10.03	FIELD SUITE 26	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub		
01B - ENDZONE SUITES	01.10.02	FIELD SUITE 27	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub		
01B - ENDZONE SUITES	01.09.02	FIELD SUITE 28	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub		



Review of DDSI #20 Scope Comparison									
LEVEL	Number	ROOM NAME	Status within GMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS	REVISIONS from 11/6/13 Meeting	
				<b>TOTAL ESTIMATE OF ADDED COST FOR DDSI #20</b>	<b>\$ 8,477,363</b>	<b>\$ 2,048,526</b>			
01B - ENDZONE SUITES	01.09.01	FIELD SUITE 29	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	TV's follow DDSI - 17	
01B - ENDZONE SUITES	01.08.02	FIELD SUITE 30	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	TV's follow DDSI - 17	
01B - ENDZONE SUITES	01.08.01	FIELD SUITE 31	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub	TV's follow DDSI - 17	
01B - ENDZONE SUITES	01.10.01	PANTRY	Rejected / DD Drawings Govern	Add 42" TV	\$ 4,124		Additional 42" TV in larger suite(s)	TV's follow DDSI - 17	
01B - ENDZONE SUITES		TV CAM							
01B - ENDZONE SUITES		TV CAM							
01C - MINI SUITES		ADD ALTERNATE #12		1. Suite Fronts are overhead sectional glass doors, not operable glass panels. 2. Suite fronts are not "alright" 3. No glass entrance doors included at Mini Suites in GMP. 4. No custom signage or "logo" for the entrance of the suite. 5. No sloped subroof with Tectum Panels is included. 6. "Upgraded Hangers" for closet are a part of the FF&E Scope and not included in the GMP proposal.			Noted on Page 28 of the 10/23/13 Program		
		Mini Suites		Add to provide AIR TIGHT Glass requires the system to be an exterior system	Alternate		These Suites are on the Add Alternate / Deferral list in the GMP		
		Mini Suites		Added sub roof system	Alternate		If subroof would be required, this cost would need to be added to the Add Alternate / Deferral item for the Suites		
		Mini Suites		Add individual suite thermostats control interface - VAV's were added with Minimum Design Standards	Alternate				
01C - MINI SUITES	01.18.02	FIELD SUITE 14	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 42" or 60" TV	TV's follow DDSI - 17	
01C - MINI SUITES	01.18.03	FIELD SUITE 13	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 42" or 60" TV	TV's follow DDSI - 17	
01C - MINI SUITES	01.19.01	FIELD SUITE 12	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 42" or 60" TV	TV's follow DDSI - 17	
01C - MINI SUITES	01.19.02	FIELD SUITE 11	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 42" or 60" TV	TV's follow DDSI - 17	
01C - MINI SUITES	01.23.01	FIELD SUITE 10	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 42" or 60" TV	TV's follow DDSI - 17	
01C - MINI SUITES	01.23.02	FIELD SUITE 9	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 42" or 60" TV	TV's follow DDSI - 17	
01C - MINI SUITES	01.24.01	FIELD SUITE 8	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 42" or 60" TV	TV's follow DDSI - 17	
01C - MINI SUITES	01.24.02	FIELD SUITE 7	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 42" or 60" TV	TV's follow DDSI - 17	
02 - EXECUTIVE SUITES				1. All TVs for the Executive Suites are per DDSI #17. DDSI #20 references "HDTV Flat Screen TV's in equivalent sizes" 2. Suite fronts are not "alright" 3. Suite interiors are not operable 4. There is no 5" deep spread rail between the 1st and 2nd row of seats. 5. 12" deep stone countertop (behind fixed seating) to run width of front glass wall			Noted on Page 32 of the 10/23/13 Program		
		Executive Suites	Rejected / DD Drawings Govern	Add to provide AIR TIGHT Glass requires the system to be an exterior system	NA		Suite Fronts are not "alright"		
		Executive Suites	Rejected / DD Drawings Govern	Add for making interior walls operable	NA		Interior Walls Not Operable		
		Executive Suites	Rejected / DD Drawings Govern	Add 152 LP of Speed Rail between 1st and 2nd Row	\$ 25,080	\$ 25,080			
		Executive Suites	Rejected / DD Drawings Govern	Add for 12" surface running the length of the seats	No Change		The drink surface is included in the GMP and is part of the front glass rail detail		
		Executive Suites	Rejected / DD Drawings Govern	Add individual suite control interface	\$ 6,600	\$ 6,600			
02 - EXECUTIVE SUITES	02.21.3	BAR AREA							
02 - EXECUTIVE SUITES	02.22.09	BEV. PANTRY							
02 - EXECUTIVE SUITES	2652	BOWL - LOWER CLUB							
02 - EXECUTIVE SUITES	2681	BOWL - SE REDZONE							
02 - EXECUTIVE SUITES	1325	BOWL - SW REDZONE							
02 - EXECUTIVE SUITES	02.19.08	CHAIRMAN'S LOUNGE		ALT 01 (4 - 42", 3 - 50")					
02 - EXECUTIVE SUITES	02.20.06	CLUB LOUNGE - VALHALLA LOWER	Rejected / DD Drawings Govern	Program had a note for a 400A panelboard and 1500KVA transformer	\$ 32,319		Noted on Page 219 of the 10/23/13 Program	Panel is in space adjacent to club	
02 - EXECUTIVE SUITES	02.20.06	CLUB LOUNGE - VALHALLA LOWER	Rejected / DD Drawings Govern	Program notes butt-jointed glass panels at open to below area. None shown on 100% DD documents.				Not required per 11/6/13 program review meeting	
02 - EXECUTIVE SUITES	02.24.02	CONCESSION							
02 - EXECUTIVE SUITES	02.17.02	CONCESSION							
02 - EXECUTIVE SUITES	02.15.04	CORRIDOR	Rejected / DD Drawings Govern	DDSI #17 did not include a TV at this location. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 4,536		Calls for 50" TV @ Elevator Lobby	TV's follow DDSI - 17	
02 - EXECUTIVE SUITES	02.25.01	CORRIDOR							
02 - EXECUTIVE SUITES	02.22.06	CORRIDOR							
02 - EXECUTIVE SUITES	02.26.02	CORRIDOR							
02 - EXECUTIVE SUITES	02.16.02	CORRIDOR							
02 - EXECUTIVE SUITES	02.19.10	CORRIDOR							
02 - EXECUTIVE SUITES	02.22.10	CORRIDOR	Rejected / DD Drawings Govern	DDSI #17 did not include a TV at this location. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 4,536		Calls for 50" TV @ Elevator Lobby	TV's follow DDSI - 17	
02 - EXECUTIVE SUITES	02.16.04	CORRIDOR							
02 - EXECUTIVE SUITES	02.23.16	CORRIDOR							
02 - EXECUTIVE SUITES	02.25.02	CORRIDOR							

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within SMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS
TOTAL ESTIMATE OF ADDED COST FOR DDSI #20					\$ 8,477,363	\$ 2,098,526	REVISIONS from 11/6/13 Meeting
02 - EXECUTIVE SUITES	02.15.02	ELEC					
02 - EXECUTIVE SUITES	02.23.14	ELEC					
02 - EXECUTIVE SUITES	02.19.11	ELEV CNTRL RM					
02 - EXECUTIVE SUITES	02.23.03	EXEC SUITE 01	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" and one (1) 60" TV at the suites. The program calls for 1-32", 1-42", and 1-60"	No Change		TV's of varying sizes
02 - EXECUTIVE SUITES	02.23.02	EXEC SUITE 02	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" and one (1) 60" TV at the suites. The program calls for 1-32", 1-42", and 1-60"	No Change		TV's of varying sizes
02 - EXECUTIVE SUITES	02.23.01	EXEC SUITE 03	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" and one (1) 60" TV at the suites. The program calls for 1-32", 1-42", and 1-60"	No Change		TV's of varying sizes
02 - EXECUTIVE SUITES	02.22.02	EXEC SUITE 04	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" and one (1) 60" TV at the suites. The program calls for 1-32", 1-42", and 1-60"	No Change		TV's of varying sizes
02 - EXECUTIVE SUITES	03.04.2	EXEC SUITE 04	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" and one (1) 60" TV at the suites. The program calls for 1-32", 1-42", and 1-60"	No Change		TV's of varying sizes
02 - EXECUTIVE SUITES	02.21.02	EXEC SUITE 06	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" and one (1) 60" TV at the suites. The program calls for 1-32", 1-42", and 1-60"	No Change		TV's of varying sizes
02 - EXECUTIVE SUITES	02.21.01	EXEC SUITE 07	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" and one (1) 60" TV at the suites. The program calls for 1-32", 1-42", and 1-60"	No Change		TV's of varying sizes
02 - EXECUTIVE SUITES	02.20.02	EXEC SUITE 08	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" and one (1) 60" TV at the suites. The program calls for 1-32", 1-42", and 1-60"	No Change		TV's of varying sizes
02 - EXECUTIVE SUITES	02.20.01	EXEC SUITE 09	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" and one (1) 60" TV at the suites. The program calls for 1-32", 1-42", and 1-60"	No Change		TV's of varying sizes
02 - EXECUTIVE SUITES	02.19.03	EXEC SUITE 10	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" and one (1) 60" TV at the suites. The program calls for 1-32", 1-42", and 1-60"	No Change		TV's of varying sizes
02 - EXECUTIVE SUITES	02.19.02	EXEC SUITE 11	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" and one (1) 60" TV at the suites. The program calls for 1-32", 1-42", and 1-60"	No Change		TV's of varying sizes
02 - EXECUTIVE SUITES	02.19.01	EXEC SUITE 12	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" and one (1) 60" TV at the suites. The program calls for 1-32", 1-42", and 1-60"	No Change		TV's of varying sizes
02 - EXECUTIVE SUITES	02.18.03	FAM					
02 - EXECUTIVE SUITES	02.24.05	FAM					
02 - EXECUTIVE SUITES	02.22.08	FAMILY					
02 - EXECUTIVE SUITES	02.26.01	FAN ROOM - BOWL					
02 - EXECUTIVE SUITES	02.15.01	FAN ROOM - BOWL					
02 - EXECUTIVE SUITES	02.19.09	FINISHING KITCHEN					
02 - EXECUTIVE SUITES	02.23.11	FOOD PANTRY					
02 - EXECUTIVE SUITES	02.22.13	IDF					
02 - EXECUTIVE SUITES	02.16.03	IDF					
02 - EXECUTIVE SUITES	02.15.05	IDF					
02 - EXECUTIVE SUITES	02.23.15	IDF					
02 - EXECUTIVE SUITES	02.23.12	JAN					
02 - EXECUTIVE SUITES	02.23.04	JAN					
02 - EXECUTIVE SUITES	02.24.03	MEN	Rejected / DO Drawings Govern	Security Locking Hose bibs - add \$53,000	See Pricing Above		Total price for all toilet rooms is \$53,000
02 - EXECUTIVE SUITES	02.22.05	MEN					
02 - EXECUTIVE SUITES	02.18.01	MEN					
02 - EXECUTIVE SUITES	02.09.01	RAMP-01					
02 - EXECUTIVE SUITES	02.23.09	RR					
02 - EXECUTIVE SUITES	02.23.06	RR					
02 - EXECUTIVE SUITES	02.23.07	RR					
02 - EXECUTIVE SUITES	02.23.10	RR					
02 - EXECUTIVE SUITES	02.23.08	RR					
02 - EXECUTIVE SUITES	02.17.01	SE REDZONE	Rejected / DO Drawings Govern	DDSI #17 Included four (4) 50" TV's. DDSI #20 Program calls for four (4) 42" TV's.	No Change		Calls for 42" TV's
02 - EXECUTIVE SUITES	02.04.01	STAIR-01					
02 - EXECUTIVE SUITES	02.07.01	STAIR-03					
02 - EXECUTIVE SUITES	02.13.01	STAIR-04					
02 - EXECUTIVE SUITES	02.15.03	STAIR-06					
02 - EXECUTIVE SUITES	02.22.12	STAIR-07					
02 - EXECUTIVE SUITES	02.22.11	STAIR-08					
02 - EXECUTIVE SUITES	02.26.03	STAIR-09					
02 - EXECUTIVE SUITES	02.38.01	STAIR-11					
02 - EXECUTIVE SUITES	02.33.01	STAIR-13					
02 - EXECUTIVE SUITES	02.16.01	STORAGE					
02 - EXECUTIVE SUITES	02.19.07	SUITE CORRIDOR					
02 - EXECUTIVE SUITES	02.24.01	SW REDZONE	Rejected / DO Drawings Govern	DDSI #17 Included four (4) 50" TV's. DDSI #20 Program calls for four (4) 42" TV's.	No Change		Calls for 42" TV's
02 - EXECUTIVE SUITES	02.22.04	TOILET					
02 - EXECUTIVE SUITES	02.20.04	TOILET					
02 - EXECUTIVE SUITES	02.21.03	TOILET					
02 - EXECUTIVE SUITES	02.21.04	TOILET					
02 - EXECUTIVE SUITES	02.22.03	TOILET					
02 - EXECUTIVE SUITES	02.19.04	TOILET					
02 - EXECUTIVE SUITES	02.19.05	TOILET					
02 - EXECUTIVE SUITES	02.19.06	TOILET					
02 - EXECUTIVE SUITES	02.20.03	TOILET					
02 - EXECUTIVE SUITES	02.23.13	TRASH					
02 - EXECUTIVE SUITES	02.23.06	VEST					
02 - EXECUTIVE SUITES	02.20.05	VEST					
02 - EXECUTIVE SUITES	02.24.04	WOMEN	Rejected / DO Drawings Govern	Security Locking Hose bibs - add \$53,000	See Pricing Above		Total price for all toilet rooms is \$53,000
02 - EXECUTIVE SUITES	02.22.07	WOMEN					
02 - EXECUTIVE SUITES	02.18.02	WOMEN					

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within BWP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS
TOTAL ESTIMATE OF ADDED COST FOR DDSI #20					\$ 8,477,363	\$ 2,098,526	REVISIONS from 11/6/13 Meeting
03 - LOWER CLUB	03.39.07	A/V					
03 - LOWER CLUB	03.02.03	BAR					
03 - LOWER CLUB	03.16.19	BAR AREA					
03 - LOWER CLUB	2738	BOWL - LOWER CLUB					
03 - LOWER CLUB	2745	BOWL - NW REDZONE					
03 - LOWER CLUB	2744	BOWL - NW REDZONE					
03 - LOWER CLUB	3596	BOWL - SE REDZONE					
03 - LOWER CLUB	3588	BOWL - SOUTH LOWER CLUB					
03 - LOWER CLUB	3595	BOWL - SW REDZONE					
03 - LOWER CLUB	03.18.02	CHAIRMAN'S SUITE LOBBY					
03 - LOWER CLUB	03.39.03	CIRCULATION					
03 - LOWER CLUB	03.19.01	CLUB LOUNGE - VALHALLA UPPER		Valhalla Club Program Changes - Mechanical - Upgraded exhibition cooking platforms and bars, restrooms and finishes - Finish kitchen with cooking immediately adjacent to support these functions - Portable food service station stations to supplement fixed food service platforms - 2 alcohol burning fireplaces	\$ 130,900	\$ 130,900	Noted on Page 67 of the 10/23/13 Program
03 - LOWER CLUB	03.19.01	CLUB LOUNGE - VALHALLA UPPER		Valhalla Club Program Changes - Electrical - Upgraded exhibition cooking platforms Added circuits for Exhibition Cooking Platform, (10) 20A, (4) 30A and (2) 100A (typical of all platforms)	\$ 14,243	\$ 14,243	Noted on Page 67 of the 10/23/13 Program
03 - LOWER CLUB	03.19.01	CLUB LOUNGE - VALHALLA UPPER	Rejected / DD Drawings Govern	Program notes built/jointed glass panels at open to below area. None shown on 100% DD documents (except at glass rail)			Not required per 11/6/13 program review meeting
03 - LOWER CLUB	03.01.01	CLUB LOUNGE - VIKING'S CLUB	Rejected / DD Drawings Govern	Note in the program called for added circuits for Exhibition Cooking Platform, 400A panelboard and 150KVA transformer	\$ 43,877		Noted on Page 225 of the 10/23/13 Program
03 - LOWER CLUB	03.39.01	CONCESSION					
03 - LOWER CLUB	03.02.02	CONCESSION					
03 - LOWER CLUB	03.40.01	CONCESSION					
03 - LOWER CLUB	03.39.09	CONCESSION					
03 - LOWER CLUB	03.04.7	CONCESSION					
03 - LOWER CLUB	03.02.04	CORRIDOR	Rejected / DD Drawings Govern	Minimum Design Standards call for one (1) 42" TV at Elevator Lobby. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 275		Calls for 50" TV @ Elevator Lobby
03 - LOWER CLUB	03.20.01	CORRIDOR	Rejected / DD Drawings Govern	Minimum Design Standards call for one (1) 42" TV at Elevator Lobby. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 275		Calls for 50" TV @ Elevator Lobby
03 - LOWER CLUB	03.23.08	CORRIDOR	Rejected / DD Drawings Govern	Minimum Design Standards call for one (1) 42" TV at Elevator Lobby. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 275		Calls for 50" TV @ Elevator Lobby
03 - LOWER CLUB	03.39.08	CORRIDOR	Rejected / DD Drawings Govern	Minimum Design Standards call for one (1) 42" TV at Elevator Lobby. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 275		Calls for 50" TV @ Elevator Lobby
03 - LOWER CLUB	03.02.06	DRY STOR.					
03 - LOWER CLUB	03.05.02	ELEC					
03 - LOWER CLUB	03.39.04	ELEC					
03 - LOWER CLUB	03.15.01	ELEC					
03 - LOWER CLUB	03.23.06	ELEC					
03 - LOWER CLUB	03.15.03	ELEV CONTRL					
03 - LOWER CLUB	03.18.04	ENTRY VESTIBULE					
03 - LOWER CLUB	03.40.03	FAM					
03 - LOWER CLUB	03.38.03	FAM					
03 - LOWER CLUB	03.04.01	FAM					
03 - LOWER CLUB	03.23.04	FAMILY					
03 - LOWER CLUB	03.19.08	FAMILY					
03 - LOWER CLUB	03.03.02	FAMILY					
03 - LOWER CLUB	03.05.01	FAN ROOM - BOWL					
03 - LOWER CLUB	03.37.01	FAN ROOM - BOWL CLUB					
03 - LOWER CLUB	03.04.00	FINISHING KITCHEN					
03 - LOWER CLUB	03.04.6	FINISHING KITCHEN					
03 - LOWER CLUB	03.23.03	IDF					
03 - LOWER CLUB	03.13.01	IDF					
03 - LOWER CLUB	03.15.08	IDF					
03 - LOWER CLUB	03.23.07	IDF					
03 - LOWER CLUB	03.05.03	IDF					
03 - LOWER CLUB	03.39.06	IDF					
03 - LOWER CLUB	03.19.02	JAN					
03 - LOWER CLUB	03.41.02	JAN					
03 - LOWER CLUB	03.38.02	JAN					
03 - LOWER CLUB	03.04.02	JAN					
03 - LOWER CLUB	03.13.05	LOBBY	Rejected / DD Drawings Govern	DDSI #17 did not include a TV at this location. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 275		Calls for 50" TV @ Elevator Lobby
03 - LOWER CLUB	03.13.07	LOBBY	Rejected / DD Drawings Govern	DDSI #17 did not include a TV at this location. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 275		Calls for 50" TV @ Elevator Lobby
03 - LOWER CLUB	03.15.05	LOBBY	Rejected / DD Drawings Govern	DDSI #17 did not include a TV at this location. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 275		Calls for 50" TV @ Elevator Lobby
03 - LOWER CLUB	03.19.06	LOUNGE	Rejected / DD Drawings Govern	Note in program called out an added 200A panelboard and 75KVA transformer	\$ 16,017		Noted on Page 229 of the 10/23/13 Program
03 - LOWER CLUB	03.18.03	LOWER CLUB LOBBY					
03 - LOWER CLUB	03.37.02	LOWER CLUB LOBBY					
03 - LOWER CLUB	03.37.03	LOWER CLUB LOBBY	Rejected / DD Drawings Govern	DDSI #17 did not include a TV at this location. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 275		Calls for 50" TV @ Elevator Lobby
03 - LOWER CLUB	03.14.01	MEDIA ENTRY	Rejected / DD Drawings Govern	DDSI #17 did not include a TV at this location. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 275		Calls for 50" TV @ Elevator Lobby
03 - LOWER CLUB	03.14.03	MEDIA VEST					
03 - LOWER CLUB	03.38.04	MEN	Rejected / DD Drawings Govern	Security Locking Hose bibs - add \$53,000	See Pricing Above		Total price for all toilet rooms is \$53,000
03 - LOWER CLUB	03.04.03	MEN		- same note as above -			



Review of DDSI #20 Scope Comparison								
LEVEL	Number	ROOM NAME	Status within SMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS	
				TOTAL ESTIMATE OF ADDED COST FOR DDSI #20	\$ 8,477,363	\$ 2,098,526		REVISIONS from 11/6/13 Meeting
03 - LOWER CLUB	03.19.03	MEN		- same note as above -				
03 - LOWER CLUB	03.23.05	MEN		- same note as above -				
03 - LOWER CLUB	03.41.01	MEN		- same note as above -				
03 - LOWER CLUB	03.03.01	MEN		- same note as above -				
03 - LOWER CLUB	03.02.01	NE REDZONE	Rejected / DD Drawings Govern	DDSI #17 Included four (4) 50" TV's. DDSI #20 Program calls for four (4) 42" TV's.	No Change		Calls for 42" TV's	TV's follow DDSI - 17
03 - LOWER CLUB	03.38.01	NW REDZONE	Rejected / DD Drawings Govern	DDSI #17 Included four (4) 50" TV's. DDSI #20 Program calls for four (4) 42" TV's.	No Change		Calls for 42" TV's	TV's follow DDSI - 17
03 - LOWER CLUB	03.19.05	PANTRY						
03 - LOWER CLUB	03.39.02	PANTRY						
03 - LOWER CLUB	03.32.01	PIVOT MECH						
03 - LOWER CLUB	03.31.01	PIVOT MECH						
03 - LOWER CLUB	03.29.02	PIVOT MECH						
03 - LOWER CLUB	03.29.01	PIVOT MECH						
03 - LOWER CLUB	03.28.01	PIVOT MECH						
03 - LOWER CLUB	03.15.04	PLAYER ENTRY						
03 - LOWER CLUB	03.15.07	PLAYER VEST						
03 - LOWER CLUB	03.15.06	PRESS WILL-CALL	Rejected / DD Drawings Govern	DDSI #17 Included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV	No Change		Calls for 27" TV	TV's follow DDSI - 17
03 - LOWER CLUB	03.15.06	PRESS WILL-CALL	Rejected / DD Drawings Govern	Added (1) additional credentials window, millwork, and mechoshade at Press Will-Call	\$ 18,656		Noted on Page 105 of the 10/23/13 Program	Not required per 11/6/13 program review meeting
03 - LOWER CLUB	03.15.06	PRESS WILL-CALL	Rejected / DD Drawings Govern	Add (1) full slide tray at Press Will-Call	\$ 5,500		Noted on Page 105 of the 10/23/13 Program	Not required per 11/6/13 program review meeting
03 - LOWER CLUB	03.07.02	RAMP-01						
03 - LOWER CLUB	03.20.02	STAIR-14						
03 - LOWER CLUB	03.19.07	STAIR-25						
03 - LOWER CLUB	03.04.05	STAIR-01						
03 - LOWER CLUB	03.04.06	STAIR-02						
03 - LOWER CLUB	03.07.01	STAIR-03						
03 - LOWER CLUB	03.13.03	STAIR-04						
03 - LOWER CLUB	03.13.04	STAIR-05						
03 - LOWER CLUB	03.15.02	STAIR-06						
03 - LOWER CLUB	03.22.01	STAIR-07						
03 - LOWER CLUB	03.22.02	STAIR-08						
03 - LOWER CLUB	03.26.01	STAIR-09						
03 - LOWER CLUB	03.33.02	STAIR-10						
03 - LOWER CLUB	03.38.06	STAIR-11						
03 - LOWER CLUB	03.38.07	STAIR-12						
03 - LOWER CLUB	03.33.01	STAIR-13						
03 - LOWER CLUB	03.13.02	STORAGE						
03 - LOWER CLUB	03.16.01	STORAGE						
03 - LOWER CLUB	03.03.04	TRASH						
03 - LOWER CLUB	03.16.02	TRASH						
03 - LOWER CLUB	03.39.05	VESTIBULE						
03 - LOWER CLUB	03.15.09	WOMEN'S VEST						
03 - LOWER CLUB	03.38.05	WOMEN	Rejected / DD Drawings Govern	Security Locking Hose bibs - add \$53,000	See Pricing Above		Total price for all toilet rooms is \$53,000	
03 - LOWER CLUB	03.04.04	WOMEN		- same note as above -				
03 - LOWER CLUB	03.19.04	WOMEN		- same note as above -				
03 - LOWER CLUB	03.23.02	WOMEN		- same note as above -				
03 - LOWER CLUB	03.40.02	WOMEN		- same note as above -				
03 - LOWER CLUB	03.02.05	WOMEN		- same note as above -				
04 - MAIN CONCOURSE								
04 - MAIN CONCOURSE	03.39.10	BAR AREA						
04 - MAIN CONCOURSE	03.39.11	BAR AREA						
04 - MAIN CONCOURSE	04.28.02	REV CONCESSION						
04 - MAIN CONCOURSE		135 BOWL - MAIN CONC GA						
04 - MAIN CONCOURSE		1304 BOWL - MAIN CONC GA						
04 - MAIN CONCOURSE	04.36.11	BREAK AREA						
04 - MAIN CONCOURSE	04.21.01	BROADCAST BOOTH						
04 - MAIN CONCOURSE	04.37.07	COMM CLOSET						
04 - MAIN CONCOURSE	04.01.06	CONCOURSE	Rejected / DD Drawings Govern	INCLUDES (6) FOR HALL OF FAME; LOCATION TBD - Program calls for 42" TV's I.D 50" TV's	\$ (20,900)		Assume Elevator Lobbies covered in 76 TV's; Calls for 42" TV's	TV's follow DDSI - 17
04 - MAIN CONCOURSE	04.37.03	COOKING CONCESS						
04 - MAIN CONCOURSE	04.14.02	COOKING CONCESS						
04 - MAIN CONCOURSE	04.05.02	COOKING CONCESS						
04 - MAIN CONCOURSE	04.08.01	COOKING CONCESS						
04 - MAIN CONCOURSE	04.24.04	COOKING CONCESS						
04 - MAIN CONCOURSE	04.12.01	COOKING CONCESS						
04 - MAIN CONCOURSE	04.06.01	COOKING CONCESS						
04 - MAIN CONCOURSE	04.24.03	COOKING CONCESS						
04 - MAIN CONCOURSE	04.02.04	COOKING CONCESS						
04 - MAIN CONCOURSE	04.34.04	COOKING CONCESS						
04 - MAIN CONCOURSE	04.17.03	COOKING CONCESS						
04 - MAIN CONCOURSE	04.13.02	CORRIDOR						
04 - MAIN CONCOURSE	04.13.04	CORRIDOR						
04 - MAIN CONCOURSE	04.16.01	CORRIDOR						
04 - MAIN CONCOURSE	04.04.02	CORRIDOR						
04 - MAIN CONCOURSE	04.04.04	CORRIDOR						
04 - MAIN CONCOURSE	04.23.06	CORRIDOR						
04 - MAIN CONCOURSE	04.15.03	ELEC						

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within GMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	
TOTAL ESTIMATE OF ADDED COST FOR DDSI #20					\$ 8,477,363	\$ 2,098,526	
COMMENTS ON PROGRAM REQUIREMENTS							REVISIONS from 11/6/13 Meeting
04 - MAIN CONCOURSE	04.05.03	ELEC					
04 - MAIN CONCOURSE	04.23.04	ELEC					
04 - MAIN CONCOURSE	04.39.02	ELEC					
04 - MAIN CONCOURSE	04.13.03	ELEC					
04 - MAIN CONCOURSE	04.34.01	ELEC					
04 - MAIN CONCOURSE	04.35.02	ELEV CNTRL RM					
04 - MAIN CONCOURSE	04.35.03	ENTRY					
04 - MAIN CONCOURSE	04.11.01	ENTRY					
04 - MAIN CONCOURSE	04.37.10	ENTRY					
04 - MAIN CONCOURSE	04.18.02	ENTRY					
04 - MAIN CONCOURSE	04.28.01	ENTRY					
04 - MAIN CONCOURSE	04.32.01	ENTRY					
04 - MAIN CONCOURSE	04.05.01	FAM					
04 - MAIN CONCOURSE	04.23.05	FAM					
04 - MAIN CONCOURSE	04.41.05	FAM					
04 - MAIN CONCOURSE	04.27.03	FAM					
04 - MAIN CONCOURSE	04.07.02	FAM					
04 - MAIN CONCOURSE	04.36.02	FAM					
04 - MAIN CONCOURSE	04.37.01	FAM					
04 - MAIN CONCOURSE	04.15.10	FAM					
04 - MAIN CONCOURSE	04.15.09	FAM					
04 - MAIN CONCOURSE	04.47.06	FAMILY					
04 - MAIN CONCOURSE	04.21.04	FAMILY					
04 - MAIN CONCOURSE	04.37.11	FAN ROOM - TEAM STORE / TICKET					
04 - MAIN CONCOURSE	04.15.07	FIRST AID	Rejected / DD Drawings Govern	DDSI #17 included one (1) 42" TV. DDSI #20 Program calls for one (1) 37" TV	No Change		Calls for 37" TV
04 - MAIN CONCOURSE	04.15.07	FIRST AID		Add sound system tied to bowl sound	\$ 8,544	\$ 8,544	Noted on Page 59 of the 10/23/13 Program
04 - MAIN CONCOURSE	04.15.07	FIRST AID		First Aid Room - add a men's and women's toilet	\$ 16,500	\$ 16,500	Noted on Page 59 of the 10/23/13 Program
04 - MAIN CONCOURSE	04.04.03	GUEST SERVICES	Rejected / DD Drawings Govern	DDSI #17 included one (1) 42" TV. DDSI #20 Program calls for one (1) 37" TV	No Change		Calls for 37" TV
04 - MAIN CONCOURSE	04.04.03	GUEST SERVICES		Add sound system tied to bowl sound	\$ 8,544		Noted on Page 61 of the 10/23/13 Program
04 - MAIN CONCOURSE	04.18.01	IDF					
04 - MAIN CONCOURSE	04.08.02	IDF					
04 - MAIN CONCOURSE	04.01.05	IDF					
04 - MAIN CONCOURSE	04.27.02	IDF					
04 - MAIN CONCOURSE	04.15.13	IDF					
04 - MAIN CONCOURSE	04.23.07	IDF					
04 - MAIN CONCOURSE	04.23.08	IDF					
04 - MAIN CONCOURSE	04.39.03	IDF					
04 - MAIN CONCOURSE	04.34.03	IDF					
04 - MAIN CONCOURSE	04.13.07	IDF					
04 - MAIN CONCOURSE	04.42.04	JAN					
04 - MAIN CONCOURSE	04.40.06	JAN					
04 - MAIN CONCOURSE	04.07.01	JAN					
04 - MAIN CONCOURSE	04.36.01	JAN					
04 - MAIN CONCOURSE	04.36.03	JAN					
04 - MAIN CONCOURSE	04.22.04	JAN					
04 - MAIN CONCOURSE	04.15.11	JAN					
04 - MAIN CONCOURSE	04.15.16	JAN					
04 - MAIN CONCOURSE	04.15.19	JAN					
04 - MAIN CONCOURSE	04.24.01	LOGE LOUNGE	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.24.01	LOGE LOUNGE		Program notes premium stain grade millwork; 100% DD indicates 3M DI-noc-clad millwork.	Included with GMP Amendment		
04 - MAIN CONCOURSE	04.17.01	LOGE LOUNGE	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.17.01	LOGE LOUNGE		Program notes premium stain grade millwork; 100% DD indicates 3M DI-noc-clad millwork.	Included with GMP Amendment		
04 - MAIN CONCOURSE	04.38.02	LOGE LOUNGE	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.38.02	LOGE LOUNGE		Program notes premium stain grade millwork; 100% DD indicates 3M DI-noc-clad millwork.	Included with GMP Amendment		
04 - MAIN CONCOURSE	04.03.01	LOGE LOUNGE	Rejected / DD Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.03.01	LOGE LOUNGE		Program notes premium stain grade millwork; 100% DD indicates 3M DI-noc-clad millwork.	Included with GMP Amendment		
04 - MAIN CONCOURSE	04.20.04	MAIN CONCOURSE LOBBY		Add individual suite control interface	\$ 6,600	\$ 6,600	
04 - MAIN CONCOURSE	04.40.05	MAIN CONCOURSE LOBBY					

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within GMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	
TOTAL ESTIMATE OF ADDED COST FOR DDSI #20					\$ 8,477,363	\$ 2,098,526	COMMENTS ON PROGRAM REQUIREMENTS
1. "Airtight separation between Suite lab seats (seating bowl) and Suite interior with operable sections" 2. Suite Fronts are not "airtight" 3. Suite interior are not operable 4. There is no 3" deep speed rail between the 1st and 2nd row of seats 5. 12" deep stone countertop (behind fixed seating) to run width of front glass wall 6. No custom signage or "plaques" for the entrance of the suite. 7. "Upgraded Hangers" for closet are a part of the FF&C Scope and not included in the GMP proposal.							Noted on Page 36 of the 10/23/13 Program
04 - MAIN CONCOURSE SUITES		Main Concourse Suites	Rejected / DO Drawings Govern	Add to provide AIR TIGHT Glass requires the system to be an exterior system	NA		Suite Fronts are not "airtight"
		Main Concourse Suites	Rejected / DO Drawings Govern	Add for making interior walls operable	NA		Interior Walls Not Operable
		Main Concourse Suites		Add for Speed Rail between 1st and 2nd Row	\$ 36,100	\$ 36,100	Adds 340 Lf of railing.
		Main Concourse Suites		Add for 12" surface running the length of the seats	No Change		Drink surface is included in front glass rail detail
		Main Concourse Suites		Add individual suite control interface	\$ 6,600	\$ 6,600	
04 - MAIN CONCOURSE		Main Concourse Suites	Rejected / DO Drawings Govern	Increase millwork rubber base from 4.25" to 6"	\$ 26,279		
04 - MAIN CONCOURSE	04.40.01	MAIN SUITE 01	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.40.02	MAIN SUITE 02	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.40.03	MAIN SUITE 03	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.41.01	MAIN SUITE 04	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.41.02	MAIN SUITE 05	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.41.03	MAIN SUITE 06	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.42.01	MAIN SUITE 07	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.42.02	MAIN SUITE 08	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.42.03	MAIN SUITE 09	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.01.01	MAIN SUITE 10	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.01.02	MAIN SUITE 11	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.01.03	MAIN SUITE 12	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.02.01	MAIN SUITE 13	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.02.02	MAIN SUITE 14	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.02.03	MAIN SUITE 15	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.19.01	MAIN SUITE 16	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.19.02	MAIN SUITE 17	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.19.03	MAIN SUITE 18	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.20.01	MAIN SUITE 19	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.20.02	MAIN SUITE 20	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.20.03	MAIN SUITE 21	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.22.01	MAIN SUITE 22	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.22.02	MAIN SUITE 23	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.22.03	MAIN SUITE 24	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.23.01	MAIN SUITE 25	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.23.02	MAIN SUITE 26	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.23.03	MAIN SUITE 27	Rejected / DO Drawings Govern	There is no infrastructure in the GMP for this future TV. Price to add infrastructure. Excludes TV, bracket and IPTV Box	\$ 1,016		Future 35" TV in Bowl Tub
04 - MAIN CONCOURSE	04.36.09	MANAGER OFFICE	Rejected / DO Drawings Govern	DDSI #17 included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV	No Change		Calls for 27" TV
04 - MAIN CONCOURSE	04.06.02	NEN	Rejected / DO Drawings Govern	Security Locking Hose bibs - add \$53,000	See Pricing Above		Total price for all toilet rooms is \$53,000
04 - MAIN CONCOURSE	04.15.12	NEN		- same note as above -			
04 - MAIN CONCOURSE	04.21.03	NEN		- same note as above -	\$ -		
04 - MAIN CONCOURSE	04.40.07	NEN		- same note as above -	\$ -		
04 - MAIN CONCOURSE	04.36.05	NEN		- same note as above -	\$ -		



Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within GMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS
TOTAL ESTIMATE OF ADDED COST FOR DDSI #20					\$ 8,477,363	\$ 2,098,526	
04 - MAIN CONCOURSE	04.26.01	NIEN		- same note as above -	\$ -		REVISIONS from 11/6/13 Meeting
04 - MAIN CONCOURSE	04.37.05	NIEN		- same note as above -	\$ -		
04 - MAIN CONCOURSE	04.38.03	NON-COOKING CONCESS			\$ -		
04 - MAIN CONCOURSE	04.03.03	NON-COOKING CONCESS			\$ -		
04 - MAIN CONCOURSE	04.33.01	NON-COOKING CONCESS			\$ -		
04 - MAIN CONCOURSE	04.21.06	NON-COOKING CONCESS			\$ -		
04 - MAIN CONCOURSE	04.17.02	NON-COOKING CONCESS			\$ -		
04 - MAIN CONCOURSE	04.15.02	OFFICE			\$ -		
04 - MAIN CONCOURSE	04.19.05	PAINTRY			\$ -		
04 - MAIN CONCOURSE	04.19.01	PAINTRY			\$ -		
04 - MAIN CONCOURSE	04.03.02	PAINTRY			\$ -		
04 - MAIN CONCOURSE	04.41.04	PAINTRY			\$ -		
04 - MAIN CONCOURSE	04.08.03	RAMP#01			\$ -		
04 - MAIN CONCOURSE	04.36.06	STAFF OFFICE	Rejected / DO Drawings Govern	DDSI #17 Included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV	\$ -		Calls for 27" TV
04 - MAIN CONCOURSE	04.36.07	STAFF OFFICE	Rejected / DO Drawings Govern	DDSI #17 Included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV	\$ -		Calls for 27" TV
04 - MAIN CONCOURSE	04.36.08	STAFF OFFICE	Rejected / DO Drawings Govern	DDSI #17 Included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV	\$ -		Calls for 27" TV
04 - MAIN CONCOURSE	04.36.10	STAFF OFFICE	Rejected / DO Drawings Govern	DDSI #17 Included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV	\$ -		Calls for 27" TV
04 - MAIN CONCOURSE	04.04.05	STAIR-01			\$ -		
04 - MAIN CONCOURSE	04.04.06	STAIR-02			\$ -		
04 - MAIN CONCOURSE	04.07.05	STAIR-03			\$ -		
04 - MAIN CONCOURSE	04.13.05	STAIR-04			\$ -		
04 - MAIN CONCOURSE	04.13.06	STAIR-05			\$ -		
04 - MAIN CONCOURSE	04.15.06	STAIR-06			\$ -		
04 - MAIN CONCOURSE	04.22.05	STAIR-07			\$ -		
04 - MAIN CONCOURSE	04.22.06	STAIR-08			\$ -		
04 - MAIN CONCOURSE	04.26.02	STAIR-09			\$ -		
04 - MAIN CONCOURSE	04.38.04	STAIR-11			\$ -		
04 - MAIN CONCOURSE	04.38.05	STAIR-12			\$ -		
04 - MAIN CONCOURSE	04.04.01	STAIR-21			\$ -		
04 - MAIN CONCOURSE	04.38.01	STAIR-24			\$ -		
04 - MAIN CONCOURSE	04.13.01	STOR			\$ -		
04 - MAIN CONCOURSE	04.24.02	STORAGE			\$ -		
04 - MAIN CONCOURSE	04.16.02	STORAGE			\$ -		
04 - MAIN CONCOURSE	04.37.08	STORAGE			\$ -		
04 - MAIN CONCOURSE	04.15.08	STORAGE			\$ -		
04 - MAIN CONCOURSE	04.35.01	STORAGE			\$ -		
04 - MAIN CONCOURSE	04.15.15	STORAGE			\$ -		
04 - MAIN CONCOURSE	04.19.04	SUITE CORRIDOR			\$ -		
04 - MAIN CONCOURSE	04.40.04	SUITE CORRIDOR			\$ -		
04 - MAIN CONCOURSE	04.42.05	SUITE MEN			\$ -		
04 - MAIN CONCOURSE	04.01.04	SUITE WOMEN			\$ -		
04 - MAIN CONCOURSE	04.34.02	TEAM STORE		The GMP proposal only includes the shell space for the team store. FR Out of the Team Store is excluded from the GMP proposal.	NA		
04 - MAIN CONCOURSE	04.36.14	TICKET WINDOWS	Rejected / DO Drawings Govern	Added in (18) connections to Mechro Shades data for shades by others. Not clear as to whether or not these are powered.	\$ 23,272		Not required per 11/6/13 program review meeting - Manual mechro-shades to be provided
04 - MAIN CONCOURSE	04.36.14	TICKET WINDOWS		Added (1) 30A 208/3 phase connection for 1 High Speed Copier and (1) Slide Glimmer	\$ 1,278	\$ 1,278	Noted on Page 95 of the 10/23/13 Program
04 - MAIN CONCOURSE	04.36.14	TICKET WINDOWS		Added (2) interior auxiliary windows at M.C. (includes millwork and meshroshade)	\$ 36,685	\$ 36,685	Noted on Page 87 of the 10/23/13 Program
04 - MAIN CONCOURSE	04.36.14	TICKET WINDOWS	Rejected / DO Drawings Govern	Add 8 If p-lam work counter at Ticket Office Manager - FFE?	\$ 792		Noted on Page 92 of the 10/23/13 Program
04 - MAIN CONCOURSE	04.36.14	TICKET WINDOWS	Rejected / DO Drawings Govern	Add 8 If p-lam work counter at (4) Ticket Office Staff Offices (32 If total)	\$ 3,168		Not required per 11/6/13 program review meeting
04 - MAIN CONCOURSE	04.36.14	TICKET WINDOWS	Rejected / DO Drawings Govern	Add 10 If p-lam shelving (3 row) at Ticket Office Work Room	\$ 1,276		Noted on Page 95 of the 10/23/13 Program
04 - MAIN CONCOURSE	04.36.14	TICKET WINDOWS	Rejected / DO Drawings Govern	Add 10 If p-lam shelving (3 row) at Ticket Office Break Room	\$ 1,276		Noted on Page 97 of the 10/23/13 Program
04 - MAIN CONCOURSE	04.21.02	TOILET			\$ -		
04 - MAIN CONCOURSE	04.03.04	TRASH			\$ -		
04 - MAIN CONCOURSE	04.15.04	TRASH			\$ -		
04 - MAIN CONCOURSE	04.14.01	TRASH			\$ -		
04 - MAIN CONCOURSE	04.35.06	VAULT		Add one security camera for communications closet within ticket office location	\$ 1,374	\$ 1,374	Noted on Page 89 of the 10/23/13 Program
04 - MAIN CONCOURSE	04.35.06	VAULT		Add solid grouted cmu at vault walls	\$ 986	\$ 986	Noted on Page 90 of the 10/23/13 Program
04 - MAIN CONCOURSE	04.07.04	VEHICOR DEPOT		Add gyp lid and metal deck at top of vault	\$ 3,163	\$ 3,163	Noted on Page 90 of the 10/23/13 Program
04 - MAIN CONCOURSE	04.16.04	VEHICOR DEPOT			\$ -		
04 - MAIN CONCOURSE	04.15.01	VEST			\$ -		
04 - MAIN CONCOURSE	04.15.05	VEST			\$ -		
04 - MAIN CONCOURSE	04.36.15	VEST			\$ -		
04 - MAIN CONCOURSE	04.35.04	VEST			\$ -		
04 - MAIN CONCOURSE	04.14.03	WOMEN	Rejected / DO Drawings Govern	Security Locking Hose bibs - add \$53,000	See Pricing Above		Total price for all toilet rooms is \$53,000
04 - MAIN CONCOURSE	04.07.03	WOMEN			\$ -		
04 - MAIN CONCOURSE	04.37.06	WOMEN			\$ -		
04 - MAIN CONCOURSE	04.21.05	WOMEN			\$ -		
04 - MAIN CONCOURSE	04.41.06	WOMEN			\$ -		
04 - MAIN CONCOURSE	04.37.04	WOMEN			\$ -		
04 - MAIN CONCOURSE	04.25.01	WOMEN			\$ -		

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within GMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS
TOTAL ESTIMATE OF ADDED COST FOR DDSI #20					\$ 8,477,363	\$ 2,098,526	REVISIONS from 11/6/13 Meeting
04 - MAIN CONCOURSE	04.18.03	WOMEN			\$ -		
04 - MAIN CONCOURSE	04.36.04	WOMEN			\$ -		
04 - MAIN CONCOURSE	04.27.01	WOMEN			\$ -		
04 - MAIN CONCOURSE	04.05.04	WOMEN			\$ -		
04 - MAIN CONCOURSE	04.36.12	WORK AREA			\$ -		
04 - MAIN CONCOURSE	04.35.07	WIDENING ROOM			\$ -		
05 - UPPER CLUB					\$ -		
05 - UPPER CLUB	05.18.03	A/V			\$ -		
05 - UPPER CLUB	05.40.01	A/V			\$ -		
05 - UPPER CLUB		BCWL - CLUB			\$ -		
05 - UPPER CLUB		BCWL - CLUB			\$ -		
05 - UPPER CLUB		BCWL - MAIN CONC UPPER GA			\$ -		
05 - UPPER CLUB		BCWL - MAIN CONC UPPER GA			\$ -		
05 - UPPER CLUB		BCWL - MAIN CONC UPPER GA	Rejected / DO Drawings Govern	Added 400A panelboard and 150KVA transformer	\$ -		
05 - UPPER CLUB		BCWL - MAIN CONC UPPER GA			\$ -		
05 - UPPER CLUB	05.37.01	BREAK			\$ -		
05 - UPPER CLUB	05.15.03	BREAK			\$ -		
05 - UPPER CLUB	05.19.02	CLUB LOUNGE - FIRE CLUB	Rejected / Removed from project scope per SDC	Rear Projection Systems were deleted from the scope of work of the GMP, but are still noted in the program document.	\$ 316,304		Amount deferred from scope of the project.
05 - UPPER CLUB	05.19.02	CLUB LOUNGE - FIRE CLUB		Club Program Changes - Upgraded exhibition cooking platforms Added circuits for Exhibition Cooking Platform. (10) 20A, (4) 30A and (2) 100A (typical of all platforms)	\$ 14,243	\$ 14,243	Noted on Page 75 of the 10/23/13 Program
05 - UPPER CLUB	05.19.02	CLUB LOUNGE - FIRE CLUB	Rejected / DO Drawings Govern	Program noted an added 400A panelboard and 150KVA transformer	\$ 31,226		Noted on Page 239 of the 10/23/13 Program
05 - UPPER CLUB	05.01.01	CLUB LOUNGE - ICE CLUB	Rejected / Removed from project scope per SDC	Rear Projection Systems were deleted from the scope of work of the GMP, but are still noted in the program document.	\$ 316,304		Amount deferred from scope of the project.
05 - UPPER CLUB	05.01.01	CLUB LOUNGE - ICE CLUB		Club Program Changes - Upgraded exhibition cooking platforms Added circuits for Exhibition Cooking Platform. (10) 20A, (4) 30A and (2) 100A (typical of all platforms)	\$ 15,192	\$ 15,192	Noted on Page 75 of the 10/23/13 Program
05 - UPPER CLUB	05.01.01	CLUB LOUNGE - ICE CLUB	Rejected / DO Drawings Govern	Program noted an added 400A panelboard and 150KVA transformer	\$ 31,226		Noted on Page 239 of the 10/23/13 Program
05 - UPPER CLUB	05.15.09	COAT			\$ -		
05 - UPPER CLUB	05.36.03	CONF RM			\$ -		
05 - UPPER CLUB	05.14.01	CONF RM			\$ -		
05 - UPPER CLUB	05.14.02	CONF RM			\$ -		
05 - UPPER CLUB	05.36.04	CONF RM			\$ -		
05 - UPPER CLUB	05.03.02	CORRIDOR	Rejected / DO Drawings Govern	Minimum Design Standards call for one (1) 42" TV at Elevator Lobby. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 275		Calls for 50" TV @ Elevator Lobby
05 - UPPER CLUB	05.35.01	CORRIDOR			\$ -		
05 - UPPER CLUB	05.17.01	CORRIDOR			\$ -		
05 - UPPER CLUB	05.24.05	CORRIDOR			\$ -		
05 - UPPER CLUB	05.15.18	CORRIDOR			\$ -		
05 - UPPER CLUB	05.06.01	CORRIDOR			\$ -		
05 - UPPER CLUB	05.15.06	DATA			\$ -		
05 - UPPER CLUB	05.23.01	ELEC			\$ -		
05 - UPPER CLUB	05.39.01	ELEC			\$ -		
05 - UPPER CLUB	05.05.01	ELEC			\$ -		
05 - UPPER CLUB	05.34.01	ELEC			\$ -		
05 - UPPER CLUB	05.15.01	ELEC			\$ -		
05 - UPPER CLUB	05.40.02	FAM			\$ -		
05 - UPPER CLUB	05.18.04	FAM			\$ -		
05 - UPPER CLUB	05.02.02	FAMILY			\$ -		
05 - UPPER CLUB	05.24.01	FAMILY			\$ -		
05 - UPPER CLUB	05.03.01	FAN ROOM - CLUB			\$ -		
05 - UPPER CLUB	05.37.04	FAN ROOM - OFFICES			\$ -		
05 - UPPER CLUB	05.34.04	FAN ROOM - RESTAURANT			\$ -		
05 - UPPER CLUB	05.23.02	FAN ROOM CLUB			\$ -		
05 - UPPER CLUB	05.22.01	FINISHING KITCHEN			\$ -		
05 - UPPER CLUB	05.02.01	FINISHING KITCHEN			\$ -		
05 - UPPER CLUB	05.15.17	IDF			\$ -		
05 - UPPER CLUB	05.39.02	IDF			\$ -		
05 - UPPER CLUB	05.05.04	IDF			\$ -		
05 - UPPER CLUB	05.23.03	IDF			\$ -		
05 - UPPER CLUB	05.34.03	IDF			\$ -		
05 - UPPER CLUB	05.24.02	JAN			\$ -		
05 - UPPER CLUB	05.03.03	JAN			\$ -		
05 - UPPER CLUB	05.35.10	JAN			\$ -		
05 - UPPER CLUB	05.40.05	JAN			\$ -		
05 - UPPER CLUB	05.35.15	JAN			\$ -		
05 - UPPER CLUB	05.35.02	KITCHEN			\$ -		
05 - UPPER CLUB	05.32.02	LANDING			\$ -		
05 - UPPER CLUB	05.27.01	LANDING			\$ -		
05 - UPPER CLUB	05.11.01	LANDING			\$ -		
05 - UPPER CLUB	05.36.06	MEN	Rejected / DO Drawings Govern	Security Locking Hose bibs - add \$53,000	\$ -		Total price for all toilet rooms is \$53,000
05 - UPPER CLUB	05.02.03	MEN					



Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within BWP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS
				TOTAL ESTIMATE OF ADDED COST FOR DDSI #20	\$ 8,477,363	\$ 2,098,526	REVISIONS from 11/6/13 Meeting
05 - UPPER CLUB	05.24.03	NIEN			\$ -		
05 - UPPER CLUB	05.18.02	NIEN			\$ -		
05 - UPPER CLUB	05.15.04	NIEN			\$ -		
05 - UPPER CLUB	05.40.03	NIEN			\$ -		
05 - UPPER CLUB	05.35.06	NIEN			\$ -		
05 - UPPER CLUB	05.35.04	MSFA OFFICES		Added Built in Speakers, Video conference capabilities, and projection screen at the Large Conference Room	\$ 57,685	\$ 57,685	Noted on Page 251 of the 10/23/13 Program
05 - UPPER CLUB	05.35.03	OFFICE			\$ -		
05 - UPPER CLUB	05.36.11	OFFICE			\$ -		
05 - UPPER CLUB	05.36.10	OFFICE			\$ -		
05 - UPPER CLUB	05.35.13	OFFICE			\$ -		
05 - UPPER CLUB	05.35.12	OFFICE			\$ -		
05 - UPPER CLUB	05.35.11	OFFICE			\$ -		
05 - UPPER CLUB	05.36.09	OFFICE			\$ -		
05 - UPPER CLUB	05.36.12	OFFICE			\$ -		
05 - UPPER CLUB	05.35.05	OFFICE			\$ -		
05 - UPPER CLUB	05.35.07	OFFICE			\$ -		
05 - UPPER CLUB	05.36.13	OFFICE			\$ -		
05 - UPPER CLUB	05.35.06	OFFICE			\$ -		
05 - UPPER CLUB	05.14.10	OFFICE			\$ -		
05 - UPPER CLUB	05.14.09	OFFICE			\$ -		
05 - UPPER CLUB	05.14.08	OFFICE			\$ -		
05 - UPPER CLUB	05.14.07	OFFICE			\$ -		
05 - UPPER CLUB	05.14.06	OFFICE			\$ -		
05 - UPPER CLUB	05.14.05	OFFICE			\$ -		
05 - UPPER CLUB	05.14.04	OFFICE			\$ -		
05 - UPPER CLUB	05.14.14	OFFICE			\$ -		
05 - UPPER CLUB	05.15.14	OFFICE			\$ -		
05 - UPPER CLUB	05.15.13	OFFICE			\$ -		
05 - UPPER CLUB	05.15.12	OFFICE			\$ -		
05 - UPPER CLUB	05.15.11	OFFICE			\$ -		
05 - UPPER CLUB	05.19.01	PAINTRY			\$ -		
05 - UPPER CLUB	05.41.01	PAINTRY			\$ -		
05 - UPPER CLUB	05.09.01	RAMP-01			\$ -		
05 - UPPER CLUB	05.36.05	RECP	Rejected / DO Drawings Govern	DDSI #17 included one (1) 50" TV. DDSI #20 Program calls for one (1) 42" TV	\$ 4,536		MSFA Reception - Calls for 42" TV
05 - UPPER CLUB	05.36.01	RECP			\$ -		TV's follow DDSI - 17
05 - UPPER CLUB	05.15.10	RECP			\$ -		
05 - UPPER CLUB	05.34.02	RESTAURANT SHELL			\$ -		
05 - UPPER CLUB	05.37.05	SKYBRIDGE ENTRY			\$ -		
05 - UPPER CLUB	05.38.01	STAIR-11			\$ -		
05 - UPPER CLUB	05.04.01	STAIR-01			\$ -		
05 - UPPER CLUB	05.04.02	STAIR-02			\$ -		
05 - UPPER CLUB	05.07.01	STAIR-03			\$ -		
05 - UPPER CLUB	05.13.01	STAIR-04			\$ -		
05 - UPPER CLUB	05.13.02	STAIR-05			\$ -		
05 - UPPER CLUB	05.15.02	STAIR-06			\$ -		
05 - UPPER CLUB	05.22.01	STAIR-07			\$ -		
05 - UPPER CLUB	05.22.02	STAIR-08			\$ -		
05 - UPPER CLUB	05.26.01	STAIR-09			\$ -		
05 - UPPER CLUB	05.17.27	STAIR-10			\$ -		
05 - UPPER CLUB	05.38.02	STAIR-12			\$ -		
05 - UPPER CLUB	05.16.01	STORAGE			\$ -		
05 - UPPER CLUB	05.37.03	STORAGE			\$ -		
05 - UPPER CLUB	05.15.16	STORAGE			\$ -		
05 - UPPER CLUB	05.36.07	STORAGE			\$ -		
05 - UPPER CLUB	05.36.08	STORAGE			\$ -		
05 - UPPER CLUB	05.35.14	TOILET			\$ -		
05 - UPPER CLUB	05.05.02	TRASH			\$ -		
05 - UPPER CLUB	05.16.02	TRASH			\$ -		
05 - UPPER CLUB	5229	TV- CAM			\$ -		
05 - UPPER CLUB	5229	TV- CAM			\$ -		
05 - UPPER CLUB	5230	TV- CAM			\$ -		
05 - UPPER CLUB	5231	TV- CAM			\$ -		
05 - UPPER CLUB	05.37.06	UPPER CLUB LOBBY			\$ -		
05 - UPPER CLUB	05.16.03	UPPER CLUB LOBBY			\$ -		
05 - UPPER CLUB	05.13.03	VEST			\$ -		
05 - UPPER CLUB	05.15.07	VEST			\$ -		
05 - UPPER CLUB	05.14.03	VRUNGS OFFICES		Added Built in Speakers, Video conference capabilities, and projection screen at the Large Conference Room	\$ 57,685	\$ 57,685	Noted on Page 257 of the 10/23/13 Program
05 - UPPER CLUB	05.14.03	VRUNGS OFFICES		Added 35 lf upper cabinets p-lam at breakroom	\$ 2,475	\$ 2,475	Noted on Page 259 of the 10/23/13 Program
05 - UPPER CLUB	05.36.02	WOMEN	Rejected / DO Drawings Govern	Security Locking Hose bibs - add \$53,000	\$ -		Total price for all toilet rooms is \$53,000
05 - UPPER CLUB	05.24.04	WOMEN			\$ -		
05 - UPPER CLUB	05.18.01	WOMEN			\$ -		
05 - UPPER CLUB	05.15.05	WOMEN			\$ -		
05 - UPPER CLUB	05.40.04	WOMEN			\$ -		
05 - UPPER CLUB	05.35.08	WOMEN			\$ -		
05 - UPPER CLUB	05.03.04	WOMEN			\$ -		
05 - UPPER CLUB	05.37.02	WOMEN			\$ -		
05 - UPPER CLUB	05.15.15	WOMEN			\$ -		

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within GMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	
<b>TOTAL ESTIMATE OF ADDED COST FOR DDSI #20</b>					<b>\$ 8,477,363</b>	<b>\$ 2,058,526</b>	<b>COMMENTS ON PROGRAM REQUIREMENTS</b>
1. No suite fronts at Upper Suites. 2. There is no 5' deep speed rail between the 1st and 2nd row of seats. 3. No custom signage or "plaque" for the entrance of the suite.							REVISIONS from 11/6/13 Meeting
<b>Add for Speed Rail between 1st and 2nd Row</b>					<b>\$ 85,305</b>	<b>\$ 85,305</b>	
<b>Add individual suite control interface</b>					<b>\$ 6,600</b>	<b>\$ 6,600</b>	
06 - UPPER SUITES	06.38.12	A-01	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.13	A-02	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.14	A-03	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.15	A-04	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.16	A-05	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.17	A-06	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.18	A-07	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.19	A-08	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.20	A-09	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.21	A-10	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.22	A-11	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.22	A-12	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.21	A-13	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.26	A-14	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.27	A-15	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.28	A-16	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.29	A-17	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	06.38.30	A-18	Rejected / DO Drawings Govern	DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 Program calls for 1-42" TV, 1-60" TV and 1-27" TV at Bowl Tub.	\$ -		Calls for (1) 42", (1) 60", (1) 27" at bowl tub
06 - UPPER SUITES	07.04.5	BAR AREA			\$ -		
06 - UPPER SUITES	06.38.04	BEV. PANTRY			\$ -		
06 - UPPER SUITES	06.23.06	BEV. PANTRY			\$ -		
06 - UPPER SUITES		BOWL - SUITE TUB			\$ -		
06 - UPPER SUITES		BOWL - SUITE TUB			\$ -		
06 - UPPER SUITES	06.35.01	CLUB PURPLE	Rejected / DO Drawings Govern	Club Program Changes - Upgraded exhibition cooking platforms Added circuits for Exhibition Cooking Platform. (10) 20A, (4) 30A and (2) 100A (typical of all platforms) Program notes an added 400A panelboard and 150KVA transformer	\$ 14,243	\$ 14,243	Noted on page 77 of the 10/23/13 Program
06 - UPPER SUITES	05.10.28	CLUB PURPLE DECK ROOF			\$ 30,165		Noted on page 241 of the 10/23/13 Program
06 - UPPER SUITES	03.04.5	CLUB PURPLE TUB		Alternate OS (25 - 22" TV's)	\$ -		This is an ALTERNATE and not included in GMP Scope
06 - UPPER SUITES	06.23.02	COACHES BOOTH	Rejected / DO Drawings Govern	DDSI #17 included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV	No Change		Calls for 27" TV
				Adding an operable sash for half height glass at the Coaches Booths	\$ 35,726	\$ 35,726	Noted on page 335 of the 10/23/13 Program
06 - UPPER SUITES	06.19.02	COACHES BOOTH	Rejected / DO Drawings Govern	DDSI #17 included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV	No Change		Calls for 27" TV
				Adding an operable sash for half height glass at the Coaches Booths	\$ 35,726	\$ 35,726	Noted on page 335 of the 10/23/13 Program
06 - UPPER SUITES	06.38.01	COMMISSARY			\$ -		
06 - UPPER SUITES	06.18.05	CORR			\$ -		
06 - UPPER SUITES	06.05.04	CORRIDOR			\$ -		
06 - UPPER SUITES	06.16.02	CORRIDOR	Rejected / DO Drawings Govern	Minimum Design Standards call for one (1) 42" TV at Elevator Lobby. DDSI #20 Program calls for one (1) 50" TV at Elevator Lobby.	\$ 275		Calls for 50" TV @ Elevator Lobby
06 - UPPER SUITES	06.16.01	CORRIDOR			\$ -		
06 - UPPER SUITES	06.38.07	CORRIDOR			\$ -		
06 - UPPER SUITES	04.15.17	CORRIDOR			\$ -		
06 - UPPER SUITES	06.39.04	ELEC			\$ -		
06 - UPPER SUITES	06.23.05	ELEC			\$ -		
06 - UPPER SUITES	06.15.02	ELEC			\$ -		
06 - UPPER SUITES	06.05.05	ELEC			\$ -		
06 - UPPER SUITES	06.13.05	ELEC			\$ -		
06 - UPPER SUITES	06.34.02	ELEC			\$ -		
06 - UPPER SUITES	03.04.8	ELEV CONTROL RM			\$ -		
06 - UPPER SUITES	06.21.05	FAMILY			\$ -		
06 - UPPER SUITES	06.41.05	FAMILY			\$ -		
06 - UPPER SUITES	06.36.04	FAMILY			\$ -		
06 - UPPER SUITES	06.14.03	FAN ROOM - PRIEST			\$ -		
06 - UPPER SUITES	06.37.06	FAN ROOM - PURPLE CLUB			\$ -		

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within RMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	
TOTAL ESTIMATE OF ADDED COST FOR DDSI #20					\$ 8,477,363	\$ 2,098,526	COMMENTS ON PROGRAM REQUIREMENTS
06 - UPPER SUITES	06.39.05	FINISH KITCHEN			\$ -		REVISIONS from 11/6/13 Meeting
06 - UPPER SUITES	06.24.04	FOOD PANTRY			\$ -		
06 - UPPER SUITES	06.19.04	HOME RADIO	Rejected / DO Drawings Govern	DDSI #17 included two (2) 32" TV's. DDSI #20 Program calls for two (2) 27" TV's	No Change		Home Radio Calls for (2) 27" TV's
06 - UPPER SUITES	06.13.01	IDF			\$ -		TV's follow DDSI - 17
06 - UPPER SUITES	06.34.01	IDF			\$ -		
06 - UPPER SUITES	06.39.06	IDF			\$ -		
06 - UPPER SUITES	06.05.07	IDF			\$ -		
06 - UPPER SUITES	06.15.05	IDF			\$ -		
06 - UPPER SUITES	06.23.07	IDF			\$ -		
06 - UPPER SUITES	06.38.31	IDF			\$ -		
06 - UPPER SUITES	06.37.04	JAN			\$ -		
06 - UPPER SUITES	06.21.04	JAN			\$ -		
06 - UPPER SUITES	06.41.04	JAN			\$ -		
06 - UPPER SUITES	06.26.03	LANDING			\$ -		
06 - UPPER SUITES	06.11.01	LANDING			\$ -		
06 - UPPER SUITES	05.17.2	LANDING			\$ -		
06 - UPPER SUITES	06.14.05	MEDIA EQUIP STORAGE			\$ -		
06 - UPPER SUITES	06.16.03	MEDIA PANTRY			\$ -		
06 - UPPER SUITES	06.14.02	MEDIA RM			\$ -		
06 - UPPER SUITES	06.14.01	MEDIA RM			\$ -		
06 - UPPER SUITES	06.13.02	MEDIA STORAGE			\$ -		
06 - UPPER SUITES	06.14.04	MEDIA WORKRM			\$ -		
06 - UPPER SUITES	06.40.04	NEN	Rejected / DO Drawings Govern	Security Locking Hose bibs - add \$53,000	See Pricing Above		Total price for all toilet rooms is \$53,000
06 - UPPER SUITES	06.21.06	NEN			\$ -		
06 - UPPER SUITES	06.36.02	NEN			\$ -		
06 - UPPER SUITES	06.38.10	NEN			\$ -		
06 - UPPER SUITES	06.38.20	PANTRY			\$ -		
06 - UPPER SUITES	06.08.05	RAAMP-01			\$ -		
06 - UPPER SUITES	06.41.07	SND SYSTEM AMP RM			\$ -		
06 - UPPER SUITES	06.20.04	SND SYSTEM AMP RM			\$ -		
06 - UPPER SUITES	06.04.04	STAIR-01			\$ -		
06 - UPPER SUITES	06.04.05	STAIR-02			\$ -		
06 - UPPER SUITES	06.07.06	STAIR-03			\$ -		
06 - UPPER SUITES	06.13.04	STAIR-04			\$ -		
06 - UPPER SUITES	06.13.03	STAIR-05			\$ -		
06 - UPPER SUITES	06.15.03	STAIR-06			\$ -		
06 - UPPER SUITES	06.22.04	STAIR-07			\$ -		
06 - UPPER SUITES	06.22.05	STAIR-08			\$ -		
06 - UPPER SUITES	06.26.04	STAIR-09			\$ -		
06 - UPPER SUITES	05.17.26	STAIR-10			\$ -		
06 - UPPER SUITES	06.38.05	STAIR-11			\$ -		
06 - UPPER SUITES	06.38.06	STAIR-12			\$ -		
06 - UPPER SUITES	06.16.04	STAIR-16			\$ -		
06 - UPPER SUITES	06.18.01	STATS BOOTH	Rejected / DO Drawings Govern	DDSI #17 included two (2) 32" TV's. DDSI #20 Program calls for two (2) 27" TV's	No Change		Calls for (2) 27" TV's
06 - UPPER SUITES	06.37.03	STOR			\$ -		TV's follow DDSI - 17
06 - UPPER SUITES	06.18.06	SUITE CORRIDOR			\$ -		
06 - UPPER SUITES	06.01.04	SUITE CORRIDOR			\$ -		
06 - UPPER SUITES	06.19.03	TOILET			\$ -		
06 - UPPER SUITES	06.23.04	TOILET			\$ -		
06 - UPPER SUITES	06.05.06	TRASH			\$ -		
06 - UPPER SUITES	06.15.04	TRASH			\$ -		
06 - UPPER SUITES	03.04.4	UPPER SUITE 01	Rejected / DO Drawings Govern	The fit out of this space is now an alternate (AR 13). DDSI #17 called for 1 -32" TV, 2 -42" TV's and 1 -60" TV. DDSI #20 called for 1-35" TV at Suite Tub.			Future 35" TV at Suite Tub
06 - UPPER SUITES	06.38.02	UPPER SUITE 02	Rejected / DO Drawings Govern	The fit out of this space is now an alternate (AR 13). DDSI #17 called for 1 -32" TV, 2 -42" TV's and 1 -60" TV. DDSI #20 called for 1-35" TV at Suite Tub.			Future 35" TV at Suite Tub
06 - UPPER SUITES	06.38.03	UPPER SUITE 03	Rejected / DO Drawings Govern	The fit out of this space is now an alternate (AR 13). DDSI #17 called for 1 -32" TV, 2 -42" TV's and 1 -60" TV. DDSI #20 called for 1-35" TV at Suite Tub.			Future 35" TV at Suite Tub
06 - UPPER SUITES	06.39.01	UPPER SUITE 04	Rejected / DO Drawings Govern	The fit out of this space is now an alternate (AR 13). DDSI #17 called for 1 -32" TV, 2 -42" TV's and 1 -60" TV. DDSI #20 called for 1-35" TV at Suite Tub.			Future 35" TV at Suite Tub
06 - UPPER SUITES	06.39.02	UPPER SUITE 05	Rejected / DO Drawings Govern	The fit out of this space is now an alternate (AR 13). DDSI #17 called for 1 -32" TV, 2 -42" TV's and 1 -60" TV. DDSI #20 called for 1-35" TV at Suite Tub.			Future 35" TV at Suite Tub
06 - UPPER SUITES	06.39.03	UPPER SUITE 06	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06.40.01	UPPER SUITE 07	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06.40.02	UPPER SUITE 08	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06.40.03	UPPER SUITE 09	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06.41.01	UPPER SUITE 10	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06.41.02	UPPER SUITE 11	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06.41.03	UPPER SUITE 12	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06.42.01	UPPER SUITE 13	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub



Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within SAMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	
TOTAL ESTIMATE OF ADDED COST FOR DDSI #20					\$ 8,477,363	\$ 2,048,526	COMMENTS ON PROGRAM REQUIREMENTS
							REVISIONS from 11/6/13 Meeting
06 - UPPER SUITES	06-42-02	UPPER SUITE 14	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-42-03	UPPER SUITE 15	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-01-01	UPPER SUITE 16	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-01-02	UPPER SUITE 17	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-01-03	UPPER SUITE 18	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-02-01	UPPER SUITE 19	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-02-02	UPPER SUITE 20	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-02-03	UPPER SUITE 21	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-03-01	UPPER SUITE 22	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-03-02	UPPER SUITE 23	Rejected / DO Drawings Govern	The fit out of this space is now an alternate (Alt 13). DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 called for 1-35" TV at Suite Tub.			Future 35" TV at Suite Tub
06 - UPPER SUITES	06-03-03	UPPER SUITE 24	Rejected / DO Drawings Govern	The fit out of this space is now an alternate (Alt 13). DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 called for 1-35" TV at Suite Tub.			Future 35" TV at Suite Tub
06 - UPPER SUITES	06-04-01	UPPER SUITE 25	Rejected / DO Drawings Govern	The fit out of this space is now an alternate (Alt 13). DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 called for 1-35" TV at Suite Tub.			Future 35" TV at Suite Tub
06 - UPPER SUITES	06-04-02	UPPER SUITE 26	Rejected / DO Drawings Govern	The fit out of this space is now an alternate (Alt 13). DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 called for 1-35" TV at Suite Tub.			Future 35" TV at Suite Tub
06 - UPPER SUITES	06-04-03	UPPER SUITE 27	Rejected / DO Drawings Govern	The fit out of this space is now an alternate (Alt 13). DDSI #17 called for 1-32" TV, 2-42" TV's and 1-60" TV. DDSI #20 called for 1-35" TV at Suite Tub.			Future 35" TV at Suite Tub
06 - UPPER SUITES	06-20-01	UPPER SUITE 28	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-20-02	UPPER SUITE 29	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-20-03	UPPER SUITE 30	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-21-01	UPPER SUITE 31	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-21-02	UPPER SUITE 32	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-21-03	UPPER SUITE 33	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-22-01	UPPER SUITE 34	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-22-02	UPPER SUITE 35	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-22-03	UPPER SUITE 36	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-23-01	UPPER SUITE 37	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-23-03	UPPER SUITE 38	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-24-01	UPPER SUITE 39	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-24-02	UPPER SUITE 40	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-24-03	UPPER SUITE 41	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-25-01	UPPER SUITE 42	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-25-02	UPPER SUITE 43	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-25-03	UPPER SUITE 44	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-26-01	UPPER SUITE 45	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-26-02	UPPER SUITE 46	Rejected / DO Drawings Govern	Minimum Design Standards calls for two (2) 42" TV and one (1) 60" TV. DDSI #20 Program calls for (1) 35" TV, (1) 42" TV, and (1) 60" TV.			Calls for 35" TV at Suite Tub
06 - UPPER SUITES	06-18-02	VIRINGS MANAGEMENT	Rejected / DO Drawings Govern	Minimum Design Standards calls for 30-42" TV's and 12-50" TV's. DDSI #20 Program calls for 12-50" TV's at Working press and 12-50" TV's at Press Box Lounge (Total of 24).	\$ 54,437		Calls for 30-42" TV's and 12-50" TV's; Press Box Lounge calls for 12-50"
06 - UPPER SUITES	06-18-04	VIRINGS PERSONNEL					
06 - UPPER SUITES	06-18-05	VIRINGS SCOUTING					
06 - UPPER SUITES	06-21-07	WOMEN	Rejected / DO Drawings Govern	Security Locking Hose bibs - add \$53,000	See Pricing Above		Total price for all toilet rooms is \$53,000
06 - UPPER SUITES	06-41-06	WOMEN					
06 - UPPER SUITES	06-05-01	WOMEN					
06 - UPPER SUITES	06-36-03	WOMEN					
06 - UPPER SUITES	06-38-11	WOMEN					
06 - UPPER SUITES	06-15-01	WORKING PRESS	Rejected / DO Drawings Govern	DDSI #17 calls for 30-42" TV's and 16-50" TV's. Price increase to go to 46" TV's, reduce count of 50" TV's to 12, and add 12-50" TV's to the Lounge	\$ 44,541		Calls for 30-46", 12-50"; Press Box Lounge calls for 12-50"
07 - UPPER CONCOURSE					\$ -		

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within S/M	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS
				TOTAL ESTIMATE OF ADDED COST FOR DDSI #20	\$ 8,477,363	\$ 2,098,526	REVISIONS from 11/6/13 Meeting
07 - UPPER CONCOURSE	07.17.02	AUDIO CONTROL		Add operable glazing (24 ft)	\$ 30,193	\$ 30,193	Noted on Page 347 of the 10/23/13 Program; Operable glazing removed per RFC #1 Question #9
07 - UPPER CONCOURSE	07.14.04	AUX/VISITING TV/ SKY CAM CONTROL	Rejected / DO Drawings Govern	DDSI #17 included one (1) 42" TV. DDSI #20 Program calls for one (1) 40" TV	No Change		Called for 40" TV
07 - UPPER CONCOURSE	07.14.04	AUX/VISITING TV/ SKY CAM CONTROL		Added 200A panelboard and 750kVA transformer	\$ 10,293		Noted on Page 337 of the 10/23/13 Program
07 - UPPER CONCOURSE	07.14.04	AUX/VISITING TV/ SKY CAM CONTROL	Rejected / DO Drawings Govern	Add operable glazing (10 ft)	\$ 16,156	\$ 16,156	Noted on Page 337 of the 10/23/13 Program; Operable glazing removed per RFC #1 Question #9
07 - UPPER CONCOURSE	07.02.01	BEV CONCESSION					
07 - UPPER CONCOURSE	07.37.04	BEV PUMP ROOM					
07 - UPPER CONCOURSE	07.13.01	BEV PUMP ROOM					
07 - UPPER CONCOURSE	07.22.02	BEV PUMP ROOM					
07 - UPPER CONCOURSE	07.41.02	BEV PUMP ROOM					
07 - UPPER CONCOURSE	177	BOWL - UPPER CONC GA					
07 - UPPER CONCOURSE	4254	BOWL - UPPER CONC GA					
07 - UPPER CONCOURSE		BOWL - UPPER CONC GA					
07 - UPPER CONCOURSE	07.01.01	CONCOURSE	Rejected / DO Drawings Govern	Minimum Design Standards calls for 50" TV's. DDSI #20 Program calls for 42" TV's.	\$ 16,300		Assume Elevator Lobbies are covered in the 52; Calls for 42" TV's
07 - UPPER CONCOURSE	07.01.02	COOKING CONCESS					
07 - UPPER CONCOURSE	07.12.01	COOKING CONCESS					
07 - UPPER CONCOURSE	07.20.07	COOKING CONCESS					
07 - UPPER CONCOURSE	07.24.01	COOKING CONCESS					
07 - UPPER CONCOURSE	07.36.01	COOKING CONCESS					
07 - UPPER CONCOURSE	07.14.07	CORRIDOR					
07 - UPPER CONCOURSE	07.39.04	ELEC					
07 - UPPER CONCOURSE	07.14.08	ELEC					
07 - UPPER CONCOURSE	07.23.01	ELEC					
07 - UPPER CONCOURSE	07.34.02	ELEC					
07 - UPPER CONCOURSE	07.15.09	ELEC					
07 - UPPER CONCOURSE	07.08.05	ELEC					
07 - UPPER CONCOURSE	07.14.01	EVENT COMMAND POST					
07 - UPPER CONCOURSE	07.06.02	FAM					
07 - UPPER CONCOURSE	07.15.08	FAM					
07 - UPPER CONCOURSE	07.36.02	FAM					
07 - UPPER CONCOURSE	07.26.02	FAM					
07 - UPPER CONCOURSE	07.16.06	FAM					
07 - UPPER CONCOURSE	07.06.01	FAM					
07 - UPPER CONCOURSE	07.20.06	FAM					
07 - UPPER CONCOURSE	07.39.02	FAM					
07 - UPPER CONCOURSE	07.04.04	FAM					
07 - UPPER CONCOURSE		FIRST AID	Rejected / DO Drawings Govern	DDSI #17 included no TV at this location. DDSI #20 Program calls for one (1) 37" TV	\$ 4,096		Called for 37" TV
07 - UPPER CONCOURSE	07.04.02	FIRST AID		Add sound system tied to bowl sound	\$ 8,544	\$ 8,544	Noted on Page 59 of the 10/23/13 Program
07 - UPPER CONCOURSE		FIRST AID	Rejected / DO Drawings Govern	DDSI #17 included one (1) 42" TV. DDSI #20 Program calls for one (1) 37" TV	No Change		Called for 37" TV
07 - UPPER CONCOURSE	07.26.01	FIRST AID		Add sound system tied to bowl sound	\$ 8,544	\$ 8,544	Noted on Page 59 of the 10/23/13 Program
07 - UPPER CONCOURSE	07.37.02	GUEST SERV	Rejected / DO Drawings Govern	DDSI #17 included one (1) 42" TV. DDSI #20 Program calls for one (1) 37" TV	No Change		Called for 37" TV
07 - UPPER CONCOURSE	07.37.02	GUEST SERV		Add sound system tied to bowl sound	\$ 8,544		Noted on Page 61 of the 10/23/13 Program
07 - UPPER CONCOURSE	07.05.02	IDF					
07 - UPPER CONCOURSE	07.07.02	IDF					
07 - UPPER CONCOURSE	07.39.06	IDF					
07 - UPPER CONCOURSE	07.34.03	IDF					
07 - UPPER CONCOURSE	07.15.10	IDF					
07 - UPPER CONCOURSE	07.23.02	IDF					
07 - UPPER CONCOURSE	07.27.04	IDF					
07 - UPPER CONCOURSE	04.13.8	IDF					
07 - UPPER CONCOURSE	07.14.06	INJURY REVIEW BOOTH					
07 - UPPER CONCOURSE	07.15.09	JAN					
07 - UPPER CONCOURSE	07.06.03	JAN					
07 - UPPER CONCOURSE	07.36.03	JAN					
07 - UPPER CONCOURSE	07.16.07	JAN					
07 - UPPER CONCOURSE	07.05.03	JAN					
07 - UPPER CONCOURSE	07.03.02	JAN					
07 - UPPER CONCOURSE	07.19.01	JAN					
07 - UPPER CONCOURSE	07.22.04	JAN					
07 - UPPER CONCOURSE	07.40.01	JAN					
07 - UPPER CONCOURSE	07.16.04	JANITOR					
07 - UPPER CONCOURSE	07.01.03	NIEN					
07 - UPPER CONCOURSE	07.37.03	NIEN					
07 - UPPER CONCOURSE	07.06.04	NIEN					
07 - UPPER CONCOURSE	07.14.09	NIEN					
07 - UPPER CONCOURSE	07.24.02	NIEN					
07 - UPPER CONCOURSE	07.20.03	NIEN					
07 - UPPER CONCOURSE	07.17.03	NIEN					
07 - UPPER CONCOURSE	07.05.01	NON-COOKING CONCESS					
07 - UPPER CONCOURSE	07.37.01	NON-COOKING CONCESS					
07 - UPPER CONCOURSE	07.27.01	NON-COOKING CONCESS					
07 - UPPER CONCOURSE	07.08.01	NON-COOKING CONCESS					
07 - UPPER CONCOURSE	07.20.04	NON-COOKING CONCESS					

Review of DDSI #20 Scope Comparison							
LEVEL	Number	ROOM NAME	Status within GMP	DESCRIPTION OF DISCREPANCY	Added Cost	Accepted Costs	COMMENTS ON PROGRAM REQUIREMENTS
TOTAL ESTIMATE OF ADDED COST FOR DDSI #20					\$ 8,477,363	\$ 2,098,526	REVISIONS from 11/6/13 Meeting
07 - UPPER CONCOURSE	07.25.01	NON-COOKING CONCESS					
07 - UPPER CONCOURSE	07.39.03	NON-COOKING CONCESS					
07 - UPPER CONCOURSE	07.41.01	NON-COOKING CONCESS					
07 - UPPER CONCOURSE	07.15.01	OFFICIAL REPLAY BOOTH	Rejected / DO Drawings Govern	DDSI #17 included one (1) 42" TV. DDSI #20 Program calls for one (1) 32" TV	No Change		Calls for 32" TV
07 - UPPER CONCOURSE	07.17.01	PA ANNOUNCER	Rejected / DO Drawings Govern	DDSI #17 did not include a TV at this location. DDSI #20 Program calls for one (1) 27" TV	\$ 3,968		Calls for 27" TV
07 - UPPER CONCOURSE	07.14.02	RADIO-AUX	Rejected / DO Drawings Govern	DDSI #17 included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV	No Change		Calls for 27" TV
07 - UPPER CONCOURSE	07.14.05	RADIO-HOME SPANISH	Rejected / DO Drawings Govern	DDSI #17 included two (2) 32" TV's. DDSI #20 Program calls for one (1) 27" TV	\$ (3,728)		Calls for (1) 27" TV
07 - UPPER CONCOURSE	07.15.04	RADIO-NATIONAL	Rejected / DO Drawings Govern	DDSI #17 included two (2) 32" TV's. DDSI #20 Program calls for one (1) 27" TV	\$ (3,728)		Calls for (1) 27" TV
07 - UPPER CONCOURSE	07.15.03	RADIO-VISITING	Rejected / DO Drawings Govern	DDSI #17 included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV	No Change		Calls for 27" TV
07 - UPPER CONCOURSE	07.14.03	RADIO-VISITING SPANISH	Rejected / DO Drawings Govern	DDSI #17 included one (1) 32" TV. DDSI #20 Program calls for one (1) 27" TV	No Change		Calls for 27" TV
07 - UPPER CONCOURSE	07.09.01	RAMP-01			\$ -		
07 - UPPER CONCOURSE	07.27.03	SKY CAM CONTROL			\$ -		
07 - UPPER CONCOURSE	07.04.01	STAIR-01			\$ -		
07 - UPPER CONCOURSE	07.04.03	STAIR-02			\$ -		
07 - UPPER CONCOURSE	07.07.01	STAIR-03			\$ -		
07 - UPPER CONCOURSE	07.13.02	STAIR-04			\$ -		
07 - UPPER CONCOURSE	07.13.03	STAIR-05			\$ -		
07 - UPPER CONCOURSE	07.15.07	STAIR-06			\$ -		
07 - UPPER CONCOURSE	07.22.01	STAIR-07			\$ -		
07 - UPPER CONCOURSE	07.22.03	STAIR-08			\$ -		
07 - UPPER CONCOURSE	07.26.03	STAIR-09			\$ -		
07 - UPPER CONCOURSE	05.17.25	STAIR-10			\$ -		
07 - UPPER CONCOURSE	07.38.02	STAIR-11			\$ -		
07 - UPPER CONCOURSE	07.38.03	STAIR-12			\$ -		
07 - UPPER CONCOURSE	07.16.05	STAIR-16			\$ -		
07 - UPPER CONCOURSE	05.17.17	STORAGE			\$ -		
07 - UPPER CONCOURSE	07.23.03	STORAGE	Rejected / DO Drawings Govern	Add card reader at Team Store Storage	\$ 2,571		Noted on Page 261 of the 10/23/13 Program
07 - UPPER CONCOURSE	07.23.03	STORAGE	Rejected / DO Drawings Govern	Note for providing Humidity Control at the Team Store Storage room	\$ 9,350		Noted on Page 261 of the 10/23/13 Program
07 - UPPER CONCOURSE	07.34.01	TEAM STORE		This is ADD ALTERNATE. The GMP Proposal has this as a shelved space.	\$ -		No Team Store Storage on the Upper Concourse
07 - UPPER CONCOURSE	07.16.02	TOILET			\$ -		
07 - UPPER CONCOURSE	07.16.03	TOILET			\$ -		
07 - UPPER CONCOURSE	07.03.01	TRASH			\$ -		
07 - UPPER CONCOURSE	07.39.01	TRASH			\$ -		
07 - UPPER CONCOURSE	07.15.02	TV CAMERA		Follow Spot power and production intercom locations (30A 200W each) at each camera location	\$ 13,753	\$ 13,753	Added (24) 30A receptacles for camera positions
07 - UPPER CONCOURSE	5226	TV CAMERA			\$ -		Noted on Page 261 of the 10/23/13 Program
07 - UPPER CONCOURSE	5227	TV CAMERA			\$ -		
07 - UPPER CONCOURSE	5228	TV CAMERA			\$ -		
07 - UPPER CONCOURSE	05.19.01	TV- CAM			\$ -		
07 - UPPER CONCOURSE	07.20.02	VENDOR DEPOT			\$ -		
07 - UPPER CONCOURSE	07.38.01	VENDOR DEPOT			\$ -		
07 - UPPER CONCOURSE	07.16.01	VIDEO CONTROL	Rejected / DO Drawings Govern	DDSI #17 included two (2) 32" TV's. DDSI #20 Program calls for two (2) 27" TV's	No Change		Calls for (2) 27" TV's
07 - UPPER CONCOURSE	07.16.01	VIDEO CONTROL		Program noted a Panel in Room - UPS Back-Up Added 72KW UPS and 200A output panelboard	\$ 87,903	\$ 87,903	Noted on Page 343 of the 10/23/13 Program
07 - UPPER CONCOURSE	07.16.01	VIDEO CONTROL		Add operable glazing (108 lf)	\$ 116,564	\$ 116,564	Noted on Page 343 of the 10/23/13 Program; Operable glazing removed per RFC #1 Question #9
07 - UPPER CONCOURSE	07.16.08	VIDEO PROD. POD					
07 - UPPER CONCOURSE	07.16.09	VIDEO PROD. POD					
07 - UPPER CONCOURSE	07.15.05	VIDEO RACK ROOM	Rejected / DO Drawings Govern	Separate 24/7 HVAC Zone			Noted on Page 345 of the 10/23/13 Program
07 - UPPER CONCOURSE	07.15.05	VIDEO RACK ROOM		Program document denotes UPS back-up for video equipment	\$ 87,903	\$ 87,903	Noted on Page 345 of the 10/23/13 Program
07 - UPPER CONCOURSE	07.39.05	WOMEN					
07 - UPPER CONCOURSE	07.07.03	WOMEN					
07 - UPPER CONCOURSE	07.15.09	WOMEN					
07 - UPPER CONCOURSE	07.18.01	WOMEN					
07 - UPPER CONCOURSE	07.25.02	WOMEN					
07 - UPPER CONCOURSE	07.05.04	WOMEN					
07 - UPPER CONCOURSE	07.20.05	WOMEN					
07 - UPPER CONCOURSE	07.36.04	WOMEN					
07.8 - PRESS ROOF							
07.8 - PRESS ROOF	5233	TV CAMERA					
08 - MECH MEZZ							
08 - MECH MEZZ	08.38.02	AV					
08 - MECH MEZZ	08.22.02	AV					
08 - MECH MEZZ	08.15.04	CIRCULATION					
08 - MECH MEZZ	08.37.03	CORRIDOR					
08 - MECH MEZZ	08.22.01	CORRIDOR					
08 - MECH MEZZ	08.03.01	CORRIDOR					
08 - MECH MEZZ	08.13.01	CORRIDOR					
08 - MECH MEZZ	08.07.03	CORRIDOR					

[illegible]



**EXHIBIT C-1****EFFECTIVE DATE MINIMUM DESIGN STANDARDS**

In addition to the items listed within Article 5.1 of the Development Agreement, the Effective Date Minimum Design Standards (MDS) shall be comprised of the items listed below. The drawings listed below are attached in order to convey the general design and orientation of the project. As the construction documents are completed and the construction progresses, these drawings may evolve as necessary and as directed by the Stadium Developer. The Stadium Developer may change the drawings as long as the purpose of the room designations and their approximate room areas and adjacencies are maintained.

- a) Floor Plans for the purpose of room designation, room area and adjacencies.
- b) Interior Finish Schedules.
- c) Exterior elevations for the purpose of exterior finishes and design features.
- d) Program Plan Narrative.

a) Floor Plans

<u>Drawing Number</u>	<u>Drawing Name</u>	<u>Date</u>
A2.01	Event Level Plan	Aug. 15, 2013
A2.02	Executive Suite Level Plan	Aug. 15, 2013
A2.03	Lower Club Level Plan	Aug. 15, 2013
A2.04	Main Concourse Level Plan	Aug. 15, 2013
A2.05	Upper Club Level Plan	Aug. 15, 2013
A2.06	Upper Suite Level Plan	Aug. 15, 2013
A2.07	Upper Concourse Level Plan	Aug. 15, 2013

b) Interior Finish Schedules

<u>Drawing Number</u>	<u>Drawing Name</u>	<u>Date</u>
A3.40	Room Finish Schedule 01	Aug. 15, 2013
A3.41	Room Finish Schedule 02	Aug. 15, 2013
A3.42	Room Finish Schedule 03	Aug. 15, 2013

c) Exterior Elevations

<u>Drawing Number</u>	<u>Drawing Name</u>	<u>Date</u>
AX5.01	Overall Exterior Elevations	Aug. 15, 2013
AX 5.02	Overall Exterior Elevations	Aug. 15, 2013
AX 5.03	Overall Exterior Elevations	Aug. 15, 2013
AX 5.04	Overall Exterior Elevations	Aug. 15, 2013



d) Program Plan Narrative

- I. Project Summary
- II. Program Elements
- III. Food Service and Merchandising
- IV. Multipurpose Event Facilities
- V. Team Facilities
- VI. Media Facilities
- VII. Operations Staff Facilities
- VIII. Mechanical and Electrical Systems
- IX. Audio/Visual and Information Technology Systems
- X. Sponsorship Related Building Systems
- XI. Design Add Alternates

**I. Project Summary**

**1. Project Description**

The project ("Project") means (1) the development, design, construction, outfitting and commissioning of a multipurpose stadium suitable for National Football League ("NFL") football and a broad range of other civic, community, athletic, educational, cultural, and commercial activities to be designed, constructed, and financed under the Stadium Legislation (the "Stadium"), (2) the open air plaza and event space adjacent to the Stadium (the "Stadium Plaza") and (3) such other plazas, parking structures, rights of way, connectors, skyways and tunnels, and other such property, facilities, and improvements, owned by or licensed or leased to the Authority or determined by the Authority, as reasonably necessary to facilitate the use and development of the Stadium as contemplated by the Stadium Legislation (the "Stadium Infrastructure").

**2. Location**

- Downtown Minneapolis, including all or portions of the current site of the existing stadium and adjacent areas, bounded generally by 5<sup>th</sup> Avenue South and Eleventh Avenue South and Third Street South and Sixth Street South.

**3. Uses**

- Multi-purpose venue capable of hosting NFL football games and a broad range of other civic, community, athletic, educational, cultural, and commercial activities.
- Primary tenant will be the Minnesota Vikings NFL franchise.
- The multipurpose design should include capability to be utilized for the following events:
  - NFL Super Bowl
  - NCAA Championships
  - Professional and amateur soccer, including Major League Soccer ("MLS")
  - Motorsports events
  - Trade shows, community, or cultural events
  - Amateur and collegiate baseball and football
  - Other national and international events

**4. Project Requirements**

The Stadium must be designed in conformance with all local and State requirements and be sufficient to allow NFL games and associated events to occur. The Project must meet or exceed the following Minimum Design Standards hereby established by the Authority and the Team, which shall include, without limitation, unless otherwise agreed by the Authority and the Team:

- The Stadium shall comprise approximately 1,700,000 square feet with approximately 65,000 seats, expandable to 72,000 seats.
- The Stadium shall have a mix of premium seating product including suites, loge boxes and club seats or other such components as agreed to by the Authority and the Team.
- To the extent practicable, the Authority and the Team will design and build a Stadium that is environmentally and energy efficient and will make an effort to build a Stadium that is eligible to receive the Leadership in Energy and Environmental Design (LEED) certification. The stadium design must to the extent of having a payback of 30 years or less follow sustainable building guidelines established under Minnesota Statute 16B.325.
- A roof that is fixed.
- Operable doors on the West Elevation of the building. 78'8" tall on north end, 54'10" tall at south end, 219'10" wide.
- Space within the main concourse for an NFL team museum and Hall of Fame.
- Patron parking, including 2,000 parking spaces within one block of the Stadium, , and 500 parking spaces within two blocks of the Stadium, some connected by skyway to the Stadium, with a dedicated walkway on game days.
- Elements sufficient to provide for community and civic uses as determined by the Authority
- Exterior shall include simulated Wood Soffit Panels.

## II. Program Elements

### 1. Seating Bowl

- Area includes the primary seating bowl (General Admission, Club Seats and Red Zone Seats) utilized by the viewing patrons during events. The primary competition Event Floor will be designed to provide general seating for approximately 65,000 seats for an NFL Football event. This venue should be designed for viewing NFL Football, NCAA Basketball, Baseball, and Concerts, MLS and International Soccer Events, Conventions and other similar Events.
- Provide field access at each vomitory front of each row including gate and stairs.
- Super Bowl seating expansion – provisions within seating bowl to expand capacity by 7,000 seats.

### 2. General Seating

- General Seating:
  - 33” treads with minimum 19” wide seats
  - Plastic back and plastic seat design
  - Twenty-eight (28) seats/row maximum
  - Laminated glass front row railing
- Red Zone Seating:
  - 36” treads at Red Zone with a minimum 19” wide seats
  - Plastic back and padded seat design
  - 28 seats/row maximum
  - Laminated glass front row railing
- Club Seating:
  - 36” treads at Club Seats with a minimum 21” wide seats
  - Padded back and padded seat design
  - 28 seats/row maximum
  - Laminated glass front row railing
- Area includes retractable seating at the North Side Red Zone and North Lower Club. Retractable seating platforms shall be constructed of a retractable decking system, as mutually agreed upon by the SDC Group, to ensure the quality of the viewing experience for the premium seating patrons as well as operational ease and flexibility.
- All fixed seating to be rail-mounted or riser-mounted self-rising chairs including upper and lower bowl
- Aisle width shall be a minimum dimension as required by code
- Includes end stanchions on aisle seats that are either embossed with Team name/logo or are able to accept removable advertising badge.
- Meet American with Disabilities Act and State of Minnesota guidelines and codes
- Provide chair back drink holders between each seat of the proceeding row with dual advertising panel mounted at wall or handrail at first row of each deck or cross aisle.
- Provide aluminum handrails with anodized finish
- Drains at first row of bowl levels for wash down.

### 3. Accessible Seating

- Accessible seating and companion seating to satisfy current ADA requirements.

### 4. Suites

- Project shall include a variety of premium suite products. Suites designed and to be included are:
  - Private End Zone Field Suites - Event Level – Eight (8) suites total. Ten (10) fixed seats and four (4) bar stool seats at a drink rail.
  - Private Sideline Field Suites – Event Level – Fifteen (15) suites total. Nine (9) typical units at twenty-eight (28) maximum people each; two (2) party suites (4 suite

- units) at fifty (50) maximum people each; and two (2) mid-size suites at forty three (43) maximum people each.
- Chairman Suites – Executive Suite Level – Twelve (12) suites total. Four (4) single suites with bathrooms at fifteen (15) maximum people each; four (4) single suites without bathrooms at fifteen (15) maximum people each; two (2) double suites with bathrooms at thirty-five (35) maximum people each; and Owner's Suite with bathroom (Owner's Suite consists of 2 suites).
  - Main Concourse Suites - Main Concourse – Twenty-seven (27) suites total. Twelve (12) fixed seats and four (4) bar stool seats at a drink rail.
  - Loge Box Seating – Main Concourse – Four (4) loge box seating areas. In each loge box seating area there shall be six (6) units of eight (8) people each; and one (1) unit of twelve (12) people each.
  - Upper Suites – Upper Suite Level – Thirty-six (36) suites total. Twenty-four (24) suite units at twelve (12) people each; and twelve (12) suite units at ten (10) people each. Each suite shall also contain four (4) bar stool seats at a drink rail. Upper Suites will not include operable walls between the suite and the seating bowl.
  - NFL home team owner suite and Team marketing suite (a/k/a visiting team owner suite)
  - NFL home team scouting booth
  - NFL home team personnel booth
  - Typical Suite Description:
    - Combination of fixed stadium seats and barstools.
    - Minimum Seat Width: 22 inches, fully upholstered.
    - Operable glass enclosure on field side to be operated by suite holder. Not included at Upper Suites.
    - Typical suite amenities to include:
      - Video/Television Monitors - All televisions should incorporate integral DTV tuners, multiple HDMI inputs, capable of over-the-air and/or digital cable reception and display as appropriate for the television distribution design. Native display resolution of displays in suites, clubs, and other premium areas should be a minimum of 1080p with the ability to receive 1080i signal. Suites have one (1) 60" and two (2) 42" HDTV's.
      - Audio Control – Ability to select press, PA, radio, TV and auxiliary; (2) ceiling speakers.
      - In house feed to televisions/monitors access. Direct TV and NFL packages, local channels, national Sports and News Channels, additional channels typically found in comparable sports facilities.
      - Three (3) phone/full bandwidth data ports w/ fiber optic backbone.
      - Additional full bandwidth data ports sized for suite.
      - Full size stainless steel refrigerator w/ bottom freezer drawer.
      - Individual thermostats for each suite control to set point  $\pm 3$  degrees Fahrenheit. Does not include Mini-Suites.
      - Outlets below counter space to accommodate four (4) electric chafing dishes; provide grommets in the counter top.
      - All lighting/TV needs to be remotely controlled.
      - One (1) Interactive touch screen computer or iPad.
      - Proximity card access/check point on entry door (proxy card access).
      - Locking hardware on closets and a minimum of 2 cabinet doors.
    - Typical suite finishes to include:
      - Finishes as defined in the attached Room Finish Schedules
      - Millwork w/solid surface tops to include:
        - Locking base cabinets.
        - Built-in trash & recycle containers.
        - Open shelf bottle storage.

- Full height monitor surround.
  - Field Level and Upper Level Suite cabinetry with 3M Dinoc Film
  - Executive and Main Concourse Suite cabinetry with wood veneer
- Two seats to be removable for disabled patrons.
- Operable separation between suite tub seats (seating bowl) and suite interior with operable sections. This feature will not be provided at the upper suites.
- Solid surface countertops.
- Divided stainless steel tub for ice bin and beer tub.
- Single stainless steel sink.
- Stained wood veneer entrance door.
- Millwork and identification signage (plaque) on interior of suite and exterior by door.
- Future Suites (Upper Suite Level):
  - Include provisions to add eighteen (18) suites total. Twelve (12) fixed seats and four (4) bar stool seats at a drink rail per each suite.
  - Include Space for Future Commissary Pantry/Finishing Kitchen at 2,000 sf to service Future Suites.
  - Include structural concrete floor slab with mechanical and electrical systems sized for the future suites.
  - Shell space shall allow for amenities and finishes as determined in the future by the funder of the enhancement. Shell space shall allow for amenities and finishes consistent with existing Upper Suite Level suites.

## 5. Club Lounges

- Project shall include a variety of premium club program areas as has been developed through the design process. Clubs designed and to be included are:
  - Field Level Club – Event Level - Club area for Private Field Suites and Event Level Club Seating to serve approximately 1,460 Patrons (1,380 Club Patrons + 80 Suite Patrons).
  - Executive Suite Club – Executive Suite Level - Club area for Private Chairman's Suite Patrons to serve approximately 240 Patrons.
  - Valhalla Club – Executive Suite Level and South Lower Club Level- Club area for Private Lower Club Patrons to serve approximately 1,200 Patrons.
  - North Lower Club (Viking's Club) – Lower Club Level - Club area for North Lower Club Patrons to serve approximately 2,885 Patrons.
  - North Upper Club (Ice Club) – Upper Club Level - Club area for North Upper Club Patrons to serve approximately 1,425 Patrons.
  - South Upper Club (Fire Club) – Upper Club Level - Club area for South Upper Club Patrons to serve approximately 1,327 Patrons.
  - Club Purple – Upper Suite Level - Club area for Northwest Upper Club Patrons to serve approximately 875 Patrons.
  - Club Purple Roof Deck.
- Typical Club Description:
  - Restrooms to include sound system tied into PA system and stadium broadcast audio.
  - Provide moveable seating components to create flexible, multi-functional space.
  - Premium club space to provide buffet style food service and full service bar. The space should be flexible to accommodate both game and non-game day events.
  - Kitchens and finishing kitchens as located on the attached floor plans.
  - Provide dedicated restrooms for club patrons.
  - Typical club amenities to include:
    - Include a combination of Video Walls, Video/Television Monitors – Provide multiple 50" HDTV equivalent flat screen monitors mounted inside of the club space with 42" HDTV at bar locations that are controlled remotely and centrally within the respective club area.

- All televisions should incorporate integral DTV tuners capable of over-the-air and/or digital cable reception with multiple HDMI inputs and display as appropriate for the television distribution design. Native display resolution of displays in suites, clubs, and other premium areas should be a minimum of 1080p with the ability to receive 1080i signal.
- Audio Control – ability to select press, PA, radio, TV and auxiliary. Centrally controlled. Audio Visual control system centrally located to control, audio, and lighting presets.
- In house feed to televisions/monitors access. Centrally controlled.
- Phone/full bandwidth data ports with fiber optic backbone to telecom closets; 8 per lounge
- Floor outlets
- All lighting/TV needs to be remotely controlled
- Dimmable lighting system for specific areas. Centrally controlled.
- Typical club finishes to include:
  - Mix of banquet seating, mobile lounge seating, high top tables and bar stools
  - Finishes as defined in the attached room finish schedules.
  - Action stations, portable bars provided as part of food service equipment
  - Full service buffet line and full service bars
  - Millwork, solid surface counter tops
  - Way finding and signage

**6. Restaurant**

- Space for a permanent restaurant with interior access during game day and exterior access during non-game day events.
- Shell space with stub up for utilities, water, drains, etc.
- Include access to converge data network backbone for future tenant
- Approximate shell space of 6,500 SF
- Proximity card reader access
- IPTV, audio and video control capabilities
- Electrical panel.

**7. Concourses**

- Concourses to appropriately service patrons with toilets and concessions
- Adequate width and clear passage to allow proper circulation and include areas for promotional activities, gathering, load in/out capabilities, and advertising
- Provide locations that can accommodate portable concessions
- Typical concourse amenities include:
  - Convenience power outlets distributed around concourse
  - Signage and way finding
  - IPTV Monitors equally distributed in all circulation areas
  - Defibrillators evenly distributed and wall mounted near vertical circulation
  - Audio systems as part of the stadium PA systems with multiple sources
  - Power and data for food service carts and ATM
  - Trash and recycling receptacles
  - Utility requirements for portable Food Service stands and ATM's
- The various concourse levels are as follows:
  - Event Level Concourse:
    - Approximate 18'-0" wide "race track" around entire Event Level
    - Drop-off areas for truck loading and unloading at Locker Rooms and Storage areas
    - Approximate 15'-0" vertical clearance
    - Extra clearance height required for portable seats
    - Field tunnel access to ramps require 16' clearance

- Allow for access, egress and space for all equipment and seating
- Corner guards
- Must have height and width clearance for all equipment to be stored (i.e.: turf, portable risers, staging, basketball goals, etc.)
- Executive Suite Level Corridor:
  - Approximate 8'-0" clear width
  - Utility and data requirements for portable Food Service stands and ATM's
  - Mounted 42" HDTV Equivalent size television monitors at each elevator lobby
  - Stained wood wainscot
  - Stained wood base
  - Concierge desk
- Lower Club Level Corridor:
  - Approximate 8'-0" clear width
  - Mounted 42" HDTV Equivalent size television monitors at each elevator lobby
- Red Zone Concourses
  - This area is intended to become an interactive sponsorship area. Any proposed design enhancements would be the responsibility of the Team and/or Sponsor. Responsibility for additional operating costs are defined within the Use Agreement.
  - ATM Locations (1 per Red Zone)
  - 42" HDTV Equivalent size Television Monitors; two (2) per concession stand
- Main Concourse
  - Area includes Main Concourse vestibule Entry Lobbies
  - Could include Minnesota Vikings Hall of Fame displays and Minnesota State High School League
  - ATM Locations (4-6)
  - Design and construction of floor slab and exterior openings to allow for vehicles to be displayed on concourse
  - Drink rail behind last seating row, typical
  - Food Service condiment stands throughout
  - Provisions for emergency phones as required by code
  - Provisions for power source for charging phones
  - 42" HDTV Equivalent size Television Monitors; two (2) per concession stand; also, elevator lobbies and plazas
- Upper Club Level Corridor
  - Minimum 8'-0" clear width
  - Includes Premium Lobbies, concourse and corridors
  - Mounted 42" HDTV Equivalent size television monitors at each elevator lobby
- Upper Suite Level Corridor
  - Minimum 8'-0" clear width
  - Mounted 42" HDTV Equivalent size television monitors at each elevator lobby
- Upper Concourse
  - ATM Locations (4)
  - Design floor slab and openings to allow for vehicles to be displayed on concourse
  - Drink rails at open views to the playing field
  - Provisions for emergency phones as required by code
  - Provisions for power source for charging phones
  - Utility requirements for portable Food Service stands and ATM's
  - Mounted 42" HDTV Equivalent Size Television Monitors: two (2) at each concession stand; also elevator lobbies and plazas

**8. Toilet Facilities**

- Club & General Admission Public Toilets to include:
  - Mirrors with shelves
  - Shelves over urinals
  - Soap dispensers
  - Paper dispensers
  - Baby changing stations
  - Freestanding Trash receptacles
  - Baked enamel wall/floor mounted toilet partitions with spring hinges
  - Wall mounted urinal screens at premium levels only
  - Entrance/Exit metal gates with padlock
  - Hose bibb for cleaning
- Suite Public Toilets to include:
  - Similar features listed above
  - At Executive Suite Level only, individual toilet rooms with lavatory/water closet with full height gypsum board walls and doors
  - Power receptacles
- Typical restroom amenities include:
  - Ceiling mounted speakers tied into event broadcasting stadium PA/radio
  - Provide floor drains as required by code
  - Provide hose bibb for general maintenance with security locking system
  - Motion sensor lighting system
  - Automatic flush (hard wired) toilets, lavatories and urinals
  - Provide tempered water at all lavatories
  - Epoxy resin floors; especially over finished/occupied areas
  - Lavatory faucets with automatic hard wired operation
- Toilets for men (50%) and women (50%) to be provided with proper distribution on every concourse level in compliance with local building codes and state law..
- Toilet ratios are to be provided at a minimum as follows:
  - General Seating Areas:
    - Lavatories: 1 per 150 Females; 1 per 200 Males
    - Water Closets: 1 per 61 Females; 1 per 350 Males
    - Urinals: 1 per 118 Males
    - Tempered Water
  - Club Seating Areas:
    - Lavatories: 1 per 75 Females; 1 per 150 Males
    - Water Closets: 1 per 50 Females; 1 per 185 Males
    - Urinals: 1 per 77 Males
    - Hot and Cold Water Service
  - Suite Levels:
    - Lavatories: 1 per 50 Females; 1 per 100 Males
    - Water Closets: 1 per 35 Females; 1 per 150 Males
    - Urinals: 1 per 51 Males
    - Hot and Cold Water Service
- Janitor's closet to be provided for every set of public toilet rooms (on average)
- Family toilets
  - Designed for public use and distributed throughout the Public and Private Concourses designated for patrons and/or families requiring additional assistance.
  - Family Toilets to include:
    - Mirrors with shelves (mirrors located over sinks with one (1) 2' x 6' full height mirror
    - Soap dispensers
    - Lockable door
    - Paper dispensers



- Baby changing stations
- Free standing trash receptacles
- Lower toilet seat height
- Wall mounted bench
- Power receptacle
- Typical family toilets amenities to include:
  - Sound system tied into PA/radio broadcasting with adjusting speaker
  - Floor drains as required by code
  - Hose bibb for general maintenance with security locking system
  - Motion sensor lighting system
  - Automatic flush (hard wired) toilets and lavatories – hard wired soap dispensers.
  - Tempered water at all lavatories

**9. Ingress/Egress**

- Stadium entries and exits should take advantage of existing points of interest and tie into existing transportation infrastructure
- Entries and exits must accommodate large crowds, ticket taking, power, data and security
- Stadium entries are intended to become sponsored. Any proposed design enhancements would be the responsibility of the Team and/or Sponsor. Responsibility for additional operating costs are defined within the Use Agreement.

**10. Patron Vertical Transportation**

- Elevators:
  - Five (5) Passenger Lifts to access designated ADA seating platforms. Lifts to be sized to accommodate a wheelchair and companion/attendant
  - Two (2) Freight elevators shall be approximately 10,000-12,000 pounds capacity, minimum 10'-0" wide opening. Stainless steel cab walls with 2 x 8 hardwood fastened along the inside perimeter (3 sides only)
  - Two (2) Passenger/Service elevators shall be approximately 5,000 pounds capacity, 350 F.P.M. and 4'-0" door openings
  - Nine (9) Passenger elevators shall be approximately 4,000 pounds capacity, 350 F.P.M., 4'-0" door openings and shall be in pairs if serving the general public if at all possible.
  - One (1) Passenger elevator shall be approximately 4,000 pounds capacity to serve the Press Box from Event to Upper Concourse.
  - One (1) Passenger elevator shall be approximately 4,000 pounds capacity to serve the Vikings Team to the Event Level.
  - Designated Premium elevators for Upper Suite Level patrons on each side of stadium
  - Ability to control elevator access to/from certain levels during game day and non-game day events
  - Access control proximity card swipe control
  - Elevators shall be sized for gurney access
  - 15" elevator display monitor in each passenger and passenger/service elevator cab
  - Elevators to be equipped with cabling to support video and audio feeds from stadium PA and video distribution systems
- Escalators
  - Designed to transport spectators vertically to all levels of the stadium.
  - Designed to allow for adequate escalator turnaround space to avoid crowded cuing scenarios.
  - 40" at general admission minimum
  - 32" at premium minimum
  - 28 separate escalators – 18 general admission, 10 Premium
  - Typical escalator finishes:
    - Premium escalators Lower Club, Main and Upper Club: Glass side balustrade

- Premium escalator Event to Lower Club: Metal side balustrade
- GA escalators: Metal balustrade
- Escalator Landings: Sealed concrete floors
- Handrails: Unfinished black steel with electrochemical conversion coating, clean welds where present.
- Stairs/Ramps
  - Stairs
    - Stair design should be incorporated to promote stair usage and make it a safe and open environment.
    - Twelve (12) sets of general admission stairs approximately 10'-0" stairs
    - Public access at the Main and Upper Concourses
    - Upgraded Premium stairs for internal circulation
    - Press Box stairs for internal circulation
    - Ramps to be designed to accommodate maintenance, and concession vehicles, and forklifts
  - Ramps
    - Floor drains at main ramp
    - 15' – 0" width
    - Sized for forklift access (12'-0" min clearance)
    - Event Level ramps to access end zone suites
    - Event Level trash and recycling ramp to access trash compactors/recycling bins
    - Audio system only required at entrance from exterior

## **11. Ticketing**

- Team Ticketing office shall be located at street level for easy public access. Design and location should be focused on providing ease of access for day to day ticketing from public drive-up traffic.
- Team Ticketing:
  - Exterior Ticket windows should be provided with coverage from the elements
  - Sixteen (16) windows adjacent to Team Store to be provided
  - Configure eight (8) separate from eight (8)
  - Eight (8) will be used for non-day game events
  - Slide trays should be provided at three (3) of the twelve (12) ticket windows
  - One (1) customer service booth at Main Concourse and one (1) customer service booth at Upper Concourse that will allow ticketing.
  - Six (6) 30-minute street parking stalls adjacent to Ticket Office Window area
  - Bullet resistant glass and amplified sound at all each individual outside ticket windows with (removable gooseneck). Talk through shall include hearing impaired headsets.
  - Signage and display per Team requirements
  - Individual LED or LCD Electronic signs above all windows
  - Electronic "Upcoming Events" LED or LCD monitor
  - Local public address system with override microphone over main PA system
  - Doorbell call button with on/ off switch with security camera
  - Multiple high speed data ports at each window
  - Security peep-hole in access door
- Team ticket office vault:
  - Vault room shall be designed and constructed as a secured room with a vault door.
  - Vault should be designed with 24" deep shelving units on three sides and an area for a free standing 4'-0" X 4'-0" safe
  - Alarm system
  - One (1) facsimile machine in vault per NFL/PCI compliance
  - Security camera surveillance
  - Telephone/fax/data ports

- Biometric card reader
- Ticket Manager Office, staff offices, break room and work room
  - Ticket Manager Office and three (3) staff offices.
  - Ticket office amenities include:
    - Shelving, desk and chairs, lockable cabinets
    - Security alarm system
    - CCTV system to monitor vault room and communications closet
    - 42" HDTV
    - Proximity card access at entry points
    - One (1) High-Speed Copier
    - One (1) Color Copier / Printer
    - One (1) Fax machine
    - Built-in case work with sink
    - Storage/work counter
    - Shelving and lockable cabinets
    - Small refrigerator
    - Microwave
- Team ticket office shall include staff toilets with the following amenities:
  - Provide 1 men's and 1 women's toilet for the Team Ticket Office
  - Toilets to include:
    - Mirror with shelves
    - Soap dispenser
    - Paper dispenser
    - Trash receptacle
    - One water closet and one lavatory for men's
    - One water closet and one lavatory for women's
    - Floor drains as required
- Include storage space room within ticket office location. Must be NFL/PCI compliant.
- Include communications closet within ticket office location
  - Security camera surveillance

## **12. Guest Services**

- Information Stations at each public level provided to serve guest needs
- First Aid
  - Located on main concourse and upper concourse with convenient access to elevators and ambulance
- Communications (mobile charging stations)
- ATMs

## **III. Food Service and Merchandising**

### **1. Food/Beverage**

- Concessions – to be primarily designed by HKS with input from the food service operator. Space must be designed to appropriately serve patrons from multiple locations throughout stadium with following minimum ratios:
  - General Seating: 1 POS per 175 spectators lower bowl; 1:200 POS upper bowl
  - Club Seating: 1 POS per 125 spectators
  - Fixed concessions must have sufficient MEP and food service infrastructure to support sales
  - Portable concessions to be placed throughout stadium with electrical and telephone/data services provided
- Restaurant
  - Space for a full service restaurant to be conveniently located to accommodate ticketed, game day patrons

- Restaurant space shall be minimally finished to allow for tenant fit-out by the Team. Base design shall include sealed concrete floor, interior taped drywall, no ceilings, temporary lighting, supply and return air stubbed into space, and an electrical panel.
- Street access through vestibule in Team Store at Main Concourse with dedicated elevator and stair access.
- Space for a dedicated full service kitchen adjacent to the restaurant
- Space for dedicated restrooms for the restaurant
- Bars
  - To be provided in Club Levels and Suite Level
- Club Lounges
  - Club lounges with sufficient food and beverage services to accommodate all club seating patrons
  - Include bars, concessions, pre-game buffet and toilets
  - Club lounges must include facilities for in-seat service wait staff

## **2. Kitchens/Commissaries**

- Central Kitchen/Commissary
  - Located on event level convenient to loading dock and freight elevators
  - Equipped for preparation of food for concessions, clubs, suites, catering, and restaurants
  - Includes concession employee lockers, toilets, laundry, and offices also preferably at event level
  - Storage and staging for dry goods, frozen and refrigerated foods, pallets, alcoholic beverages and carts
  - Converged Data Network shall be sized to support Concessionaires requirements for back of House, Credit Card, amenity programs and POS functions.
- Vendor Commissaries
  - On all general concourse levels
- Pantries
  - On suite levels and each club lounge to provide support for in-suite catering and pre-game buffets in club lounges
  - One large pantry in each club lounge with supporting smaller club pantries
- Empties Storage– recycling and waste facilities
- Cart Storage and Wash Down Arenas

## **3. Merchandising**

- Team Stores
  - Space for one permanent Vikings themed retail store on Main Concourse and a second permanent Vikings themed retail store on Upper Concourse dedicated to the sale of NFL and sponsor merchandise.
  - Main Concourse store shall be accessible on game days and non-game days.
  - Store spaces shall be minimally finished to allow for tenant fit-out by the Team. Base design shall include sealed concrete floor, interior taped drywall, no ceilings, temporary lighting, supply and return air stubbed into space and an electrical panel.
  - Team stores shall be located at Main Concourse at approximately 7,850 SF and in one location at the Upper Concourse at approximately 1,850 SF.
  - Additional design considerations include:
    - Provide Team store storage spaces
    - Provide network backbone
- Merchandise Storage on event level to accommodate Team store and mobile merchandise.

- Data Network to support Concessionaires Network requirements for back of House, Credit Car and amenity programs and POS functions

#### **IV. Multipurpose Event Facilities**

##### **1. Event Floor/Field**

- Designed to accommodate all NFL, NCAA, MLS and Minnesota State High School League facility standards
- Permanently installed solid green single synthetic infill playing surface suitable for NFL events and MSFA events.
- Provide storage space for one removable turf system.
- Temperature controlled – ability to cool playing field to sub-70 degrees at time of kick off for NFL games
- Allow for NCAA Soccer Field configuration Seating Bowl design
- Provide access to Playing Surface by semi-trucks (one location)
- Allow for approximately 10,000 patrons in concert and basketball configuration
- 247'-6" Field Wall to Field Wall dimension at 50 yard line (401'-0" in perpendicular direction)
- Provide inserts in the slab for various nets, goal posts etc... for football and baseball
- Provide football equipment; goal posts, box & chains, end zone pylons, end zone netting and support system
- Provide baseball equipment; foul ball posts, backstop netting and support system, field wall, field wall padding, bases, home plate, dugout equipment, portable pitching mound
- Additional considerations for design of the event floor include:
  - Provide NFL required – technical communication outlets flush mounted in field wall. Conduit from Show Power to sideline
  - Provide camera JBT boxes (12" deep) at field wall
  - Recessed fire hose boxes, hose bibbs and electrical outlets at Field Wall
  - Allow for cabling at Field Wall
  - Provide open ladder cable tray that allows for drainage at Field Wall
  - Show Power at Stage end and Mid-field locations

##### **2. Stage/Rigging**

- Designed to accommodate large touring concert and entertainment acts in end and center stage configurations.

##### **3. Scoreboard**

- The MSFA and Team have established a total budget allowance of twenty-eight million dollars (\$28,000,000) for Vendor Contract Technology, including scoreboard systems. The SDC Group shall manage the design and procurement process for this system until a contract is executed to furnish and install this system in accordance with the SDC Group approved design.

##### **4. Video Control Room**

- The MSFA and Team have established a total budget allowance of twenty-eight million dollars (\$28,000,000) for Vendor Contract Technology, including the Video Control Room. The SDC Group shall manage the design and procurement process for Video Control Room systems until a contract is executed to furnish and install these systems in accordance with the SDC Group approved design.
- The Video Control Room will be located on press level to accommodate Scoreboard and video control equipment with link to the distributed audio system.
- Video Control rooms shall manage the video distribution to all video displays in all accepted formats and resolutions available at the time of procurement..

- This budget also includes in-house production cameras and associated production equipment.
- 5. Public Announcer/Audio Control Booth**
- Primary control location for the Stadium PA system, announcers, spotters and audio presentation equipment.
- 6. Minnesota Vikings Team Family Lounge**
- Locate between route from Parking Area to Home Team Locker Room
  - Locate away from route from Home Team Locker Room to Tunnel/Field
  - 8'-0" counter with base cabinets for storage and food service
  - Baby changing station at both toilets
  - Men's and women's separate toilet facilities with floor mounted water closets and lavatories to have automatic operation
  - Provide two (2) 50" HDTV equivalent
  - Provide full-size refrigerator with bottom freezer
  - Microwave
  - Power and water for beverage station
  - Audio control – ability to select press, PA, radio and TV
  - Two (2) phone data ports
  - Individual thermostat
  - Outlets below kitchen counter to accommodate 4 electric chafing dishes; provide grommets in counter top
  - One (1) interactive touch screen computer or iPad
  - Charging station at kitchen counter
  - Soft Seating
  - Thirty (30) stackable chairs
  - Four (4) round 72" tables
- 7. Minnesota Vikings Staff Family Lounge**
- 8'-0" counter with base cabinets for storage and food service
  - Baby changing station at both toilets
  - Men's and women's separate toilet facilities with floor mounted water closets and lavatories to have automatic operation
  - Provide two (2) 50" HDTV equivalent
  - Provide full-size refrigerator with bottom freezer
  - Microwave
  - Power and water for beverage station
  - Duplex outlets
  - Audio control – ability to select press, PA, radio and TV
  - Two (2) phone data ports
  - Individual thermostat
  - Outlets below kitchen counter to accommodate 4 electric chafing dishes; provide grommets in counter top
  - One (1) interactive touch screen computer or iPad
  - Charging station at kitchen counter
  - Soft Seating
  - Thirty (30) stackable chairs
  - Four (4) round 72" tables
- 8. NFL Family Nursery**
- Locate between Vikings Staff Family Lounge and Vikings Team Family Lounge
  - Locate away from route from Home Team Locker Room to Tunnel/Field
  - 8'-0" counter with sink and base cabinets for storage

- Incorporate baby changing station within counter
- Single sink
- Ice maker
- Provide two (2) television monitors - 50" HDTV equivalent
- Provide refrigerator/freezer
- Soft seating
- Children's furniture tables, chairs, soft seating

**9. Auxiliary Locker Rooms (1)**

- One locker room with minimum 60 permanent lockers each sub-dividable into Two locker rooms of 30 lockers each
- Shower, toilet and drying area (in both)
- Training Room (in both)
- Storage (in both)
- Coaches' lockers, showers and toilet (in both)
- Elements include;
  - Free standing stool with locker storage
  - Counter for food and drink distribution
  - Video/ Television monitors
  - Floor drains and hose Bibs
  - Lockers and toilets should be stacked front to back
  - Game clock
  - One (1) 50" HDTV equivalent size television
  - Dry erase board in each
  - One ice machine per pair
- Include shell space for one additional 60 locker auxiliary locker room similar to above.

**10. Visitors NFL Locker Rooms**

- Comparable to recent NFL stadiums
- Shower, toilet and drying area with discreet access from press areas
  - Fifteen (15) Shower heads
  - Six (6) automatic water closets (floor mounted)
  - Six (6) automatic urinals
  - Six (6) automatic Lavatories with mirrors (1 ADA)
  - Drying Area
  - Full height mirrors
  - Area to be at or below 40% RH (relative humidity)
- Training Room/Exam Room
  - Area should be designed with NFL team to incorporate all training equipment and required floor space layout for training requirements
  - 16'-0" minimum ceiling height
  - Space will include doctor examine room
  - Double door access
  - Digital communication with x-ray room and viewer in exam room
  - Ice machine
  - Game clock
  - One (1) 42" HDTV equivalent size television
  - Minimal overhead cabinet space
  - One (1) 12-pack hydro collator unit
  - Four (4) taping tables
  - Three (3) treatment tables, 80" x 30"
  - 10' linear feet of p-lam counter at 36" x 24" deep
  - 10' linear feet of adjustable shelving to begin 26" above counter, 12" deep
  - Two (2) 4' wide x 70" tall X 24" deep mobile wire shelf unit with clothes rod

- One (1) treatment table in exam room, 80" x 30"
- Four linear feet of p-lam counter at 36" high in exam room
- Supply storage room and Equipment storage room
  - Provide overhead door direct access to Event Level
  - Design convenient loading and unloading area
  - 12'-0" counter top
  - Ten (10) 18" wide x 24" deep x 7'-0" metal lockers
  - Ten (10) stackable chairs
  - Work center
- Office for Head Coach with dressing room
  - Dry erase board
  - Provide sound insulation in walls and ceiling
  - One (1) desk and chair
  - Shower and drying area at 8'-0" AFF
  - One (1) automatic hard wired water closet floor mounted
  - One (1) automatic hard wired lavatory with mirror
  - Two (2) lockers (24" x 24" x 8'-0" high)
  - One (1) 42" HDTV equivalent size television
  - Game clock
- Assistant Coaches Locker Rooms
  - Twenty-five (25) lockable metal lockers (24" x 24" x 7'-0" high)
  - Twenty-five (25) Plastic stackable chairs
  - Separate shower and drying area
  - Six (6) showers
  - Two (2) water closet – floor mounted with automatic operation
  - Four (4) lavatory with automatic operation with mirrors
  - Three (3) urinals with automatic operation
  - Drying Area
  - Game clock
  - One (1) 42" HDTV equivalent size television

**11. X-Ray Room**

- First Aid/X-ray Room near team facility with compliance to NFL, NCAA, and MLS regulations

**12. Officials Locker Rooms**

- Officials Meeting Room
- Game Crew locker room to have 10 lockers with shower and restroom facilities
- Dressing area to have ten (10) (5 per side) 24" x 24" x 7'-0" metal lockers
- Open lockers with stool
- 6' counter with base cabinets, plastic laminate
- Women: 1 shower and 1 water closet
- Men: 2 showers, 1 water closet and 1 urinal
- 1 exercise bike
- Ball warming area
- Sound system tied into Event broadcasting
- Game Clock
- Multimedia (VCR/ CD/ DVD) over 42" HDTV
- Plastic stacking chairs
- Refrigerator

**13. Chain Crew Locker Rooms**

- Ten (10) 36" wide x 24" deep x 7'-0" high metal lockers with folding chairs



- One (1) shower / side
- One (1) water closet / side with automatic operation
- Two (2) lavatories / side with automatic operation
- One (1) urinal / side with automatic operation
- Sound system tied into Event broadcasting
- Game Clock
- PA System
- Multimedia (VCR/ CD/ DVD)
- 42" HDTV

**14. Cheerleaders Locker Room**

The Cheerleaders Locker Room area shall be provided as Core/Shell space under the base contract

**15. Field Toilets with direct access to both bench areas**

**16. VIP/Team Parking**

- One Hundred Seventy-Three (173) exterior parking stalls with secured entry access to the Lower Club Level
- 8'-5" min stall width
- Used as non-game day parking for Vikings Team and MSFA
- Security barrier from general public
- Adequate Security Lighting and CCTV
- Access control gates

**17. Coaches Booths (located at Upper Suite Level)**

- Spaces for home and visiting team coaches, 10 seats each, shall contain built-in writing desks and telephone connections to player benches and operable sash
- 42" HDTV Equivalent TV Set with duplex outlet per booth
- Coaching Intercom/ Communications Systems – at box location 2 – 110V circuits
- Four (4) 20A, 120V circuits in room – alongside of room
- Outlet for instant replay TV
- Pre-wired for coaching intercom and video
- Stackable plastic chairs

**18. Coaches Video Platforms**

- Camera Platforms shall be located at the following locations at the Upper Seating Bowl and Upper Suite Level:
  - Team 50 yard line, home team position. Four camera positions. One platform shall be located at the Upper Suite Level 50 yard line. Two camera platforms shall be located at the Upper Suite Level – one at each end zone. Platform sizes shall be 8' x 32' at all 3 locations. The Vikings and NFL will be consulted regarding all aspects including booth, platforms, conduit, and electrical requirements
- One (1) 20A, 120V circuit, each location
- 110V outlet for each camera at each location
- Cable connections to coaches booths and both sidelines

**19. Video Replay Booth**

- Feeds to/from field, coaching video systems and network TV trucks
- Six (6) 20A, 120V circuits
- Four (4) 20, 120V at Field
- Separate HVAC system controls
- Investigate potential pre-action sprinkler systems or specialty dry chemical systems

- 42" HDTV

**V. Team Facilities**

**1. Home NFL Locker Room**

- Vikings locker room shall be comparable to recent NFL stadiums to include 60 permanent lockers and 30 temporary lockers. Lockers shall be (3'-6" wide x 3'-0" deep x 8'-0" high) lockable (4 digit code) wood lockers
- Vikings locker room complex, including locker rooms, training room, offices, exam room, Owner's room, meeting rooms, lounges and nursery to be temperature controlled, temperature range 65-70 degrees area to be at or below 40% RH (relative humidity)
- Vikings locker room shall include;
  - Three (3'-0" x 5'-0") portable dry erase boards
  - Counter for food and drink distribution (kiosk) – Portable or Permanent in Meeting Room
  - Double door access
  - Two (2) reach-in (GDM) style coolers, lockable
  - Provide roof over Vikings area to provide a level of security and protection from above water elements within the seating bowl
  - Four (4) 50" HDTV mounted televisions
  - Four (4) refrigerators
  - Equipped for projectors
  - Separate audio controls from the rest of the Vikings spaces
  - Game clock
  - Separate digital thermostat. The Authority will explore opportunities to provide the Team with monitoring and control capabilities for the environmental controls in the Team spaces through the building management system.
  - 100 FT candle lighting with dimming system
  - JBT Box
  - USB port in each locker
  - In house feed to Televisions/monitors
  - 80 folding Vikings themed vinyl chairs
  - 4 refrigerators
- Shower, toilet and drying area with discreet access from press areas, to include;
  - Variable pressure shower heads mounted at 8'-0" AFF with controls at 4'-6"
  - Water closet rim mounted at 1'-7" AFF Floor Mounted
  - One (1) ADA Lavatory counter mounted at 2'-10" AFF (Standard height 36")
  - Non slip tile flooring
  - Privacy curtain to locker room
  - Porcelain tile counter above lavatory counter
  - Stainless steel towel shelves and storage
  - Twenty-four (24) Shower heads (open shower)
  - Eight (8) Hard wired automatic water closets (floor mounted)
  - Eight (8) Hard wired automatic urinals
  - Eight (8) Hard wired automatic lavatories with mirrors
  - Drying Area to accommodate fifteen (15) players at one time
  - Hair dryers
  - Full height mirrors
  - Trench drains at shower/floor drains throughout
- Training Room, to include;
  - Area should be designed with NFL team to incorporate training equipment outlined below and required floor space layout for training requirements.
  - Privacy curtain 17' long
  - Outlets as required for training equipment layout
  - Ventilation for "gymnasium" type design requirements
  - Crushed ice machine

- Television monitors – two (2) 50” HDTV equivalent, on swivel mounts
- Temperature control – separate system from locker rooms
- Telephone/data port
- Game Clock
- Four (4) adjustable exam stools, on wheels
- Five (5) taping tables
- Five (5) 80” x 30” treatment (exam) tables
- Four (4) treatment carts
- Ten (10) electrical outlets (quad and heights TBD)
- One (1) additional light fixture in taping area
- Two (2) electrical outlets, quad, height TBD; one (1) non-GFI
- One (1) electrical outlet at standard height in locker area
- Two (2) data outlets to fiber optic backbone
- Ice Machine with storage bin in hydro room
- Chiropractor table
- Two (2) chairs to match chairs in main training area
- One (1) adjustable office chair
- Sports Flooring
- Head Athletic Trainer/Team Physician Room (42” HDTV)
- Trainers’ Changing Room
- Hydrotherapy Room, to include;
  - Windows above 4’-0” for sightline from main training room
  - Double-wide glass doors
  - Ice machine
  - Adequate power
  - Provide continuous perimeter drain ahead of hydrotherapy tubs
  - One (1) hydro collator unit
  - Plumbing to handle 100 gpm dump from tub
  - Mixing valves for extremity tubs to code
  - GFI receptacles per code placed at 48” off floor
  - Area to be at or below 40% RH (relative humidity)
  - Telephone/data port
  - Hose bibb near room
- Exam Room
- Supply Storage and Equipment Storage
  - Includes Team home video storage room
    - Requires double door access
    - Wall racks/ shelving
    - Built-in storage units
    - Plastic laminate millwork
  - Office for Equipment Manager
  - Provide overhead door direct access to Event Level circulation/corridor
  - Design convenient loading and unloading area
  - Work center
  - Dutch door toward Minnesota Vikings Locker Room at door pair
  - Built in shelves
  - Twenty-five (25) 24” x 24” x 7’-0” lockers with privacy separation wall
  - 6’ - 4” Long counter top only
  - 5’-0” counter height overhead door above a pass-thru counter with access door adjacent
  - Equipment room to include full height overhead door
  - Telephone / Data port
  - In house feed to Television/monitors
  - One (1) 50” HDTV Equivalent wall or ceiling hung television
  - Twenty-five (25) Plastic stackable chairs
  - Twenty-five (25) 24” x 24” x 7’-0” lockers

- Upper and lower lockable storage lockers with p-lam countertop
- Stretching Room, to include;
  - One (1) 50" HDTV Equivalent wall or ceiling hung television
  - Sports flooring.
  - Audio Control – ability to select press, PA, radio, TV and auxiliary; (2) ceiling speakers
- Team Owner's room, to include;
  - Designed to comfortable accommodate 8-10 people
  - Conference room table with 8 (eight) chairs
  - Soft seating area
  - Separate restroom area with toilet and lavatory with mirror in each
  - Kitchenette with lower cabinets, stone countertop and built-in sink
  - Telephone/data port
  - One (1) 50" HDTV
  - Audio Control – ability to select press, PA, radio, TV and auxiliary; (2) ceiling speakers
  - In house feed to televisions/monitors access
  - One (1) phone/data port w/fiber optic backbone
  - Full size stainless steel refrigerator
  - Individual thermostat
  - Charging station at kitchen counter
  - Trash and recycling receptacles
- Vikings General Manager Office, to include;
  - Dry erase board
  - Small table with six chairs
  - Sound insulation in walls and ceiling
  - One (1) work station
  - One (1) 50" HDTV equivalent size Television monitor
  - Game clock
  - Telephone/data port
  - In house feed to televisions/monitors
  - Under-counter refrigerator
  - 36" x 36" metal locker
- Coaches Locker Rooms with work and lounge areas, to include;
  - Thirty-five (35) lockable wood lockers – 24" x 24" x 8'-0" high
  - Separate shower and drying area
  - Eight (8) showers at 8'-0" AFF
  - Four (4) hardwired auto valves water closets – floor mounted rim mounted 1'-7"
  - Four (4) hardwired auto valves lavatories with mirrors
  - Four (4) hardwired auto valves urinals
  - Full height fridge
  - Storage Areas
  - Engineered stone counter at lavatories and kitchenette
  - Work area
  - Soft seating area
  - Minimum one (1) 50" video, wall or ceiling hung television monitors
  - Equipped for projectors
  - Game clock
  - Telephone/data port
  - In house feed to televisions/monitors
  - Area to be at or below 40% RH (relative humidity)
  - Proximity card access
  - Thirty-five (35) Vikings themed folding vinyl chairs
  - Conference room table with 8 (eight) chairs
- Team meetings rooms, to include;
  - Two (2) meeting room areas with space for 30 people

- Space planned for preseason temporary locker room facilities for Vikings team
- Area to view chalk talks
- Dry erase boards/marker boards
- 10'-0" wide clear area in front of seating
- 12'-0" minimum ceiling height
- Operable manual acoustical partition between rooms for ability to create 1 room, include man door for 2nd exit
- Sound attenuation insulation in walls
- Two (2) Game Clocks (one per team room)
- Area to be at or below 40% RH (relative humidity)
- Equipped for projectors
- Telephone / Data port
- TV sized appropriate for rooms (50" HDTV in each)
- Themed folding chairs vinyl chairs
- One (1) dry erase board (minimum 4' x 10') in each
- Staff Locker Room, to include;
  - Twenty-two (22) each 30" wide x 24" deep x 7'-0" tall lockable metal lockers
  - One (1) Toilet room with water closet and lavatory
  - One (1) 50" HDTV Equivalent mounted monitor
  - Telephone/data port
- Locker Room/Office for Head Coach, to include;
  - Dry erase board
  - Table with six chairs
  - Sound insulation in walls and ceiling
  - Built in storage for multi-media
  - One (1) work station
  - Separate shower and drying area
  - One (1) automatic hard wired water closet Floor Mounted
  - One (1) hard wired lavatory with mirror
  - Under counter refrigerator
  - Two (2) wood lockers - 30" wide x 24" deep x 7'-0" high
  - Storage Areas
  - One (1) 42" HDTV equivalent size Television monitor
  - Equipped for projectors
  - Game clock
  - Telephone / Data port
  - In house feed to Televisions/monitors
  - Area to be at or below 40% RH (relative humidity)
  - Proximity card access

## **VI. Media Facilities**

### **1. Press Box**

- Located on the upper suite level
- Stations for approximately 200 (additional loose seating should be able to be added to achieve 300) writers shall be provided. This area shall contain built-in writing counter, seating, electrical, and telephone outlets, sound system and closed circuit television
- Coat hooks with shelving
- Space for 200 cubbies
- NFL game clock and Stadium clock operator
- Coach to quarterback official NFL observer
- Aisle width to allow bar stool additional seating behind each desktop position
- Storage room for Vikings PR items (150 SF)
- HDTV; 30 @ 46" display and 12 @ 50" display

- Open fronts
  - Each station to include one electric and two telephone/data outlets
- 2. Broadcast Booths**
- One (1) TV Broadcast Booth located at midfield per broadcast requirements
  - TV Broadcast Booth at midfield to include;
    - 24' wide required by networks
    - Lighting grid, sound attenuation, internal circuit breaker panel, data, front opening to have camera catch and overhead grid. Flat, not tiered floor
    - Dedicated toilet room
    - "Captains" chair height furniture
    - TV monitors by broadcast networks
  - One (1) auxiliary visiting TV/skycam Broadcast Booth located in press box.
  - Six (6) Radio Broadcast Booths per broadcast requirements
- 3. Broadcast Truck Facilities**
- Minimum Four (4) 56 foot broadcast TV tractor/trailer truck positions with four (4) expandable to 16 foot trailer width with eight (8) foot working area on all sides.
  - Parking for a minimum of three (3) TV satellite trucks with clear sightlines to southern sky with minimum dimensions
  - Parking for up to six (6) local TV microwave trucks (exterior)
  - Parking for TV crew
  - Power and Broadcast Infrastructure per NFL and HD Specifications
- 4. TV Host Locations**
- Provide at least one JBT box on the main concourse as currently configured for use as a Television Host broadcast location.
- 5. Camera Positions**
- In compliance with NFL, NCAA, and MLS network broadcast requirements and supporting Vikings game production locations.
  - Television camera platforms shall be located at the following locations at the mid deck/club level: Home team 50 yard line, home team both, 25 yard lines, visiting team 50 yard line, each corner (slash position). Four camera positions shall be located at field level; two in each end zone aligned with between each hash mark and numbers and clear of net. One camera platform shall be located at the Upper Suite Level 50 yard line. Two camera platforms shall be located at the Upper Suite Level – one at each end zone. Platform sizes vary for dedicated/combined use by network, TV, club, visiting club
  - Space for two (2) cameras minimum each location except 50 yard line (assume 8' x 8' each camera - 6' for team cameras)
- 6. Interview Rooms**
- Interview space for post-game shall be provided convenient to both home and visitor's locker rooms. This room shall be accessible by television cable tray. Electrical requirements shall be provided. Television networks shall be consulted
  - Flat floor space
  - Raised podium 8' x 12' x 18"H for speaker - carpeted
  - Raised camera riser in rear 6'D x 20'W x 18"H - carpeted
  - Podium and camera riser may be portable
  - Seating capacity for 100 (with stackable chairs) in home team interview room and 50 (with stackable chairs) in visiting team interview room
  - Rear wall acoustical panels and side wall rear 1/3 acoustical panels.
  - Stackable and folding chairs

**7. Press Support**

- Media Work Room
- Press Dining Room and Lounge for minimum 150 people
- Media Function Room
- Photographers Work Room
- TV Cable Connection Room
- Broadcast Crew Room
- Equipment Storage
- Restrooms
- Converge Data Network to support Broadcast and Press Network requirements for back of House, production and distribution requirements

**VII. Authority and Operations Staff Facilities**

**1. Offices**

- Year round administrative offices for the Authority
- Offices and cubicles for Stadium operations staff
- Include conference room, break room, work room, storage and kitchen

**2. Employee Locker rooms for men and women to accommodate staff**

**3. Gathering Rooms**

- Employee Break Room
- Ticket Taker and Usher Briefing Room
- Event Security Briefing Room

**4. Storage**

- Employee Uniform Storage and Laundry Facilities
- Field Equipment Storage
- Stage Storage and Support
- General Storage

**5. Security and Loading Dock Command Center**

- 42" IPTV monitor
- One central game day office
- Restrooms
- Two (2) holding cells
- Roll-call room
- BMS Control Rooms
- Command Center to control access to loading dock and service tunnel
  - Stadium and Field Lighting Controls
  - Communications Systems
  - Fire Command Center
  - Public Address Systems
  - Monitors for Surveillance Camera Systems
  - Record, replay and distribute Camera Surveillance Systems

**6. Janitorial/Maintenance Facilities**

- Private offices, open office area, storage and break rooms on event level for Back of House, Cleaning and Janitorial
- Maintenance shops for Machinery, Carpentry, Paint, Electrical and Plumbing
- Central Supply Room
- Janitors Closets on all levels near toilet facilities

**7. Trash Collection/Recycling**

- Main handling facility located near loading dock to accommodate separate treatment of trash and recyclable materials, including compactor(s)
- Trash container and recycling container storage/staging on each level

**8. Freight Elevators**

- Minimum two freight elevators on each side of stadium with stops at levels as indicated within the design documents and accommodate 12,000 pounds minimum 10 feet wide by 20 feet deep.

**9. Event Command Post**

- Stadium Operations Booth – including video, data, PA, BMS controls. Security Observation Booth – including video data, remote operation of security cameras and monitoring of building systems.

**10. Loading Dock**

- Convenient access to field level and service areas with easy street access
- Minimum of 6 truck bays with dock levelers and appropriate ventilation
- Additional two truck docks for central commissary
- Dedicated truck dock adjacent to NFL home team locker room

**11. Concessionaires Offices**

- Includes finished space for concessionaires offices and cash handling operations.

**VIII. Mechanical and Electrical Systems**

The Project shall include mechanical and electrical systems and fixtures to support the design standards set forth in this **Exhibit C-1** and shall be designed in conformance with all local and state requirements and shall be sufficient to allow NFL games and associated events to occur, including the following:

- 1. District Steam and Chilled Water**
- 2. HVAC Distribution System**
- 3. Plumbing System**
- 4. Fire Protection**
- 5. Electrical Power distribution**
- 6. Emergency Power System**
- 7. Lighting, including Field Lighting**
- 8. Fire Alarm and Detection Systems**

**IX. Audio/Visual and Information Technology Systems**

The Project shall incorporate audio and high definition video systems, including, without limitation, the following:

**1. Distributed Audio System**

- The seating bowl loudspeaker system is based on a distributed line array configuration. The lower and mid-level bowl seating is covered by eight line arrays (Type 1) arranged in a 300 foot diameter circle centered over the playing field. Sub-woofers located with each line array provide additional low frequency sound reinforcement. Additional loudspeaker arrays and fill speakers cover the upper seating sections. Loudspeaker system to deliver minimum performance criteria as measured from the spectator seats: Frequency response to be +/-3db from 55Hz to 10,500Hz, 106dBA sustained loudness, +/-3dB uniformity of coverage, and intelligibility factor > 0.52 STI-PA.



- Power Amplifiers are located in dedicated equipment rooms. Amplifiers and associated processors are connected back to a centralized monitoring system in the audio control room.
  - The audio control room on the upper concourse southeast corner will be the primary location for the mixing console along with program sources and patch panels. In addition, the digital signal processing system and amplifier control computers will be located in this room. Analog tie lines from the floor, video replay system, main broadcast interconnect, and other areas will terminate in the audio control room. Connector panels on the field level and camera platforms provide analog and digital audio connections to the system.
  - A dedicated digital audio network is provided to connect the audio control room feeds with the digital mixing console and the network connected amplifier and DSP equipment. The network cabling is routed with other building structured cabling systems. The audio equipment is also connected to the building Ethernet network to allow control and monitoring from network drop locations.
  - Portable digital audio console can be located at the main concourse or event level and connected using the digital audio network from the audio control room down to the dedicated connection boxes (JBA's) Digital stage boxes with connectors allow the console to be easily moved and setup between positions. Snake cables will allow portable source and outboard processing equipment racks to be easily interconnected with the console. JBA boxes will have rack space for in house video replay broadcast cabling and intercom panels.
  - As an aid to the fire alarm system, the main seating bowl will receive warning signals and announcements from the main fire command center. Tie lines to interface these systems will be the responsibility of this contractor, but the components to implement the connections shall be the obligation of the fire alarm installer. During an emergency with the fire alarm, all systems other than those that cover the main seating bowl shall mute.
  - A hearing assistance system will be provided for the seating bowl. System transmitting frequencies to be coordinated and not interfere with clubs, interview rooms, video replay and writing press RF systems.
  - Entry gates and queuing areas within concourses will have speakers with programming selected in the audio control system. Pendant mounted speakers in areas where there are no ceilings or high ceilings. Provide recessed speakers in areas with finished ceilings. The network connected amplifiers and processors for these systems are located in TR rooms in each quad on Event, Main and Upper Concourse levels.
  - Restrooms on each public level will have speakers with programming selected in the audio control system. Speaker enclosure types are to be coordinated with ceiling conditions. Provide surface or pendant mounted speakers in restrooms with no ceiling and recessed speaker assemblies in areas with a finished ceiling.
  - Ticket offices will be equipped with a paging system with exterior speakers over ticket windows and ceiling speakers in the inside lobby. This system will deliver informational announcements and messages to patrons waiting in line from a local CD player. The ticket office will receive a remote feed from the audio control room consisting of preprogrammed announcements or other building wide audio signals.
  - The Pedestrian Plaza on the west side of the grounds will be supported with an outdoor rated loudspeaker system to deliver messaging and entertainment to pedestrian patrons.
- 2. Communications Systems/Information Management**
- The MSFA and Team have established a total budget allowance of twenty-eight million dollars (\$28,000,000) for Vendor Contract Technology, including certain Communications Systems and Information Management systems. The SDC Group shall manage the design and procurement process for these designated systems until a contract is executed to furnish and install the applicable systems in accordance with the SDC Group approved design.
- 3. Security and Surveillance**
- The physical security systems shall consist of the following:
    - Electronic Access Control including Visitor Management and Badging station to include:

- New and complete enterprise-wide, low-voltage, electronic access control system (EACS).
- Access control hardware devices, mounting brackets, power supplies, switches, controls, consoles and other components of the system as required.
- Access control related software to allow this system expansion. Software includes required license addition for access control readers and electrified portals, workstations and Video Management System (VMS) Integration.
- Intrusion Detection System (IDS) to include:
  - Materials, hardware, software and cabling required to provide a fully functional system.
  - Low voltage signal, control, and power cables to and from power supplies, remote panels, expansion panels, and other devices as required for a complete turnkey system.
- Video Surveillance System to include:
  - IP cameras and a server based NVR with client stations and storage.
  - Programming and configuration of system components as well as all associated software upgrades and patches.
- IP Video Management System
- Command and Control Centers including video walls and security consoles.
- Uninterruptable Power Supplies (UPS) and in panel battery backup

**X. Sponsorship Related Building Systems**

The Team will identify during construction certain areas throughout the building in which it intends to create Sponsorship opportunities using branding and theming elements. Any proposed design enhancements and the costs for such design enhancements would be the responsibility of the Team and/or Sponsor. Responsibility for additional operating costs are defined within the Use Agreement.

**XI. Design Add Alternates**

The items identified below are not currently included within the Minimum Design Standards. Consistent with Section 8.1(e) of the Development Agreement, if either Party elects to add any of the Design Add Alternates set forth on **Exhibits I-1 or I-2** to the Project, subject to the requesting Party's obligation to fund the completion of the work, the selected Design Add Alternate shall be included in the Minimum Design Standards.

**EXHIBIT C-2****FINAL MINIMUM DESIGN STANDARDS**

In addition to the items listed within Article 5.1 of the Development Agreement, the Final Minimum Design Standards (MDS) shall be comprised of the items listed below. The drawings listed below are attached in order to convey the general design and orientation of the project. As the construction documents are completed and the construction progresses, these drawings may evolve as necessary and as directed by the Stadium Developer. The Stadium Developer may change the drawings as long as the purpose of the room designations and their approximate room areas and adjacencies are maintained.

- a) Floor Plans for the purpose of room designation, room area and adjacencies.
- b) Interior Finish Schedules.
- c) Exterior elevations for the purpose of exterior finishes and design features.
- d) Program Plan Narrative.

a) Floor Plans

<u>Drawing Number</u>	<u>Drawing Name</u>	<u>Date</u>
A2.01	Event Level Plan	Aug. 15, 2013
A2.02	Executive Suite Level Plan	Aug. 15, 2013
A2.03	Lower Club Level Plan	Aug. 15, 2013
A2.04	Main Concourse Level Plan	Aug. 15, 2013
A2.05	Upper Club Level Plan	Aug. 15, 2013
A2.06	Upper Suite Level Plan	Aug. 15, 2013
A2.07	Upper Concourse Level Plan	Aug. 15, 2013

b) Interior Finish Schedules

<u>Drawing Number</u>	<u>Drawing Name</u>	<u>Date</u>
A3.40	Room Finish Schedule 01	Aug. 15, 2013
A3.41	Room Finish Schedule 02	Aug. 15, 2013
A3.42	Room Finish Schedule 03	Aug. 15, 2013

c) Exterior Elevations

<u>Drawing Number</u>	<u>Drawing Name</u>	<u>Date</u>
AX5.01	Overall Exterior Elevations	Aug. 15, 2013
AX 5.02	Overall Exterior Elevations	Aug. 15, 2013
AX 5.03	Overall Exterior Elevations	Aug. 15, 2013
AX 5.04	Overall Exterior Elevations	Aug. 15, 2013

d) Value Analysis Log Dated October 25, 2013

e) Program Plan Narrative

- I. Project Summary
- II. Program Elements
- III. Food Service and Merchandising
- IV. Multipurpose Event Facilities
- V. Team Facilities
- VI. Media Facilities
- VII. Operations Staff Facilities
- VIII. Mechanical and Electrical Systems
- IX. Audio/Visual and Information Technology Systems
- X. Sponsorship Related Building Systems
- XI. Design Add Alternates

**I. Project Summary**

**1. Project Description**

The project (“Project”) means (1) the development, design, construction, outfitting and commissioning of a multipurpose stadium suitable for National Football League (“NFL”) football and a broad range of other civic, community, athletic, educational, cultural, and commercial activities to be designed, constructed, and financed under the Stadium Legislation (the “Stadium”), (2) the open air plaza and event space adjacent to the Stadium (the “Stadium Plaza”) and (3) such other plazas, parking structures, rights of way, connectors, skyways and tunnels, and other such property, facilities, and improvements, owned by or licensed or leased to the Authority or determined by the Authority, as reasonably necessary to facilitate the use and development of the Stadium as contemplated by the Stadium Legislation (the “Stadium Infrastructure”).

**2. Location**

- Downtown Minneapolis, including all or portions of the current site of the existing stadium and adjacent areas, bounded generally by 5<sup>th</sup> Avenue South and Eleventh Avenue South and Third Street South and Sixth Street South.

**3. Uses**

- Multi-purpose venue capable of hosting NFL football games and a broad range of other civic, community, athletic, educational, cultural, and commercial activities.
- Primary tenant will be the Minnesota Vikings NFL franchise.
- The multipurpose design should include capability to be utilized for the following events:
  - NFL Super Bowl
  - NCAA Championships
  - Professional and amateur soccer, including Major League Soccer (“MLS”)
  - Motorsports events
  - Trade shows, community, or cultural events
  - Amateur and collegiate baseball and football
  - Other national and international events

**4. Project Requirements**

The Stadium must be designed in conformance with all local and State requirements and be sufficient to allow NFL games and associated events to occur. The Project must meet or exceed the following Minimum Design Standards hereby established by the Authority and the Team, which shall include, without limitation, unless otherwise agreed by the Authority and the Team:

- The Stadium shall comprise approximately 1,700,000 square feet with approximately 65,000 seats, expandable to 72,000 seats.
- The Stadium shall have a mix of premium seating product including suites, loge boxes and club seats or other such components as agreed to by the Authority and the Team.
- To the extent practicable, the Authority and the Team will design and build a Stadium that is environmentally and energy efficient and will make an effort to build a Stadium that is eligible to receive the Leadership in Energy and Environmental Design (LEED) certification. The stadium design must to the extent of having a payback of 30 years or less follow sustainable building guidelines established under Minnesota Statute 16B.325.
- A roof that is fixed.
- Operable doors on the West Elevation of the building.
- Space within the main concourse for an NFL team museum and Hall of Fame.
- Patron parking, including 2,000 parking spaces within one block of the Stadium, , and 500 parking spaces within two blocks of the Stadium, some connected by skyway to the Stadium, with a dedicated walkway on game days.
- Elements sufficient to provide for community and civic uses as determined by the Authority

- Exterior shall include 12” wide flush panel with custom paint finish and a powder coat finish at soffits.
- Quantity and types of televisions are per DDSI-017 – Television Monitor Schedule dated October 1, 2013. Authority and Team will work together to determine the final location of the televisions within the final Construction Documents.

## **II. Program Elements**

### **1. Seating Bowl**

- Area includes the primary seating bowl (General Admission, Club Seats and Red Zone Seats) utilized by the viewing patrons during events. The primary competition Event Floor will be designed to provide general seating for approximately 65,000 seats for an NFL Football event. This venue should be designed for viewing NFL Football, NCAA Basketball, Baseball, and Concerts, MLS and International Soccer Events, Conventions and other similar Events.
- Provide field access where possible at each vomitory front of each row including gate and stairs.
- Super Bowl seating expansion – provisions within seating bowl to expand capacity by 7,000 seats.

### **2. General Seating**

- General Seating:
  - 33” treads with minimum 19” wide seats
  - Plastic back and plastic seat design
  - Laminated glass front row railing except at Lower Bowl where the front row railings will be cable rail.
- Red Zone Seating:
  - 36” treads at Red Zone with a minimum 19” wide seats
  - Plastic back and padded seat design
  - Laminated glass front row railing except at Lower Bowl where the front row railings will be cable rail.
- Club Seating:
  - 36” treads at Club Seats with a minimum 21” wide seats
  - Padded back and padded seat design
  - Laminated glass front row railing except at Lower Bowl where the front row railings will be cable rail.
- Area includes retractable seating at the North Side Red Zone and North Lower Club. Retractable seating platforms shall be constructed of a retractable decking system, as mutually agreed upon by the SDC Group, to ensure the quality of the viewing experience for the premium seating patrons as well as operational ease and flexibility.
- All fixed seating to be rail-mounted or riser-mounted self-rising chairs including upper and lower bowl
- Aisle width shall be a minimum dimension as required by code or as approved by variance.
- Includes end stanchions on aisle seats that are either embossed with Team name/logo or are able to accept removable advertising badge.
- Meet American with Disabilities Act and State of Minnesota guidelines and codes
- Provide chair back drink holders between each seat of the proceeding row with dual advertising panel mounted at wall or handrail at first row of each deck or cross aisle.
- Provide aluminum handrails with anodized finish
- Drains at first row of bowl levels for wash down.

### **3. Accessible Seating**

- Accessible seating and companion seating to satisfy current ADA requirements.

**4. Suites**

- Project shall include a variety of premium suite products. Suites designed and to be included are:
  - Private End Zone Field Suites - Event Level – Eight (8) suites total. Ten (10) fixed seats and four (4) bar stool seats at a drink rail.
  - Private Sideline Field Suites – Event Level – Fifteen (15) suites total. Nine (9) typical units at twenty-eight (28) maximum people each; two (2) party suites (4 suite units) at forty-nine (49) maximum people each; and two (2) mid-size suites at forty three (43) maximum people each.
  - Chairman Suites – Executive Suite Level – Twelve (12) suites total. Four (4) single suites with bathrooms at fifteen (15) maximum people each; four (4) single suites without bathrooms at fifteen (15) maximum people each; two (2) double suites with bathrooms at thirty-five (35) maximum people each; and Owner's Suite with bathroom (Owner's Suite consists of 2 suites).
  - Main Concourse Suites - Main Concourse – Twenty-seven (27) suites total. Twelve (12) fixed seats and four (4) bar stool seats at a drink rail.
  - Loge Box Seating – Main Concourse – Four (4) loge box seating areas. In each loge box seating area there shall be six (6) units of eight (8) people each; and one (1) unit of twelve (12) people each.
  - Upper Suites – Upper Suite Level – Thirty-six (36) suites total. Twenty-four (24) suite units at twelve (12) people each; and twelve (12) suite units at ten (10) people each. Each suite shall also contain four (4) bar stool seats at a drink rail. Upper Suites will not include operable walls between the suite and the seating bowl.
  - NFL home team owner suite and Team marketing suite (a/k/a visiting team owner suite) are included within the above Suite counts.
  - NFL home team scouting booth
  - NFL home team personnel booth
- Typical Suite Description:
  - Combination of fixed stadium seats and barstools.
  - Minimum Seat Width: 22 inches, fully upholstered.
  - Operable glass enclosure on field side to be operated by suite holder. Not included at Upper Suites. Half height operable glass at Executive and Main Level Suites. Sectional overhead glass doors at Event Level Suites.
  - Typical suite amenities to include;
    - Video/Television Monitors - All televisions should incorporate integral DTV tuners, multiple HDMI inputs, capable of centralized over-the-air and/or digital cable reception and display as appropriate for the television distribution design. Native display resolution of displays in suites, clubs, and other premium areas should be a minimum of 1080p with the ability to receive 1080i signal.
    - Audio Control – Ability to select press, PA, radio, TV and auxiliary; (2) ceiling speakers.
    - In house feed to televisions/monitors access. Direct TV and NFL packages, local channels, national Sports and News Channels, additional channels typically found in comparable sports facilities.
    - Three (3) phone/full bandwidth data ports w/ fiber optic backbone.
    - Additional full bandwidth data ports sized for suite.
    - Full size stainless steel refrigerator w/ bottom freezer drawer.
    - Individual thermostats for each suite control to set point  $\pm 3$  degrees Fahrenheit. Does not include Mini-Suites.
    - Outlets below counter space to accommodate four (4) electric chafing dishes; provide grommets in the counter top.
    - All lighting/TV needs to be remotely controlled.
    - One (1) Interactive touch screen computer or iPad.

- Rough-in and wiring for proximity card access/check point on entry door (proxy card access).
- Locking hardware on closets and a minimum of 2 cabinet doors.
- Typical suite finishes to include:
  - Finishes as defined in the Room Finish Schedules
  - Millwork w/solid surface tops to include:
    - Locking base cabinets.
    - Built-in trash & recycle containers.
    - Open shelf bottle storage.
    - Eight foot high monitor surround.
    - Field Level and Upper Level Suite cabinetry with 3M Dinoc Film
    - Executive and Main Concourse Suite cabinetry with wood veneer
  - Two seats to be removable for disabled patrons.
  - Operable separation between suite tub seats (seating bowl) and suite interior with operable sections. This feature will not be provided at the upper suites. Half height operable glass at Executive and Main Level Suites. Sectional overhead glass doors at Event Level Suites.
  - Solid surface countertops.
  - Stainless steel tub for ice bin.
  - Single stainless steel sink.
  - Stained wood veneer entrance door.
  - Identification signage (plaque) on exterior of suite by door.
- Future Suites (Upper Suite Level):
  - Include provisions to add eighteen (18) suites total. Twelve (12) fixed seats and four (4) bar stool seats at a drink rail per each suite.
  - Include Space for Future Commissary Pantry at 750 sf to service Future Suites.
  - Include structural concrete floor slab with mechanical and electrical systems sized for the future suites.
  - Shell space shall allow for amenities and finishes as determined in the future by the funder of the enhancement. Shell space shall allow for amenities and finishes consistent with existing Upper Suite Level suites.

## **5. Club Lounges**

- Project shall include a variety of premium club program areas as has been developed through the design process. Clubs designed and to be included are:
  - Field Level Club – Event Level - Club area for Private Field Suites and Event Level Club Seating to serve approximately 1,460 Patrons (1,380 Club Patrons + 80 Suite Patrons).
  - Executive Suite Club (Included as an Add Alternate) – Executive Suite Level – Future Club area for Private Chairman’s Suite Patrons to serve approximately 240 Patrons.
  - Valhalla Club – Executive Suite Level and South Lower Club Level- Club area for Private Lower Club Patrons to serve approximately 1,200 Patrons.
  - North Lower Club (Viking’s Club) – Lower Club Level - Club area for North Lower Club Patrons to serve approximately 2,885 Patrons.
  - North Upper Club (Ice Club) – Upper Club Level - Club area for North Upper Club Patrons to serve approximately 1,425 Patrons.
  - South Upper Club (Fire Club) – Upper Club Level - Club area for South Upper Club Patrons to serve approximately 1,327 Patrons.
  - Club Purple – Upper Suite Level - Club area for Northwest Upper Club Patrons to serve approximately 875 Patrons.
- Typical Club Description:
  - Restrooms to include sound system tied into PA system and stadium broadcast audio.
  - Provide moveable seating components to create flexible, multi-functional space.



- Premium club space to provide buffet style food service and full service bar. The space should be flexible to accommodate both game and non-game day events.
- Kitchens and finishing kitchens as located on the attached floor plans.
- Provide dedicated restrooms for club patrons.
- Typical club amenities to include:
  - Include a combination of Television Walls, Video/Television Monitors in accordance with DDSI-017.
  - All televisions should incorporate integral DTV tuners capable of centralized over-the-air and/or digital cable reception with multiple HDMI inputs and display as appropriate for the television distribution design. Native display resolution of displays in suites, clubs, and other premium areas should be a minimum of 1080p with the ability to receive 1080i signal.
  - Audio Control – ability to select press, PA, radio, TV and auxiliary. Centrally controlled. Audio Visual control system centrally located to control, audio, and lighting presets.
  - In house feed to televisions/monitors access. Centrally controlled.
  - Phone/full bandwidth data ports with fiber optic backbone to telecom closets; 8 per lounge
  - Floor outlets
  - All lighting/TV needs to be remotely controlled
  - Dimmable lighting system for specific areas. Centrally controlled.
- Typical club finishes to include:
  - Mix of banquet seating, mobile lounge seating, high top tables and bar stools
  - Finishes as defined in the room finish schedules.
  - Action stations, portable bars provided as part of food service equipment
  - Full service buffet line and full service bars
  - Millwork, solid surface counter tops
  - Way finding and signage

**6. Restaurant – Shell Space – No Finishes**

- Space for a permanent restaurant with interior access during game day and exterior access during non-game day events.
- Shell space with stub up for utilities, water, drains, etc.
- Include access to converge data network backbone for future tenant
- Approximate shell space of 6,500 SF
- Proximity card reader access
- Electrical panel.

**7. Concourses**

- Concourses to appropriately service patrons with toilets and concessions
- Adequate width and clear passage to allow proper circulation and include areas for promotional activities, gathering, load in/out capabilities, and advertising
- Provide locations that can accommodate portable concessions
- Typical concourse amenities include:
  - Convenience power outlets distributed around concourse
  - Signage and way finding
  - IPTV Monitors equally distributed in all circulation areas
  - Defibrillators evenly distributed and wall mounted near vertical circulation
  - Audio systems as part of the stadium PA systems with multiple sources
  - Power and data for food service carts and ATM
  - Trash and recycling receptacles
  - Utility requirements for portable Food Service stands and ATM's
- The various concourse levels are as follows:
  - Event Level Concourse:

- Approximate 18'-0" wide "race track" around entire Event Level
- Drop-off areas for truck loading and unloading at Locker Rooms and Storage areas
- Approximate 15'-0" vertical clearance
- Field tunnel access to ramps require 16' clearance
- Allow for access, egress and space for all equipment and seating
- Corner guards
- Must have height and width clearance for all equipment to be stored (i.e.: turf, portable risers, staging, basketball goals, etc.)
- Executive Suite Level Corridor:
  - Approximate 8'-0" clear width
  - Utility and data requirements for portable Food Service stands and ATM's
  - Stained wood wainscot
  - Stained wood base
- Lower Club Level Corridor:
  - Approximate 8'-0" clear width
- Red Zone Concourses
  - This area is intended to become an interactive sponsorship area. Any proposed design enhancements would be the responsibility of the Team and/or Sponsor. Responsibility for additional operating costs are defined within the Use Agreement.
  - ATM Locations (1 per Red Zone)
- Main Concourse
  - Area includes Main Concourse vestibule Entry Lobbies
  - Could include Minnesota Vikings Hall of Fame displays and Minnesota State High School League
  - ATM Locations (4-6)
  - Design and construction of floor slab and exterior openings to allow for vehicles to be displayed on concourse
  - Drink rail behind last seating row, typical
  - Food Service condiment stands throughout
  - Provisions for emergency phones as required by code
  - Provisions for power source for charging phones
- Upper Club Level Corridor
  - Minimum 8'-0" clear width
  - Includes Premium Lobbies, concourse and corridors
  -
- Upper Suite Level Corridor
  - Minimum 8'-0" clear width
- Upper Concourse
  - ATM Locations (4)
  - Design floor slab and openings to allow for vehicles to be displayed on concourse
  - Drink rails at open views to the playing field
  - Provisions for emergency phones as required by code
  - Provisions for power source for charging phones
  - Utility requirements for portable Food Service stands and ATM's

**8. Toilet Facilities**

- Club & General Admission Public Toilets to include:
  - Mirrors with shelves
  - Shelves over urinals
  - Soap dispensers

- Paper dispensers
- Baby changing stations
- Freestanding Trash receptacles
- Baked enamel wall/floor mounted toilet partitions
- Wall mounted urinal screens at premium levels only
- Entrance/Exit metal gates with padlock
- Hose bibb for cleaning
- Suite Public Toilets to include:
  - Similar features listed above
  - At Executive Suite Level only, individual toilet rooms with lavatory/water closet with full height gypsum board walls and doors
  - Power receptacles
- Typical restroom amenities include:
  - Ceiling mounted speakers tied into event broadcasting stadium PA/radio
  - Provide floor drains as required by code
  - Provide loose key type hose bibb for general maintenance
  - Motion sensor lighting system
  - Automatic flush (hard wired) toilets, lavatories and urinals
  - Provide tempered water at all lavatories
  - Epoxy resin floors; especially over finished/occupied areas
  - Lavatory faucets with automatic hard wired operation
- Toilets for men (50%) and women (50%) to be provided with proper distribution on every concourse level in compliance with local building codes and state law..
- Toilet ratios are to be provided at a minimum as follows:
  - General Seating Areas:
    - Lavatories: 1 per 150 Females; 1 per 200 Males
    - Water Closets: 1 per 61 Females; 1 per 350 Males
    - Urinals: 1 per 118 Males
    - Tempered Water
  - Club Seating Areas:
    - Lavatories: 1 per 75 Females; 1 per 150 Males
    - Water Closets: 1 per 50 Females; 1 per 185 Males
    - Urinals: 1 per 77 Males
    - Hot and Cold Water Service
  - Suite Levels:
    - Lavatories: 1 per 50 Females; 1 per 100 Males
    - Water Closets: 1 per 35 Females; 1 per 150 Males
    - Urinals: 1 per 51 Males
    - Hot and Cold Water Service
- Janitor's closet to be provided for every set of public toilet rooms (on average)
- Family toilets
  - Designed for public use and distributed throughout the Public and Private Concourses designated for patrons and/or families requiring additional assistance.
  - Family Toilets to include:
    - Mirrors with shelves (mirrors located over sinks)
    - Soap dispensers
    - Lockable door
    - Paper dispensers
    - Baby changing stations
    - Free standing trash receptacles
    - Lower toilet seat height
    - Wall mounted bench
    - Power receptacle
  - Typical family toilets amenities to include:

- Sound system tied into PA/radio broadcasting with adjusting speaker
- Floor drains as required by code
- Motion sensor lighting system
- Automatic flush (hard wired) toilets and lavatories – hard wired soap dispensers.
- Tempered water at all lavatories

**9. Ingress/Egress**

- Stadium entries and exits should take advantage of existing points of interest and tie into existing transportation infrastructure
- Entries and exits must accommodate large crowds, ticket taking, power, data and security
- Stadium entries are intended to become sponsored. Any proposed design enhancements would be the responsibility of the Team and/or Sponsor. Responsibility for additional operating costs are defined within the Use Agreement.

**10. Patron Vertical Transportation**

- Elevators:
  - Five (5) Platform Lifts to access designated ADA seating platforms. Lifts to be sized to accommodate a wheelchair and companion/attendant
  - Two (2) Freight elevators shall be approximately 10,000-12,000 pounds capacity, minimum 10'-0" wide opening. Stainless steel cab walls with 2 x 8 hardwood fastened along the inside perimeter (3 sides only)
  - Two (2) Passenger/Service elevators shall be approximately 5,000 pounds capacity, 350 F.P.M. and 4'-0" door openings
  - Nine (9) Passenger elevators shall be approximately 4,000 pounds capacity, 350 F.P.M., 4'-0" door openings and shall be in pairs if serving the general public if at all possible.
  - One (1) Passenger elevator shall be approximately 4,000 pounds capacity to serve the Press Box from Event to Upper Concourse.
  - One (1) Passenger elevator shall be approximately 4,000 pounds capacity to serve the Vikings Team to the Event Level.
  - Designated Premium elevators for Upper Suite Level patrons on each side of stadium
  - Ability to control elevator access to/from certain levels during game day and non-game day events
  - Access control proximity card swipe control
  - Elevators shall be sized for gurney access
  - 15" elevator display monitor in each passenger and passenger/service elevator cab
  - Elevators to be equipped with cabling to support video and audio feeds from stadium PA and video distribution systems
- Escalators
  - Designed to transport spectators vertically to all levels of the stadium.
  - Designed to allow for adequate escalator turnaround space to avoid crowded cuing scenarios.
  - 40" at general admission minimum
  - 32" at premium minimum
  - 27 separate escalators – 18 general admission, 9 Premium
  - Typical escalator finishes:
    - Premium escalators Lower Club, Main and Upper Club: Glass side balustrade
    - Premium escalator Event to Lower Club: Metal side balustrade
    - GA escalators: Metal balustrade
    - Escalator Landings: Sealed concrete floors
    - Handrails: Unfinished black steel with electrochemical conversion coating, clean welds where present.
- Stairs/Ramps
  - Stairs

- Stair design should be incorporated to promote stair usage and make it a safe and open environment.
- Twelve (12) sets of general admission stairs approximately 10'-0" stairs
- Public access at the Main and Upper Concourses
- Upgraded Premium stairs for internal circulation
- Press Box stairs for internal circulation
- Ramps to be designed to accommodate maintenance, and concession vehicles, and forklifts
- Ramps
  - Floor drains at main ramp
  - 15' – 0" width
  - Sized for forklift access (12'-0" min clearance)
  - Event Level ramps to access end zone suites
  - Event Level trash and recycling ramp to access trash compactors/recycling bins
  - Audio system only required at entrance from exterior

#### **11. Ticketing**

- Team Ticketing office shall be located at street level for easy public access. Design and location should be focused on providing ease of access for day to day ticketing from public drive-up traffic.
- Team Ticketing:
  - Exterior Ticket windows should be provided with coverage from the elements
  - Sixteen (16) windows adjacent to Team Store to be provided
  - Configure eight (8) separate from eight (8)
  - Eight (8) will be used for non-day game events
  - Slide trays should be provided at three (3) of the twelve (12) ticket windows
  - One (1) customer service booth at Main Concourse and one (1) customer service booth at Upper Concourse that will allow ticketing.
  - Street parking stalls along Chicago Avenue.
  - Bullet resistant glass and amplified sound at all each individual outside ticket windows with (removable gooseneck).
  - Signage and display per Team requirements
  - Individual LED or LCD Electronic signs above all windows
  - Electronic "Upcoming Events" LED or LCD monitor
  - Local public address system with override microphone over main PA system
  - Doorbell call button with on/ off switch with security camera
  - Multiple high speed data ports at each window
  - Security peep-hole in access door
- Team ticket office vault:
  - Vault room shall be designed and constructed as a secured room with a vault door.
  - Vault should be designed with 24" deep shelving units on three sides and an area for a free standing 4'-0" X 4'-0" safe
  - Alarm system
  - One (1) facsimile machine in vault per NFL/PCI compliance
  - Security camera surveillance
  - Telephone/fax/data ports
  - Biometric card reader
- Ticket Manager Office, staff offices, break room and work room
  - Ticket Manager Office and three (3) staff offices.
  - Ticket office amenities include:
    - Shelving, desk and chairs, lockable cabinets
    - Security alarm system
    - CCTV system to monitor vault room and communications closet
    - Proximity card access at entry points

- One (1) High-Speed Copier
- One (1) Color Copier / Printer
- One (1) Fax machine
- Built-in case work with sink
- Storage/work counter
- Shelving and lockable cabinets
- Small refrigerator
- Microwave
- Team ticket office shall include staff toilets with the following amenities:
  - Provide 1 men's and 1 women's toilet for the Team Ticket Office
  - Toilets to include:
    - Mirror with shelves
    - Soap dispenser
    - Paper dispenser
    - Trash receptacle
    - One water closet and one lavatory for men's
    - One water closet and one lavatory for women's
    - Floor drains as required
- Include storage space room within ticket office location. Must be NFL/PCI compliant.
- Include communications closet within ticket office location
  - Security camera surveillance

#### **12. Guest Services**

- Information Stations at each public level provided to serve guest needs
- First Aid
  - Located on main concourse and upper concourse with convenient access to elevators and ambulance
- Communications
- Provisions for ATMs

### **III. Food Service and Merchandising**

#### **1. Food/Beverage**

- Concessions – to be primarily designed by HKS with input from the food service operator. Space must be designed to appropriately serve patrons from multiple locations throughout stadium with following minimum ratios:
  - General Seating: 1 POS per 175 spectators lower bowl; 1:200 POS upper bowl
  - Club Seating: 1 POS per 125 spectators
  - Fixed concessions must have sufficient MEP and food service infrastructure to support sales
  - Portable concessions to be placed throughout stadium with electrical and telephone/data services provided
- Restaurant – Shell Space, No Finishes
  - Space for a full service restaurant to be conveniently located to accommodate ticketed, game day patrons
  - Restaurant space shall be minimally finished to allow for tenant fit-out by the Team. Base design shall include sealed concrete floor, interior taped drywall, no ceilings, temporary lighting, supply and return air stubbed into space, and an electrical panel.
  - Street access through vestibule in Team Store at Main Concourse with dedicated elevator and stair access.
  - Space for a dedicated full service kitchen adjacent to the restaurant
  - Space for dedicated restrooms for the restaurant
- Bars

- To be provided in Club Levels and Suite Level
- Club Lounges
  - Club lounges with sufficient food and beverage services to accommodate all club seating patrons
  - Include bars, concessions, pre-game buffet and toilets
  - Club lounges must include facilities for in-seat service wait staff

**2. Kitchens/Commissaries**

- Central Kitchen/Commissary
  - Located on event level convenient to loading dock and freight elevators
  - Equipped for preparation of food for concessions, clubs, suites, catering, and restaurants
  - Includes concession employee lockers, toilets, laundry, and offices also preferably at event level
  - Storage and staging for dry goods, frozen and refrigerated foods, pallets, alcoholic beverages and carts
  - Converged Data Network shall be sized to support Concessionaires requirements for back of House, Credit Card, amenity programs and POS functions.
- Vendor Commissaries
  - On all general concourse levels
- Pantries
  - On suite levels and each club lounge to provide support for in-suite catering and pre-game buffets in club lounges
  - One large pantry in each club lounge with supporting smaller club pantries
- Empties Storage– recycling and waste facilities
- Cart Storage and Wash Down Arenas

**3. Merchandising**

- Team Stores – Shell Space, No Finishes
  - Space for one permanent Vikings themed retail store on Main Concourse and a second permanent Vikings themed retail store on Upper Concourse dedicated to the sale of NFL and sponsor merchandise.
  - Main Concourse store shall be accessible on game days and non-game days.
  - Store spaces shall be minimally finished to allow for tenant fit-out by the Team. Base design shall include sealed concrete floor, interior taped drywall, no ceilings, temporary lighting, supply and return air stubbed into space and an electrical panel.
  - Team stores shall be located at Main Concourse and at the Upper Concourse as shown on the floor plans.
  - Additional design considerations include:
    - Provide Team store storage spaces
    - Provide network backbone
- Merchandise Storage on event level to accommodate Team store and mobile merchandise.
- Data Network to support Concessionaires Sub-Network requirements for back of House, Credit Card and amenity programs and POS functions

**IV. Multipurpose Event Facilities**

**1. Event Floor/Field**

- Designed to accommodate all NFL, NCAA, MLS and Minnesota State High School League facility standards
- Permanently installed solid green single synthetic infill playing surface suitable for NFL events and MSFA events.

- Provide storage space but not storage racks for one removable turf system.
  - Temperature controlled – ability to cool playing field to sub-70 degrees at time of kick off for NFL games
  - Allow for NCAA Soccer Field configuration Seating Bowl design
  - Provide access to Playing Surface by semi-trucks (one location)
  - Allow for approximately 10,000 patrons in concert and basketball configuration
  - 247'-6" Field Wall to Field Wall dimension at 50 yard line (401'-0" in perpendicular direction)
  - Provide inserts in the slab for various nets, goal posts etc... for football and baseball
  - Provide football equipment; goal posts, box & chains, end zone pylons, end zone netting and support system
  - Provide baseball equipment; foul ball posts, backstop netting and support system, field wall, field wall padding, bases, home plate, dugout equipment, portable pitching mound
  - Additional considerations for design of the event floor include:
    - Provide NFL required – technical communication outlets flush mounted in field wall with a communications conduit to the football bench area
    - Provide camera JBT boxes (12" deep) at field wall
    - Fire hose connections at quadrant tunnels, hose bibbs and electrical outlets at Field Wall
    - Allow for cabling at Field Wall
    - Provide open ladder cable tray that allows for drainage at Field Wall
- 2. Stage/Rigging**
- Designed to accommodate large touring concert and entertainment acts in end and center stage configurations.
- 3. Scoreboard**
- The MSFA and Team have established a total budget allowance of twenty-eight million dollars (\$28,000,000) for Vendor Contract Technology, including scoreboard systems. The SDC Group shall manage the design and procurement process for this system until a contract is executed to furnish and install this system in accordance with the SDC Group approved design. The west endzone foundations will be designed and constructed to support an add alternate to potentially accommodate a larger scoreboard.
- 4. Video Control Room**
- The MSFA and Team have established a total budget allowance of twenty-eight million dollars (\$28,000,000) for Vendor Contract Technology, including the Video Control Room. The SDC Group shall manage the design and procurement process for Video Control Room systems until a contract is executed to furnish and install these systems in accordance with the SDC Group approved design.
  - The Video Control Room will be located on press level to accommodate Scoreboard and video control equipment with link to the distributed audio system.
  - Video Control rooms shall manage the video distribution to all video displays in formats and resolutions available at the time of procurement.
  - This budget also includes in-house production cameras and associated production equipment.
- 5. Public Announcer/Audio Control Booth**
- Primary control location for the Stadium PA system, announcers, spotters and audio presentation equipment.
- 6. Minnesota Vikings Team Family Lounge**
- Locate between route from Parking Area to Home Team Locker Room
  - Locate away from route from Home Team Locker Room to Tunnel/Field



- 8'-0" counter with base cabinets for storage and food service
- Baby changing station at both toilets
- Men's and women's separate toilet facilities with floor mounted water closets and lavatories to have automatic operation
- Provide full-size refrigerator with bottom freezer
- Microwave
- Power and water for beverage station
- Audio control – ability to select press, PA, radio and TV
- Two (2) phone data ports
- Individual thermostat
- Outlets below kitchen counter to accommodate 4 electric chafing dishes; provide grommets in counter top
- One (1) interactive touch screen computer or iPad
- Charging station at kitchen counter
- Soft Seating
- Thirty (30) stackable chairs
- Four (4) round 72" tables

**7. Minnesota Vikings Staff Family Lounge**

- 8'-0" counter with base cabinets for storage and food service
- Baby changing station at both toilets
- Men's and women's separate toilet facilities with floor mounted water closets and lavatories to have automatic operation
- Provide full-size refrigerator with bottom freezer
- Microwave
- Power and water for beverage station
- Duplex outlets
- Audio control – ability to select press, PA, radio and TV
- Two (2) phone data ports
- Individual thermostat
- Outlets below kitchen counter to accommodate 4 electric chafing dishes; provide grommets in counter top
- One (1) interactive touch screen computer or iPad
- Charging station at kitchen counter
- Soft Seating
- Thirty (30) stackable chairs
- Four (4) round 72" tables

**8. NFL Family Nursery**

- Locate between Vikings Staff Family Lounge and Vikings Team Family Lounge
- Locate away from route from Home Team Locker Room to Tunnel/Field
- 8'-0" counter with sink and base cabinets for storage
- Incorporate baby changing station within counter
- Single sink
- Provide refrigerator/freezer
- Soft seating
- Children's furniture tables, chairs, soft seating

**9. Auxiliary Locker Rooms (1)**

- One locker room with minimum 60 permanent lockers each sub-dividable into Two locker rooms of 30 lockers each
- Shower, toilet and drying area (in both)
- Training Room (in both)
- Storage (in both)

- Coaches' lockers, showers and toilet (in both)
- Elements include;
  - Free standing stool with locker storage
  - Counter for food and drink distribution
  - Floor drains and hose Bibs
  - Lockers and toilets should be stacked front to back
  - Game clock
  - Dry erase board in each
  - One ice machine per pair
- Include shell space for one additional 60 locker auxiliary locker room similar to above.

**10. Visitors NFL Locker Rooms**

- Comparable to recent NFL stadiums
- Shower, toilet and drying area with discreet access from press areas
  - Fifteen (15) Shower heads
  - Six (6) automatic water closets (floor mounted)
  - Six (6) automatic urinals
  - Six (6) automatic Lavatories with mirrors (1 ADA)
  - Drying Area
  - Three (3) full height mirrors
  - Area to be at or below 40% RH (relative humidity)
- Training Room/Exam Room
  - Area should be designed with NFL team to incorporate all training equipment and required floor space layout for training requirements
  - 16'-0" minimum ceiling height
  - Space will include doctor examine room
  - Double door access
  - Digital communication infrastructure with x-ray room and viewer in exam room
  - Ice machine
  - Game clock
  - Minimal overhead cabinet space
  - One (1) 12-pack hydro collator unit
  - Four (4) taping tables
  - Three (3) treatment tables, 80" x 30"
  - 10' linear feet of p-lam counter at 36" x 24" deep
  - 10' linear feet of adjustable shelving to begin 26" above counter, 12" deep
  - Two (2) 4' wide x 70" tall X 24" deep mobile wire shelf unit with clothes rod
  - One (1) treatment table in exam room, 80" x 30"
  - Four linear feet of p-lam counter at 36" high in exam room
- Supply storage room and Equipment storage room
  - Provide overhead door direct access to Event Level
  - Design convenient loading and unloading area
  - 12'-0" counter top
  - Ten (10) 18" wide x 24" deep x 7'-0" metal lockers
  - Ten (10) stackable chairs
  - Work center
- Office for Head Coach with dressing room
  - Dry erase board
  - Provide sound insulation in walls and ceiling
  - One (1) desk and chair
  - Shower and drying area at 8'-0" AFF
  - One (1) automatic hard wired water closet floor mounted
  - One (1) automatic hard wired lavatory with mirror
  - Two (2) lockers (24"x 24" x 8'-0" high)

- Game clock
- Assistant Coaches Locker Rooms
  - Twenty-five (25) lockable metal lockers (24" x 24" x 7'-0" high)
  - Twenty-five (25) Plastic stackable chairs
  - Separate shower and drying area
  - Six (6) showers
  - Two (2) water closet – floor mounted with automatic operation
  - Four (4) lavatory with automatic operation with mirrors
  - Three (3) urinals with automatic operation
  - Drying Area
  - Game clock

**11. X-Ray Room**

- First Aid/X-ray Room near team facility with compliance to NFL, NCAA, and MLS regulations

**12. Officials Locker Rooms**

- Officials Meeting Room
- Game Crew locker room to have 10 lockers with shower and restroom facilities
- Dressing area to have ten (10) (5 per side) 24" x 24" x 7'-0" metal lockers
- Open lockers with stool
- 6' counter with base cabinets, plastic laminate
- Women: 1 shower and 1 water closet
- Men: 2 showers, 1 water closet and 1 urinal
- 1 exercise bike
- Ball warming area
- Game Clock
- Multimedia (VCR/ CD/ DVD)
- Plastic stacking chairs
- Refrigerator
- Separate Women's Locker Room available for Officials and Chain Crew

**13. Chain Crew Locker Room**

- Ten (10) 36" wide x 24" deep x 7'-0" high metal lockers with folding chairs
- One (1) shower / side
- One (1) water closet / side with automatic operation
- Two (2) lavatories / side with automatic operation
- One (1) urinal / side with automatic operation
- Sound system tied into Event broadcasting
- Game Clock
- PA System
- Multimedia (VCR/ CD/ DVD)

**14. Cheerleaders Locker Room**

The Cheerleaders Locker Room area shall be provided as Core/Shell space under the base contract

**15. Field Toilets (total of 2) with direct access to each bench area**

**16. VIP/Team Parking**

- One Hundred Seventy-Three (173) exterior parking stalls with secured entry access to the Lower Club Level
- 8'-5" min stall width

- Used as non-game day parking for Vikings Team and MSFA
- Security barrier from general public
- Adequate Security Lighting and CCTV
- Access control gates

**17. Coaches Booths (located at Upper Suite Level)**

- Spaces for home and visiting team coaches, 10 seats each, shall contain built-in writing desks and telephone connections to player benches and operable sash
- Coaching Intercom/ Communications Systems – at box location 2 – 110V circuits
- Four (4) 20A, 120V circuits in room – alongside of room
- Outlet for instant replay TV
- Pre-wired for coaching intercom and video
- Stackable plastic chairs

**18. Coaches Video Platforms**

- Camera Platforms shall be located at the following locations at the Upper Seating Bowl and Upper Suite Level:
  - Team 50 yard line, home team position. Four camera positions. One platform shall be located at the Upper Suite Level 50 yard line. Two camera platforms shall be located at the Upper Suite Level – one at each end zone. Platform sizes shall be 8' x 32' at all 3 locations. The Vikings and NFL will be consulted regarding all aspects including booth, platforms, conduit, and electrical requirements
- One (1) 20A, 120V circuit, each location
- 110V outlet for each camera at each location
- Cable connections to coaches booths and both sidelines

**19. Video Replay Booth**

- Feeds to/from field, coaching video systems and network TV trucks
- Six (6) 20A, 120V circuits
- Four (4) 20, 120V at Field
- Separate HVAC system controls
- Investigate potential pre-action sprinkler systems or specialty dry chemical systems

**V. Team Facilities**

**1. Home NFL Locker Room**

- Vikings locker room shall be comparable to recent NFL stadiums to include 60 permanent lockers and 30 removable lockers. All lockers shall be (3'-6" wide x 3'-0" deep x 8'-0" high) lockable (4 digit code) wood lockers
- Vikings locker room complex, including locker rooms, training room, offices, exam room, Owner's room, meeting rooms, lounges and nursery to be temperature controlled, temperature range 65-70 degrees area to be at or below 40% RH (relative humidity)
- Vikings locker room shall include;
  - Three (3'-0" x 5'-0") portable dry erase boards
  - Counter for food and drink distribution (kiosk) – Portable or Permanent in Meeting Room
  - Double door access
  - Two (2) reach-in (GDM) style coolers, lockable
  - Four (4) refrigerators
  - Equipped for projectors
  - Separate audio controls from the rest of the Vikings spaces
  - Game clock
  - Separate digital thermostat. The Authority will explore opportunities to provide the Team with monitoring and control capabilities via password controlled control points within the single control system for the environmental controls in the Team spaces.

- 100 FT candle lighting with dimming system
- JBT Box
- USB port in each locker
- IPTV feed to Televisions/monitors
- 80 folding Vikings themed vinyl chairs
- 4 refrigerators
- Shower, toilet and drying area with discreet access from press areas, to include;
  - Variable pressure shower heads mounted at 8'-0" AFF with controls at 4'-6"
  - Water closet rim mounted at 1'-7" AFF Floor Mounted
  - One (1) ADA Lavatory counter mounted at 2'-10" AFF (Standard height 36")
  - Non slip tile flooring
  - Privacy curtain to locker room
  - Porcelain tile counter above lavatory counter
  - Stainless steel towel shelves and storage
  - Twenty-four (24) Shower heads (open shower)
  - Eight (8) Hard wired automatic water closets (floor mounted)
  - Eight (8) Hard wired automatic urinals
  - Eight (8) Hard wired automatic lavatories with mirrors
  - Drying Area to accommodate fifteen (15) players at one time
  - Six (6) hair dryers
  - Three (3) full height mirrors
  - Trench drains at shower/floor drains throughout
- Training Room, to include;
  - Area should be designed with NFL team to incorporate training equipment outlined below and required floor space layout for training requirements.
  - Privacy curtain 17' long
  - Outlets as required for training equipment layout
  - Ventilation for "gymnasium" type design requirements
  - Crushed ice machine
  - Temperature control – separate control from locker rooms
  - Telephone/data port
  - Game Clock
  - Four (4) adjustable exam stools, on wheels
  - Five (5) taping tables
  - Five (5) 80" x 30" treatment (exam) tables
  - Four (4) treatment carts
  - Ten (10) electrical outlets (quad and heights TBD)
  - One (1) additional light fixture in taping area
  - Two (2) electrical outlets, quad, height TBD; one (1) non-GFI
  - One (1) electrical outlet at standard height in locker area
  - Two (2) data outlets to fiber optic backbone
  - Ice Machine with storage bin in hydro room
  - Chiropractor table
  - Two (2) chairs to match chairs in main training area
  - One (1) adjustable office chair
  - Sports Flooring
- Head Athletic Trainer/Team Physician Room
- Trainers' Changing Room
- Hydrotherapy Room, to include;
  - Windows above 4'-0" for sightline from main training room
  - Double-wide glass doors
  - Ice machine
  - Adequate power
  - Provide continuous perimeter drain ahead of hydrotherapy tubs
  - One (1) hydro collator unit

- Plumbing to handle 100 gpm dump from tub
- Mixing valves for extremity tubs to code
- GFI receptacles per code placed at 48" off floor
- Area to be at or below 40% RH (relative humidity)
- Telephone/data port
- Hose bibb near room
- Exam Room
- Supply Storage and Equipment Storage
  - Includes Team home video storage room
    - Requires double door access
    - Wall racks/ shelving
    - Built-in storage units
    - Plastic laminate millwork
  - Office for Equipment Manager
  - Provide overhead door direct access to Event Level circulation/corridor
  - Design convenient loading and unloading area
  - Work center
  - Dutch door toward Minnesota Vikings Locker Room at door pair
  - Built in shelves
  - Twenty-five (25) 24" x 24" x 7'-0" lockers with privacy separation wall
  - 6' - 4" Long counter top only
  - 5'-0" counter height overhead door above a pass-thru counter with access door adjacent
  - Equipment room to include full height overhead door
  - Telephone / Data port
  - In house feed to Television/monitors
  - Twenty-five (25) Plastic stackable chairs
  - Twenty-five (25) 24" x 24" x 7'-0" lockers
  - Upper and lower lockable storage lockers with p-lam countertop
- Stretching Room, to include;
  - Sports flooring.
  - Audio Control – ability to select press, PA, radio, TV and auxiliary; (2) ceiling speakers
- Team Owner's room, to include;
  - Designed to comfortably accommodate 8-10 people
  - Conference room table with 8 (eight) chairs
  - Soft seating area
  - Separate restroom area with toilet and lavatory with mirror in each
  - Kitchenette with lower cabinets, stone countertop and built-in sink
  - Telephone/data port
  - Audio Control – ability to select press, PA, radio, TV and auxiliary; (2) ceiling speakers
  - In house feed to televisions/monitors access
  - One (1) phone/data port w/fiber optic backbone
  - Full size stainless steel refrigerator
  - Individual thermostat
  - Charging station at kitchen counter
  - Trash and recycling receptacles
- Vikings General Manager Office, to include;
  - Dry erase board
  - Small table with six chairs
  - Sound insulation in walls and ceiling
  - One (1) work station
  - Game clock
  - Telephone/data port
  - In house feed to televisions/monitors
  - Under-counter refrigerator

- 36" x 36" metal locker
- Coaches Locker Rooms with work and lounge areas, to include;
  - Thirty-five (35) lockable wood lockers – 24" x 24" x 8'-0" high
  - Separate shower and drying area
  - Eight (8) showers at 8'-0" AFF
  - Four (4) hardwired auto valves water closets – floor mounted rim mounted 1'-7"
  - Four (4) hardwired auto valves lavatories with mirrors
  - Four (4) hardwired auto valves urinals
  - Full height fridge
  - Storage Areas
  - Engineered stone counter at lavatories and kitchenette
  - Work area
  - Soft seating area
  - Equipped for projectors
  - Game clock
  - Telephone/data port
  - In house feed to televisions/monitors
  - Area to be at or below 40% RH (relative humidity)
  - Proximity card access
  - Thirty-five (35) Vikings themed folding vinyl chairs
  - Conference room table with 8 (eight) chairs
- Team meetings rooms, to include;
  - Two (2) meeting room areas with space for 30 people
  - Space planned for preseason temporary locker room facilities for Vikings team
  - Area to view chalk talks
  - Dry erase boards/marker boards
  - 10'-0" wide clear area in front of seating
  - 12'-0" minimum ceiling height
  - Operable manual acoustical partition between rooms for ability to create 1 room, include man door for 2nd exit
  - Sound attenuation insulation in walls
  - Two (2) Game Clocks (one per team room)
  - Area to be at or below 40% RH (relative humidity)
  - Equipped for projectors
  - Telephone / Data port
  - Themed folding chairs vinyl chairs
  - One (1) dry erase board (minimum 4' x 10') in each
- Staff Locker Room, to include;
  - Twenty-two (22) each 30" wide x 24" deep x 7'-0" tall lockable metal lockers
  - One (1) Toilet room with water closet and lavatory
  - Telephone/data port
- Locker Room/Office for Head Coach, to include;
  - Dry erase board
  - Table with six chairs
  - Sound insulation in walls and ceiling
  - Built in storage for multi-media
  - One (1) work station
  - Separate shower and drying area
  - One (1) automatic hard wired water closet Floor Mounted
  - One (1) hard wired lavatory with mirror
  - Under counter refrigerator
  - Two (2) wood lockers - 30" wide x 24" deep x 7'-0" high
  - Storage Areas
  - Equipped for projectors

- Game clock
- Telephone / Data port
- In house feed to Televisions/monitors
- Area to be at or below 40% RH (relative humidity)
- Proximity card access

**VI. Media Facilities**

**1. Press Box**

- Located on the upper suite level
- Stations for approximately 200 (additional loose seating should be able to be added to achieve 300) writers shall be provided. This area shall contain built-in writing counter, seating, electrical, and telephone outlets, sound system and closed circuit television
- Coat hooks with shelving at each station
- Space for 200 cubbies
- NFL game clock and Stadium clock operator
- Coach to quarterback official NFL observer
- Aisle width to allow bar stool additional seating behind each desktop position at the back row
- Storage room for Vikings PR items (150 SF)
- Open fronts
- Each station to include one electric and two telephone/data outlets

**2. Broadcast Booths**

- One (1) TV Broadcast Booth located at midfield per broadcast requirements
- TV Broadcast Booth at midfield to include;
  - 24' wide required by networks
  - Lighting grid, sound attenuation, internal circuit breaker panel, data, front opening to have camera catch and overhead grid. Flat, not tiered floor
  - Dedicated toilet room
  - "Captains" chair height furniture
  - TV monitors by broadcast networks
- One (1) auxiliary visiting TV/skycam Broadcast Booth located in press box.
- Six (6) Radio Broadcast Booths per broadcast requirements

**3. Broadcast Truck Facilities**

- Minimum Four (4) 56 foot broadcast TV tractor/trailer truck positions with four (4) expandable to 16 foot trailer width with eight (8) foot working area on all sides.
- Parking for a minimum of three (3) TV satellite trucks with clear sightlines to southern sky with minimum dimensions
- Parking for up to six (6) local TV microwave trucks (exterior)
- Parking for TV crew
- Power and Broadcast Infrastructure per NFL and HD Specifications

**4. TV Host Locations**

- Provide at least one JBT box on the main concourse as currently configured for use as a Television Host broadcast location.

**5. Camera Positions**

- In compliance with NFL, NCAA, and MLS network broadcast requirements and supporting Vikings game production locations.
- Television camera platforms shall be located at the following locations at the mid deck/club level: Home team 50 yard line, home team both, 25 yard lines, visiting team 50 yard line, each corner (slash position). Four camera positions shall be located at field level; two in each end



zone aligned with between each hash mark and numbers and clear of net. One camera platform shall be located at the Upper Suite Level 50 yard line. Two camera platforms shall be located at the Upper Suite Level – one at each end zone. Platform sizes vary for dedicated/combined use by network, TV, club, visiting club

- Space for two (2) cameras minimum each location except 50 yard line (assume 8' x 8' each camera - 6' for team cameras)

**6. Interview Rooms**

- Interview space for post-game shall be provided convenient to both home and visitor's locker rooms. This room shall be accessible by television cable tray. Electrical requirements shall be provided. Television networks shall be consulted
- Flat floor space
- Raised podium 8' x 12' x 18"H for speaker - carpeted
- Raised camera riser in rear 6'D x 20'W x 18"H - carpeted
- Podium and camera riser may be portable
- Seating capacity for 100 (with stackable chairs) in home team interview room and 50 (with stackable chairs) in visiting team interview room
- Rear wall acoustical panels and side wall rear 1/3 acoustical panels.
- Stackable and folding chairs

**7. Press Support**

- Media Work Room
- Press Dining Room and Lounge for minimum 150 people
- Media Function Room
- Photographers Work Room
- TV Cable Connection Room
- Broadcast Crew Room
- Equipment Storage
- Restrooms
- Converge Data Network to support Broadcast and Press Network requirements for back of House, production and distribution requirements

**VII. Authority and Operations Staff Facilities**

**1. Offices**

- Year round administrative offices for the Authority
- Offices and cubicles for Stadium operations staff
- Include conference room, break room, work room, storage and kitchen

**2. Employee Locker rooms for men and women to accommodate staff**

**3. Gathering Rooms**

- Employee Break Room
- Ticket Taker and Usher Briefing Room
- Event Security Briefing Room

**4. Storage**

- Employee Uniform Storage and Laundry Facilities
- Field Equipment Storage
- Stage Storage and Support
- General Storage

**5. Security and Loading Dock Command Center**

- One central game day office

- Restrooms
  - Two (2) holding cells
  - Roll-call room
  - BMS Control
  - Command Center to control access to loading dock and service tunnel
    - Stadium and Field Lighting Controls
    - Communications Systems
    - Fire Command Center
    - Public Address Systems
    - Monitors for Surveillance Camera Systems
    - Record, replay and distribute Camera Surveillance Systems
- 6. Janitorial/Maintenance Facilities**
- Private offices, open office area, storage and break rooms on event level for Back of House, Cleaning and Janitorial
  - Maintenance shops for Machinery, Carpentry, Paint, Electrical and Plumbing
  - Central Supply Room
  - Janitors Closets on all levels near toilet facilities
- 7. Trash Collection/Recycling**
- Main handling facility located near loading dock to accommodate separate treatment of trash and recyclable materials, including compactor(s)
  - Trash container and recycling container storage/staging on each level
- 8. Freight Elevators**
- Minimum two freight elevators on each side of stadium with stops at levels as indicated within the design documents and accommodate 12,000 pounds minimum 10 feet wide by 20 feet deep.
- 9. Event Command Post**
- Stadium Operations Booth – including video, data, PA, BMS controls. Security Observation Booth – including video data, remote operation of security cameras and monitoring of building systems.
- 10. Loading Dock**
- Convenient access to field level and service areas with easy street access
  - Minimum of 6 truck bays with dock levelers and appropriate ventilation
  - Additional two truck docks for central commissary
  - Dedicated truck dock adjacent to NFL home team locker room
- 11. Concessionaires Offices**
- Includes finished space for concessionaires offices and cash handling operations.

**VIII. Mechanical and Electrical Systems**

The Project shall include mechanical and electrical systems and fixtures to support the design standards set forth in this **Exhibit C-2** and shall be designed in conformance with all local and state requirements and shall be sufficient to allow NFL games and associated events to occur, including the following:

- 1. District Steam and Chilled Water**
- 2. HVAC Distribution System**
- 3. Plumbing System**
- 4. Fire Protection**

- 5. Electrical Power distribution**
- 6. Emergency Power System**
- 7. Lighting, including Field Lighting**
- 8. Fire Alarm and Detection Systems**

**IX. Audio/Visual and Information Technology Systems**

The Project shall incorporate audio and high definition video systems, including, without limitation, the following:

**1. Distributed Audio System**

- The seating bowl loudspeaker system is based on a distributed line array configuration. The lower and mid-level bowl seating is covered by eight line arrays (Type 1) arranged in a 300 foot diameter circle centered over the playing field. Sub-woofers located with each line array provide additional low frequency sound reinforcement. Additional loudspeaker arrays and fill speakers cover the upper seating sections. Loudspeaker system to deliver minimum performance criteria as measured from the spectator seats: Frequency response to be +/-3db from 55Hz to 10,500Hz, 106dBA sustained loudness, +/-3dB uniformity of coverage, and intelligibility factor > 0.52 STI-PA.
- Power Amplifiers are located in dedicated equipment rooms. Amplifiers and associated processors are connected back to a centralized monitoring system in the audio control room.
- The audio control room on the upper concourse southeast corner will be the primary location for the mixing console along with program sources and patch panels. In addition, the digital signal processing system and amplifier control computers will be located in this room. Analog tie lines from the floor, video replay system, main broadcast interconnect, and other areas will terminate in the audio control room. Connector panels on the field level and camera platforms provide analog and digital audio connections to the system.
- A dedicated digital audio network is provided to connect the audio control room feeds with the digital mixing console and the network connected amplifier and DSP equipment. The network cabling is routed with other building structured cabling systems. The audio equipment is also connected to the building Ethernet network to allow control and monitoring from network drop locations.
- Portable digital audio console can be located at the main concourse or event level and connected using the digital audio network from the audio control room down to the dedicated connection boxes (JBA's) Digital stage boxes with connectors allow the console to be easily moved and setup between positions. Snake cables will allow portable source and outboard processing equipment racks to be easily interconnected with the console. JBA boxes will have rack space for in house video replay broadcast cabling and intercom panels.
- As an aid to the fire alarm system, the main seating bowl will receive warning signals and announcements from the main fire command center. Tie lines to interface these systems will be the responsibility of this contractor, but the components to implement the connections shall be the obligation of the fire alarm installer. During an emergency with the fire alarm, all systems other than those that cover the main seating bowl shall mute.
- A hearing assistance system will be provided for the seating bowl. System transmitting frequencies to be coordinated and not interfere with clubs, interview rooms, video replay and writing press RF systems.
- Entry gates and queuing areas within concourses will have speakers with programming selected in the audio control system. Pendant mounted speakers in areas where there are no ceilings or high ceilings. Provide recessed speakers in areas with finished ceilings. The network connected amplifiers and processors for these systems are located in TR rooms in each quad on Event, Main and Upper Concourse levels.
- Restrooms on each public level will have speakers with programming selected in the audio control system. Speaker enclosure types are to be coordinated with ceiling conditions. Provide surface or pendant mounted speakers in restrooms with no ceiling and recessed speaker assemblies in areas with a finished ceiling.

- Ticket offices will be equipped with a paging system with exterior speakers over ticket windows and ceiling speakers in the inside lobby. This system will deliver informational announcements and messages to patrons waiting in line from a local CD player. The ticket office will receive a remote feed from the audio control room consisting of preprogrammed announcements or other building wide audio signals.
- The Pedestrian Plaza on the west side of the grounds will be supported with an outdoor rated loudspeaker system to deliver messaging and entertainment to pedestrian patrons.

**2. Communications Systems/Information Management**

- The MSFA and Team have established a total budget allowance of twenty-eight million dollars (\$28,000,000) for Vendor Contract Technology, including certain Communications Systems and Information Management systems. The SDC Group shall manage the design and procurement process for these designated systems until a contract is executed to furnish and install the applicable systems in accordance with the SDC Group approved design.

**3. Security and Surveillance**

- The physical security systems shall consist of the following:
  - Electronic Access Control including Visitor Management and Badging station to include:
    - New and complete enterprise-wide, low-voltage, electronic access control system (EACS).
    - Access control hardware devices, mounting brackets, power supplies, switches, controls, consoles and other components of the system as required.
    - Access control related software to allow this system expansion. Software includes required license addition for access control readers and electrified portals, workstations and Video Management System (VMS) Integration.
  - Intrusion Detection System (IDS) to include:
    - Materials, hardware, software and cabling required to provide a fully functional system.
    - Low voltage signal, control, and power cables to and from power supplies, remote panels, expansion panels, and other devices as required for a complete turnkey system.
  - Video Surveillance System to include:
    - IP cameras and a server based NVR with client stations and storage.
    - Programming and configuration of system components as well as all associated software upgrades and patches.
  - IP Video Management System
  - Command and Control Centers including video walls and security consoles.
  - Uninterruptable Power Supplies (UPS) and in panel battery backup

**X. Sponsorship Related Building Systems**


The Team will identify during construction certain areas throughout the building in which it intends to create Sponsorship opportunities using branding and theming elements. Any proposed design enhancements and the costs for such design enhancements would be the responsibility of the Team and/or Sponsor. Responsibility for additional operating costs are defined within the Use Agreement.

**XI. Design Add Alternates**

The items identified below are not currently included within the Minimum Design Standards. Consistent with Section 8.1(e) of the Development Agreement, if either Party elects to add any of the Design Add Alternates set forth on **Exhibits I-1 or I-2** to the Project, subject to the requesting Party's obligation to fund the completion of the work, the selected Design Add Alternate shall be included in the Minimum Design Standards.

**EXHIBIT D-1-A**

**EFFECTIVE DATE STADIUM SITE (SITE PLAN)**



**EXHIBIT D-1-B**

**EFFECTIVE DATE STADIUM SITE (LEGAL DESCRIPTION)**

Parcel 1:

That part of:

Lots 2 through 5, inclusive, Block 71, Town of Minneapolis;  
Lots 1 through 10, inclusive, Block 72, Town of Minneapolis;  
Lots 1 through 10, inclusive, Block 95, Town of Minneapolis;  
Lots 1 through 5, inclusive, Block 106, Town of Minneapolis;  
Lots 1 through 10, inclusive, Block 96, Town of Minneapolis;  
Lots 3, 4 and 5, Block 96, Morrison, Smith, and Hancock's Addition to Minneapolis;  
Lots 1 through 10, inclusive, Block 103, Town of Minneapolis;  
Lots 6 and 7, Block 103, Morrison, Smith, and Hancock's Addition to Minneapolis;  
Lot 1 and Lots 6 through 10, inclusive, Block 104, Town of Minneapolis;  
Lots 1 through 11, inclusive, Block 104, Morrison, Smith, and Hancock's Addition to Minneapolis;  
Lot 1, Block 119, Town of Minneapolis;  
Lots 1 through 12, inclusive, Block 119, Morrison, Smith, and Hancock's Addition to Minneapolis;

Together with that part of vacated 4th Street South, Town of Minneapolis, lying Southeasterly of a line connecting the most Northerly corner of Block 72, Town of Minneapolis with the most Westerly corner of Block 71, Town of Minneapolis and lying Northwesterly of a line connecting the most Northerly corner of Block 104, Town of Minneapolis with the most Westerly corner of Block 105, Town of Minneapolis;

Together with that part of vacated 4th Street South, Town of Minneapolis, described as follows: Beginning at the most Westerly corner of Block 105, Town of Minneapolis; thence South 59 degrees 54 minutes 07 seconds East on an assumed bearing along the Southwesterly line of said Block 105, a distance of 86.78 feet; thence South 21 degrees 39 minutes 25 seconds East, a distance of 129.24 feet to a point distant 56.00 feet Southeasterly of the most Northerly corner of Lot 8, Block 104, Town of Minneapolis; thence North 59 degrees 54 minutes 07 seconds West along the Northeast line of said Block 104, to the most Northerly corner of said Block 104, thence North 30 degrees 08 minutes 36 seconds East, a distance of 80.00 feet to the point of beginning.

Together with that part of vacated 5th Street South, Town of Minneapolis and Morrison, Smith and Hancock's Addition to Minneapolis, lying Southeasterly of a line connecting the most Northerly corner of Block 95, Town of Minneapolis, with the most Westerly corner of Block 72, Town of Minneapolis and lying Northwesterly of a line connecting the most Easterly corner of Block 119, Morrison, Smith and Hancock's Addition to Minneapolis with the most Southerly corner of Block 104, Morrison, Smith and Hancock's Addition to Minneapolis;  
Together with that part of vacated 9th Avenue South, Town of Minneapolis, lying Northeasterly of a line connecting the most Westerly corner of Block 103, Town of Minneapolis with the most

Southerly corner of Block 95, Town of Minneapolis and lying Southwesterly of a line connecting the most Easterly corner of Lot 5, Block 71, Town of Minneapolis with the most Northerly corner of Lot 1, Block 106, Town of Minneapolis;

Together with that part of vacated 10th Avenue South, Town of Minneapolis and Morrison, Smith and Hancock's Addition to Minneapolis, lying Northeasterly of a line connecting the most Westerly corner of Block 119, Town of Minneapolis, with the most Southerly corner of Block 103, Town of Minneapolis, and lying Southwesterly of a line drawn parallel with and distant 140 feet Northeasterly from, as measured at a right angle to, a line connecting the most Southerly corner of Block 106, Town of Minneapolis with the most Westerly corner of Block 105, Town of Minneapolis;

which lies within the following described boundary:

Beginning at the most Westerly corner of Block 72, Town of Minneapolis; thence North 30 degrees 10 minutes 52 seconds East on an assumed bearing along the Northwest line of said Block 72, a distance of 330.34 feet to the most Northerly corner of said Block 72; thence North 81 degrees 07 minutes 40 seconds East, a distance of 123.00 feet; thence Southeasterly, a distance of 190.64 feet along a non-tangential curve concave to the Southwest having a central angle of 37 degrees 55 minutes 39 seconds, a radius of 288.00 feet and the chord of said curve bears South 78 degrees 52 minutes 02 seconds East; thence South 59 degrees 54 minutes 12 seconds East tangent to the last described curve, a distance of 393.77 feet; thence Southeasterly, a distance of 157.73 feet along a tangential curve concave to the Southwest having a central angle of 16 degrees 57 minutes 23 seconds and a radius of 532.96 feet to the Northwest line of Block 105, Town of Minneapolis; thence South 30 degrees 08 minutes 23 seconds West along said Northwest line, a distance of 35.03 feet to the most Westerly corner of said Block 105; thence South 59 degrees 54 minutes 07 seconds East along the Southwest line of said Block 105, a distance of 86.78 feet; thence South 21 degrees 39 minutes 25 seconds East, a distance of 129.24 feet to a point on the Northeast line of Lot 8, Block 104, Town of Minneapolis, distant 56.00 feet Southeasterly from the most Northerly corner of said Lot 8; thence South 38 degrees 43 minutes 55 seconds East, a distance of 152.77 feet to a point on the Southeast line of Lot 7, Block 104, Morrison, Smith and Hancock's Addition to Minneapolis, distant 110.00 feet Northeasterly of the most Southerly corner of said Lot 7; thence South 30 degrees 08 minutes 38 seconds West along the Southeast line of said Block 104, a distance of 275.17 feet to the most Southerly corner of said Block 104; thence South 30 degrees 16 minutes 53 seconds West, a distance of 80.00 feet to the most Easterly corner of Block 119, Morrison, Smith and Hancock's Addition to Minneapolis; thence South 30 degrees 04 minutes 43 seconds West along the Southeast line of said Block 119, a distance of 109.08 feet; thence Southwesterly, Westerly and Northwesterly, a distance of 348.96 feet along a non-tangential curve concave to the North having a central angle of 64 degrees 29 minutes 27 seconds, a radius of 310.03 feet and a chord of said curve bears South 87 degrees 51 minutes 16 seconds West; thence North 59 degrees 54 minutes 00 seconds West, a distance of 637.85 feet; thence Northwesterly, Northerly and Northeasterly, a distance of 291.47 feet along a tangential curve concave to the East having a central angle of 69 degrees 39 minutes 20 seconds and a radius of 239.75 feet to a point of reverse curve; thence Northeasterly, a distance of 26.34 feet along said reverse curve having a central angle of 4 degrees 42 minutes 57 seconds and a radius of 320.00 feet to the Northwest line of Block 95, Town of Minneapolis; thence North

30 degrees 06 minutes 16 seconds East along said Northwest line, a distance of 104.87 feet to the most Northerly corner of said Block 95; thence North 30 degrees 05 minutes 44 seconds East, a distance of 80.00 feet to the point of beginning;

part of which is registered land and described as follows:

Parcel 1: The front or Southwesterly 85.7 feet of Lots 1 and 2, Block 95;  
Lots 3 and 4, Block 95;  
Lots 3 to 9, inclusive, Block 103;  
Lot 1, Block 119,  
all in Town of Minneapolis.

Parcel 2: Lots 6 and 7, Block 103;  
Lots 1, 3, 5, 9 and 12, Block 119;

That part of vacated 5th Street lying Southwesterly of the center line of said street and between the extensions across it of the Northwesterly and Southeasterly lines of Lot 9;  
Also that part of 10th Avenue South, vacated, lying between extensions across it of the Northeasterly and Southwesterly lines of said Blocks 103 and 119,  
all in Morrison Smith and Hancock's Addition to Minneapolis.  
Hennepin County, Minnesota;

which lies within the following described boundary:

Beginning at the most Westerly corner of Block 72, Town of Minneapolis; thence North 30 degrees 10 minutes 52 seconds East on an assumed bearing along the Northwest line of said Block 72, a distance of 330.34 feet to the most Northerly corner of said Block 72; thence North 81 degrees 07 minutes 40 seconds East, a distance of 123.00 feet; thence Southeasterly, a distance of 190.64 feet along a non-tangential curve concave to the Southwest having a central angle of 37 degrees 55 minutes 39 seconds, a radius of 288.00 feet and the chord of said curve bears South 78 degrees 52 minutes 02 seconds East; thence South 59 degrees 54 minutes 12 seconds East tangent to the last described curve, a distance of 393.77 feet; thence Southeasterly, a distance of 157.73 feet along a tangential curve concave to the Southwest having a central angle of 16 degrees 57 minutes 23 seconds and a radius of 532.96 feet to the Northwest line of Block 105, Town of Minneapolis; thence South 30 degrees 08 minutes 23 seconds West along said Northwest line, a distance of 35.03 feet to the most Westerly corner of said Block 105; thence South 59 degrees 54 minutes 07 seconds East along the Southwest line of said Block 105, a distance of 86.78 feet; thence South 21 degrees 39 minutes 25 seconds East, a distance of 129.24 feet to a point on the Northeast line of Lot 8, Block 104, Town of Minneapolis, distant 56.00 feet Southeasterly from the most Northerly corner of said Lot 8; thence South 38 degrees 43 minutes 55 seconds East, a distance of 152.77 feet to a point on the Southeast line of Lot 7, Block 104, Morrison, Smith and Hancock's Addition to Minneapolis, distant 110.00 feet Northeasterly of the most Southerly corner of said Lot 7; thence South 30 degrees 08 minutes 38 seconds West along the Southeast line of said Block 104, a distance of 275.17 feet to the most Southerly corner of said Block 104; thence South 30 degrees 16 minutes 53 seconds West, a distance of 80.00 feet to the most Easterly corner of Block 119, Morrison, Smith and Hancock's Addition to Minneapolis; thence South 30 degrees 04 minutes 43 seconds West along the Southeast line of said Block 119, a distance of 109.08 feet; thence Southwesterly, Westerly and Northwesterly, a distance of 348.96 feet along a non-



## EXECUTION COPY

tangential curve concave to the North having a central angle of 64 degrees 29 minutes 27 seconds, a radius of 310.03 feet and a chord of said curve bears South 87 degrees 51 minutes 16 seconds West; thence North 59 degrees 54 minutes 00 seconds West, a distance of 637.85 feet; thence Northwesterly, Northerly and Northeasterly, a distance of 291.47 feet along a tangential curve concave to the East having a central angle of 69 degrees 39 minutes 20 seconds and a radius of 239.75 feet to a point of reverse curve; thence Northeasterly, a distance of 26.34 feet along said reverse curve having a central angle of 4 degrees 42 minutes 57 seconds and a radius of 320.00 feet to the Northwest line of Block 95, Town of Minneapolis; thence North 30 degrees 06 minutes 16 seconds East along said Northwest line, a distance of 104.87 feet to the most Northerly corner of said Block 95; thence North 30 degrees 05 minutes 44 seconds East, a distance of 80.00 feet to the point of beginning;

Abstract Property and  
Torrens Property - Certificate of Title No. 1355300

### Parcel 2:

Lots 1, 2, 3, 4, 5, 6, 7, 8, 9 and 10, Block 70, Town of Minneapolis, Hennepin County, Minnesota.

Torrens Property  
Certificate of Title No. \_\_\_\_\_

### Parcel 3:

Lots 1, 2, 3, 4, 5, 6, 7, 8, 9 and 10, Block 73;

That part of the Southeasterly 6 feet of Seventh Avenue vacated, lying between extensions across said strip of land of the Southwesterly line of said Lot 1 and the Northeasterly line of said Lot 10;

All in Town of Minneapolis.

Hennepin County, Minnesota .

Torrens Property  
Certificate of Title No. 1381959

### Parcel 4:

Together with any easements set forth in that certain Agreement for Skyway Construction, Operation, Maintenance, and Easements dated February \_\_, 2014, recorded February \_\_, 2014 in the office of the Hennepin Court Recorder as Document No. \_\_\_\_\_, and in the office of the Hennepin County Registrar of Titles as Document No. \_\_\_\_\_.

Parcel 5:

Together with easement and use rights set forth in that certain Urban Park Use Agreement between Ryan Companies US, Inc., a Minnesota corporation and Minnesota Sports Facilities Authority, a public body and political subdivision of the State of Minnesota dated February \_\_, 2014, recorded February \_\_, 2014 in the office of the Hennepin County Recorder as Document No. \_\_\_\_\_ and in the office of the Hennepin County Registrar of Titles as Document No. \_\_\_\_\_.

**EXHIBIT D-2**

**FINAL STADIUM SITE**

**[TO BE AFFIXED BY THE PARTIES AFTER THE EFFECTIVE DATE.]**

**EXHIBIT E**

**MINNEAPOLIS CITY COUNCIL AGENDA**

**SEE ATTACHED**

# Minneapolis City Council Agenda

## Regular Meeting

August 30, 2013

9:30 a.m. - Room 317 City Hall

**NOTE:** *All cellular telephones, pagers and BlackBerry devices to be switched to a non-audible function during Council and Committee meetings.*

Present: Council President Johnson, Vice President Lilligren, Majority Leader Schiff, Minority Leader Gordon, Council Members Reich, Hofstede, Samuels, Glidden, Tuthill, Quincy, Colvin Roy and Hodges. (Majority vote of all members, 7; 2/3 vote of all members, 9)

Absent: Council Member Goodman.

1. Roll Call.

2. Adoption of the agenda.

**Action Taken: Adopted, as amended, to include a Mayoral Proclamation under New Business.**

3. Acceptance of minutes of the special meeting of August 15, 2013 and the regular meeting of August 16, 2013.

**Action Taken: Accepted.**

4. Referral of petitions and communications and reports of the City officers to proper committees and departments.

**Action Taken: Referred.**

## REPORTS OF STANDING COMMITTEES

### Community Development

*CD agenda of [8/20/2013](#)*

1. 2012 Consolidated Annual Performance & Evaluation Report (CAPER):

Authorize submittal of the CAPER to the U.S. Department of Housing & Urban Development.

**Action Taken: Adopted.**

2. Land Sale (2644 Minnehaha Ave):

Passage of Resolution authorizing sale of property to RCK Development, LLC; Grant driveway easement over 2620 Minnehaha Ave (*9 votes*).

**Action Taken: Adopted.**

3. Emerge Career & Technology Center (1834 Emerson Ave N):

- a) Authorize increase in Great Streets \$350,000 loan to \$500,000 for the creation of the publicly accessible computer & technology center;
- b) Authorize loan agreement, related documents & execution of applications, grant agreements, associated documents.

*Early signature by Mayor requested.*

**Action Taken: Adopted.**

4. Community Garden Policy:

Approve waiver of policy to allow short-term garden leases on City-owned buildable lots within the tornado affected areas of Mpls.

**Action Taken: Adopted.**

## Public Safety, Civil Rights & Health

*PSCH agenda of [8/21/2013](#)*

*Referred Reports to Ways & Means/Budget*

1. Minnesota Board of Firefighter Training & Education (MBFTE):

Accept redistribution funding from MBFTE, \$37,223.23, for firefighter training conducted between 7/1/2012-6/30/2013; Passage of Resolution appropriating funds (9 votes).

**Action Taken: Adopted.**

2. Animal Care & Control Donations:

Passage of Resolution accepting in-kind donations of dog & cat food & supplies (9 votes).

**Action Taken: Adopted.**

3. Local Initiatives Support Corporation:

Accept & allocate funds from Local Initiatives Support Corporation, \$5,000, for the Urban Scholars program; Passage of Resolution appropriating funds (9 votes).

**Action Taken: Adopted.**

## Regulatory, Energy & Environment

*RE&E agenda of [8/19/2013](#)*

1. Liquor Licenses:

Passage of Resolution granting licenses to the following businesses:

- a) Whole Foods Market, 222 Hennepin Ave (new business);
- b) Nico's Tacos, 2516 Hennepin Ave (new business); and
- c) Spyhouse Coffee, 945 Broadway St NE (Sidewalk Cafe) (new business).

*Early signature by Mayor requested.*

**Action Taken: Adopted.**

2. Al-Madina Halal Market, 1001 Franklin Ave E:  
Passage of Resolution approving reduction in administrative citations relating to a Grocery License.

**Action Taken: Adopted.**

3. Class A Valet Parking Lot, 330 1st Ave N:  
Passage of Resolution approving Business License Operating Conditions relating to a Commercial Class A Parking Lot License.

**Action Taken: Adopted.**

4. Rental Dwelling License at 4043 Penn Ave N:  
Approve reinstatement of license to be held by AREE Properties, LLC - Ronald Mash.

**Action Taken: Adopted.**

5. Rental Dwelling License at 2914 Logan Ave N:  
Approve reinstatement of license to be held by Charles P. Johnson.

**Action Taken: Adopted.**

6. Rental Dwelling License at 3506 Girard Ave N:  
Approve reinstatement of license to be held by Rae Kittleson Jones.

**Action Taken: Adopted.**

7. Liquor, Wine and Beer Licenses:  
Passage of Resolution granting license applications.

**Action Taken: Adopted.**

8. Business Licenses:  
Passage of Resolution granting license applications.

**Action Taken: Adopted.**

9. Gambling Licenses:  
Passage of Resolution granting license applications.

**Action Taken: Adopted.**

*Referred Reports to Ways & Means/Budget*

10. Annual Taxicab Meter Rate Adjustment:  
Passage of Resolution enacting a one-year suspension of the automatic taxicab meter rate adjustment.

**Action Taken: Adopted.**

11. 2014 License Fee Schedule:  
Approve 2014 License Fee Schedule with no (0%) increase in eligible fees, effective January 1, 2014.

**Action Taken: Adopted.**

## Rules

*Rules agenda of [8/29/2013](#)*

1. City Council Rules:

Passage of Resolution approving the 2013 revision of Council rules and adopting that revision as the definitive Minneapolis City Council *Rules of Order*.

**Action Taken: Adopted.**

## Transportation & Public Works

*T&PW agenda of [8/20/2013](#)*

1. LynLake Municipal Parking Lots:

a) Determine that no special assessment proceeding is necessary for payable 2014 due to an operating profit that exceeded 2013 assessments; and

b) Set impact fees through August 31, 2014.

**Action Taken: Adopted.**

*Referred Reports to Ways & Means/Budget*

2. 39th Ave S Speed Hump Installation Project (between Minnehaha Pkwy & 49th St):

a) Passage of Resolution ordering work to proceed and adopting special assessments in the amount of \$7,000; and

b) Accept Appeal Waivers from assessed property owners.

**Action Taken: Adopted.**

3. Contract Amendment - Crane Carrier Parts and Service:

Authorize increase to contract with Midwest Diesel, Inc. by \$100,000 for OEM Crane Carrier truck parts and service for the Solid Waste and Recycling Division.

**Action Taken: Adopted.**

4. Contract Amendment - Nicollet Mall Redesign:

Authorize amendment to contract with Peter Brown increasing the contract by \$90,000, extending the term of the contract, and making modifications to allow reimbursement of eligible expenses in accordance with City policy.

**Action Taken: Adopted.**

5. Waiver Agreement:

Authorize execution of an agreement with the Hennepin County Department of Environmental Services to waive the \$40,000 bonding requirement for the Minneapolis North and South Transfer Stations.

**Action Taken: Adopted.**



6. Bids:

- a) OP 7828, Accept single bid of Northwestern Power Equipment to furnish and deliver finished water flowmeters to the Water Treatment and Distribution Division; and
- b) OP 7835, Accept low bid of Engineering and Construction Innovations, Inc. to complete the St. Mary's/Hiawatha Tunnel Rehabilitation Project, Phase 2.

**Action Taken: Adopted.**

## Ways & Means/Budget

*W&M/Budget agenda of 8/27/2013*

1. Legal Settlement:

Passage of Resolution authorizing settlement of Andrew Josef Brenner vs. City of Minneapolis (\$5,000).

**Action Taken: Adopted.**

2. Homegrown Minneapolis:

Authorize increase contract with Shey Associates by \$36,000 for Homegrown Minneapolis consulting services.

**Action Taken: Adopted.**

3. Communication Services Gift:

Passage of Resolution accepting a gift of professional communications services from Resource Media for the purpose of generating positive media coverage relative to the City's public buildings report and benchmarking ordinance. (9 votes)

**Action Taken: Adopted.**

4. Fall 2013 Tree Planting Program:

Authorize increase contract with Tree Trust by \$20,000 for a special Fall of 2013 tree planting program.

*Early Signature by Mayor Requested.*

**Action Taken: Adopted.**

5. Utility Billing Insert:

Approve October 2013 utility billing insert, on behalf of the Public Works Department, providing information on fall street sweeping and yard bags and brush collection.

**Action Taken: Adopted.**

6. Dome Roof Replacement:

Authorize amendment to OP 7650 with Central Roofing Company increasing the original contract amount by \$436,755.06 to allow close-out and final payment.

**Action Taken: Adopted.**

7. Convention Center Wall Fabric:

Authorize to execute contract with Julius B. Nelson and Son, Inc., for an estimated expenditure of \$98,975, to furnish and deliver all labor and materials necessary for wall fabric at the Convention Center.

**Action Taken: Adopted.**

8. Retail and Storage Space Lease:

Authorize to negotiate and execute a sixty-three (63) month lease, including renewal options, with DiNoko's Pizzeria and Zia, LLC, for retail and storage space in the Jerry Haaf Municipal Parking Facility.

**Action Taken: Adopted.**

9. 2nd Precinct Desk Remodeling Project:

Authorize to execute Amendment No. 1 to contract with Construction Results Corporation increasing the cost by \$35,595.48 for security improvements and minor changes.

**Action Taken: Adopted.**

10. Camera Surveillance System:

OP #7832, accept low bids of A+ Systems Group and Pro-Tech Design, Inc. to furnish and deliver a City Wide Camera System Surveillance System, for a total estimated annual expenditure of \$500,000 to be distributed between the two vendors.

**Action Taken: Adopted.**

11. Proprietary Database Contract:

Authorize to execute contract with MINPOINT, LLC, to:

a) Provide hosting services and a license to its proprietary database for two (2) years at a not-to-exceed value of \$50,000; and

b) Customize liability terms and conditions to reflect that in no event shall damages exceed the amount of monies paid under this contract for the year immediately preceding the date of any claim.

**Action Taken: Adopted.**

12. Labor Negotiations:

Passage of Resolutions (4) approving the following:

a) Tentative Agreement with the Minneapolis Foreman's Association;

b) Tentative Agreement with the Minneapolis City Supervisory Association;

c) Labor Agreement with Teamsters Local #320, Truck Drivers Unit; and

d) Tentative Agreement with the Minneapolis Convention Center Teamsters Local #320.

**Action Taken: Adopted.**

## Zoning & Planning

*Z&P agenda of [8/22/2013](#)*

1. Heritage Preservation Commission (HPC) Appointments:

Approve of the following HPC Council appointments:

a) Chris Hartnett, Ward 10, to expire December 31, 2016; and

b) Constance Vork, Ward 5, to expire December 31, 2014.

**Action Taken: Adopted.**

2. Wood From The Hood - 2620, 2644, and 2652 Minnehaha Avenue:

Passage of Ordinance amending the *Zoning Code* to rezone the properties located at 2620, 2644, and 2652 Minnehaha Avenue from I1 Light Industrial District to I2 Medium Industrial District to allow outdoor storage of lumber and wood products. (Wards 2, 9)

**Action Taken: Adopted.**

3. 1315 12th Avenue North:

Passage of Ordinance amending the *Zoning Code* to rezone the property located at 1315 12th Avenue North from R4 Multiple-family District to OR2 High Density Office Residence District to allow use of the existing building for offices, a child care center, and a development

achievement center. (Ward 5)

**Action Taken: Adopted.**

4. 2827 Williams Ave SE:

Passage of Ordinance amending the *Zoning Code* to rezone the property located at 2827 Williams Ave SE from R4 Multiple-family District to C2 Neighborhood Corridor Commercial District and PO Pedestrian Oriented Overlay District to allow for the expansion of an accessory parking lot. (Ward 2)

**Action Taken: Adopted.**

5. Minnesota Multi-purpose Stadium - 401 Chicago Ave; 701, 713, 719, and 811 3rd St S; 700, 716, and 728 4th St S; and 300 and 309 9th Ave S:

Approve recommendation of the Stadium Implementation Committee to construct the Minnesota Multi-purpose Stadium, a 1,500,000 square foot, 65,500 seat stadium, with expansion up to 73,000, for use by the Minnesota Vikings and other civic and community uses, and stadium related infrastructure, subject to conditions and mitigation measures along with the following additional recommendations: (Ward 7)

- a) Following completion of the improvements referenced in the action of the Stadium Implementation Committee, subsequent changes will be subject to the City's zoning ordinance and all applicable city regulations; and
- b) Condition to be added as 5G in the Implementation Committee action: Delegate final review and approval of the parking garage designs to the City of Minneapolis Community Planning and Economic Development Director and the Public Works Director.

**Action Taken: Adopted.**

## Motions

## Resolutions

## Unfinished Business

### 1. Ordinance Introduction:

Pursuant to notice on August 16, 2013, Schiff moves to introduce the subject matter of the following ordinances amending Title 20 of the Minneapolis Code of Ordinances relating to *Zoning Code*, for first reading and referral to the Zoning & Planning Committee (comprehensively reviewing and amending the Zoning Code for the purpose of improving customer service, implementing numerous technical changes and ensuring more effective alignment with policy objectives):

- a) Chapter 520 relating to Introductory Provisions.
- b) Chapter 521 relating to Zoning Districts and Maps Generally.
- c) Chapter 525 relating to Administration and Enforcement.
- d) Chapter 527 relating to Planning Unit Development.
- e) Chapter 529 relating to Interim Ordinances.
- f) Chapter 530 relating to Site Plan Review.
- g) Chapter 531 relating to Nonconforming Uses and Structures.
- h) Chapter 535 relating to Regulations of General Applicability.
- i) Chapter 536 relating to Specific Development Standards.

- j) Chapter 537 relating to Accessory Uses and Structures.
- k) Chapter 541 relating to Off-Street Parking and Loading.
- l) Chapter 543 relating to On-Premise Signs.
- m) Chapter 544 relating to Off-Premise Advertising Signs and Billboards.
- n) Chapter 546 relating to Residence Districts.
- o) Chapter 547 relating to Office Residence Districts.
- p) Chapter 548 relating to Commercial Districts.
- q) Chapter 549 relating to Downtown Districts.
- r) Chapter 550 relating to Industrial Districts.
- s) Chapter 551 relating to Overlay Districts.

**Action Taken: Adopted and Referred to Zoning & Planning Committee.**

2. Ordinance Introduction:

Pursuant to notice on August 16, 2013, Schiff moves to introduce the subject matter of an ordinance amending Title 22, Chapter 598 of the Minneapolis Code of Ordinances relating to *Land Subdivision: Land Subdivision Regulations*, for first reading and referral to the Zoning & Planning Committee (streamlining and simplifying subdivision and platting regulations).

**Action Taken: Adopted and Referred to Zoning & Planning Committee.**

3. Ordinance Introduction:

Pursuant to notice on August 16, 2013, Gordon moves to introduce the subject matter of an ordinance amending Title 17, Chapter 427 of the Minneapolis Code of Ordinances relating to *Streets and Sidewalks: In General*, for first reading and referral to the Transportation & Public Works Committee (legalizing the approved operation and use of community ovens within the right of way).

**Action Taken: Adopted and Referred to Transportation & Public Works Committee.**

4. Ordinance Introduction:

Pursuant to notice on August 16, 2013, Glidden moves to introduce the subject matter of an ordinance amending Title 2, Chapter 16 of the Minneapolis Code of Ordinances relating to *Administration: Finance*, for first reading and referral to the Ways & Means/Budget Committee (regarding financial institutions to disclose certain information).

**Action Taken: Adopted and Referred to Ways & Means/Budget Committee.**

5. Ordinance Introduction:

Pursuant to notice on August 16, 2013, Hofstede moves to introduce the subject matter of an ordinance amending Title 21 of the Minneapolis Code of Ordinances relating to *Interim Ordinances*, for first reading and referral to the Zoning & Planning Committee (adding a new Chapter 590 providing for a moratorium on development within the Dinkytown Area).

**No Action Taken; Motion Lost.**

## New Business

1. Notice of Intent:

Hofstede gives notice of intent to introduce at the next regular meeting of the City Council the subject matter of an ordinance amending Title 21 of the Minneapolis Code of Ordinances

relating to Interim Ordinances (adding a new Chapter 592 providing for a moratorium on development within the Nicollet Island-East Bank neighborhood).

**Notice Given.**

2. Notice of Intent:

Glidden gives notice of intent to introduce at the next regular meeting of the City Council the subject matter of an ordinance amending Title 13, Chapter 341 of the Minneapolis Code of Ordinances relating to *Licenses and Business Regulations: Taxicabs* (clarifying definitions and language related to taxicab rideshare companies).

**Notice Given.**

3. Mayoral Proclamation:  
Latino Heritage Month.

## Announcements

### Closed Session

Adjourn to Room 315, City Hall for the purpose of discussing the following matters:

a) Riverside Homes of Minneapolis Limited Partnership v. City of Minneapolis

**Action Taken: Approved Settlement.**

b) Mark Landstrom v. City of Minneapolis

**Action Taken: Approved Settlement.**

c) Darryl Gill v. Stewart, et al.

**Action Taken: Approved Settlement.**

d) Bobby Hayward Smith v. City of Minneapolis, et al.

**Action Taken: Approved Settlement.**

### Adjournment

**Notice:** A portion of this meeting may be closed to the public pursuant to Minnesota Statutes Section 13D.03 or 13D.05.

**Next Regular City Council Meeting: September 20, 2013**

**City Clerk email:** [councilcommitteecoordinators@minneapolismn.gov](mailto:councilcommitteecoordinators@minneapolismn.gov)

**Minneapolis Web Page:** [www.minneapolismn.gov](http://www.minneapolismn.gov)

**Attention:** If you need this material in an alternative format please call (612) 673-3737 or email [NCR@minneapolismn.gov](mailto:NCR@minneapolismn.gov). Deaf and hard-of-hearing persons may use a relay service to call 311 agents at (612) 673-3000. TTY users may call (612) 673-2157 or (612) 673-2626.

**Attention:** If you have any questions regarding this material please call 311 or (612) 673-2046.  
Hmong - Ceeb toom. Yog koj xav tau kev pab txhais cov xov no rau koj dawb, hu (612) 673-

2800; Spanish - Atención. Si desea recibir asistencia gratuita para traducir esta información, llama (612) 673-2700; Somali - Ogow. Haddii aad dooneyso in lagaa kaalmeeyo tarjamadda macluumaadkani oo lacag la'aan wac (612) 673-3500.

The City of Minneapolis invites and encourages participation by every resident to each program, service and event within our city. Should you require an accommodation in order for you to fully participate, or should you require this document in a different format, please let us know by contacting 311 or 612-673-3000, at least 5 days prior to the meeting.

Last updated Sep. 3, 2013



## **Zoning & Planning Committee Agenda**

Standing Committee of the City Council, Minneapolis, Minnesota

Regular Meeting

Thursday, August 22, 2013

9:30 a.m. - Room 317, City Hall

*NOTE: All cellular telephones and electronic devices to be switched to a non-audible function during Council and Committee meetings.*

Committee Members Present: Schiff, Tuthill, Goodman, Gordon, Reich

Committee Members Absent: Johnson

## **Consent**

*Referred by CPED*

### **1. Heritage Preservation Commission (HPC) Appointments:**

Approve the following HPC Council appointments:

- a) Chris Hartnett, Ward 10: 9/1/2013-12/31/2016; and
- b) Constance Vork, Ward 5: 9/1/2013-12/31/2014.

Staff Report: [HPC Appointments RCA](#)

### **Action Taken: Approved**

*Referred by Planning Commission (7/29/2013)*

[Planning Commission RCA](#); [Planning Commission MINS](#)

### **2. Wood From The Hood - 2620, 2644, and 2652 Minnehaha Avenue:**

Approve petition from BW Development LLC to rezone the properties located at 2620, 2644, and 2652 Minnehaha Avenue from I1 Light Industrial District to I2 Medium Industrial District. (Wards 2, 9)

Staff Reports: [Minnehaha Ave RPT](#)

### **Action Taken: Approved**

### **3. Residential Density Standards (Zoning Code Text Amendments):**

Approve ordinances amending Title 20 of the Minneapolis Code of Ordinances relating to *Zoning Code*, regarding residential density standards as follows:

- a) Chapter 527 relating to Planning Unit Development;
- b) Chapter 546 relating to Residence Districts;
- c) Chapter 547 relating to Office Residence Districts;
- d) Chapter 548 relating to Commercial Districts; and
- e) Chapter 551 relating to Overlay District.

Return Chapter 520 to the author.

Staff Report: [Text Amendments RPT](#); [Chapter 527 ORD](#); [Chapter 546 ORD](#); [Chapter 547 ORD](#); [Chapter 548 ORD](#); [Chapter 551 ORD](#)

### **Action Taken: Postponed two (2) cycles to the Tuesday, October 1, 2013, Z&P meeting.**

*Referred by Planning Commission 8/12/2013*

[Planning Commission RCA](#); [Planning Commission MINS](#)

### **4. 1315 12th Avenue North:**

Approve petition from Olu's Home, Inc., to rezone the property located at 1315 12th Avenue North from R4 Multiple-family District to OR2 High Density Office Residence District to allow

use of the existing building for offices, a child care center, and a development achievement center. (Ward 5)

Staff Reports: [1315 12th Ave N RPT](#)

**Action Taken: Approved**

**5. 2827 Williams Avenue Southeast:**

Approve petition from David Barnhart to rezone the property located at 2827 Williams Avenue Southeast from R4 Multiple-family District to C2 Neighborhood Corridor Commercial District and PO Pedestrian Oriented Overlay District to allow for the expansion of an accessory parking lot. (Ward 2)

Staff Reports: [2827 William Ave RPT](#)

**Action Taken: Approved**

**6. Minnesota Multi-purpose Stadium - 401 Chicago Avenue; 701, 713, 719, and 811 3rd Street South; 700, 716, and 728 4th Street South; and 300 and 309 9th Avenue South:**

Approve a recommendation of the Stadium Implementation Committee to construct the Minnesota Multi-purpose Stadium, a 1,500,000 square foot, 65,500 seat stadium, with expansion up to 73,000, for use by the Minnesota Vikings and other civic and community uses, and stadium related infrastructure, subject to conditions and mitigation measures along with the following additional recommendation: (Ward 7)

- a) Following completion of the improvements referenced in the action of the Stadium Implementation Committee, subsequent changes will be subject to the City's zoning ordinance and all applicable city regulations; and
- b) Condition to be added as 5G in the Implementation Committee action: Delegate final review and approval of the parking garage designs to the City of Minneapolis Community Planning and Economic Development Director and the Public Works Director.

Staff Report: [Stadium RPT](#)

**Action Taken: Approved**

*Referred by City Council (8/16/2013)*

**7. Assisted Living Facilities (Zoning Code Text Amendment):**

Subject matter of the following ordinances amending Title 20 of the Minneapolis Code of Ordinances relating to *Zoning Code* (broadening districts in which assisted living facilities may be located):

- a) Chapter 520 relating to Introductory Provisions; and
- b) Chapter 548 relating to Commercial Districts.

**Action Taken: Referred to CPED Staff**

## Public Hearing

*Appeal from the Zoning Board of Adjustment (7/11/2013)*

**8. 2924 Grand Avenue South:**

Appeal filed by Maze Properties, LLC, of the decision of the Zoning Board of Adjustment denying an application for a Certificate of Nonconforming Use to establish legal nonconforming rights to a three-unit, multiple-family residence in an existing structure located at 2924 Grand Avenue South in the R2B Two-family District. (Ward 6)

Staff Report: [2924 Grand Ave RCA](#); [2924 Grand Ave RPT](#); [2924 Grand MINS](#)

**Action Taken: Postponed two (2) cycles to the Tuesday, October 1, 2013, Z&P meeting.**



## Postponed Items

*Appeal from the Zoning Board of Adjustment (6/6/2013)*

### **9. Megabus USA, LLC - 247 Chicago Avenue South:**

*Postponed from the July 11 Z&P meeting*

Appeal filed by 903 Washington Partners, LLC, from the decision of the Board of Adjustment granting an appeal of the Zoning Administrator's determination that bus passenger loading and unloading at the property is classified as a Bus Turnaround under the Minneapolis Code of Ordinances, thus requiring a Conditional Use Permit. (Ward 7)

Staff Reports: [Megabus RCA](#); [Megabus RPT](#); [Megabus MINS](#); [Megabus Reasons for Appeal](#); [Megabus Appeal Documents](#)

**Action Taken: Postponed one (1) cycle to the Thursday, September 12, 2013, Z&P meeting.**

*Notice: A portion of this meeting may be closed to the public pursuant to Minnesota Statutes Section 13D.03 or 13D.05*

*Committee actions will be referred to the next Council meeting: Friday, August 30, 2013*

*The next regular Zoning & Planning Committee Meeting is scheduled for Thursday, September 12, 2013*

*Attention: If you need this material in an alternative format, please call (612) 673-3737 or email*

*[NCR@minneapolismn.gov](mailto:NCR@minneapolismn.gov). Deaf and hard-of-hearing persons may use a relay service to call 311 agents at (612) 673-3000. TTY users may call (612) 673-2157 or (612) 673-2626.*

*Attention: If you have any questions regarding this material, please call 311 or (612) 673-2046. Hmong – Ceeb toom. Yog koj xav tau kev pab txhais cov xov no rau koy dawb, hu 612.673.2800; Spanish – Atención. Si desea recibir asistencia gratuita para traducir esta información, llame 612.673.2700; Somali – Ogow. Haddii aad dooneyso in lagaa kaalmeeyo tarjamadda macluumaadkani oo lacag la' aan wac 612.673.3500.*

*The City of Minneapolis invites and encourages participation by every resident to each program, service and event within our city. Should you require an accommodation in order for you to fully participate, or should you require this document in a different format, please let us know by contacting 311 or (612) 673-3000 at least 5 days prior to the meeting.*

Last updated Aug. 22, 2013

**Community Planning and Economic Development**

250 South Fourth Street, Room 300

Minneapolis, MN 55415-1385

(612) 673-2639 Phone

(612) 673-2526 Fax

(612) 673-2157 TDD

**Public Works Department**

350 South Fifth Street, Room 203

Minneapolis, MN 55415-1385

(612) 673-2352 Phone

(612) 673-2410 Fax

(612) 673-3565 TDD

---

**MEMORANDUM**

---

**DATE:** August 12, 2013

**TO:** City Planning Commission

**FROM:** Hilary Dvorak, Principal Planner  
Jeff Handeland, Principal Professional Engineer  
Brendon Slotterback, Sustainability Program Coordinator

**SUBJECT:** Minnesota Multi-Purpose Stadium – Design Plans

---

On May 14, 2012, Governor Dayton signed legislation related to the construction of a National Football League stadium in Minnesota. The legislation tasked the City of Minneapolis with establishing a Stadium Implementation Committee, which is charged with making recommendations on the design plans submitted for the stadium, stadium infrastructure and related improvements.

The legislation defines the stadium site as “all or portions of the current site of the existing football stadium and adjacent areas, bounded generally by Park and Eleventh Avenues and Third and Sixth Streets in the City of Minneapolis, the definitive boundaries of which shall be determined by the authority and agreed to by the NFL team.” The stadium project includes construction of the stadium and stadium infrastructure. Stadium infrastructure is defined in the legislation as “plazas, parking structures, rights of way, connectors, skyways and tunnels, and other such property, facilities, and improvements, owned by the authority or determined by the authority to facilitate the use and development of the stadium”.

On June 15, 2012, the Minneapolis City Council appointed the City of Minneapolis representatives to the Stadium Implementation Committee and on June 29, 2012, appointed the remaining representatives. On August 6, 2012, the Stadium Implementation Committee held its first meeting. On November 27, 2012, the Stadium Implementation Committee adopted a Stadium Implementation Committee vision and principles for purposes of establishing parameters for its review.

The Stadium Implementation Committee has forwarded a recommendation (attached) to the City of Minneapolis to approve a request by the Minnesota Sports Facilities Authority to construct the Minnesota Multi-Purpose Stadium, a 1,500,000 square foot, 65,500 seat stadium, with expansion up to 73,000, for use by the Minnesota Vikings and other civic and community uses, and stadium related infrastructure, subject to conditions and mitigation measures, on property currently occupied by the

Minnesota Multi-Purpose Stadium – Design Plans

existing football stadium and adjacent areas, bounded generally by Park and Eleventh Avenues and Third and Sixth Streets.

The Stadium Implementation Committee's recommendation is to be forwarded to the Minneapolis Planning Commission for an advisory recommendation and then to the City Council for final action in a single resolution. As mandated by Minn. Stat. 473J.17 subd. 6, "construction of a stadium within the development area is consistent with the adopted area plan, is the preferred stadium location, and is a permitted land use." Further, the City Council "shall not impose any unreasonable conditions on the recommendations of the implementation committee, nor take any action or impose any conditions that will result in delay from the time frames established in the planning and construction timetable or in additional overall costs." Failure of the City Council to act on the recommendation of the Stadium Implementation Committee within 45 days of the submission of the recommendation to the City Planning Commission is deemed to be approved.

At its meeting of July 25, 2013, the Stadium Implementation Committee acted to forward a recommendation to the City of Minneapolis.

*Project Description*

The primary exterior materials of the building include glass and metal. The primary metal on the building is a 1-foot tall by 12-foot wide zinc panel which will be staggered when installed. In addition, there is a stainless steel ribbon that wraps around the building. The northern half of the roof will be made out of PVC and the southern half of the roof will be made out of Ethylene tetrafluoroethylene (ETFE), which is a fluorine based plastic. The ETFE will be installed using a three-layer system. Frit will be applied to one or more of the ETFE layers which will help reduce the amount of ultraviolet rays entering the building.

The west side of the building has been designed to be the true front of the structure. Five, 95-foot tall pivoting doors line the southerly half of this façade which can be opened 180 degrees during events. When you enter these doors you walk directly into the main concourse level. Also, along the west side of the building is the large prow that rises approximately 272 feet above grade. The majority of this side of the building is glass. Between Chicago Avenue and the building is a 2 acre plaza. On average, the dimensions of the plaza are 198 feet deep and 425 feet wide. At this time, the plaza is proposed to be made out of gray concrete with a decorative scoring pattern that will be applied during construction. The scoring should be compatible with accessibility considerations. No other details about the plaza design, such as pervious materials, lighting, seating, trash receptacles, etc. have been provided. There is a large area of trees located on both the north and south ends of the plaza. Combined, the two areas of trees total 40,000 square feet. The edges of both tree areas are flanked with deep stairs that rise between one foot and 10 feet depending on the site grades. The trees have been arranged so people can walk between them and an appropriate surfacing material will be used in these areas for accessibility purposes.

The north and south sides of the building have entrances that allow one to access the main concourse level and the lower club level of the building. On the north side of the building, the lower club level is accessed from 4<sup>th</sup> Street South. On the south side of the building the lower club level is accessed from 6<sup>th</sup> Street South. Lower club level is approximately 16 feet lower than the main concourse level. There are staircases and ramps on both sides of the building that allow movement between the two levels on the

Minnesota Multi-Purpose Stadium – Design Plans

exterior of the building. While these two sides of the building have large expanses of metal on them there is an abundance of glass, especially at street level.

The east side of the building is the least transparent. There is a 108-foot wide glass entrance that provides access to the main concourse level of the building. This expanse of glass tapers to 16 feet towards the top of the building. The remainder of this side of the building is metal. Given the grade change on the site, the main concourse level of the building is situated 16 feet above 11<sup>th</sup> Avenue South. A series of steps and a switchback ramp have been designed to provide access to the entrance. At street level there are entrances leading into the building for the players, media and for service purposes.

On the southeast corner of the site there is a 190-space surface parking lot. On Vikings game days the parking lot will be utilized by players and coaching staff. The parking lot will be enclosed with a fence and the driveways leading into it will be gated. Between the parking lot and the east property line there will also be an off-street loading zone. The loading zone will be accessed off of 11<sup>th</sup> Avenue South. On Vikings game days the loading zone will also be utilized by media trucks. Landscaping is proposed along the south and east sides of the parking lot and loading bay for screening purposes. There is also a 30-inch high wall located on these two sides of the parking lot. The wall provides screening for the parking lot and also serves as a security barrier.

*Stadium Related Infrastructure*

Plaza

At this time, the plaza is proposed to be made out of gray concrete with a decorative scoring pattern that will be applied during construction. The scoring should be compatible with accessibility considerations. No other details about the plaza design, such as pervious materials, lighting, seating, trash receptacles, etc. have been provided. The recommendation from the Stadium Implementation Committee related to the plaza states that the detailed plaza design incorporate a pervious paving system, a summer shade system, lighting, seating, trash receptacles, etc. and be coordinated with City of Minneapolis staff.

Parking garages and skyways

Two new parking garages are proposed on the north side of the stadium site. The parking garages would be connected to the stadium via a series of skyways. The design of the parking garages is still being discussed. While the stadium and related stadium infrastructure are not subject to the zoning code regulations, there was concern that without any standards in place to help influence the design of the parking structures that they will be visually unappealing. The recommendation from the Stadium Implementation Committee related to the parking garages states that the stadium design team continue to work with the City of Minneapolis staff to meet the design standards of the zoning code related to building design and parking garages with the exception that the parking garages be allowed to be constructed above ground.

Skyways are proposed to connect the two new parking garages on the north side of the stadium site and an existing parking garage on the south side of the stadium site. The design of the skyways is still being discussed. The recommendation from the Stadium Implementation Committee related to the skyways states that the design and operation of skyways be consistent with the *Minneapolis Skyway System*

Minnesota Multi-Purpose Stadium – Design Plans

*Standards and Procedures Manual*, which was approved by the Downtown Council’s Skyway Advisory Committee in 2006.

In addition, the Stadium Implementation Committee recommended that the design of the parking garages and skyways be compatible with the design of the stadium and the surrounding environment.

6<sup>th</sup> Street

The vacation of 5<sup>th</sup> Street, between 11<sup>th</sup> Avenue and Chicago Avenue, requires that the existing 6<sup>th</sup> Street be redesigned. The existing Jersey barrier between 5<sup>th</sup> Street and 6<sup>th</sup> Street will be removed, which will allow pedestrians to access the stadium more readily from the south. Proper intersection control along 6<sup>th</sup> Street will be important once the Jersey barrier has been removed. The recommendation from the Stadium Implementation Committee related to the design of 6<sup>th</sup> Street states the conceptual roadway changes to 6<sup>th</sup> Street between Park Avenue and 11<sup>th</sup> Avenue, should include the west-bound automobile lane and off-street bicycle path as shown in Exhibit E be approved. In addition, the Stadium Implementation Committee recommended that a full signal system should be installed at the intersections of 6<sup>th</sup> Street and both 9<sup>th</sup> Avenue (Carew Drive) and 10<sup>th</sup> Avenue.

Downtown East Light Rail Transit Station

The Downtown East Light Rail Transit Station is located directly across Chicago Avenue from the 2 acre plaza and the main entrance into the stadium. No changes are being proposed to the station as part of the stadium design. It has been identified in the Draft Environmental Impact Statement (DEIS) that the amount of queuing space at the LRT station during events is inadequate now and that event transit ridership will continue to increase, as additional LRT lines become operational. Therefore, the LRT station will be even more inadequate to accommodate queuing and loading of event LRT riders in the future. For these reasons it will be important to modify the LRT station area to accommodate these large increases in LRT ridership. The stadium design team must address connections from the stadium to the LRT station in order to provide safe and orderly passage to accommodate event day crowds. The recommendation from the Stadium Implementation Committee related to the Downtown East Light Rail Transit Station states that an adequate design of the station needs to be coordinated with the City of Minneapolis Public Works Director and the Director of Metro Transit.

***Environmental Impact Statement***

The project triggered a state mandated EIS. The Minnesota Sports Facilities Authority was authorized by statute as the Responsible Government Unit. The final EIS is currently being reviewed. While the EIS addressed a wide variety of potential environmental consequences, issues related to transportation and parking were analyzed most extensively. The ballpark site offers excellent opportunities for fans to arrive by multiple modes. The final EIS identifies a range of potential mitigation measures and notes that a Traffic Management Plan (TMP) will be developed by representatives from a range of stakeholders, including the Minnesota Sports Facilities Authority, the City of Minneapolis, Hennepin County, Metro Transit, local business groups and nearby residents.

Minnesota Multi-Purpose Stadium – Design Plans

*Changes to Approved Plans*

Given that the stadium legislation did not address a procedure for reviewing changes to the project following the Stadium Implementation Committee recommendation, the Stadium Implementation Committee adopted an alternative process allowing the City of Minneapolis Community Planning and Economic Development Director and Public Works Director to determine whether changes are substantive enough to require the committee to reconvene. The solution does not address the issue of changes to the plans following completion of the stadium. Staff recommends that it be made clear that such future changes (e.g., additions to the facility) will be subject to applicable City regulations.

**RECOMMENDATION**

The Community Planning and Economic Development Department and Public Works Department recommend that the City Planning Commission forward a recommendation to the City Council to **approve** the recommendation of the Stadium Implementation Committee, with the following additional recommendations:

1. Following completion of the improvements referenced in the action of the Stadium Implementation Committee, subsequent changes will be subject to the City's zoning ordinance and all applicable City regulations.



**Minnesota Multi-Purpose Stadium Implementation Committee Action**

**FINAL**

**August 25, 2013**

**Background**

On May 14, 2012, Governor Dayton signed legislation related to the construction of a National Football League stadium in Minnesota. The legislation tasked the City of Minneapolis with establishing a Stadium Implementation Committee who was charged to make recommendations on the design plans submitted for the stadium, stadium infrastructure and related improvements. The Stadium Implementation Committee's recommendation is to be forwarded to the Minneapolis Planning Commission for an advisory recommendation and then to the City Council for final action in a single resolution. The review process established in the legislation supersedes Minnesota Statutes section 15.99.

The legislation defines the stadium site as "all or portions of the current site of the existing football stadium and adjacent areas, bounded generally by Park and Eleventh Avenues and Third and Sixth Streets in the City of Minneapolis, the definitive boundaries of which shall be determined by the authority and agreed to by the NFL team".

The stadium project includes construction of the stadium and stadium infrastructure. Stadium infrastructure is defined in the legislation as "plazas, parking structures, rights of way, connectors, skyways and tunnels, and other such property, facilities, and improvements, owned by the authority or determined by the authority to facilitate the use and development of the stadium".

On June 15, 2012, the Minneapolis City Council appointed the City of Minneapolis representatives to the Stadium Implementation Committee and on June 29, 2012, appointed the remaining representatives.

On August 6, 2012, the Stadium Implementation Committee held its first meeting. At this meeting an overview of the stadium legislation and policies was provided, a presentation of the stadium site and planning area was given, the purpose of the Metropolitan Stadium Facilities Authority (MSFA) was explained, and the Stadium Implementation Committee objectives and deliverables was discussed. At this meeting it was also decided that three sub-committees would be formed: the Design Subcommittee, the Planning Subcommittee and the Stakeholder Subcommittee.

On November 27, 2012, the Stadium Implementation Committee adopted a Stadium Implementation Committee vision and principles for purposes of establishing parameters for its review. The adopted vision for the Stadium Implementation Committee is "*The best urban football stadium in the county at the core of a vibrant place*". A total of 73 principles were adopted ranging from building design to regional influence.

DESIGN PRINCIPLES

**A. Building Design**

- A.1 Be bold, iconic, sophisticated, and cosmopolitan.

*Comments: The building is bold, iconic, sophisticated and cosmopolitan. The building is geometric in shape and has a large prow that rises approximately 272 feet on the west side of the structure. The prow is a defining element of the building.*

- A.2 Design the building exterior using climate-appropriate and local materials that reflect and incorporate the strength of Minnesota's natural resources.

*Comments: The primary exterior materials of the building include glass and metal. The primary metal on the building is a 1-foot tall by 12-foot wide zinc panel which will be staggered when installed. In addition, there is a stainless steel ribbon that wraps around the building. The northern half of the roof will be made out of PVC and the southern half of the roof will be made out of Ethylene tetrafluoroethylene (ETFE), which is a fluorine based plastic. The ETFE will be installed using a three-layer system. Frit will be applied to one or more of the ETFE layers which will help reduce the amount of ultraviolet rays entering the building. While the sourcing of the materials is unknown they are climate appropriate for Minnesota.*

- A.3 Every view of the stadium is important in an urban environment – emphasize all sides by incorporating public entrances into all facades of the building, using similar materials and architectural continuity around the entire perimeter, and hiding loading areas and parking.

*Comments: Each side of the building is impressive. The building is geometric in shape and the way that the glass and metal have been applied on each side of the structure emphasizes the various angles.*

*The west side of the building has been designed to be the true front of the structure. Five, 95-foot tall pivoting doors line the southerly half of this façade which can be opened 180 degrees during events. When you enter these doors you walk directly into the main concourse level. Also, along the west side of the building is the large prow that rises approximately 272 feet above grade. The majority of this side of the building is glass.*

*There are entrances on both the north and south sides of the building. Both of these sides of the building have entrances that allow one to access the main concourse level and the lower club level of the building. On the north side of the building the lower club level is accessed from 4<sup>th</sup> Street South and on the south side of the building the lower club level is accessed from 6<sup>th</sup> Street South. Lower club level is approximately 16 feet lower than the main concourse level. There are staircases and ramps on both sides of the building that allow movement between the two levels on the exterior of the building. While these two sides of the building have large expanses of metal on them there is an abundance of glass especially at street level.*



*The east side of the building is the least transparent. There is a 108-foot wide glass entrance that provides access to the main concourse level of the building. This expanse of glass tapers to 16 feet towards the top of the building. The remainder of this side of the building is metal. Given the grade change on the site the main concourse level of the building is situated 16 feet above 11<sup>th</sup> Avenue South. A series of steps and a switchback ramp have been designed to provide access to the entrance. At street level there are entrances leading into the building but they are for the players, media and for service purposes.*

*On the southeast corner of the site there is a 190-space surface parking lot. On Vikings game days the parking lot will be utilized by players and coaching staff. The parking lot will be enclosed with a fence and the driveways leading into it will be gated. The type of fence has not yet been decided. Between the parking lot and the east property line there will also be an off-street loading zone. The loading zone will be accessed off of 11<sup>th</sup> Avenue South. On Vikings game days the loading zone will also be utilized by media trucks.*

*Landscaping is proposed along the south and east sides of the parking lot and loading bay for screening purposes. There is also a 30-inch high wall located on these two sides of the parking lot. The wall provides screening for the parking lot but it also serves as a security barrier. Along the south side of the parking lot there will be a 10-foot wide landscaped area with a row of 20 Prairie Dream Paper Birch trees planted in it. This particular species of tree has the potential to grow to a height of 60 feet with a spread of 35 feet. The tree has a low canopy with a typical clearance of 3 feet. Along the east side of the parking lot and loading bay there will be 2, 6-foot wide landscaped areas with a total of 17 Bur Oak trees planted in them. This particular species of tree has the potential to grow to a height of 80 feet with a spread of 80 feet. The tree has a high canopy with a typical clearance of 8 feet. Underneath the tree canopy hundreds of Panicum virgatum (Switch grass) will be planted to screen the parking lot and loading bay from the public realm. Switch grass has the potential to grow to a height of 5 feet with a spread of 3 feet. This landscaped area is located in the right-of-way. Trees are also proposed to be located in the interior of the parking lot. Some of the trees are located in tree islands while others have been located within tree grates. To encourage the longevity of the proposed trees within the parking lot it is recommended that all trees be located within tree islands that have a minimum dimension of 7 feet in every direction.*

*Best practices should be used for tree plantings throughout the site to ensure maximum growth.*

- A.4 Design a porous exterior that incorporates windows and retractable features to help break up the façade and allow views into and out of the building at all levels.

*Comments: There are large expanses of glass on all four sides of the building. Where there isn't glass on the facades the primary material will be zinc. Scattered irregularly throughout the zinc areas are 1-foot tall by 12-foot wide windows that will be located behind a perforated zinc panel. On the west façade there will be 5, 95-foot tall pivoting doors which can be opened 180 degrees during events.*

*The design must comply with Minnesota Audubon guidelines for creating a bird safe structure. Forty percent of all North American waterfowl use the Mississippi River as a*

*navigational aid so this is an important consideration in the selection of glazing reflectivity and transparency. In addition, site lighting and exterior building illumination must comply with Minnesota Audubon guidelines for creating a bird safe environment and not contribute to increasing light pollution of the nighttime sky.*

- A.5 Design the stadium so its primary facade faces downtown and the plaza, and use landscape materials to soften the edge of the stadium and to help break up long expanses of wall.

*Comments: The west side of the building has been designed to be the true front of the structure. The west side of the building faces downtown and the 2 acre on-site plaza. The site has been designed with green space all around the perimeter of the building with the exception of the on-site plaza, which is all hardscaped. The landscape materials that have been selected include turf grass, native grasses and 6 species of canopy trees.*

- A.6 Incorporate sports, fitness, recreation, and other commercial uses such as meeting rooms, restaurants, cafés, and a team store, that can all be accessed and viewed from the surrounding streets and plaza and that will be used by nearby neighbors and residents every day of the year, day and night, including during the winter months.

*Comments: The commercial uses that have been planned for and shown on the plans include a team store and a restaurant. The team store and restaurant will be located on the west side of the building facing the on-site plaza. There are other rooms within the stadium that can be used for meetings, community events, etc. The team store and the restaurant can be accessed from both the exterior and interior of the building. The store will be open to the public on non-Vikings game days.*

*A truly urban site design should accommodate additional on-site uses that benefit the wider community. The stadium design team is strongly encouraged to include additional on-site uses that benefit the wider community such as a daycare, recreational uses, etc. These uses should be visually connected to the street and accessible directly from the building's exterior, with additional internal connections as needed by the stadium.*

- A.7 Design the stadium so that the locations of entries, facades, commercial uses, and other major exterior features reflect the existing context surrounding the stadium including street grid, traffic patterns, pedestrian and bicycle routes, and future plans for the neighborhood.

*Comments: The City of Minneapolis has concerns with the number and location of curb cuts and drop off bays on all four sides of the site. Each curb cut adds conflict points for potential vehicle and pedestrian accidents. In the interest of public safety, the number of curb cuts should be minimized. These concerns need to be discussed in more detail with City of Minneapolis staff.*

*The location and design of the skyways connecting the building to either existing or proposed parking structures is still being discussed. Skyways should have direct connections to the public streets which are visible and easily accessible from the public sidewalks. The design and operation of skyways should be consistent with the Minneapolis Skyway System Standards and Procedures Manual, which was approved by the Downtown Council's Skyway Advisory Committee in 2006.*

*A skyway over Chicago Avenue could impede views looking north of significant structures and landscapes in the St. Anthony Falls Historic District, including the Pillsbury A Mill on the east bank, and the Mississippi River if not designed with this consideration in mind. Design considerations should include height in relation to the street and transparency.*

- A.8 Integrate convenient and generous bicycle amenities within the stadium itself, in the plaza, and throughout the site and coordinate the location of these amenities with stadium entrances, streets, and the bicycle route system in the area.

*Comments: There will be 300 bicycle parking spaces located on the site. The bicycle parking spaces are located on the southwest, northwest and northeast sides of the site. Given the City's bicycle path system and the location of the entrances to the building the placement of the bicycle parking is adequate.*

*The site should embrace bicycle traffic and act as a connector to bicycle lanes on surrounding streets and the Hiawatha Trail. This will add vitality to the site at all times of the day and night.*

*The stadium design team should work with Nice Ride Minnesota to accommodate a large bike rental kiosk on the stadium site.*

## **B. The Place**

### **Site Design**

- B.1 Site the building so that no street closures are required, to allow for the reopening of closed streets where practical, and to allow for the creation and strengthening of pedestrian connections to Elliot Park, Cedar-Riverside and Downtown East.

*Comments: The vacation of 5<sup>th</sup> Street, between 11<sup>th</sup> Avenue South and Chicago Avenue, is recognized by the City of Minneapolis as a key to the stadium design. The existing Jersey barrier between 5<sup>th</sup> Street and 6<sup>th</sup> Street will be removed which will allow pedestrians to access the stadium more readily from the south. No streets are being reopened as part of the stadium development.*

*There are entrances leading into the stadium on all four sides of the structure. During major events every entrance will be open. However, the west side of the building has been designed to be the true front of the structure which is where the 5, 95-foot tall pivoting doors are located. The on-site plaza is also located on the west side of the site. It is anticipated that the majority of those attending an event at the stadium will enter from the west.*

*Accessing the stadium from the intersection of 4<sup>th</sup> Street and Chicago Avenue is a concern of the City of Minneapolis because of the frequency of trains arriving and departing from the Downtown East Light Rail Transit Station and the conflict that arises with the large number of stadium-event pedestrians crossing through the intersection. Improvements need to be incorporated into the design to reduce the size of the crowds and to safely accommodate and control the remaining significant crowds of pedestrians crossing through this intersection.*

*Features which could reduce the size of the crowds should include skyway or tunnel connections which are designed such that they will be the preferred route for the maximum number of pedestrians feasible. Design considerations should include ample route width, ample vertical circulation, visual cues which promote the route, and wayfinding signage.*

*There are a number of uncontrolled intersections that will be created along 6<sup>th</sup> Street once the Jersey barrier has been removed. Connections to the Elliot Park neighborhood rely on safe and convenient crossing of 6<sup>th</sup> Street. Improvements need to be made to the site design in order to safely accommodate the number of people entering and exiting the stadium on game days as well as those using the site throughout the year. A full signal system should be installed at the intersections of 6<sup>th</sup> Street and both 9<sup>th</sup> Avenue (Carew Drive) and 10<sup>th</sup> Avenue.*

*There will be public sidewalks on all four sides of the stadium site. The public sidewalks should be of an appropriate width and should be separated from traffic by streetscape elements to protect pedestrians from activity in the street. Minimum pedestrian zones adjacent to public roadways in downtown Minneapolis should generally be 15 to 20 feet (recommended) to include adequate space for a zone for landscaping, signage, light poles, clearances, snow banks, etc. These concerns need to be discussed in more detail with City of Minneapolis staff.*

- B.2 Create dramatic approaches, vistas, and archways that take advantage of existing and create new view corridors of the stadium site.

*Comments: The building is geometric in shape and has a large prow that rises approximately 272 feet on the west side of the structure. The prow is a defining element of the building. The unique shape of the building provides for interesting views from every approach. In particular, the view looking east on both 4<sup>th</sup> Street and 5<sup>th</sup> Street will be dramatic given the stadium design and large on-site plaza and the view looking west from the Cedar Riverside neighborhood will be dramatic given the change in grade and the large staircase leading to the wide glass entrance.*

*As noted above, the location and design of the skyways connecting the building to either existing or proposed parking structures is still being discussed. All skyways should be designed to be as transparent as possible in order to minimize the blocking of views of the stadium. In addition, any proposed structure on the east side of Chicago Avenue north of 4<sup>th</sup> Street should adhere to setbacks as outlined in the Update to the Historic Mills District Master Plan. The goals for this setback are to better pull the river into Downtown, highlight Chicago Avenue as a major pedestrian spine, and preserve views of the historic Pillsbury A-Mill and the Guthrie Theater.*

- B.3 Allow visitors coming from all directions to walk around the entire circumference of the facility on their way from one place to another without being impeded.

*Comments: One can walk around the entire facility using the on-site walkways which incorporate longitudinal slopes of up to five percent in some locations and which include a staircase alternative at three locations. The stadium site should be a connector through the*

*neighborhood, not merely an end point. Access to the on-site walking path should be made at as many locations as possible from the neighborhood, including all major intersections.*

*There will be public sidewalks on all four sides of the stadium site. The public sidewalk on 4<sup>th</sup> Street has been designed to end at the loading dock entrance in the northeast corner of the site. Building a sidewalk that ends brings pedestrians out of their way. The public sidewalk on 4<sup>th</sup> Street should connect to the on-site walkway which will lead pedestrians to 11<sup>th</sup> Avenue. If an exterior walkway to the loading dock is needed for stadium maintenance purposes, it should be designed so the general public knows that the sidewalk ends at a private walkway.*

- B.4 Be friendly and inviting for all by ensuring access and easy movement for people of all abilities and by all modes of transport.

*Comments: The building has been designed with entrances on all four sides of the building. Each entrance is ADA accessible. In addition, the walking path around the facility is ADA accessible too. The on-site plaza details are still being worked out. To ensure that the plaza is ADA accessible design considerations including site grades, location and configuration of stairways and walkway widths and alignments should be coordinated with the City of Minneapolis before detailed designs are finalized.*

*The stadium has also been designed to be accessible from all modes of traffic. The Downtown East Light Rail Transit Station is located directly across Chicago Avenue from the main entrance into the stadium, there are bicycle parking spaces located on the southwest, northwest and northeast sides of the site, public sidewalks connect to the on-site walkways leading directly to the building entrances and new skyways will connect new and existing structured parking ramps to the stadium.*

- B.5 Create direct and seamless connections to the Downtown East LRT Station from the stadium structure.

*Comments: One can walk directly from the stadium to the Downtown East Light Rail Transit Station. With this said it has been identified in the Draft Environmental Impact Statement (DEIS) that the amount of queuing space at the LRT station during events is inadequate now and that event transit ridership will continue to increase, as additional LRT lines become operational. Therefore, the LRT station will be even more inadequate to accommodate queuing and loading of event LRT riders in the future. For these reasons it will be important to modify the LRT station area to accommodate these large increases in LRT ridership. The stadium design team must address connections from the stadium to the LRT station in order to provide safe and orderly passage to accommodate event day crowds. An adequate design needs to be coordinated with City of Minneapolis staff and Metro Transit staff.*

#### **Plaza Design**

- B.6 Create a bold, iconic, urban plaza and world-class outdoor destination that stands up to and complements the stadium design.

*Comments: The plaza located on the stadium site is 2 acres in size which complements the size of the stadium building. On average, the dimensions of the plaza are 198 feet deep and 425 feet wide. The prow on the west side of the building is approximately 272 feet high. The plaza is located on the west side of the building which has been designed to be the true front of the structure. The 5, 95-foot tall pivoting doors line the southerly half of the west façade which can be opened 180 degrees during events. When these doors are open the plaza becomes an extension of the building's interior. The shape of the plaza is geometric which also complements the building.*

*At this time, the plaza is proposed to be made out of gray concrete with a decorative scoring pattern that will be applied during construction. The scoring should be compatible with accessibility considerations. No other details about the plaza design, such as pervious materials, lighting, seating, trash receptacles, etc. have been provided.*

*There is a large area of trees located on both the north and south ends of the plaza. Combined, the two areas of trees total 40,000 square feet. The edges of both tree areas are flanked with deep stairs that rise between one foot and 10 feet depending on the site grades. The trees have been arranged so people can walk between them and an appropriate surfacing material will be used in these areas for accessibility purposes.*

- B.7 Make the plaza a cherished community destination that is flexible, multi-functional and beautiful to look at, walk by, and pass through every day, day and night, year round, and through the winter, even when it is not in use.

*Comments: The size of the plaza allows it to be flexible and multi-functional. Although the plaza has not yet been fully designed a 2 acre area of gray concrete that is void of any other features will not be beautiful to look at, walk by or pass through on days when there is not an event occurring at the stadium. A detailed plaza design that incorporates a pervious paving system, a summer shade system, lighting, seating, trash receptacles, etc. needs to be coordinated with City of Minneapolis staff. Additionally, more information is needed on how the design will create an actively used environment.*

- B.8 Implement a landscape design that is lush and green to attract people to the plaza from the neighborhoods to the north, south, and east, the downtown core to the west, and the Mississippi River.

*Comments: There is landscaping located on each side of the stadium site so as one looks towards the stadium from any direction they will see greenery. The landscape materials that have been selected to be used throughout the stadium site include turf grass, native grasses and 6 species of canopy trees.*

- B.9 Make the plaza a safe place by using principles of crime prevention through environmental design. Incorporate physical features designed for people and activities that maximize visibility and natural surveillance to foster positive social interactions.

*Comments: Crime Prevention Through Environmental Design (CPTED) has been considered at a high level but more information is needed to confirm that the site details are designed with safety in mind. The plaza has been located adjacent to the main doors of the*



*stadium. The majority of the west wall of the stadium is glass. The ticket office, team store, a restaurant and stadium offices are located on the west side of the building. All on-site walkways lead to the plaza. Triumph Elm trees are proposed to be located on each end of the plaza which have the potential to grow to a height of 60 feet with a spread of 40 feet and has a high canopy with a typical clearance of 8 feet. More details are needed about lighting and other CPTED considerations.*

- B.10 Use daylight and sun angles to inform the design and minimize shade and shadow in the plaza and on features and at the entrances, particularly in the winter months.

*Comments: The plaza is located on the west side of the stadium. Throughout the year the building itself will shadow the plaza during the morning hours. However, until development occurs on adjacent blocks to the west the plaza will not be shaded or in shadow for the remainder of the day.*

- B.11 Prioritize quality over quantity in the sizing, design, and materials selection for the plaza.

*Comments: At this time, the plaza is proposed to be made out of gray concrete with a decorative scoring pattern that will be applied during construction. No other details about the plaza design, such as a pervious paving system, a summer shade system, lighting, seating, trash receptacles, etc. have been provided.*

- B.12 Plan the site, plaza, and related design features to reflect the existing context, street grid, the needs of pedestrians, and future plans for the neighborhood and the city.

*Comments: The plaza is located between Chicago Avenue – a significant pedestrian corridor - and the stadium. The depth of the plaza along Chicago Avenue will help to preserve a significant view shed toward the Mississippi River and prominent buildings in the St. Anthony Falls Historic District.*

- B.13 Design the plaza as a 21st Century urban landscape with an ecological ethic rooted in natural and cultural processes that integrate storm water management, native plants and regional materials.

*Comments: The stadium project will be required to meet Chapter 54 City requirements for stormwater. Based on the plans submitted, which include the plaza, the stadium will likely meet the City requirements for stormwater management. Additional investigation is being done to see what other stormwater management practices could be incorporated into the site.*

- B.14 Use high-quality materials - ranging from paving and trees to lights and street furniture– to create a memorable urban experience.

*Comments: At this time, the plaza is proposed to be made out of gray concrete with a decorative scoring pattern that will be applied during construction. No other details about the plaza design, such as a pervious paving system, a summer shade system, lighting, seating, trash receptacles, etc. have been provided. A variety of seating options will be particularly important if the plaza is to be usable on non-game days by residents, visitors, and nearby employees.*

- B.15 Include a generous tree canopy to provide shade, wind protection, and reduce heat- island effects.

*Comments: There is a large area of trees located on both the north and south ends of the 2 acre plaza that is on the stadium site. The Triumph Elm tree is proposed to be planted in these two areas. This particular species has the potential to grow to a height of 60 feet with a canopy spread of 40 feet. When the trees have grown to a substantial size they will help to provide shade, wind protection and reduce heat island effects. Given the size of the plaza and the placement of the trees the majority of the plaza will be in full sun for the majority of the day.*

- B.16 Integrate family-friendly features for use on game days and for neighbors year round.

*Comments: At this time, the plaza is proposed to be made out of gray concrete with a decorative scoring pattern that will be applied during construction. No other details about the plaza design, such as a pervious paving system, a summer shade system, lighting, seating, water features, trash receptacles, etc. have been provided.*

- B.17 Integrate public art into the infrastructure of the plaza space.

*Comments: It appears from the plans that there is a place holder for a piece of public art in the plaza that is located on the stadium site. No details other than noting the placeholder have been provided. A public art process should occur as early in the design as possible in order to integrate public art into the building and site design. If public dollars are used for public art, the selection process should include an open call for artists.*

- B.18 Design to allow active programming and use on game days and every day.

*Comments: The size of the plaza allows for active programming on game days and every other day of the year.*

- B.19 Design to enhance the visitor experience by including exterior video screens and historical memorabilia.

*Comments: On the southwesterly side of the prow of the building there is a 50-foot by 50-foot LED screen that can be used to display different images. The stadium design team is strongly encouraged to include the LED screen on the prow of the building as it is a unique feature that compliments the design.*

*No details about public art or the inclusion of historical memorabilia on the site have been provided.*

### **C. Sustainability**

#### **Design and Construction**



- C.1 Given the City of Minneapolis' commitment to the operating and maintenance costs, design a stadium that meets the City, State, community, and team needs while also producing the lowest total cost of ownership. This includes ongoing energy, maintenance and materials costs.

*Comments: According to the stadium design team, any and all avenues are being pursued to make sure the facility operates to the level the City would like. Through the design, they are trying to reduce as much energy demand as possible. The mechanical, electrical and plumbing (MEP) systems are being designed to reduce maintenance costs. The building is being designed to last more than 30 years. Materials selected are low maintenance, durable materials.*

*Before the energy modeling and B3 design process is complete, City of Minneapolis staff can't make an independent judgment about the energy and operating costs of the building. The stadium design team should continue to work with the City of Minneapolis staff to share the results of the energy modeling to understand long-term costs.*

- C.2 Meet B3 Minnesota Sustainable Building Guidelines, including the SB 2030 Energy Standard as required of other state-financed projects. Use the Xcel Enhanced Energy Design Assistance program. Document the payback period for the investment in energy efficiency and renewable energy. Source as many energy efficiency products from Minnesota sources as possible.

*Comments: The stadium design team is working on B3 compliance with the Weidt Group. The team has had conversations with the Weidt Group, Xcel Energy, and Centerpoint to review any and all strategies to reduce energy demand. The Weidt Group is currently building an energy model for the building which will allow B3 compliance to be estimated. Since it is a stadium, it doesn't fit nicely into the B3 standard, which requires comparable properties. Preliminary numbers from the energy modeling and status of compliance with B3 will be available in August.*

*Some features may automatically reduce energy demand, for example, the clear roof lowers lighting use and heating load in the winter. These features may have tradeoffs however, as a clear roof may mean more cooling load in the summer.*

*No information has been provided about the sourcing of energy efficiency products included in the design.*

*Before the energy modeling and B3 design process is complete, City of Minneapolis staff can't make an independent judgment about whether B3 compliance has been met. The stadium design team should continue to work with the City of Minneapolis staff to share the results of the energy modeling and compliance work.*

- C.3 Provide a minimum of 20%, up to the amount that can feasibly be provided based on a 30 year payback, of the facilities on-site energy use through on-site renewable energy production. Document how many years the investment renewable energy provided will take to payback. Document how many years the investment in renewable energy provided will take to payback using systems manufactured in Minnesota.

*Comments: The design team has indicated to staff that on-site energy production is not being pursued at this time. No information has been provided on the pay-back period for on-site energy generation facilities or other potential reasons for not pursuing on-site generation.*

*The Implementation Committee believes strongly that renewable energy generation is a goal that needs to be achieved within the stadium design, and that careful analysis should be performed to understand how this goal could be met.*

- C.4 Pursue LEED ND certification to the highest level possible (minimum of LEED Silver) for the stadium and surrounding site development.

*Comments: The stadium design team is pursuing LEED for New Construction certification at the "Certified" level, which is lower than Silver. The stadium design team is strongly encouraged to pursue at least a LEED Silver level of certification to demonstrate high environmental performance.*

*Given that the site in question primarily includes only the stadium, the LEED ND requirements for block size, intersection density, and employment/residential density would likely not be met. As design details of the neighborhood around the stadium continue to be developed by the design team, other developers, or the City, careful attention should be paid to how changes could make the neighborhood more or less likely to eventually achieve LEED ND certification, with the goal of having a certified neighborhood in the future. Specific design elements that could be important include street design, walkability, transportation options, and minimum development densities.*

*Any decisions about certifying the stadium for Operations & Maintenance would have to be made by the MSFA and after the stadium began operations.*

- C.5 Evaluate the possibility of a district heat and power system for heating and cooling all the facilities part of the stadium complex during the Energy Design Assistance (EDA) process.

*Comments: Evaluation of district heating and cooling for facilities is currently ongoing via the energy modeling process with The Weidt Group. The stadium design team has expressed a desire to not need to include on-site boilers and chillers in the design.*

*The stadium design team should continue to work with the City of Minneapolis staff to share the results of the energy modeling.*

- C.6 Achieve compliance with the City's Chapter 54 ordinance dealing with stormwater, removing at least 70% of Total Suspended Solids (TSS) from the site and implement other stormwater best management practices on site.

*Comments: The stadium project will be required to meet Chapter 54 City requirements for stormwater. Based on the plans submitted the stadium will likely meet the City requirements for stormwater management. Additional investigation is being done to see what other stormwater best management practices could be incorporated into the site.*

- C.7 Coordinate with Minneapolis Department of Health and their proposed health guidelines for the design and operation of the stadium and surrounding site.

*Comments: The stadium design team has noted that they are in communication with the Minneapolis Health Department and has had initial dialogue as it pertains to food service design requirements and guidelines. This discussion included a review of what local code requires for flooring types, paints and other items primarily as it relates to food safety.*

*The choice of food vendor and how concessions are laid out, which will impact healthy food choices, has not yet been made. This may be a decision that is made by the MSFA, rather than the stadium design team.*

*Other Health Department guidelines – such as secure employment, opportunities for physical activity, access to open space, improving community cohesion and ensuring a tobacco-free campus may not yet have been discussed by the stadium design team and Health Department.*

*Because few details are available on how the design and operations will incorporate all health guidelines, the stadium design team and MSFA should continue discussions with City of Minneapolis staff to understand how these principles will be incorporated.*

- C.8 Design the stadium and surrounding site to encourage a wide choice of transportation modes – transit, bike, pedestrian and car – for game-day and non-game day visitors.

*Comments: The stadium has been designed to be accessible from a wide choice of transportation modes. The Downtown East Light Rail Transit Station is located directly across Chicago Avenue from the main entrance into the stadium. The plans show bicycle facilities including 300 bicycle parking spaces located on the southwest, northwest and northeast sides of the site and a two-way bike lane on 6<sup>th</sup> Street. The City of Minneapolis has been discussing options with the stadium design team to revise the design of 6<sup>th</sup> Street and the site to include an off-street bike path instead of the on-street bike lane. Public sidewalks connect to the on-site walkways leading directly to the building entrances and new skyways will connect new and existing structured parking ramps to the stadium.*

- C.9 Design for material efficiency to reduce materials, promote durability, and facilitate maintenance using materials that are appropriate to Minneapolis's climate and weather.

*Comments: The primary exterior materials of the building include glass and metal. The primary metal on the building is a 1-foot tall by 12-foot wide zinc panel which will be staggered when installed. In addition, there is a stainless steel ribbon that wraps around the building. The northern half of the roof will be made out of PVC and the southern half of the roof will be made out of Ethylene tetrafluoroethylene (ETFE), which is a fluorine based plastic. The ETFE will be installed using a three-layer system. Frit will be applied to one or more of the ETFE layers which will help reduce the amount of ultraviolet rays entering the building. While the sourcing of the materials is unknown they are climate appropriate for Minnesota.*

## Operations

- C.10 On an ongoing basis, use the B3 Benchmarking system to report the stadium's energy performance to the City and State.

*Comments: The stadium design team has indicated that benchmarking information will be provided to the City and State. As noted earlier, the energy modeling process has begun, and initial results are anticipated in August.*

- C.11 Pursue LEED Operations and Maintenance (O&M) certification to the highest level possible.

*Comments: The decision to pursue LEED O&M certification will have to be made by the MSFA after a period of occupancy and operation. The MSFA should continue discussions of LEED O&M with City of Minneapolis staff, and pursue LEED O&M certification when it becomes possible.*

- C.12 Implement a facility and site wide coordinated waste reduction and recycling program that includes reduced packaging, convenient recycling and organics collection.

*Comments: The stadium design team has planned for adequate space for recycling and compost collection in the loading dock areas, as well as space for collection in concourse and vendor areas. However, the decision to implement any recycling or organics collection program rests with the MSFA. Implementation of recycling and organics programs may need to be coordinated with the selection of the food service and waste management companies that are selected by the MSFA.*

*The MSFA should continue discussions with the City of Minneapolis staff and the Minnesota Pollution Control Agency to implement successful recycling and organics programs.*

- C.13 Allow and encourage the use of local, fresh foods that reflect the cultural diversity of the state through the vendor choice process and the sourcing of products and the design of food preparation facilities.

*Comments: It is unclear whether the design of the food preparation facilities includes space for local preparation of food. The selection of food vendors is a decision that will be made by the MSFA.*

## PLANNING PRINCIPLES

### **D. Neighborhood**

- D.1 With the best urban stadium in the country at its core that attracts residents, business, and investment, and becomes a true, mixed use urban community.

*Comments: The stadium development alone cannot realize this principle; however, it can and possibly already is acting as a catalyst for new development in the area. If the proposed adjacent 5-block redevelopment by Ryan Companies is realized the stadium development will have fostered more development than the existing Metrodome has done during its entire existence.*

- D.2 That engages with the stadium and plaza by supporting commercial activity and flexible formal and informal programming and use at the stadium, on the plaza, and in the surrounding areas on game days and every day, day and night, and all year round including the winter months.

*Comments: The stadium plays host to a wide variety of activities throughout the year and will continue to do so in the future. There will be spaces within and surrounding the stadium that can be used for formal and informal programming events on game days and every day, day and night, and all year round including the winter months.*

- D.3 That will benefit from a stadium design that reflects the existing context, street grid, the needs of pedestrians, and future plans for the neighborhood and the city.

*Comments: The stadium will be constructed on the same property as the existing Metrodome. While 5<sup>th</sup> Street will be vacated the surrounding street grid will not be disrupted as 6<sup>th</sup> Street will accommodate two-way operations for that portion of roadway between Park Avenue and 11<sup>th</sup> Avenue. Pedestrian improvements near the intersection of 4<sup>th</sup> and Chicago and along 6<sup>th</sup> Street, appropriate sidewalk designs and queuing space at the Downtown East Light Rail Transit Station all need to be discussed in more detail with City of Minneapolis staff.*

- D.4 That is sustainable, integrated with the stadium development, and that meets the criteria for LEED ND (Neighborhood Development).

*Comments: LEED ND is not being pursued at this time.*

- D.5 That integrates the best principles of transit oriented development in a dense, mixed-use community.

*Comments: The stadium design team should study LRT, bicycle and pedestrian connections with a commitment to providing a truly multi-modal transit oriented site development.*

*City adopted policies perpetuate strong transit oriented development principles in this area in order to promote a dense, mixed-use community including a mixture of transit stations, commercial, office, retail, housing, and parks/plazas. Additionally, all development in the City of Minneapolis is required to meet the Zoning Code standards including Chapter 530, Site Plan Review. The purpose of the site plan review chapter is to "promote development that is compatible with nearby properties, neighborhood character, natural features and plans adopted by the city council, to minimize pedestrian and vehicular conflict, to reinforce public spaces, to promote public safety, and to visually enhance development. The regulations recognize the unique character of land and development throughout the city and the need for flexibility in site plan review".*

- D.6 That encourages commercial uses on the ground floor of buildings that promote extended hours of operation in pursuit of city streets that are lively at appropriate hours of the day and night.

*Comments: The stadium development alone cannot realize this principle; however, it can be a catalyst for new development. The proposed ground level team store, restaurant and*

*adjacent 2 acre on-site plaza will help activate the surrounding streets on non-event days. The stadium should animate the streets and surrounding area by providing visual connections to the neighborhood.*

- D.7 That encourages activities and uses for people of all ages, including the growing number of families living in and visiting Downtown.

*Comments: The on-site plaza is 2 acres in size. With this amount of useable space a wide variety of activities could be accommodated for people of all ages, including families living and visiting downtown. The outdoor public spaces should be designed for active uses.*

- D.8 Where large public facilities are woven into the rest of the Downtown fabric by creating more humane public spaces and streetscapes surrounding these buildings to provide a greater sense of comfort for pedestrians.

*Comments: The plaza located on the stadium site is 2 acres in size which complements the size of the stadium building. On average, the dimensions of the plaza are 198 feet deep and 425 feet wide. There is a large area of trees located on both the north and south ends of the plaza. Combined, the two areas of trees total 40,000 square feet. The edges of both tree areas are flanked with deep stairs that rise between one foot and 10 feet depending on the site grades. The trees have been arranged so people can walk between them and an appropriate surfacing material will be used in these areas for accessibility purposes.*

*There is landscaping located on the other three sides of the stadium site as well. These landscaped areas are designed to help soften the edge of the building or the parking lot. The landscape materials that have been selected to be used throughout the stadium site include turf grass, native grasses and 6 species of canopy trees.*

*There will be public sidewalks on all four sides of the stadium site. The public sidewalks should be of an appropriate width and should be separated from traffic by streetscape elements to protect pedestrians from activity in the street. Minimum pedestrian zones adjacent to public roadways in downtown Minneapolis should generally be 15 to 20 feet (recommended) to include adequate space for a zone for landscaping, signage, light poles, clearances, snow banks, etc. These concerns need to be discussed in more detail with City of Minneapolis staff.*

- D.9 That endeavors to strengthen and re-establish the original street grid in the area by not closing any streets and to re-establish the area's street grid, where practical.

*Comments: The vacation of 5<sup>th</sup> Street, between 11<sup>th</sup> Avenue South and Chicago Avenue, is recognized by the City of Minneapolis as a key to the stadium design. The existing Jersey barrier between 5<sup>th</sup> Street and 6<sup>th</sup> Street will be removed which will allow pedestrians to access the stadium more readily from the south. No streets are being reopened as part of the stadium development.*

- D.10 Where skyways, tunnels, and dedicated walkways are required, design them to support the stadium and serve as an asset to the surrounding neighborhood by providing visible entries to stairs and elevators at street level, supporting ground-floor uses, and tying into parking systems.

*Comments: The location and design of the skyways, tunnels and dedicated walkways connecting the building to either existing or proposed parking structures is still being discussed. Skyways should have direct connections to the public streets which are visible and easily accessible from the public sidewalks. The design and operation of skyways should be consistent with the Minneapolis Skyway System Standards and Procedures Manual, which was approved by the Downtown Council's Skyway Advisory Committee in 2006.*

- D.11 That creates green corridors by integrating strong streetscape design features such as continuous street tree canopy, pedestrian and bicycle systems, public art, seating opportunities, rain gardens, "sensory" gardens, and storm water management systems.

*Comments: A generous amount of trees are proposed to be planted on the stadium site and in the right-of-way along portions of the stadium-side of surrounding streets.*

*The proposed stadium design includes pedestrian and bicycle facilities. One can walk around the entire facility using the on-site walkways which incorporate longitudinal slopes of up to five percent in some locations and which include a staircase alternative at three locations. The on-site walkways are connected to the public sidewalks. The plans show bicycle facilities including 300 bicycle parking spaces located on the southwest, northwest and northeast sides of the site and a two-way bike lane on 6<sup>th</sup> Street. The City of Minneapolis has been discussing options with the stadium design team to revise the design of 6<sup>th</sup> Street and the site to include an off-street bike path instead of the on-street bike lane.*

*No details about public art, seating opportunities, rain gardens or sensory gardens have been provided.*

*Based on the plans submitted the stadium will likely meet the City requirements for stormwater management. The submitted stormwater plan includes an underground, large diameter, perforated pipe gallery infiltration system. Additional investigation is being done to see what other stormwater management practices could be incorporated into the site.*

- D.12 That uses green corridors and view corridors to connect the site and area to the Mississippi River, enhance Chicago Avenue, 5th Street and 11th Avenue, and strengthens connections between the riverfront, Cedar Riverside, Elliot Park and the Central Business District.

*Comments: There is landscaping located on each side of the stadium site so as one looks towards the stadium from any direction they will see greenery. The landscape materials that have been selected to be used throughout the stadium site include turf grass, native grasses and 6 species of canopy trees.*

*The unique shape of the building provides for interesting views from every approach. In particular, the view looking east on both 4<sup>th</sup> Street and 5<sup>th</sup> Street will be dramatic given the stadium design and large on-site plaza and the view looking west from the Cedar Riverside*



*neighborhood will be dramatic given the change in grade and the large staircase leading to the wide glass entrance.*

*The location and design of the skyways connecting the building to either existing or proposed parking structures is still being discussed. All skyways should be designed to be as transparent as possible in order to minimize the blocking of views of the stadium. A skyway over Chicago Avenue could impede views looking north of significant structures and landscapes in the St. Anthony Falls Historic District, including the Pillsbury A Mill on the east bank, and the Mississippi River if not designed with this consideration in mind. Design considerations should include height in relation to the street and transparency.*

*In addition, any proposed structure on the east side of Chicago Avenue north of 4<sup>th</sup> Street should adhere to setbacks as outlined in the Update to the Historic Mills District Master Plan. The goals for this setback are to better pull the river into Downtown, highlight Chicago Avenue as a major pedestrian spine, and preserve views of the historic Pillsbury A-Mill and the Guthrie Theater.*

- D.13 Coordinates with planned infrastructure improvement projects in the surrounding area to eliminate barriers and enhance connections between the neighborhoods and to the Mississippi River.

*Comments: The proposed plans do not appear to preclude any planned infrastructure improvement projects. The existing Jersey barrier between 5<sup>th</sup> Street and 6<sup>th</sup> Street will be removed which will allow pedestrians to access the stadium more readily from the south. In addition, the stadium plans include bicycle facilities consistent with the Minneapolis Bicycle Master Plan.*

- D.14 That stimulates and enables the growth of existing corridors including the Chicago Avenue commercial corridor and the Washington Avenue arts corridor and that strengthens connections to existing cultural and community assets in the surrounding neighborhoods.

*Comments: The stadium development alone cannot realize this principle; however, it can and possibly already is acting as a catalyst for new development in the area. If the proposed adjacent 5-block redevelopment by Ryan Companies is realized the stadium development will have fostered more development than the existing Metrodome has done during its entire existence.*

*A transparent skyway design over Chicago Avenue and setting buildings back on the east side of the street will be critical in perpetuating Chicago Avenue as a strong connection to the river and advancing City goals for more commercial amenities along Chicago itself.*

- D.15 Where surface parking lots are replaced by development over time and tail-gating and game day parking is accommodated increasingly on closed-off public streets, plazas, and parks.

*Comments: The stadium development is substantially limited to the existing Metrodome site between 4<sup>th</sup> and 6<sup>th</sup> Streets and between Chicago and 11<sup>th</sup> Avenues. However, it should be noted that Ryan Companies is proposing to redevelop 5 adjacent blocks to the west of the stadium development that are primarily occupied by surface parking lots.*



- D.16 That highlights the history of the area, values its historic resources, and places a priority on preserving and reusing important buildings.

*Comments: Developments that involve changes to historically designated buildings or buildings located in historically designated districts or new buildings in historically designated districts are subject to review by the City's Heritage Preservation Commission.*

- D.17 That is safe and utilizes the principles of crime prevention through environmental design (CPETD) to maximize visibility and natural surveillance and foster positive social interactions.

*Comments: Crime Prevention Through Environmental Design (CPTED) has been considered at a high level but more information is needed to confirm that the site details are designed with safety in mind. The plaza has been located adjacent to the main doors of the stadium. The majority of the west wall of the stadium is glass. The ticket office, team store, a restaurant and stadium offices are located on the west side of the building. All on-site walkways lead to the plaza. Triumph Elm trees are proposed to be located on each end of the plaza which have the potential to grow to a height of 60 feet with a spread of 40 feet and has a high canopy with a typical clearance of 8 feet. More details are needed about lighting and other CPTED considerations.*

*All development in the City of Minneapolis is required to meet the Zoning Code standards including Chapter 530, Site Plan Review. As part of this review development is required to employ best practices to include crime prevention through environmental design standards.*

- D.18 Encourages sustainable, long-range economic growth and development that benefits the larger region and increases regional equity by supporting city and county policies related to the attraction and retention of women- and minority-owned businesses and the creation of a diversified workforce through the use of inclusionary hiring practices in the creation of permanent jobs.

*Comments: The MSFA has enacted an Equity Plan that calls for the inclusion of 19 percent women and minority owned businesses in the design services phase. In the construction phase, the Equity Plan calls for 20 percent of women and minority owned businesses be utilized. The Equity Plan also lays out workforce goals of including 6 percent women and 32 percent minority in the workforce building the stadium.*

## E. Transportation System

- E.1 Integrates the new station into the stadium development as much as is feasibly possible.

*Comments: The Downtown East Light Rail Transit Station is located directly across Chicago Avenue from the 2 acre plaza and the main entrance into the stadium. No changes are being proposed to the station as part of the stadium design. It has been identified in the Draft Environmental Impact Statement (DEIS) that the amount of queuing space at the LRT station during events is inadequate now and that event transit ridership will continue to increase, as additional LRT lines become operational. Therefore, the LRT station will be even more inadequate to accommodate queuing and loading of event LRT riders in the*

*future. For these reasons it will be important to modify the LRT station area to accommodate these large increases in LRT ridership. The stadium design team must address connections from the stadium to the LRT station in order to provide safe and orderly passage to accommodate event day crowds. An adequate design needs to be coordinated with City of Minneapolis staff and Metro Transit staff.*

- E.2 Supports growth and reinvestment in Downtown East, Elliot Park, and Cedar Riverside by improving walking, biking, and transit connections between them and placing people, pedestrians, and cyclists first over vehicles.

*Comments: The proposed stadium design includes pedestrian and bicycle facilities. One can walk around the entire facility using the on-site walkways which incorporate longitudinal slopes of up to five percent in some locations and which include a staircase alternative at three locations. The on-site walkways are connected to the public sidewalks. The plans show bicycle facilities including 300 bicycle parking spaces located on the southwest, northwest and northeast sides of the site and a two-way bike lane on 6<sup>th</sup> Street. The City of Minneapolis has been discussing options with the stadium design team to revise the design of 6<sup>th</sup> Street and the site to include an off-street bike path instead of the on-street bike lane.*

- E.3 Ensures safe, enjoyable, and accessible pedestrian routes to the stadium and other nearby destinations through strategies such as wider sidewalks, trees, landscaping, and street furniture.

*Comments: There will be public sidewalks on all four sides of the stadium site. The public sidewalks should be of an appropriate width and should be separated from traffic by streetscape elements to protect pedestrians from activity in the street. Minimum pedestrian zones adjacent to public roadways in downtown Minneapolis should generally be 15 to 20 feet (recommended) to include adequate space for a zone for landscaping, signage, light poles, clearances, snow banks, etc. These concerns need to be discussed in more detail with City of Minneapolis staff.*

- E.4 Integrates bicycle connections and amenities within the stadium site and throughout the surrounding area.

*Comments: The plans show bicycle facilities including 300 bicycle parking spaces located on the southwest, northwest and northeast sides of the site and a two-way bike lane on 6<sup>th</sup> Street. The City of Minneapolis has been discussing options with the stadium design team to revise the design of 6<sup>th</sup> Street and the site to include an off-street bike path instead of the on-street bike lane.*

- E.5 Improves the experience for transit users at the Downtown East LRT station during peak times – such as after Vikings games – through consideration of queuing space, loading times, and overall safety and comfort.

*Comments: No changes are being proposed to the station as part of the stadium design. However, it has been identified in the Draft Environmental Impact Statement (DEIS) that the amount of queuing space at the LRT station during events is inadequate now and that event transit ridership will continue to increase, as additional LRT lines become operational. Therefore, the LRT station will be even more inadequate to accommodate queuing and*

*loading of event LRT riders in the future. For these reasons it will be important to modify the LRT station area to accommodate these large increases in LRT ridership. An adequate design needs to be coordinated with City of Minneapolis staff and Metro Transit staff.*

- E.6 Manages the role and impact of automobiles in a multi-modal transportation system.

*Comments: A traffic management plan will be required to be completed by the stadium design team prior to the opening of the stadium.*

- E.7 Guarantees that parking serves as a resource to the entire area and not just the stadium development, by prioritizing below grade and structured above grade parking that incorporates active ground floor uses, that stimulates development, and leads to the reduction of surface parking lots in the area over time.

*Comments: On the southeast corner of the site there is a 190-space surface parking lot. On Vikings game days the parking lot will be utilized by players and coaching staff. The MSFA is also proposing to construct two new parking garages on the north side of the stadium site. The parking garages would be connected to the stadium via a series of skyways. The design of the parking garages and the skyways is still being discussed.*

*All development in the City of Minneapolis is required to meet the Zoning Code standards including Chapter 530, Site Plan Review. There are specific building design standards in the site plan review chapter. Specifically, building walls shall provide architectural detail in order to create visual interest. In larger buildings, architectural elements, including recesses or projections, windows and entries, shall be emphasized to divide the building into smaller identifiable sections. Blank, uninterrupted walls that do not include windows, entries, recesses or projections, or other architectural elements, shall not exceed 25 feet in length. Exterior materials shall be durable, including but not limited to masonry, brick, stone, stucco, wood, metal, and glass. The exterior materials and appearance of the rear and side walls of any building shall be similar to and compatible with the front of the building. The use of plain face concrete block as an exterior material shall be prohibited where fronting along a public street, public sidewalk, or public pathway.*

*In addition, there are specific design standards for parking garages in the site plan review chapter. Specifically, the exterior design of parking garages shall ensure that sloped floors do not dominate the appearance of the walls and that vehicles are screened from view. And in the downtown districts, the ground floor of principal parking garages shall have commercial, residential, office, or hotel uses located between the parking garage and any public sidewalk except where frontage is needed to provide vehicular and pedestrian access to the facility. And principal parking garages shall have all parking spaces located entirely below grade except where the garage includes integrated transit facilities within the structure.*

*While the stadium and stadium infrastructure are not subject to the zoning code regulations, the City of Minneapolis is concerned that without any standards in place to help influence the design of the parking structures that they will be visually unappealing. Therefore, the City of Minneapolis is recommending that the stadium design team continue to work with the City of Minneapolis staff to meet the above design standards for the building design and*

*parking garages with the exception that the parking garages be allowed to be constructed above ground. In addition, the City of Minneapolis is recommending that the design of the parking garages and skyways be compatible with the design of the stadium and the surrounding environment.*

- E.8 Improves connections to the regional freeway system.

*Comments: The stadium development has an impact on a connection from the freeway system by removing a portion of 5<sup>th</sup> Street. While 5<sup>th</sup> Street will be vacated the surrounding street grid will not be disrupted as 6<sup>th</sup> Street will accommodate two-way operations for that portion of roadway between Park Avenue and 11<sup>th</sup> Avenue.*

*An unrelated freeway project has recently been partially funded which would replace the existing I-94 ramp to 5<sup>th</sup> Street with a new I-94 ramp to 7<sup>th</sup> Street. Conversion of 6<sup>th</sup> Street to two-way operation remains important to mitigating the impact to local access and the redundancy of the transportation network.*

#### **F. Region**

- F.1 Encourages sustainable, long-range economic growth and development in the Downtown East/Elliott Park neighborhood that benefits the larger region and increases regional equity by supporting city and county policies related to the attraction and retention of women- and minority-owned businesses and the creation of a diversified workforce through the use of inclusionary hiring practices in the creation of permanent jobs.

*Comments: The stadium development alone cannot realize this principle; however, it can and possibly already is acting as a catalyst for new development in the area.*

- F.2 Supports diversity in our local workforce through high inclusionary goals in all aspects of the stadium design, construction, vendor contracting, and operations processes as reflected in Resolution 2012R-456 of the City of Minneapolis.

*Comments: The MSFA has enacted an Equity Plan that calls for the inclusion of 19 percent women and minority owned businesses in the design services phase. In the construction phase, the Equity Plan calls for 20 percent of women and minority owned businesses be utilized. The Equity Plan also lays out workforce goals of including 6 percent women and 32 percent minority in the workforce building the stadium.*

- F.3 Encourages business retention and expansion in and around the stadium site.

*Comments: The stadium development alone cannot realize this principle; however, it can and possibly already is acting as a catalyst for new development in the area.*

- F.4 Enhances and maintains transportation, wastewater, green space, and other physical infrastructure to serve the needs of businesses.

*Comments: The stadium development alone cannot realize this principle; however, it can and possibly already is acting as a catalyst for new development in the area.*

- F.5 Promotes sustainability practices in the redevelopment of areas, including access to mass transit and the use of green technology.

*Comments: The stadium development alone cannot realize this principle; however, it can and possibly already is acting as a catalyst for new development in the area that would support access to mass transit and the use of green technology.*

- F.6 Forges connections with higher education institutions such as the University of Minnesota in research, service, teaching, and development activities.

*Comments: The stadium development alone cannot realize this principle; however, it can and possibly already is acting as a catalyst for new development in the area.*

- F.7 Provides opportunities for current and future residents at all income levels to work in close proximity to where they live.

*Comments: The stadium development alone cannot realize this principle; however, it can and possibly already is acting as a catalyst for new development in the area.*

**Action:**

Based upon its review of the Schematic Design Documents, the Stadium Implementation Committee recommends the following:

**1. Building Design**

- a. Approve the location and layout of the stadium, primary entrances, on-site plaza and on-site parking area as shown in Exhibit B.
- b. Approve the stadium elevations as shown in Exhibits C, C1, C2 and C3.
- c. Approve the landscape plan for the stadium site as shown in Exhibits D and D1.
- d. Recommend that the fencing around the on-site parking area be made out of decorative metal and be ornamental in design.
- e. Recommend that all trees within the parking lot be located within tree islands that have a minimum dimension of 7 feet in every direction.
- f. Best practices should be used for tree plantings throughout the site to ensure maximum growth.
- g. Strongly encourage the stadium design team to include additional on-site uses that benefit the wider community such as a daycare, recreational uses, etc. These uses should be visually connected to the street and accessible directly from the building's exterior, with additional internal connections as needed by the stadium..

- ~~h. Recommend that the MSFA consider locating a daycare facility within the stadium.~~
- i. Delegate final review and approval of curb cut locations to the City of Minneapolis Public Works Director.
- j. Recommend that skyways have direct connections to the public streets which are visible and easily accessible from the public sidewalks.
- k. Recommend that the design and operation of skyways be consistent with the *Minneapolis Skyway System Standards and Procedures Manual*, which was approved by the Downtown Council's Skyway Advisory Committee in 2006.
- l. Recommend that design considerations for skyways include height in relation to the street and transparency.
- m. The stadium design team should work with Nice Ride Minnesota to accommodate a large bike rental kiosk on the stadium site.
- n. Delegate approval of the detailed signage plan for the exterior building and site to the City of Minneapolis Community Planning and Economic Development Director.
- o. Delegate final fire and life safety review to the City of Minneapolis Community Planning and Economic Development Director and other applicable regulatory authorities.
- p. Delegate final review and approval of the lighting plan to the City of Minneapolis Community Planning and Economic Development Director and Public Works Director. The lighting plan shall include location and type of lighting and photometric detail regarding the impact of light spillover on the surrounding area.

**2. The Place**

**Site Design**

- a. Recommend that improvements be incorporated into the design to safely accommodate and control significant crowds of pedestrians crossing through the 4<sup>th</sup> Street and Chicago Avenue intersection.
- b. Recommend that improvements be made to the site design in order to safely accommodate the number of people entering and exiting the stadium on game days as well as those using the site throughout the year from 6<sup>th</sup> Street.
- c. Recommend that a full signal system be installed at the intersections of 6<sup>th</sup> Street and both 9<sup>th</sup> Avenue (Carew Drive) and 10<sup>th</sup> Avenue.
- c. Delegate final review and approval of public sidewalks to the City of Minneapolis Public Works Director.
- d. Recommend that all skyways be designed to be as transparent as possible.

- e. Recommend that any proposed structure on the east side of Chicago Avenue north of 4<sup>th</sup> Street reasonably adhere to the setbacks as outlined in the *Update to the Historic Mills District Master Plan*.
- f. Recommend that the public sidewalk on 4<sup>th</sup> Street connect to the on-site walkway which will lead pedestrians to 11<sup>th</sup> Avenue.
- g. Recommend that if an exterior walkway to the loading dock is needed for stadium maintenance purposes, that it be designed so the general public knows that the sidewalk ends at a private walkway.
- h. Recommend that the site grades, location and configuration of stairways and walkway widths and alignments be coordinated with the City of Minneapolis staff before detailed designs are finalized.
- i. Recommend that the stadium design team address connections from the stadium to the LRT station in order to provide safe and orderly passage to accommodate event day crowds.
- j. Recommend that an adequate design of the Downtown East Light Rail Transit Station be coordinated with the City of Minneapolis Public Works Director and the Director of Metro Transit.

**Plaza Design**

- a. Recommend that the detailed plaza design incorporate a pervious paving system, a summer shade system, lighting, seating, trash receptacles, etc. and be coordinated with City of Minneapolis staff.
- b. A public art process should occur as early in the design as possible in order to integrate public art into the building and site design. If public dollars are used for public art, the selection process should include an open call for artists.
- c. The stadium design team is strongly encouraged to include the LED screen on the prow of the building as it is a unique feature that compliments the design.

**3. Sustainability**

**Design and Construction**

- a. Recommend that the stadium design team continue to work with City of Minneapolis staff to share the results of the energy modeling to understand long-term costs.
- b. Recommend that the stadium design team continue to work with City of Minneapolis staff to share the results of the energy modeling and compliance work.
- c. The stadium design team is strongly encouraged to provide reasoning to staff for the decision not to include on-site generation, including the greatest detail possible on



feasibility, costs and payback, prior to the Planning Commission's action on the stadium design in August.

- d. As soon as possible, the stadium design team shall complete an expedited analysis to be reviewed by staff of the costs and payback period of providing on-site renewable energy generation on the stadium or associated structures like parking ramps. This analysis should include the costs and payback period for systems that could accommodate up to and including 20% of the facilities energy use in a 30-year payback period, but should also include detail on what size system can be accommodated in that payback period if the 20% goal is not achievable for cost or design reasons.
- e. The stadium design team shall complete an analysis of the marginal cost of designing the stadium and associated structures like parking ramps to be "renewable energy" ready. For example, simple changes to the parking ramp design may make it easier or not cost-prohibitive to add solar energy generation to the roof of the building at a later date.
- f. Acknowledge that the stadium design team is pursuing LEED for New Construction certification at the "Certified" level.
- g. The stadium design team is strongly encouraged to pursue at least a LEED Silver level of certification to demonstrate high environmental performance.
- h. Recommend that the stadium design team and MSFA continue discussions with City of Minneapolis staff to understand how the Minneapolis Department of Health guidelines will be incorporated into the stadium.

#### **Operations**

- a. Recommend that the MSFA continue discussions of LEED Operations & Maintenance with City of Minneapolis staff and pursue LEED Operations & Maintenance certification when it becomes possible.
- b. Recommend that the MSFA continue discussions of incorporating fresh, local food options into the vending and operations of the stadium with City of Minneapolis staff.
- c. Recommend that the MSFA continue discussions with City of Minneapolis staff and the Minnesota Pollution Control Agency to implement successful recycling and organics programs.

#### **4. Neighborhood**

- a. Approve the conceptual roadway changes to 6<sup>th</sup> Street between Park Avenue and 11<sup>th</sup> Avenue, including the west-bound automobile lane and off-street bicycle path as shown in Exhibit E.
- b. Recommend the stadium design team study LRT, bicycle and pedestrian connections with a commitment to providing a truly multi-modal transit-oriented site development.



**5. Transportation System**

- a. Recommend that the exterior design of all new parking garages ensure that sloped floors do not dominate the appearance of the walls and that vehicles are screened from view.
- b. Recommend that the ground floor of all new parking garages have commercial, residential, office, or hotel uses located between the parking garage and any public sidewalk except where frontage is needed to provide vehicular and pedestrian access to the facility.
- c. Recommend that the parking garages meet the following building design standards: provide architectural detail in order to create visual interest; in larger buildings, architectural elements, including recesses or projections, windows and entries, shall be emphasized to divide the building into smaller identifiable sections; blank, uninterrupted walls that do not include windows, entries, recesses or projections, or other architectural elements, shall not exceed 25 feet in length; exterior materials shall be durable, including but not limited to masonry, brick, stone, stucco, wood, metal, and glass; the exterior materials and appearance of the rear and side walls of any building shall be similar to and compatible with the front of the building; and the use of plain face concrete block as an exterior material shall be prohibited where fronting along a public street, public sidewalk, or public pathway.
- d. Recommend that the design of the parking garages and skyways be compatible with the design of the stadium and the surrounding environment.
- e. Recommend that the parking garages be designed so that they could be converted to another use in the future.
- f. Delegate final review and approval of a traffic management plan to the City of Minneapolis Director of Public Works and where applicable, the Hennepin County Engineer and Mn/DOT.

**6. Region**

- a. Recommend that the MSFA continue to work with the City of Minneapolis Civil Rights Department to achieve the Equity Plan for both stadium related construction jobs and for permanent jobs after the opening of the stadium and on-going operations.

**7. Other**

- a. Delegate final review and approval of public infrastructure and related improvements, including, but not limited to, public utility relocations and directional/way finding signage to the City of Minneapolis Public Works Director, and when applicable the Hennepin County Engineer and Mn/DOT.
- b. Delegate review and approval of public utilities and appropriate easements to the City of Minneapolis Public Works Director, Minnesota Sports Facilities Authority, and when applicable, the Hennepin County Engineer and Mn/DOT.

- c. Delegate review and approval of storm water drainage to the City of Minneapolis Public Works Director, Mn/DOT and other organizations as it relates to ownership and permitting requirements.
- d. Environmental remediation shall meet all applicable requirements of the Minnesota Pollution Control Agency and the City of Minneapolis.
- e. Recommend that the stadium design team continue to work with City of Minneapolis staff to obtain required permits for the construction of the Minnesota Multi-Purpose Stadium. The City will facilitate the project through a modified Preliminary Development Review process.
- f. Recommend that the stadium design team, the MSFA and/or the Minnesota Vikings obtain all required City right-of-way encroachment permits.

**8. Plan Changes After Stadium Implementation Committee Action**

The Minnesota State Statute establishing the Stadium Implementation Committee and alternative process for municipal land use and development review does not provide a process for reviewing and approving changes to the project design plans after the Stadium Implementation Committee forwards its action on the final design. The standard process in the City's zoning code does not apply.

Changes to the stadium development that are proposed following the issuance of the recommendations of the Stadium Implementation Committee and consideration by the Minneapolis City Planning Commission and City Council shall be forwarded to the City of Minneapolis Community Planning and Economic Development Director and Public Works Director.

The Directors shall meet and mutually agree that:

- 1) The change does not materially impact the project design plans as recommended by the Stadium Implementation Committee, or
- 2) The change does materially impact the project design plans and request that the MSFA take appropriate action to ensure that the change conforms with the project design plans approved by the Stadium Implementation Committee, or
- 3) The change materially impacts the project design plans and requires review by the Stadium Implementation Committee, in which case the City shall reconvene the Committee for the limited purpose of reviewing the specific change(s) and recommending appropriate action to the MSFA.

Current development plans shall be kept on-file with the Minneapolis Department of Community Planning and Economic Development and Minneapolis Public Works.

**Next Steps:**

Per Statute, the recommendations of the Stadium Implementation Committee shall be forwarded to the Minneapolis Planning Commission for an advisory recommendation and then to the City Council for final action in a single resolution. The Stadium Implementation Committee recommends that the City Planning Commission hold a public hearing. The final City Council action must be taken within 45 days of the receipt of the Stadium Implementation Committee recommendation to the Minneapolis Planning Commission.

**EXHIBIT F-1****PRELIMINARY PROJECT BUDGET**

MN Preliminary Project Budget  
October 3, 2013

		<b><u>OVERRUN RISK</u></b>
<b>Total Construction Cost Budget</b>	<b>\$ 737,768,142</b>	Owner's Contingency
Vendor Contract Technology	\$ 28,000,000	Owner's Contingency
Concession Equipment	\$ 16,500,000	Owner's Contingency
FF&E	\$ 13,100,000	Owner's Contingency
	<u>\$ 57,600,000</u>	
Soft Costs	\$ 74,391,400	See Below
Owner's Contingency	\$ 37,500,000	
Team-Financed Contingency	\$ (13,089,542) *	
Parking / Skyway / Site Acquisition	\$ 49,600,000	Owner's Contingency
TCF - Stadium Costs	<u>\$ 31,230,000</u>	Team
<b>TOTAL BUDGET</b>	<b><u>\$ 975,000,000</u></b>	
<b><u>SOFT COSTS</u></b>		
Development Costs:		
MSFA Project Consultants	\$ 3,465,000	Authority
Team Project Consultants	\$ 1,035,000	Team
MSFA Equipment Storage	\$ 216,000	Owner's Contingency
Traffic Consultant	\$ 172,800	Owner's Contingency
Pre-Con Project Management - MSFA	\$ 2,317,500	Authority
Pre-Con Project Management - Team	\$ 2,317,500	Team
Construction Management	\$ 3,592,500	Owner's Contingency
Site Investigation:		
Geotech	\$ 432,000	Owner's Contingency
Site Survey	\$ 225,000	Owner's Contingency
Environmental Survey	\$ 864,000	Owner's Contingency
Professional Services:		
Architect and Engineers	\$ 34,000,000	Owner's Contingency
A/E Reimbursables	\$ -	
Additional A/E Services	\$ 3,060,000	Owner's Contingency
Testing & Inspection	\$ 3,505,500	Owner's Contingency
Project Reporting / Audit	\$ 2,430,000	Owner's Contingency
Project Legal Services - MSFA	\$ 900,000	Authority
Project Legal Services - Team	\$ 900,000	Team
Workforce Training + Equity Plan	\$ 1,200,000	Not to Exceed
Peer Review	\$ 216,000	Owner's Contingency
Miscellaneous and Printing	\$ 270,000	Owner's Contingency
Commissioning	\$ 700,000	Owner's Contingency
Marketing:		
Sales/Marketing - Team	\$ 675,000	Team
Market Studies - MSFA	\$ 225,000	Authority
Market Studies - Team	\$ 225,000	Team
Sales Office / Suite Mock-up - Team	\$ 540,000	Team
Ground Breaking Ceremony	\$ 50,000	Owner's Contingency
Insurance:		
Builder's Risk	\$ 4,197,600	Owner's Contingency
Owner's Protective Policy	\$ 2,160,000	Owner's Contingency
Capital Reserves - MSFA	<u>\$ 4,500,000</u>	Authority
<b>TOTAL SOFT COSTS</b>	<b><u>\$ 74,391,400</u></b>	

\* Team-Financed Contingency is funding available in the event the Owner's Contingency is not sufficient to fund project overruns.

**EXHIBIT F-2**

**MASTER PROJECT BUDGET**

**[SEE ATTACHED]**


**MASTER PROJECT BUDGET**
**February 19, 2015**

Division	Description	Master Project Budget 2/15/16	Mediation Settlement	Other 2/19/16 Budget Adjustments	Master Project Budget 2/19/16	Overrun Risk	Notes
	<b>SITE ACQUISITION &amp; IMPROVEMENTS</b>						
10-05-000	Parking / Skyway / Site Acquisition	\$53,723,365.35	\$1,675,000.00	\$1,300,000.00	\$56,698,365.35	Owner's Contingency	Includes \$3,975 Million for Stadium Plaza Improvements.
10-15-000	Site Utilities & Improvements	\$966,389.00			\$966,389.00	Owner's Contingency	
	<b>Subtotal</b>	<b>\$54,679,754.35</b>	<b>\$1,675,000.00</b>	<b>\$1,300,000.00</b>	<b>\$57,654,754.35</b>		
	<b>CONSTRUCTION COSTS</b>						
20-00-000	Construction Costs	\$857,676,186.10		\$419,542.00	\$858,095,728.10	Owner's Contingency	
	<b>Subtotal</b>	<b>\$857,676,186.10</b>	<b>\$0.00</b>	<b>\$419,542.00</b>	<b>\$858,095,728.10</b>		
	<b>FURNISHINGS, FIXTURES &amp; EQUIPMENT</b>						
30-12-000	Audio-Visual	\$16,491.71			\$16,491.71	Owner's Contingency	
30-16-000	Computer Equipment	\$109,729.78			\$109,729.78	Owner's Contingency	Repayment to MSFA for interim funding
30-28-000	Food Service / Concessions Equipment	\$5,121,890.57	(\$175,000.00)		\$4,946,890.57	Owner's Contingency	
30-36-000	Graphics & Signage	\$756,644.07		\$1,334,448.00	\$2,091,092.07	Owner's Contingency	
30-48-000	Maintenance Equipment	\$599,033.82			\$599,033.82	Owner's Contingency	
30-84-000	Technology	\$35,219,624.19	\$177,000.00		\$35,396,624.19	Owner's Contingency	See Development Agreement for VCT design and procurement guidelines and overrun responsibility.
30-90-000	Other FF&E	\$14,080,626.13	(\$1,000,000.00)		\$13,080,626.13	Owner's Contingency	
	<b>Subtotal</b>	<b>\$55,904,040.27</b>	<b>(\$995,000.00)</b>	<b>\$1,334,448.00</b>	<b>\$56,240,488.27</b>		
	<b>DEVELOPMENT COSTS</b>						
40-05-005	Architects & Engineers Fee	\$94,000,000.00			\$94,000,000.00	Owner's Contingency	
40-05-010	Additional A/E Services	\$7,471,062.00			\$7,471,062.00	Owner's Contingency	
40-10-005	Site Survey	\$471,960.00			\$471,960.00	Owner's Contingency	
40-16-005	Geotechnical Report & Groundwater Analysis	\$700,000.00			\$700,000.00	Owner's Contingency	
40-20-010	Commissioning	\$371,951.60			\$371,951.60	Owner's Contingency	
40-20-015	Construction Testing & Inspection	\$5,236,481.21			\$5,236,481.21	Owner's Contingency	
40-25-015	Team Sales & Marketing	\$876,000.00			\$876,000.00	Team	
40-30-005	Team Project Consultants	\$1,047,348.18			\$1,047,348.18	Authority	
40-30-010	MSFA Project Consultants	\$3,492,897.89			\$3,492,897.89	Authority	
40-30-020	Pre-Con Project Management-MSFA	\$2,317,500.00			\$2,317,500.00	Authority	
40-30-025	Pre-Con Project Management-Team	\$1,594,081.00			\$1,594,081.00	Team	
40-30-030	Construction Management	\$3,592,500.00			\$3,592,500.00	Owner's Contingency	
40-35-005	Project Legal Services - Team	\$1,210,230.83			\$1,210,230.83	Team	
40-35-010	Project Legal Services - MSFA	\$1,033,612.03			\$1,033,612.03	Authority	
40-40-005	Builders Risk Insurance	\$2,687,488.50			\$2,687,488.50	Owner's Contingency	
40-40-010	OPPI	\$5,212,767.14			\$5,212,767.14	Owner's Contingency	
40-40-011	Railroad Protective Liability	\$946,080.00			\$946,080.00	Owner's Contingency	
40-40-012	Ryen Project Insurance	\$726,107.05			\$726,107.05	Owner's Contingency	
40-40-013	Insurance Deductibles	\$21,789.36			\$21,789.36	Owner's Contingency	
40-40-015	Insurance Consultant	\$973,892.95			\$973,892.95	Owner's Contingency	
40-40-025	OOP Program - General	\$3,342,862.00			\$3,342,862.00	Owner's Contingency	



MASTER PROJECT BUDGET February 19, 2015

Division	Description	Master Project Budget 2/15/16	Mediation Settlement	Other 2/19/16 Budget Adjustments	Master Project Budget 2/19/16	Overrun Risk	Notes
40-40-026	OOP Program - Excess	\$2,200,651.00			\$2,200,651.00	Owner's Contingency	
40-40-027	OOP Program - Environmental	\$362,674.00			\$362,674.00	Owner's Contingency	
40-45-000	Permits & Regulatory Costs	\$0.00			\$0.00	Owner's Contingency	
40-50-005	Groundbreaking	\$50,000.00			\$50,000.00	Owner's Contingency	
40-50-020	MSFA Capital Reserve	\$4,500,000.00			\$4,500,000.00	Owner's Contingency	
40-55-005	Environmental Survey	\$942,841.26			\$942,841.26	Owner's Contingency	
40-55-010	Market Studies-MSFA	\$225,000.00			\$225,000.00	Authority	
40-55-015	Market Studies-Team	\$0.00			\$0.00	Team	
40-55-020	Project Reporting / Audit	\$2,430,000.00			\$2,430,000.00	Owner's Contingency	
40-55-035	Peer Reviews	\$223,980.00			\$223,980.00	Owner's Contingency	
40-55-040	Traffic & Parking Studies	\$265,700.00			\$265,700.00	Owner's Contingency	
40-55-045	Cost Consultant	\$0.00			\$0.00	Owner's Contingency	
40-55-050	Workforce Training and Equity Plan	\$1,351,736.88			\$1,351,736.88	Owner's Contingency	
40-90-015	MSFA Equipment Storage During Construction	\$216,000.00			\$216,000.00	Owner's Contingency	
40-90-020	Miscellaneous and Printing	\$270,000.00			\$270,000.00	Owner's Contingency	
	<b>Subtotal</b>	<b>\$89,364,143.88</b>	<b>(\$4,500,000.00)</b>	<b>\$0.00</b>	<b>\$84,864,143.88</b>		
	<b>FINANCING COSTS</b>						
50-00-000	Financing Costs	\$0.00			\$0.00		
	<b>Subtotal</b>	<b>\$0.00</b>		<b>\$0.00</b>	<b>\$0.00</b>		
	<b>OTHER PROJECT COSTS</b>						
60-00-005	TCF Stadium Improvements & Relocation Expenses	\$7,896,597.96			\$7,896,597.96	Team	
60-00-010	SDC Group Contingency	\$8,000,000.00			\$8,000,000.00	Team	
60-00-015	East Event Buildout	\$1,949,300.94			\$1,949,300.94	See DA	
60-00-020	Other Mutually Agreed Cost Issues 1	\$733,407.00			\$733,407.00	See DA	
60-00-023	Other Mutually Agreed Cost Issues 2	\$0.00			\$0.00	Team	
60-00-025	IPTV Enhancement	\$4,244,090.69			\$4,244,090.69	Fixed	
60-00-030	Mediation Settlement	\$0.00			\$0.00		
	<b>Subtotal</b>	<b>\$22,823,386.59</b>	<b>\$12,265,000.00</b>	<b>\$0.00</b>	<b>\$35,088,386.59</b>		
	<b>PROJECT CONTINGENCY</b>						
90-00-000	Owner Contingency	\$16,543,512.75			\$13,554,512.75		
	<b>Subtotal</b>	<b>\$16,543,512.75</b>	<b>(\$2,989,000.00)</b>	<b>\$0.00</b>	<b>\$13,554,512.75</b>		
	<b>PROJECT TOTAL</b>	<b>\$1,086,991,023.94</b>	<b>\$5,455,000.00</b>	<b>\$3,053,900.00</b>	<b>\$1,095,498,013.94</b>		

**EXHIBIT G****OWNER'S CONTINGENCY RELEASE SCHEDULE**

<b>Milestone</b>	<b>Likely Date**</b>	<b>Acceptable Minimum Level of Owner's Contingency**</b>
GMP Contract Signed	Nov-13	\$30,000,000
Property Acquisition Complete	Feb-14	\$29,000,000
Demolition Complete	Jul-14	\$28,000,000
Construction Documents Incorporated Into Mortenson Contract / Buyout Complete	Jul-14	\$26,000,000
Below Grade Structure Complete	Jan-15	\$23,000,000
Superstructure Complete and Completion of Naming Rights Deal & Design Impacts	Jul-15	\$20,000,000
Roof Erection Complete	Oct-15	\$18,000,000
Roof and Enclosure Complete and Stadium Weather Tight	Dec-15	\$15,000,000
February 1, 2016	Feb-16	\$12,000,000
Closeout 50% Complete	Dec-16	Greater of \$6,000,000 or amount of documented claims.
Outside Release Date - Project Complete	Apr-17	\$0 (subject to any reservation from release for unresolved Claims pursuant to DA§ 8.1)

\*\* In connection with the Settlement Agreement, certain Owner's Contingency funds will be escrowed in a settlement funds trust account pending acceptance or rejection of the settlement of claims by the Construction Manager and Authority pursuant to the terms of the Settlement Agreement. Pending such acceptance or rejection of the settlement of claims pursuant to the Settlement Agreement, the Authority and Team acknowledge and agree that the release schedule set forth in this **Exhibit G** will be suspended and no releases of Owner's Contingency will be made pursuant to such release schedule. If the Construction Manager and Authority accept the settlement of claims pursuant to the terms of the Settlement Agreement, the escrowed Owner's Contingency funds will be (i) returned to the construction funds trust to be administered pursuant to the terms of the Settlement Agreement and Construction Services Agreement and (ii) deemed applied to the settlement of valid Claims or Change Orders under the Construction Services Agreement pursuant to **Section 8.1** of the Development Agreement. The release schedule set forth in this **Exhibit G** will then be reinstated and applied to the remaining Owner's Contingency. If either the Construction Manager or the Authority rejects the settlement of claims pursuant to the terms of the Settlement Agreement, the escrowed Owner's Contingency funds will be (x) returned to the construction funds trust to be administered pursuant to **Section 8.1** of the Development Agreement and (y) deemed reserved and delayed for release pending the resolution of Change Orders or Claims of the Construction Manager and Architect. Upon resolution of any such Change Orders or Claims of the Construction Manager and Architect, the release schedule set forth in this **Exhibit G** will then be reinstated and applied to any remaining Owner's Contingency.



**EXHIBIT H****AGREED UPON ALLOCATIONS OF PROJECT COSTS**

<b>Basis for agreed upon allocation of Project Costs</b>	All costs, expenses and reimbursements set forth in this <b><u>Exhibit H</u></b> shall be paid out of the funds allocated for such purpose as set forth herein and, except as provided herein below, will be authorized for payment by the SDC Group based on the representation and certification of the applicable Party that the substance of the bills is for the purposes designated. Any amounts so allocated to a Party that are not used for the designated purpose shall be available to the Party to cover other Project Costs and will be authorized by the SDC Group in a similar manner. Except as otherwise set forth in the Development Agreement, in the event one Party exceeds the total of its allocated costs, that Party shall be responsible for those additional costs. The covenants set forth herein shall be binding upon the respected parties with regard to the terms and conditions of the applicable allocations.
<b>Project Costs Incurred After July 2016</b>	<ul style="list-style-type: none"> <li>If there is a delay, such as the occurrence of a force majeure event, in the commencement date of use of the Stadium, the Parties acknowledge that, unless otherwise agreed, Project Costs will continue to be incurred in order to commission the Stadium and Stadium Infrastructure. As a consequence, in order to complete the Project, the Parties will cooperate to facilitate financing for those costs which have been and are anticipated to be "Project Costs," including all costs described in this <b><u>Exhibit H</u></b>. The Parties acknowledge that there is no assurance that additional funding will be available in the event of Project delay.</li> </ul>
<b>Owner's Representative/Project Manager Costs:</b>	<ul style="list-style-type: none"> <li><u>Allocation</u> - The \$7,504,081 in owner's representative/project manager costs included in the Preliminary Project Budget is allocated as follows: <ul style="list-style-type: none"> <li>Pre-Con project Management – Authority: \$2,317,500</li> <li>Pre-Con project Management –Team: \$1,594,081</li> <li>Construction Management: \$3,592,500</li> </ul> </li> </ul>
<b>Project Management Accounting/Reporting Costs:</b>	<ul style="list-style-type: none"> <li><u>Costs Included in Project Costs</u> - Project management accounting/reporting software or services cost will be included as Project Costs.</li> <li><u>Preliminary Allocation</u> – Two Million Four Hundred Thirty Thousand Dollars (\$2.430 million).</li> </ul>
<b>Project Cost Budget Allocation:</b>	<ul style="list-style-type: none"> <li><u>Project Consultant Allocation</u> - The Authority and the Team will be allocated the following costs out of the Preliminary Project Budget and the Master Project Budget, as applicable, for their consultants: <ul style="list-style-type: none"> <li>Authority – \$3,465,000</li> <li>Team – \$1,035,000</li> </ul> </li> <li><u>Legal Services Allocation</u> – Nine Hundred Thousand Dollars (\$900,000) each will be allocated in the budget on behalf of the Authority and the Team (One Million Eight Hundred Thousand Dollars (\$1.8 million) in total) for their respective legal services.</li> </ul>

<b>Capital Reserves:</b>	<ul style="list-style-type: none"> <li>• [RESERVED]</li> </ul>
<b>TCF Bank Stadium – Team Project Costs:</b>	<ul style="list-style-type: none"> <li>• <u>Project Cost Maximum for First Two Years at TCF Stadium</u> – The maximum amount allocated to the funds expendable for the first two (2) years at TCF Stadium will not exceed Seven Million Nine Hundred Ninety Seven Thousand Four Hundred Fifty Four Dollars (\$7,997,454). The expenditures have been designated by category of expenditure for convenience only; amounts may be transferred freely by the Team between the categories for allocation purposes. If the Team has not utilized the full amount of the Seven Million Nine Hundred Ninety Seven Thousand Four Hundred Fifty Four Dollars (\$7,997,454) allocated funding amount for such two (2) year period, the amount not utilized shall be deemed Cost Savings subject to the apportionment and use requirements set forth in <u>Section 8.1(e)</u> of the Development Agreement.</li> <li>• <u>Public Purpose</u> – The Parties have made, and the SDC Group shall make, a specific finding that the Team’s TCF Bank Stadium Project Costs as described herein serve the public purpose intended by the statute. The Team’s TCF Bank Stadium costs would not be incurred “but for” the Authority’s need to relocate the Vikings from the Mall of America Field at the Metrodome to another stadium for the purpose of building the Stadium and Stadium Infrastructure. The Parties and the SDC Group actively will support this position with the legislative auditor, in legislative hearings and any court action, and in any other venues.</li> <li>• <u>Team Funds</u> – The Parties agree that the funds to pay the Team’s TCF Bank Stadium Project Costs shall be paid from the funding for the Project provided by the Team.</li> </ul>
<b>Stadium Pre-Marketing Costs:</b>	<ul style="list-style-type: none"> <li>• <u>Authority Allocation</u> – The Authority will be allocated Two Hundred Twenty-Five Thousand Dollars (\$225,000) out of Project Costs for pre-marketing of the Stadium for non-Team events.</li> <li>• <u>Team Allocation</u> – The Team will be allocated Six-Hundred Seventy-Five Thousand Dollars (\$675,000) for Stadium sales and marketing (including costs incurred by the Team acting as agent for the Authority). The Team will be allocated One Million Four Hundred Eighty-Eight Thousand Four Hundred Nineteen Dollars (\$1,488,419) for Stadium suite prototype mock-up/sales center, which sum is and will continue to be included in the Fixed Construction Budget, as such term is defined in the Construction Services Agreement. The Team shall remain responsible for cost overruns for change orders that cause the construction costs for the Stadium suite prototype mock-up/sales center to exceed the established budget of \$1,488,419.</li> </ul>

**EXHIBIT I-1****AUTHORITY DESIGN ADD ALTERNATES**

<b>Joint Priority Items</b>	<b>Estimated Costs (millions)</b>
Two (2) Sets of Escalators	\$1.1
One (1) Freight Elevator	\$0.6
Laundry and Hydro Equipment	\$0.2
Incremental Allocation to the Retractable Bowl Seating System	\$1.3
Finish Out Two (2) Auxiliary Locker Rooms	\$0.9
East Relief Louvers	\$1.2
<b>Total</b>	<b>\$5.3</b>

<b>Other Items</b>	<b>Estimated Costs (millions)</b>
Change Field Slab back to CIP Concrete	\$0.3
Fifty Percent (50%) event level corridor crash barrier	\$0.1
19,520 SF Sub-roof	\$0.5
Sub Roof Drains	\$0.2
Minor Mechanical or Electrical Items	\$0.5
<b>Total</b>	<b>\$1.6</b>

<b>Cumulative Total</b>	<b>\$6.9</b>
-------------------------	--------------

**EXHIBIT I-2****TEAM DESIGN ADD ALTERNATES**

<b>Joint Priority Items</b>	<b>Estimated Costs (millions)</b>
Two (2) Sets of Escalators	\$1.1
One (1) Freight Elevator	\$0.6
Laundry and Hydro Equipment	\$0.2
Incremental Allocation to the Retractable Bowl Seating System	\$1.3
Finish Out Two (2) Auxiliary Locker Rooms	\$0.9
East Relief Louvers	\$1.2
<b>Total</b>	<b>\$5.3</b>

<b>Other Items</b>	<b>Estimated Costs (millions)</b>
Bowl Lounge Seating – Club Purple	\$1.0
Add Back Clerestory – South Side	\$0.2
Media Mesh Displays – West and East	\$2.0
Media Mesh Infrastructure	\$0.2
Sound System - Exterior Plaza	\$0.4
Redundant Backbone Segment	\$0.4
Add Video Walls in Fire and Ice Clubs	\$0.6
Add Second Ribbon Board	\$1.8
Second Turf & Storage System	\$1.3
Concessionaire Contribution	\$3.5
Build Out 8 Sideline Mini Suites	\$0.6
Build Out 10 Upper Level Suites	\$1.3
1010 Skyway	\$3.5
Event Level Parking	\$0.1
Sponsor Provide Wifi	\$4.0
Large West Video Board (120x68)	\$0.6
Large Operable Doors (275x95))	\$2.5
Lower Club Lounge Finish Out	\$0.3
Chairman's Lounge Finish Out	\$0.9
Electrochromic Glass in Interview Room	\$0.1
Build Out Cheerleaders Locker Room	\$0.4
Change to Automatic Faucets in GA Bathrooms	\$0.3
Change Upper Bowl Duct Configuration	\$1.4
Block 7 Parking Garage	\$12.4
Expand North and South Eyebrows in Design	\$0.3
Third Ribbon Board	\$1.8
<b>Total</b>	<b>\$41.90</b>

<b>Cumulative Total From Above</b>	<b>\$47.20</b>
------------------------------------	----------------

Other Items (Continued)	
<p>In addition to those items set forth above in this <u>Exhibit I-2</u>, each of the items set forth in (i) the "Should be Removed" column of the Mortenson 100% CD Trend Log dated July 25, 2014, attached as Exhibit B to Contract Revision No. 016 to the Construction Service Agreement dated August 22, 2014, (ii) the "Adjustment to Accepted Values" column of the Mortenson Potential Cost Reductions document dated July 25, 2014, attached as Exhibit C to Contract Revision No. 016 to the Construction Service Agreement dated August 22, 2014, and (iii) Exhibit H to Contract Revision No. 016 to the Construction Service Agreement dated August 22, 2014, each of which is hereby incorporated by reference as if fully set forth herein, are and will be considered Team Design Add Alternates.</p>	

**EXHIBIT I-3****AUTHORITY PROJECT COST ALLOCATION REDUCTIONS**

<b>ITEM</b>	<b>Amount</b>
MSFA Project Consultants	\$385,000
Pre-Con Project Management – MSFA	\$257,500
Construction Management	\$399,168
Project Legal Services – MSFA	\$100,000
Capital Reserves – MSFA	\$500,000
<b>TOTAL</b>	<b>\$1,641,668</b>

**EXHIBIT I-4****TEAM PROJECT COST ALLOCATION REDUCTIONS**

<b>ITEM</b>	<b>Amount</b>
TCF – Stadium Improvements, Portables, Non-Capitals and Variable Costs	\$26,700,000
Team Project Consultants	\$115,000
Pre-Con Project Management – Team	\$257,500
Project Legal Services – Team	\$100,000
Sales/Marketing – Team	\$75,000
Market Studies – Team	\$25,000
Sales Office / Suite Mock-up – Team	\$60,000
<b>TOTAL</b>	<b>\$27,332,500</b>

**EXHIBIT J**

**IRREVOCABLE LETTER OF CREDIT**

**SEE ATTACHED**



**EXECUTION COPY**

W&W FINAL DRAFT:

**U.S. Bank National Association**

Standby Letters of Credit: BC-MN-H20G  
800 Nicollet Mall  
Minneapolis, Minnesota 55402

SWIFT: USBKUS44

TELEX:

Phone: 866-359-2503 x 5854

612-303-7395

Fax: 612-303-5226

November 22, 2013

U.S. Bank National Association

EP-MN-WS3C

60 Livingston Avenue

St. Paul, MN 55107

We hereby establish our Irrevocable Standby Letter of Credit No. SLCMMSP07103 for the account of Zygmunt Wilf, Mark Wilf and Leonard Wilf (individually and collectively, the "Applicant"), in your favor as Trustee under that Amended and Restated Construction Funds Trust and Disbursement Agreement, dated as of November 22, 2013, as thereafter amended or supplemented (the "Agreement") by and among Minnesota Sports Facility Authority (the "Authority"), Minnesota Vikings Football Stadium, LLC and you, as Trustee, in accordance with the following terms and conditions. The maximum aggregate amount available to be drawn under this Letter of Credit is TWENTY-FIVE MILLION DOLLARS (\$25,000,000), which amount, as from time to time permanently reduced as provided in the next-following paragraph hereof, is referred to as the "Stated Amount." Partial and multiple drawings are permitted hereunder.

Concurrently with the honoring of a drawing hereunder, the Stated Amount shall be permanently reduced without amendment by the amount of such drawing. The Stated Amount shall also be permanently reduced upon our receipt of a certificate in the form of Annex A attached hereto (a "Reduction Certificate"), duly completed and signed by your authorized signer.

Drafts on us at sight must be accompanied a draft in the form of Annex B attached hereto, duly completed and a draw certificate (signed by your authorized signer) in the form of Annex C attached hereto.

This Letter of Credit expires at the earlier of (a) 4:00 p.m. central time on November 21, 2014, *provided*, that if this Letter of Credit has not been drawn in full on or prior to such expiration date (or on or prior to any successive expiration date), the expiration date of this Letter of Credit will automatically extend without amendment for an additional period of one year from the expiration date then in effect unless not less than thirty days prior to such expiration date we notify you in writing that we elect not to so extend this Letter of Credit, *provided, further*, that, notwithstanding the foregoing, the final expiration date of this Letter of Credit shall not be later than November 21, 2016, or (b) such time as the Stated Amount shall be reduced to \$0 by any combination of drawings hereunder and reductions upon our receipt of Reduction Certificates.

We hereby agree with drawers that drafts and documents as specified above will be duly honored upon presentation to U.S. Bank National Association, 800 Nicollet Mall, attn: Standby Letters of Credit BC-MN-H20G, Minneapolis, Minnesota 55402, if presented on or before the expiration date then in effect.

Notices hereunder shall be sent by registered mail or overnight courier to (a) you at your address set forth above, and (b) to us at U.S. Bank National Association, 800 Nicollet Mall, attn: Standby Letters of Credit BC-MN-H20G, Minneapolis, Minnesota 55402.

This Letter of Credit is successively transferable in its entirety (but not in part) to a successor Trustee under the Agreement upon receipt by us of your written request for such transfer in the form of Annex D

## EXECUTION COPY

attached hereto, addressed to us and certifying that the transferee is a successor Trustee under the Agreement, accompanied by presentation to us of this original Letter of Credit and payment of our transfer fee as set forth in such form. Upon effectiveness of such transfer, all references to the prior Trustee's name in this Letter of Credit shall be deemed to refer to such transferee's name, and all notices under this Letter of Credit shall be given to such transferee at the address provided in Annex D.

This Letter of Credit sets forth in full terms of our obligation to you, and such undertaking shall not in any way be modified or amplified by any agreement in which this Letter of Credit is referred to or to which this Letter of Credit relates, and any such reference shall not be deemed to incorporate herein by reference any agreement.

Pursuant to U.S. Law, we are required to obtain, verify and record information that identifies parties to the transaction and we are prohibited from issuing, transferring, accepting, or effecting payment to any party or entity identified by the U.S. Department of Treasury including any office and bureau thereof or subject to the denial of export privileges by the U.S. Department of Commerce.

This credit is subject to the International Standby Practices (ISP98), International Chamber of Commerce Publication Number 590, or any subsequent revision thereto.

U.S. Bank National Association

---

Authorized Signature

8508771v6

ANNEX A

REDUCTION CERTIFICATE

Re: U.S. Bank National Association  
Letter of Credit No. SLCMMSP07103

The undersigned, a duly authorized officer of U.S. Bank National Association, a national banking association, as trustee (the "Trustee") under that certain Amended and Restated Construction Funds Trust and Disbursement Agreement dated as of November 22, 2013 (as thereafter amended or supplemented, the "Agreement"), by and among the Trustee, Minnesota Sports Facilities Authority and Minnesota Vikings Football Stadium, LLC, hereby certifies to U.S. Bank National Association, a national banking association, in its capacity as letter of credit issuer (the "Bank"), with reference to the Letter of Credit identified above, issued by the Bank in favor of the Trustee as beneficiary (the "Letter of Credit"), that:

1. On or about the date hereof \$[\_\_\_\_\_] has been deposited in the Equity Direct Contribution Subaccount (as defined in the Agreement) which amount was not counted as part of the Team Initial Payment (as defined in the Agreement).
2. Pursuant to the Letter of Credit, upon receipt by the Bank of this Certificate, the Stated Amount of the Letter of Credit shall be reduced by the amount set forth in paragraph 1 to a new total of \_\_\_\_\_ DOLLARS (\$\_\_\_\_\_).

IN WITNESS WHEREOF, the Trustee has executed and delivered this Certificate as of the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_.

U.S. Bank National Association,  
as trustee

By: \_\_\_\_\_  
Name: \_\_\_\_\_  
Title: \_\_\_\_\_

ANNEX B

SIGHT DRAFT

\_\_\_\_\_, 20\_\_

Drawn Under U.S. Bank National Association Letter of Credit No. SLCMMSP07103, dated as of November 22, 2013

At Sight

Pay to: U.S. Bank National Association, as Trustee, under the Amended and Restated Construction Funds Trust and Disbursement Agreement, dated as of November 22, 2013, as thereafter amended or supplemented, by and among Minnesota Vikings Football Stadium, LLC, Minnesota Sports Facilities Authority, and U.S. Bank National Association, as Trustee, the amount of:

\_\_\_\_\_ DOLLARS (\$\_\_\_\_\_)

U.S. Bank National Association,  
as Trustee

By: \_\_\_\_\_  
Name: \_\_\_\_\_  
Title: \_\_\_\_\_

ANNEX C

DRAW CERTIFICATE

Re: U.S. Bank National Association  
Letter of Credit No. SLCMMSP07103

The undersigned, a duly authorized officer of U.S. Bank National Association, a national banking association, as trustee (the "Trustee") under that certain Amended and Restated Construction Funds Trust and Disbursement Agreement dated as of November 22, 2013 (as thereafter amended or supplemented, the "Agreement"), by and among the Trustee, Minnesota Sports Facilities Authority, a public body and political subdivision of the State of Minnesota (the "Authority"), and Minnesota Vikings Football Stadium, LLC, a Delaware limited liability company, hereby certifies to U.S. Bank National Association, a national banking association, in its capacity as letter of credit issuer (the "Bank"), with reference to the Letter of Credit identified above, issued by the Bank in favor of the Trustee as beneficiary (the "Letter of Credit"), that:

1. The Trustee is the Trustee under the Agreement.
2. Check either (a) or (b) (and not both) as applicable:  
  
    \_\_\_ (a) The Trustee is in receipt of a certificate dated on or about the date hereof, duly executed by an authorized officer of the Authority and duly notarized, in the form attached as Exhibit B-2 to the Agreement (the "Authority Certificate"). Funds drawn under this paragraph (a) will be credited by the Trustee to the Equity Letter of Credit Subaccount under the Agreement.  
  
    \_\_\_ (b) The Letter of Credit expires within fifteen (15) days after the date of this certificate and the sight draft presented herewith and has not been extended or replaced by a Substitute Letter of Credit under the terms of the Agreement. Funds drawn under this paragraph (b) will be credited by the Trustee to the Equity Letter of Credit Termination Subaccount under the Agreement.
3. The amount of the sight draft accompanying this Certificate is \$\_\_\_\_\_, which is equal to the lesser of:  
  
    (a) either (i) the applicable amount described in paragraph 6 of the Authority Certificate if 2(a) above is checked, or (ii) the Stated Amount of the Letter of Credit if 2(b) above is checked, and  
  
    (b) the Stated Amount of the Letter of Credit as of the date hereof, *minus* any amounts deposited in the Equity Direct Contribution Subaccount (as defined in the Agreement) that would have caused the Trustee to deliver a certificate in the form of Annex A to the Letter of Credit, but for which such a certificate has not yet been delivered by the Trustee or processed by the Bank.
4. Pursuant to the Letter of Credit, upon the honoring by the Bank of the sight draft accompanying this Certificate, the Stated Amount of the Letter of Credit shall be reduced by the amount set forth in Paragraph 3 to a new total of \_\_\_\_\_ Dollars (\$\_\_\_\_\_).

**EXECUTION COPY**

5. The amount of the sight draft accompanying this Certificate shall be paid to the Trustee, by wire transfer to: [ ]

IN WITNESS WHEREOF, the Trustee has executed and delivered this Certificate as of the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_.

U.S. Bank National Association,  
as trustee

By: \_\_\_\_\_  
Name: \_\_\_\_\_  
Title: \_\_\_\_\_

ANNEX D

TRANSFER OF LETTER OF CREDIT IN ITS ENTIRETY  
STANDBY LETTER OF CREDIT NO. XXXXXXXXXX

\_\_\_\_\_, 2013

TO: U.S. BANK NATIONAL ASSOCIATION  
800 Nicollet Mall, BC-MN-H20G  
Minneapolis, Minnesota 55402  
866-359-2503 x 5854/612-303-7395

FROM: [Name and address of present  
beneficiary]

Re: Letter of Credit No. SLCMMSP07103

Issued by: U.S. Bank National Association

We, the undersigned beneficiary, hereby authorize and direct you to transfer irrevocably the referenced letter of credit in its entirety

To:

Whose Address is:

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

(Herein called the "transferee") with no changes in terms and conditions of the Letter of Credit.

We are returning the original instrument, including original amendments, if any, to you herewith in order that you may deliver it to the transferee together with your customary Letter of Transfer. Enclosed is our check/draft for the transfer fee of 0.10% of the face amount of the letter of credit (minimum \$1,000.00).

Any amendments to the Letter of Credit that you may issue or receive are to be advised by you directly to the transferee, and the documents (including drafts if required under the Credit) of the transferee are to be processed by you (or any intermediary) without our intervention and without any further responsibility on your part to us.

We understand that pursuant to U.S. Law, you are required to obtain, verify and record information that identifies parties to the transaction and you are prohibited from issuing, transferring, accepting, or effecting payment to any party or entity identified by the U.S. Department of Treasury including any office and bureau thereof or subject to the denial of export privileges by the U.S. Department of Commerce.

U.S. Bank National Association,  
as Trustee

By: \_\_\_\_\_

Name: \_\_\_\_\_

Authorized Signatory

Title: \_\_\_\_\_

J-1-8

## EXECUTION COPY

\*\*The signature of the beneficiary with title as stated conforms with that on file with us and is authorized for the execution of such instruction.

\_\_\_\_\_  
(Official Bank Stamp)

\_\_\_\_\_  
(Name of Bank)

\_\_\_\_\_  
(Address of Bank)

By:

\_\_\_\_\_  
(Authorized Signature)

\_\_\_\_\_  
(Title)

\_\_\_\_\_  
(Telephone Number)

Date:

\_\_\_\_\_



**EXHIBIT K**

**FORM OF BANK LOAN COMMITMENT ACKNOWLEDGEMENT**

**SEE ATTACHED**

### **Acknowledgment of the Authority**

Reference is made to the Development Agreement, dated as of the date hereof, by and between Minnesota Sports Facilities Authority, a public body and political subdivision of the State of Minnesota (the “**Authority**”), and Minnesota Vikings Football, LLC, a Delaware limited liability company (the “**Team**”) (the “**Development Agreement**”). Capitalized terms used but not otherwise defined herein are defined in the Development Agreement.

This Acknowledgment (the “**Acknowledgment**”) is executed and delivered in connection with the Development Agreement by the Authority for the benefit of Minnesota Stadium Funding Trust, a bankruptcy remote special purpose Delaware statutory trust (the “**Borrower**”), Minnesota Vikings Football Stadium, LLC, a bankruptcy remote special purpose Delaware limited liability company (“**StadCo**”), the Team, U.S. Bank National Association (“**U.S. Bank**”), Goldman Sachs Bank USA (“**Goldman Sachs**”), Merrill Lynch, Pierce, Fenner & Smith Incorporated (“**MLPFS**”), Bank of America, N.A. (“**BOA**”) and Sumitomo Mitsui Banking Corporation (“**SMBC**” and together with U.S. Bank, Goldman Sachs, MLPFS and BOA, the “**Commitment Parties**”).

By executing and delivering this Acknowledgment, the Authority hereby acknowledges and agrees that (i) the Authority has received and reviewed the terms contained in Annex B and Annex C to the Bank Loan Commitment and advises the Borrower, StadCo, the Team and the Commitment Parties that the terms of the financing to be provided to finance all or a portion of the Team/Private Contribution described in Annex B and Annex C to the Bank Loan Commitment are satisfactory to the Authority, (ii) the Authority shall negotiate in good faith such agreements as are required to evidence its role described in Annex B and Annex C to the Bank Loan Commitment, and (iii) the Authority shall reflect the assignment and sale of the SBL Revenues (as defined in Annex B to the Bank Loan Commitment) on its books and records, including its financial statements, as a true sale.

In addition, by executing and delivering this Acknowledgment, the Authority hereby acknowledges and agrees that (i) in connection with the syndication of the loans contemplated by the Bank Loan Commitment, StadCo and the Borrower may reasonably request the cooperation of the Authority in the preparation of syndication materials and attendance at lender meetings, which cooperation the Authority will provide as contemplated by the Development Agreement, (ii) the Commitment Parties will rely on the accuracy of the information provided by the Authority without independent verification thereof, (iii) none of the Commitment Parties have assumed (A) an advisory responsibility in favor of the Authority or its affiliates with respect to the financing transactions contemplated by the Bank Loan Commitment, (B) a fiduciary responsibility in favor of the Authority or its affiliates with respect to the transactions contemplated thereby, except to the extent of any fiduciary duties arising in connection with U.S. Bank’s service as construction funds trustee in connection with the transactions contemplated thereby, or (C) any other obligation to the Authority in connection with the transactions contemplated thereby.

Each Commitment Party hereby notifies the Authority that pursuant to the requirements of the USA PATRIOT Act (Title III of Pub. L. 107 56 (signed into law October 26, 2001)) (the “Patriot”

Act”) such Commitment Party and each lender may be required to obtain, verify and record information that identifies the Authority, which information includes the name and address of the Authority and other information that will allow such Commitment Party and each lender to identify the Authority in accordance with the Patriot Act. This notice is given in accordance with the requirements of the Patriot Act and is effective for each Commitment Party and each lender.

**ACKNOWLEDGED AND AGREED:**

**MINNESOTA SPORTS FACILITIES AUTHORITY**

By:\_\_\_\_\_

Name:

Title:

Date:\_\_\_\_\_

**EXHIBIT L-1**

**INDEMNIFICATION AND CONTRIBUTION AGREEMENT**

**SEE ATTACHED**

## INDEMNIFICATION CONTRIBUTION AGREEMENT

### (Commitment Letter)

THIS INDEMNIFICATION CONTRIBUTION AGREEMENT (this “*Agreement*”), dated as of November 6, 2013, is made by and among MINNESOTA VIKINGS FOOTBALL STADIUM, LLC, a Delaware limited liability company (the “*Company*”), MINNESOTA STADIUM FUNDING TRUST, a Delaware statutory trust (the “*Borrower*”), and MINNESOTA SPORTS FACILITIES AUTHORITY, a public body and political subdivision of the State of Minnesota (the “*Authority*” and, together with the Borrower and the Company, the “*Parties*”).

### RECITALS:

A. The Company and the Borrower are parties to that certain Commitment Letter dated as of November 6, 2013 (inclusive of Annexes A, B and C attached thereto, the “*Commitment Letter*”) among the Company, the Borrower, U.S. Bank National Association (“*U.S. Bank*”), Goldman Sachs Bank USA (“*Goldman Sachs*”), Merrill Lynch, Pierce, Fenner & Smith Incorporated (“*MLPFS*”), Bank of America (“*BOA*”), and Sumitomo Mitsui Banking Corporation (“*SMBC*”, and together with U.S. Bank, Goldman Sachs, MLPFS and BOA, the “*Commitment Indemnified Parties*”). Capitalized terms used herein and not otherwise defined herein shall have the respective meanings provided in the Commitment Letter.

B. The Commitment Letter provides for joint and several obligations of the Company and the Borrower to the Commitment Indemnified Parties, and the Parties desire to have any and all indemnity claims brought against the Company or the Borrower under the Commitment Letter pursuant to which a claim is asserted against either or both of Borrower and Company by a Commitment Indemnified Party treated in the manner hereinafter set forth.

### AGREEMENTS:

NOW, THEREFORE, the Parties, intending to be legally bound, and for good and adequate consideration, the sufficiency of which is hereby acknowledged, hereby agree as follows:

1. **Indemnification Contribution; Limited Borrower and Authority Obligations.**

(a) (i) *Company Obligations.* Subject to the limited contribution obligations of the Borrower set forth in Section 1(a)(ii) and of the Authority set forth in Section 1(a)(iii), the Company hereby agrees to bear such claims by any Commitment Indemnified Party pursuant to Section 5 (incorporating Annex A) of the Commitment Letter, but only to the extent arising with respect to the Commitment Letter itself (the amount of any claim, in each case, “*Indemnifiable Damages*”). Such obligations shall exist without regard to which Party or Parties the claim is made against.

(ii) *Borrower Obligation.* Subject to the obligations of the Company set forth in Section 1(a)(i) and the limited contribution obligations of the Authority set forth

in Section 1(a)(iii), the Borrower hereby agrees to contribute an amount sufficient to provide for payment of the Indemnifiable Damages (x) in whole, to the extent that the Indemnifiable Damages result solely from the action or inaction of the Borrower, and (y) in part, in proportion to the Borrower's relative fault as determined among the Parties, to the extent that the Indemnifiable Damages results from the action or inaction of the Borrower and one or more of the other Parties. Such obligations shall exist without regard to which Party or Parties the claim is made against.

(iii) *Authority Obligation.* Subject to the obligations of the Company set forth in Section 1(a)(i) and the limited contribution obligations of the Borrower set forth in Section 1(a)(ii), the Authority hereby agrees to contribute an amount sufficient to provide for payment of the Indemnifiable Damages (x) in whole, to the extent that the Indemnifiable Damages result solely from the gross negligence or willful misconduct of the Authority as determined by the final, nonappealable judgment of a court of competent jurisdiction, and (y) in part, in proportion to the Authority's relative fault as determined among the Parties (to the extent that the Indemnifiable Damages result from the gross negligence or willful misconduct of the Authority as determined by the final, nonappealable judgment of a court of competent jurisdiction) and the actions or inactions of one or more of the other Parties. Such obligations shall exist without regard to which Party or Parties the claim is made against.

(b) Notwithstanding anything in this Agreement to the contrary, a Party shall not have any obligation to bear any Indemnifiable Damages relating to, arising from, or in connection with (i) the breach by any other Party of any representation or warranty regarding such other Party set forth in the Commitment Letter, if such representation and warranty was known by such other Party to be untrue when made, or (ii) any claim that is based upon any fraudulent, grossly negligent or intentional misconduct (including the failure to act) by such other Parties.

(c) In the event that any Party initially pays more than its applicable share of Indemnifiable Damages, then the Parties shall make such payments to each other such that the net payments reflect their applicable, respective shares.

(d) In the event a Party shall have made payment of its applicable share of Indemnifiable Damages and, subsequent to such payment, there shall be the recovery or receipt of payment respecting the previously paid claim by any Party, the effect of which is to reduce the amount of funds previously paid with respect to such claim, whether by the recovery of insurance proceeds, third party indemnification or otherwise, then the aggregate amount so recovered or received shall be shared among the Parties, in proportion to their payments and shall be paid to the other Parties within ten (10) days after the date upon which such amount shall be received.

## **2. Settlement of Claims.**

Any Party which receives notice of a claim for Indemnifiable Damages from a Commitment Indemnified Party pursuant to the Commitment Letter shall give prompt written notice thereof and a copy of such notice to the other Parties. If a Party has an obligation for the

payment of an indemnification contribution pursuant to Section 1(a) above, such Party shall cooperate with the other Parties in connection with the defense and settlement of the claims pursuant to the Commitment Letter with respect to which such contribution obligation applies. The Party from whom contribution is sought will be entitled (but not obligated) to participate in any negotiations to settle or otherwise resolve any claim for which contribution is sought. No Party shall settle any such claim, or agree to settle any such claim, without the prior written consent of the other Parties, unless such settling Party waives its right to contribution hereunder against the other Parties, and any settlement made in violation of this restriction, without notice or the obligation of any party to perform any act, shall have the immediate and irrevocable effect of fully releasing and discharging such non-consenting Parties from any obligation to make payment hereunder with respect to the settled claims.

**3. Authority; No Conflict.**

Each Party represents and warrants to the other Parties that (a) it has full capacity and power to execute, deliver and perform this Agreement, (b) this Agreement has been duly executed and delivered by such Party, and is enforceable against such Party in accordance with its terms, and (c) the obligations of such Party hereunder do not and will not conflict with any law, rule or statute applicable to such Party or create a breach or default under any material agreement to which such Party is a party.

**4. Binding Effect; Assignment.**

This Agreement shall be binding upon and inure to the benefit of the Parties and their respective successors and assigns. Notwithstanding any provision to the contrary in this Agreement, no member, officer, official, councilmember, commissioner, partner, employee, shareholder, manager, director or agent (as applicable) of a Party shall be personally liable to any other Party (or any of their respective successors-in-interest) under Section 1(a) of this Agreement. No Party shall assign its obligations under this Agreement without the prior written consent of the other Parties.

It is expressly understood and agreed by the Parties that (a) this Agreement is executed and delivered by Wilmington Trust, National Association (the "*Trustee*"), not individually or personally but solely as trustee of the Borrower, in the exercise of the powers and authority conferred and vested in it under that certain Trust Agreement dated as of October 10, 2013 among the Company, as trust depositor, and the Trustee, as owner trustee (the "*Trust Agreement*"), (b) each of the representations, undertakings and agreements herein made on the part of the Borrower is made and intended not as personal representations, undertakings and agreements by the Trustee but is made and intended for the purpose for binding only the Borrower, (c) nothing herein contained shall be construed as creating any liability on the Trustee, individually or personally, to perform any covenant either express or implied contained herein, all such liability, if any, being expressly waived by the parties hereto and any person claiming by, through or under the parties hereto, and (d) under no circumstances shall the Trustee be personally liable for the payment of any amount to be paid by the Borrower pursuant to the terms hereof or be liable for the breach or failure of any obligation, representation, warranty or covenant made or undertaken by the Borrower hereunder.

**5. Severability.**

Each provision of this Agreement constitutes a separate and distinct undertaking, covenant and provision with respect to the Parties. In the event that one or more provisions of this Agreement are held illegal or unenforceable with respect to any Party, such provisions shall be deemed severed and the remaining provisions of this Agreement shall survive and remain fully enforceable against the Parties. The determination that any one or more provisions of this Agreement are illegal or unenforceable with respect to any Party shall not be construed to mean that any such provision is illegal or unenforceable with respect to the other Parties.

**6. Construction.**

This Agreement shall be construed in accordance with and governed for all purposes by the laws of the State of Minnesota without regard to principles of conflicts of laws. The captions in this Agreement are for convenience only and shall not be construed to limit or otherwise affect the meaning of any term or provision of this Agreement. Unless otherwise stated, section references refer to the sections of this Agreement.

**7. Notices.**

Any notice to be given to the Parties shall be made in writing and shall be addressed to the Parties at the addresses set forth on the signature page hereto, or at such other address provided in writing by a Party to the other Parties.

**8. Termination.**

This Agreement shall terminate and be of no further force or effect upon the execution and delivery (a) by the Company and the Borrower of the credit agreement for the Senior Secured Facility, described in the Commitment Letter, (b) by the Authority and the Borrower of the Sale Agreement described in the Commitment Letter, and (c) by the Authority and Minnesota Vikings Football, LLC, a Delaware limited liability company, or its designee, of the SBL Marketing and Sales Agreement described in the Commitment Letter; provided, no such termination shall affect the liabilities and obligations of any Party hereunder with respect to any claim for Indemnifiable Damages arising or accruing prior to the date of such termination.

*[Remainder of page left blank;  
signature pages follow]*



**EXECUTION COPY**

IN WITNESS WHEREOF, the Parties have executed this Agreement as of the date first written above.

MINNESOTA STADIUM FUNDING TRUST, a  
Delaware statutory trust

By: Wilmington Trust, national association,  
not in its individual capacity but solely as  
Trustee

By: \_\_\_\_\_  
Name: \_\_\_\_\_  
Title: \_\_\_\_\_

Address for Notices:  
Minnesota Stadium Funding Trust  
c/o Wilmington Trust, National Association  
Rodney Square North  
1100 North Market Street  
Wilmington, Delaware 19890-0001  
Attention: Corporate Trust Administration

SIGNATURE PAGE 1 TO INDEMNIFICATION CONTRIBUTION AGREEMENT (Commitment Letter)

**EXECUTION COPY**

MINNESOTA VIKINGS FOOTBALL STADIUM,  
LLC, a Delaware limited liability company

By: \_\_\_\_\_

Name: Mark Wilf

Title: President

Address for Notices:

Minnesota Vikings Football Stadium, LLC

c/o Minnesota Vikings Football, LLC

9520 Viking Drive

Eden Prairie, MN 55344

Attention: Chief Financial Officer

SIGNATURE PAGE 2 TO INDEMNIFICATION CONTRIBUTION AGREEMENT (Commitment Letter)

L-1-7

**EXECUTION COPY**

MINNESOTA SPORTS FACILITIES AUTHORITY, a  
public body and political subdivision of the  
State of Minnesota

By: \_\_\_\_\_  
Name: Michele Kelm-Helgen  
Title: Chair

By: \_\_\_\_\_  
Name: Ted Mondale  
Title: CEO / Executive Director

Address for Notices:  
Minnesota Sports Facilities Authority  
Mall of America Field  
900 South Fifth Street  
Minneapolis, MN 55415  
Attention: Executive Director

SIGNATURE PAGE 3 TO INDEMNIFICATION CONTRIBUTION AGREEMENT (Commitment Letter)

**EXHIBIT L-2**

**INDEMNIFICATION AND CONTRIBUTION AGREEMENT**

**SEE ATTACHED**

## INDEMNIFICATION CONTRIBUTION AGREEMENT

### (Purchase and Sale Agreement)

THIS INDEMNIFICATION CONTRIBUTION AGREEMENT (this “*Agreement*”), dated as of November 22, 2013, is made by and among MINNESOTA VIKINGS FOOTBALL STADIUM, LLC, a Delaware limited liability company (“*Stadco*”), MINNESOTA VIKINGS FOOTBALL, LLC, a Delaware limited liability company (the “*Team*”), and MINNESOTA SPORTS FACILITIES AUTHORITY, a public body and political subdivision of the State of Minnesota (the “*Authority*”; *Stadco*, the *Team* and the *Authority* may be referred to herein collectively as the “*Parties*” and separately and without distinction as a “*Party*”),.

### RECITALS:

A. The Authority and Minnesota Stadium Fund Trust, a Delaware statutory trust (“*Finco*”) are parties to that certain Purchase and Sale Agreement dated of even date with this Agreement] (the “*Purchase and Sale Agreement*”). Capitalized terms used herein and not otherwise defined herein shall have the respective meanings provided in the Purchase and Sale Agreement.

B. The Purchase and Sale Agreement provides for indemnification obligations of the Authority to Finco, and the Parties desire to have certain indemnity claims brought against the Authority by Finco under the Purchase and Sale Agreement, or which would be eligible as indemnity claims brought against the Authority by Finco under the Purchase and Sale Agreement but which are, in fact, brought against Stadco, treated in the manner hereinafter set forth.

### AGREEMENTS:

NOW, THEREFORE, the Parties, intending to be legally bound, and for good and adequate consideration, the sufficiency of which is hereby acknowledged, hereby agree as follows:

1. **Indemnification Contribution; Limited Authority Obligations.**

(a) (i) *Stadco and Team Obligations.* Stadco and the Team jointly and severally agree to contribute to the Authority an amount sufficient to provide for payment of claims against the Authority arising under Article VII of the Purchase and Sale Agreement (x) in whole where such claims do not result in any part from the gross negligence or willful misconduct of the Authority as determined by the final, nonappealable judgment of a court of competent jurisdiction, and (y) in part, where such claims result in part from the gross negligence or willful misconduct of the Authority as determined by the final, nonappealable judgment of a court of competent jurisdiction, such contribution to be made only to the extent the claims did not result from the gross negligence or willful misconduct of the Authority as determined by the final,

nonappealable judgment of a court of competent jurisdiction (the claims described in clauses (x) and (y) of this Section 1(a)(i), “*Authority Indemnifiable Damages*”).

(ii) *Authority Obligation*. The Authority hereby agrees to contribute to Stadco an amount sufficient to provide for payment of claims against Stadco to the extent and only to the extent such claims could have been brought by Finco against the Authority under Article VII of the Purchase and Sale Agreement (x) in whole where such claims result entirely from the gross negligence or willful misconduct of the Authority as determined by the final, nonappealable judgment of a court of competent jurisdiction, and (y) in part, where such claims result in part from the gross negligence or willful misconduct of the Authority as determined by the final, nonappealable judgment of a court of competent jurisdiction, such contribution to be made only to the extent the claims result from the gross negligence or willful misconduct of the Authority as determined by the final, nonappealable judgment of a court of competent jurisdiction (the claims described in clauses (x) and (y) of this Section 1(a)(i), “*Stadco Indemnifiable Damages*,” the Authority Identifiable Damages and the Stadco Indemnifiable Damages may be referred to herein collectively as the “*Indemnifiable Damages*”).

(b) Notwithstanding anything in this Agreement to the contrary, a Party shall not have any obligation to bear any Indemnifiable Damages relating to, arising from, or in connection with (i) the breach by any other Party of any representation or warranty regarding such other Party set forth in the Purchase and Sale Agreement, if such representation and warranty was known by such other Party to be untrue when made, or (ii) any claim that is based upon any fraudulent, grossly negligent or intentional misconduct (including the failure to act) by such other Party.

(c) In the event that any Party initially pays more than its applicable share of Indemnifiable Damages, then the Parties shall make such payments to each other such that the net payments reflect their applicable, respective shares.

(d) In the event a Party shall have made payment of its applicable share of Indemnifiable Damages and, subsequent to such payment, there shall be the recovery or receipt of payment respecting the previously paid claim by any Party, the effect of which is to reduce the amount of funds previously paid with respect to such claim, whether by the recovery of insurance proceeds, third party indemnification or otherwise, then the aggregate amount so recovered or received shall be shared among the Parties, in proportion to their payments and shall be paid to the other Parties within ten (10) days after the date upon which such amount shall be received.

## **2. Settlement of Claims.**

Any Party which receives notice of a claim for Indemnifiable Damages shall give prompt written notice thereof and a copy of such notice to the other Parties. If a Party has an obligation for the payment of an indemnification contribution pursuant to Section 1(a) above, such Party shall cooperate with the other Parties in connection with the defense and settlement of the claims pursuant to the Purchase and Sale Agreement with respect to which such contribution obligation applies. The Party from whom contribution is sought will be entitled

(but not obligated) to participate in any negotiations to settle or otherwise resolve any claim for which contribution is sought. No Party shall settle any such claim, or agree to settle any such claim, without the prior written consent of the other Parties, unless such settling Party waives its right to contribution hereunder against the other Parties, and any settlement made in violation of this restriction, without notice or the obligation of any party to perform any act, shall have the immediate and irrevocable effect of fully releasing and discharging such non-consenting Parties from any obligation to make payment hereunder with respect to the settled claims.

**3. Authority; No Conflict.**

Each Party represents and warrants to the other Parties that (a) it has full capacity and power to execute, deliver and perform this Agreement, (b) this Agreement has been duly executed and delivered by such Party, and is enforceable against such Party in accordance with its terms, and (c) the obligations of such Party hereunder do not and will not conflict with any law, rule or statute applicable to such Party or create a breach or default under any material agreement to which such Party is a party.

**4. Binding Effect; Assignment.**

This Agreement shall be binding upon and inure to the benefit of the Parties and their respective successors and assigns. Notwithstanding any provision to the contrary in this Agreement, no member, officer, official, councilmember, commissioner, partner, employee, shareholder, manager, director or agent (as applicable) of a Party shall be personally liable to any other Party (or any of their respective successors-in-interest) under Section 1(a) of this Agreement. No Party shall assign its obligations under this Agreement without the prior written consent of the other Parties.

**5. Severability.**

Each provision of this Agreement constitutes a separate and distinct undertaking, covenant and provision with respect to the Parties. In the event that one or more provisions of this Agreement are held illegal or unenforceable with respect to any Party, such provisions shall be deemed severed and the remaining provisions of this Agreement shall survive and remain fully enforceable against the Parties. The determination that any one or more provisions of this Agreement are illegal or unenforceable with respect to any Party shall not be construed to mean that any such provision is illegal or unenforceable with respect to the other Parties.

**6. Construction.**

This Agreement shall be construed in accordance with and governed for all purposes by the laws of the State of Minnesota without regard to principles of conflicts of laws. The captions in this Agreement are for convenience only and shall not be construed to limit or otherwise affect the meaning of any term or provision of this Agreement. Unless otherwise stated, section references refer to the sections of this Agreement.

**7. Notices.**

Any notice to be given to the Parties shall be made in writing and shall be addressed to the Parties at the addresses set forth on the signature page hereto, or at such other address provided in writing by a Party to the other Parties.

**8. Termination.**

This Agreement shall terminate and be of no further force or effect upon the termination or expiration of the Purchase and Sale Agreement; provided, no such termination shall affect the liabilities and obligations of any Party hereunder with respect to any claim for Indemnifiable Damages arising or accruing prior to the date of such termination.

*[Remainder of page left blank;  
signature pages follow]*



**EXECUTION COPY**

IN WITNESS WHEREOF, the Parties have executed this Agreement as of the date first written above.

MINNESOTA VIKINGS FOOTBALL STADIUM,  
LLC, a Delaware limited liability company

By: \_\_\_\_\_

Name: Mark Wilf

Title: President

Address for Notices:

c/o Minnesota Vikings Football, LLC

9520 Viking Drive

Eden Prairie, MN 55344

Attention: Chief Financial Officer

MINNESOTA VIKINGS FOOTBALL, LLC, a  
Delaware limited liability company

By: \_\_\_\_\_

Name: Mark Wilf

Title: President

Address for Notices:

c/o Minnesota Vikings Football, LLC

9520 Viking Drive

Eden Prairie, MN 55344

Attention: Chief Financial Officer

SIGNATURE PAGE 1 TO INDEMNIFICATION CONTRIBUTION AGREEMENT  
(Purchase and Sale Agreement)

**EXECUTION COPY**

MINNESOTA SPORTS FACILITIES AUTHORITY, a  
public body and political subdivision of the  
State of Minnesota

By: \_\_\_\_\_  
Name: Michele Kelm-Helgen  
Title: Chair

By: \_\_\_\_\_  
Name: Ted Mondale  
Title: CEO / Executive Director

Address for Notices:  
Minnesota Sports Facilities Authority  
Mall of America Field  
900 South Fifth Street  
Minneapolis, MN 55415  
Attention: Executive Director

SIGNATURE PAGE 2 TO INDEMNIFICATION CONTRIBUTION AGREEMENT  
(Purchase and Sale Agreement)

L-2-7

**EXHIBIT M-1**

**AUTHORITY STADIUM BUILDER LICENSE PROGRAM**

The general terms of the Authority Stadium Builder License Program (the “**Program**”) are as follows:

1. Gross Amount of Program – \$125,000,000 (One Hundred Twenty-Five Million Dollars).
2. Estimated Construction Fund Deposit - (Gross Amount of Program less estimated cost of SBL sales and interest costs) - Approximately \$100,000,000 (One Hundred Million Dollars).
2. Non-Stadium Builder License Percentage of Stadium Seating – 25% (Twenty-five Percent).
3. Stadium Builder License (“SBL”) Percentage of Stadium Seating – 75% (Seventy-five Percent).
4. Maximum SBL Price Per Seat – Less than \$10,000.
5. Average SBL will be approximately - \$2,500.
6. Payment Opportunities – At least two (2) forms:
  - (a) On an Interest Free basis with three (3) equal installments beginning in 2014 (if purchased in 2014) with one-third (1/3) of the amount due paid at signing, one-third (1/3) of the amount due paid by July 1, 2015, and one-third (1/3) of the amount due paid by July 1, 2016.
  - (b) Financing options will be available for purchasers. Currently considering offering financing terms as follows:
    - Down payment at purchase
    - Two additional installments prior to stadium opening in 2015 and 2016
    - Financing will initially be interest free prior to stadium opening
    - Upon stadium opening, financing will be provided for remaining balance due at market interest rates, for up to a period of five years.
    - Purchasers can elect to pre-pay anytime
7. Commencement of SBL Program – Upon the Effective Date of the Stadium Development Agreement.
8. Statutory and Contractual SBL Agent for the Authority – Minnesota Vikings Football, LLC (with right to sublicense).

**EXHIBIT M-2**

**SBL MARKETING AND SALES AGREEMENT**

**SEE ATTACHED**

**STADIUM BUILDER'S LICENSE MARKETING AND SALES  
AGREEMENT**

**BY AND BETWEEN**

**MINNESOTA SPORTS FACILITIES AUTHORITY**

**AND**

**MINNESOTA VIKINGS FOOTBALL, LLC**

**DATED AS OF NOVEMBER 22, 2013**

## TABLE OF CONTENTS

	Page
ARTICLE I      DEFINITIONS.....	2
Section 1.1.      Defined Terms .....	2
ARTICLE II      APPOINTMENT OF AGENT; SCOPE OF SERVICES .....	2
Section 2.1.      Appointment of the Team as Agent .....	2
Section 2.2.      Marketing Plan.....	2
Section 2.3.      Provision of Technical and Professional Services .....	2
Section 2.4.      Form of SBL Sales Agreement .....	3
Section 2.5.      Marketing Materials.....	3
Section 2.6.      Standard of Performance.....	3
ARTICLE III      TERM OF AGREEMENT.....	3
Section 3.1.      Term of Agreement.....	3
ARTICLE IV      SBL PROCEEDS .....	3
Section 4.1.      Payments .....	3
Section 4.2.      Proceeds for Benefit of Authority.....	3
ARTICLE V      BUDGET .....	3
Section 5.1.      SBL Budget.....	3
ARTICLE VI      COMPENSATION AND PAYMENT .....	4
Section 6.1.      Cost Reimbursement.....	4
Section 6.2.      Compensation .....	4
ARTICLE VII      ASSIGNMENT AND SUBCONTRACTING OF AGREEMENT .....	4
Section 7.1.      The Team .....	4
Section 7.2.      The Authority.....	5
ARTICLE VIII      CONFIDENTIALITY.....	5
Section 8.1.      Confidential Information .....	5
ARTICLE IX      USE OF AUTHORITY NAME OR EMBLEM .....	5
Section 9.1.      Grant of License.....	5
ARTICLE X      RIGHT TO INSPECT RECORDS OF THE SBL AGENT.....	5
Section 10.1.      Right to Inspect .....	5
ARTICLE XI      NON-DISCRIMINATION .....	5
Section 11.1.      Employee Non-Discrimination .....	5

**TABLE OF CONTENTS**  
(continued)

	<b>Page</b>
Section 11.2. SBL Purchaser Non-Discrimination .....	6
Section 11.3. SBL Agent Covenants Regarding Women and Minorities .....	6
ARTICLE XII INDEMNIFICATION.....	6
Section 12.1. Indemnification and Payment of Damages by Team.....	6
ARTICLE XIII INSURANCE.....	6
Section 13.1. Insurance .....	6
ARTICLE XIV MISCELLANEOUS .....	6
Section 14.1. Amendments .....	6
Section 14.2. Entire Agreement .....	6
Section 14.3. No Presumption Against Drafter .....	6
Section 14.4. Severability .....	7
Section 14.5. Relationship of Parties .....	7
Section 14.6. Incorporation by Reference.....	7
Section 14.7. Waiver.....	7
Section 14.8. Notice of Matters .....	7
Section 14.9. Form of Notices; Addresses.....	7
Section 14.10. Calculation of Time .....	9
Section 14.11. Headings .....	9
Section 14.12. Additional Documents and Approval .....	9
Section 14.13. Good Faith .....	9
Section 14.14. Governing Law .....	10
Section 14.15. Third Party Beneficiaries .....	10
Section 14.16. No Waiver of Authority Immunity or Liability .....	10
Section 14.17. Conformity with the Act .....	10
Section 14.18. Execution in Counterparts and Delivery of Electronic Signatures.....	10
Section 14.19. Conflicts of Interest.....	10
ARTICLE XV DISPUTE RESOLUTION .....	11
Section 15.1. Mediation .....	11
Section 15.2. Mediation Rules .....	11

**TABLE OF CONTENTS**  
**(continued)**

	<b>Page</b>
Section 15.3. Cost of Mediation .....	11
Section 15.4. Mediation as Condition Precedent .....	11
Section 15.5. Forum Selection; Waiver of Jury Trial .....	11
Section 15.6. Injunctive Relief; Specific Performance .....	11
Section 15.7. Remedies Cumulative .....	11

**SCHEDULES AND EXHIBITS**

SCHEDULE 1 –	DEFINITIONS
EXHIBIT A –	AUTHORITY STADIUM BUILDER LICENSE PROGRAM
EXHIBIT B –	INSURANCE COVERAGE REQUIREMENTS



**STADIUM BUILDER'S LICENSE MARKETING AND SALES AGREEMENT**

This **STADIUM BUILDER'S LICENSE MARKETING AND SALES AGREEMENT** (this "**Agreement**") is made as of the 22<sup>nd</sup> day of November, 2013, by and between Minnesota Sports Facilities Authority, a public body and political subdivision of the State of Minnesota (the "**Authority**"), and Minnesota Vikings Football, LLC, a Delaware limited liability company (the "**Team**").

**RECITALS**

A. The Team holds, owns, and controls a professional football franchise that is a member of the National Football League ("**NFL**").

B. In 2012, the Minnesota legislature, finding that the expenditure of public money for the construction, financing, operation, and long-term use of a multi-purpose stadium and related infrastructure (the "**Stadium**") as a venue for an NFL team in Minnesota and a broad range of other civic, community, athletic, educational, cultural, and commercial activities serves a public purpose, enacted legislation (the "**Act**") creating the Authority and authorizing the construction of the Stadium in the City of Minneapolis, Minnesota (the "**City**").

C. The Minnesota legislature provided for the public financing of the Stadium, with certain private contributions and contributions by the Team, and for tax-exempt ownership of such Stadium by the Authority.

D. In furtherance of the purposes of the Act, the Authority and the Team are concurrently entering into (i) that certain Development Agreement dated October 3, 2013 (the "**Development Agreement**") pursuant to which the Stadium, to be owned by the Authority, is to be constructed in the City, and (ii) that certain Stadium Use Agreement dated October 3, 2013 (the "**Stadium Use Agreement**") concerning the long-term use of the Stadium. This Agreement must be concurrently executed with the Development Agreement and the Stadium Use Agreement.

E. The Authority is the sole owner of the right to sell stadium builder licenses ("**SBLs**") with respect to seating in the Stadium for games played at the Stadium by the Team and for certain other events held at the Stadium. Pursuant to the terms of the Act, the Authority is required to appoint the Team as its agent to market and sell SBLs. The net proceeds from the sale of SBLs shall be used as a component part to finance, as a portion of the private contribution contemplated by the Act, the cost of construction of the Stadium. The Authority and the Team have agreed on the general terms of the SBL program, the terms of which are outlined as set forth on **Exhibit A** of this Agreement, consistent with the corresponding exhibit set forth in the Development Agreement.

F. In connection with the construction, financing, operation, and long-term use of the Stadium, Minnesota Stadium Funding Trust, a statutory trust and bankruptcy remote special purpose entity established under the laws of the State of Delaware (the "**Stadium Funding Trust**"), intend to enter into a senior secured multi-draw construction term loan facility (the "**Initial Senior Secured Facility**") which will, pursuant to the terms of definitive loan

documents relating to the Senior Secured Facility including, among other things and without limitation, credit agreements, and guarantee, pledge, security, and other related definitive documents (collectively, the “**Initial Senior Secured Facility Loan Documents**”) pursuant to which the Stadium Funding Trust will, among other things, (i) borrow funds, (ii) collect revenues from the sale of SBLs through the Collateral Account, (iii) provide funds under the SBL Purchase Facility (as defined below) to the Authority for use by the Team (acting as agent for the Authority) for the SBL Costs incurred in or for, as applicable, the marketing and sales of SBLs hereunder, subject to specified procedures and documentation required therewith, (iv) enter into a purchase and sale agreement with the Authority providing for the sale of SBL revenues by the Authority to the Stadium Funding Trust pursuant to a “true sale” sale transaction (the “**SBL Purchase Facility**”), and (v) provide funds under the SBL Purchase Facility to the Authority for use by the authority to pay for all other costs and expenses of the Authority in connection with the SBLs and “true sale” transaction.

G. Pursuant to the terms of the Act, the Authority enters into this Agreement to retain the Team to act as the Authority’s agent in marketing and selling the SBLs to SBL Licensees.

**NOW, THEREFORE**, in consideration of the foregoing Recitals, which are hereby incorporated into this Agreement, and the mutual promises, undertakings and covenants hereinafter set forth, and intending to be legally bound hereby, the Authority and the Team covenant and agree as follows:

## ARTICLE I DEFINITIONS

Section 1.1. Defined Terms. Capitalized terms used in this Agreement shall have the meanings set forth in **Schedule 1** except where otherwise stated.

## ARTICLE II APPOINTMENT OF AGENT; SCOPE OF SERVICES

Section 2.1. Appointment of the Team as Agent. Subject to the terms of this Agreement, during the Sales Term the Authority hereby appoints the Team to serve, and the Team shall act as, the Authority’s exclusive agent (in such capacity, the “**SBL Agent**”), with the right to appoint subagents pursuant to the terms hereof (each, a “**Subagent**”), for the marketing of, solicitation of orders for, sales of and contract execution and delivery of SBLs. The SBLs will be sold with respect to seating in the Stadium for preseason, regular season and postseason games played by the Team in the Stadium, excluding the Super Bowl, and for certain other events held at the Stadium. Such other events shall include (a) such Team sponsored events as the Team may from time to time elect to offer to SBL Licensees, and (b) such other events as the Authority may from time to time elect to offer to SBL Licensees. The Authority has developed and approved the framework for structure, terms and other material provisions of the SBLs as set forth on **Exhibit A** hereto. The Authority hereby directs the SBL Agent, as the Authority’s agent, to develop a pricing structure for the SBLs consistent with such framework that will be based upon the Affordable Ticket program described in **Section 9.4** and **Exhibit F** of the Stadium Use Agreement. Among other things, the location of the Stadium seating associated

with the SBLs, and their associated amenities will be considered with respect to the pricing structure.

Section 2.2. Efforts; Marketing Plan. During the Sales Term, the SBL Agent shall market, solicit orders for, and sell SBLs in accordance with the Marketing Plan. In particular the SBL Agent shall be responsible for the following:

(a) The SBL Agent shall or shall cause its Subagent to, on an annual basis on or before January 1<sup>st</sup> of the relevant year, develop a plan for the marketing and promotion of SBLs for each year hereunder (each, a “**Marketing Plan**”); provided, that for the first year the SBL Agent shall develop a Marketing Plan within ninety (90) days of the Effective Date. The Authority shall retain the right to review, provide feedback and approve each Marketing Plan.

(b) The SBL Agent shall or shall cause its Subagent to establish a marketing and sales center for use with respect to the SBL Agent’s obligations under this Agreement, currently anticipated to be located at 1010 Metrodome Square, or such other location as may be determined by the SBL Agent (the “**Sales Center**”).

The Team shall not make any promises or commitments on behalf of the Authority or act in any way that suggests it has authority to bind the Authority, except in its capacity as agent for the Authority in marketing and selling SBL Licenses. The Authority shall pay or reimburse the SBL Agent all of the costs and expenses incurred in connection in connection with the marketing, solicitation of orders for, and sale of SBLs, in each case as an SBL-related expense, including without limitation costs and expenses relating to the preparation of each Marketing Plan and to the establishment, maintenance and operation of the Sales Center.

Section 2.3. Provision of Technical and Professional Services. The SBL Agent shall furnish all technical and professional services, including labor, material, equipment, transportation, supervision and expertise to satisfactorily complete the work required by the Authority under this Agreement at no risk to the Authority.

Section 2.4. SBL Sales Agreement. The SBL Agent shall develop standardized forms of contracts for the sale of SBLs (“**SBL Sales Agreements**”), which forms of contract shall be subject to the approval of (i) the Authority (such approval not to be unreasonably withheld), (ii) Stadium Funding Trust and (iii) the collateral trustee under the Senior Secured Facility. Each SBL Sales Agreement shall provide, among other things (i) that an SBL does not grant or provide an SBL Licensee with any property right, nor does it grant or provide any ownership or other equity interest in the Stadium; (ii) for indemnification of the Authority and its officers, employees and agents from and against any liability, losses, claims, demands, costs and expenses, including attorneys’ fees and litigation expenses, arising out of any personal injury or property damage occurring in or upon the Stadium or related Authority property in connection with the SBL Licensee’s use of the SBL; (iii) that the SBL Agent or a Subagent execute such contracts on behalf of the Authority as agent of the Authority, but only if such executed agreement(s) is in the form approved by the Authority in all material respects; and (iv) that the interest of the Authority in such contracts and revenues associated therewith may from time to time be sold, transferred and assigned (whether absolutely or for collateral purposes) to one or more third-parties, including without limitation the Stadium Funding Trust or any other lenders

providing financing for SBL revenues, and may be further collaterally assigned by the Stadium Funding Trust or any such other lender in connection with the Senior Secured Facility or other financing provided for SBL revenues. Upon request of the Authority, the Team shall provide to the Authority certification that (a) such SBL Sales Agreement was executed by an duly authorized officer, employee or other individual on behalf of SBL Agent or Subagent, as agent for the Authority, and (b) the SBL Agent has complied in all material respects with Applicable Law in the performance of its obligations under this Agreement.

Section 2.5. Marketing Materials. The SBL Agent shall develop marketing materials for distribution to potential SBL Licensees (“**Marketing Materials**”). All Marketing Materials shall be submitted by the SBL Agent to the Authority for review, comment and approval before use, which review comment and approval shall be accomplished by the Authority in a timely manner. The Authority shall own all right, title and interest in and to the Marketing Materials, including all copyrights appurtenant thereto but excluding any rights in or to the Team IP, and the Team hereby assigns all right, title and interest in and to the Marketing Materials to the Authority including all intellectual property rights therein but expressly excluding the Team IP. The Authority hereby grants to the SBL Agent the non-exclusive right, during the Sales Term, to use the Marketing Materials in connection with its promotion of the SBLs and in accordance with this Agreement.

Section 2.6. Standard of Performance. The SBL Agent will perform all services under this Agreement in accordance with Applicable Law.

### ARTICLE III TERM OF AGREEMENT; TERMINATION

Section 3.1. Term of Agreement. This Agreement, and the rights and obligations established thereby, is effective as of November 22, 2013 (the “**Effective Date**”) and expires on the earlier to occur of (a) the last day of the Term (as defined in the Use Agreement), or (b) December 31<sup>st</sup> of the calendar year during which the tenth (10<sup>th</sup>) anniversary of the date on which the first Team Game is played at the Stadium, unless in either case this Agreement is terminated as set forth herein (the “**Sales Term**”). Promptly following the completion of the Sales Term, the SBL Agent shall submit to the Authority a final report on the SBL sales program, including the information set forth in Section 4.1 and such other information as the Authority may reasonably request.

Section 3.2. Basis for Termination. This Agreement may be terminated at any time during the Sales Term:

- (a) upon the mutual written agreement of the parties;
- (b) automatically upon the termination of the Stadium Use Agreement;
- (c) by the Team upon the material breach of this Agreement by the Authority, which failure is not cured within thirty (30) days after the Authority receives notice of such breach from the Team; and

(d) by the Authority, upon (i) the adjudication of the Team as bankrupt, or Team suffering permanent or temporary court-appointed receivership of all or substantially all of its property or assets, making a general assignment for the benefit of creditors or suffering the filing of a voluntary or involuntary bankruptcy petition that is not dismissed within sixty (60) days after filing, in which case termination shall be effective thirty (30) days after notice is given of such intent to terminate; or (ii) the material breach of this Agreement by the Team, which failure is not cured within thirty (30) days after the Team receives notice of such breach from the Authority.

Section 3.3. Effect of Termination.

(a) Upon any termination or expiry of this Agreement, for whatever reason, then, in any such case, all of the Team's rights hereunder regarding the SBLs and the use of the Authority Marks, Architecture Images and the Marketing Materials shall automatically terminate and automatically revert to the Authority, effective as of such time, and the Team shall have no further rights thereto.

(b) The termination or expiration of this Agreement shall not release or relieve any Party from any obligations or liabilities incurred prior to or as a result of such termination or expiration.

(c) Upon any expiration or termination of this Agreement, the Team shall provide to the Authority a copy of all SBL Sales Agreements that have not already been delivered to the Authority.

(d) Notwithstanding any expiration or termination of this Agreement, the provisions of Articles VI (to the extent amounts are due), VIII, XIII, XI (for three (3) years from the date of the termination or expiration of this Agreement), XIV and XVI, and Sections 3.3 and 4.2, shall survive any such expiration or termination of this Agreement.

**ARTICLE IV**  
**SBL PROCEEDS**

Section 4.1. Payments. During the Sales Term, the SBL Agent is authorized to enter into SBL Sales Agreements with SBL purchasers on behalf of the Authority and to process payments in connection therewith in accordance with the terms of the Senior Secured Facility Loan Documents and this Agreement. The SBL Agent shall, pursuant to the SBL Sales Agreements, direct all SBL Licensees to make payments due under the SBL Sales Agreements to a collateral account established pursuant to the terms of the Senior Secured Facility Loan Documents (the "**Collateral Account**"). The SBL Agent shall maintain an accurate accounting and records of all SBL deposits and sales. The SBL Agent shall deliver to the Authority, upon request, periodic reports setting forth the following: (a) the SBLs sold; (b) any forecast for the SBLs to be sold; (c) the amount of gross proceeds from sales of the SBLs collected; (d) the aggregate SBL Costs and Commissions; (e) the amount of net proceeds from sales of the SBLs collected; (f) a copy of all executed SBL Sales Agreements executed; (g) records for the Collateral Account; and (h) a variance report. Copies of such reports shall also be made available, upon request, to Stadium Funding Trust and the lenders and collateral agents under the

Senior Secured Facility. All costs of establishing, maintaining and securing (to the SBL Agent's and the Authority's reasonable satisfaction) the Collateral Account, and all other costs and expenses associated with the marketing, solicitation of orders for and sale of SBLs and the performance of the obligations of the SBL Agent as agent for the Authority under this Agreement, shall be included in the SBL Budget and reimbursed as provided in **Section 6.1** below.

Section 4.2. **Proceeds for Benefit of Authority; No Liens.** Proceeds from the sale of SBLs shall be owned solely by, and collected solely for the benefit of, the Authority and shall be used, in accordance with Applicable Law, to satisfy the private contribution component of the Stadium financing plan with respect to the construction of the Stadium and to pay all costs and expenses of the SBL program and "true sale" transaction. The Team shall not sell, assign (by operation of law or otherwise) or otherwise dispose of, or create or suffer to exist any Lien upon (or grant the right to file any financing statement), or with respect to, any payments due under the SBL Sales Agreements or the Collateral Account, or assign any right to receive income in respect thereof, except as expressly allowed herein.

## ARTICLE V BUDGET

Section 5.1. **SBL Budget.** Following the Effective Date of this Agreement, the SBL Agent shall promptly prepare a budget, on an annual basis on or before October 1<sup>st</sup> of the relevant year, for the costs and expenses incurred to perform the marketing and promotion of SBLs for each year hereunder ("**SBL Budget**") identifying projected costs associated with the SBL Agent's performance of services under this Agreement, consistent with the Senior Secured Facility Loan Documents. The Authority shall review, provide feedback and approve the original and each updated SBL Budget for consistency with the terms of this Agreement and the Development Agreement. The Authority shall reimburse the SBL Agent and its Subagents for all of the costs and expenses incurred in connection with preparing the SBL Budget. SBL Budget costs and expenses shall include, without limitation, salaries of dedicated personnel who are performing services under this Agreement, including Authority staff who are performing services related to SBLs (to the extent costs and expenses of such staff can be properly segregated and allocated to the activities of the Authority related to the SBL Purchase Facility), and costs of feasibility studies, an equitable share of the costs and expenses of the Sales Center, preparation of Marketing Plans and SBL Budgets, creation of Marketing Materials, all other fees, costs and expenses related to SBLs, and other items identified in the SBL Budget. Only the costs and expenses incurred by the SBL Agent or the Authority with respect to SBL sales shall be (i) included in the SBL Budget, and (ii) as incurred, reimbursable as SBL costs and expenses ("**SBL Costs**"). The SBL Budget shall be updated from time to time as circumstances warrant.

## ARTICLE VI COMPENSATION AND PAYMENT

Section 6.1. **Cost Reimbursement.** The Authority shall reimburse the SBL Agent, and the SBL Agent shall be solely responsible for reimbursing any Subagent (to the extent such Subagents are not directly reimbursed by the Authority) pursuant to the Senior Secured Facility Loan Documents for the SBL Costs incurred consistent with the approved SBL Budget

throughout the Sales Term. The SBL Agent shall compile and submit to the Authority, and the Authority shall submit to the appropriate Person as designated in the Senior Secured Facility Loan Documents, an invoice and copies of all requisite receipts and other documentation reasonably required to verify SBL Costs incurred by the SBL Agent or its Subagents in performing services under this Agreement.

Section 6.2. Compensation. In addition to reimbursement of the SBL Costs incurred by the SBL Agent and/or its Subagents pursuant to **Section 6.1** above, the SBL Agent and/or the SBL Agent's Subagent(s), as applicable, will receive commissions for sales of SBLs sold by the SBL Agent or its Subagent(s) (the "**Commissions**"), as determined pursuant to this **Section 6.2** and the Senior Secured Facility Loan Documents. Payment of Commissions earned hereunder shall be as specified in or with reference to the terms and conditions of the Senior Secured Facility Loan Documents. Payment of Commissions may be based on the attainment of certain performance benchmarks by the SBL Agent and/or its Subagent(s). Prior to the commencement of SBL sales, the SBL Agent shall enter into appropriate agreements with each Subagent which establish performance benchmarks on which to base the payment of all or a portion of the Commissions to be received by such Subagent. Such performance benchmarks shall take into account the SBL pricing structure, prepayments and other factors and may be subject to adjustment from time to time. Any performance benchmarks applicable to Commissions payable to the SBL Agent shall be subject to review and approval by the Authority.

## ARTICLE VII ASSIGNMENT AND SUBCONTRACTING OF AGREEMENT

Section 7.1. The Team. The Team may not assign, transfer, or otherwise dispose of or encumber any of its rights or duties hereunder without the prior written Consent of the Authority; **provided, however**, that nothing in this Agreement shall prevent the SBL Agent from utilizing the services of such subcontractors and subagents as it deems reasonably appropriate to perform its obligations under this Agreement; **provided, further**, that the SBL Agent shall require its subcontractors and subagents to comply with all applicable terms and conditions of this Agreement, and any applicable Senior Secured Facility Loan Documents, in providing such services. The Team shall be wholly responsible for the acts and omissions of its subcontractors and subagents, and use of such subcontractors and subagents shall not relieve the Team of any of its obligations under this Agreement.

Section 7.2. The Authority. The rights and duties of the Authority under this Agreement shall inure to the benefit of and be binding upon any successor to the Authority without any further action or approval by the Team.

## ARTICLE VIII CONFIDENTIALITY

All ideas, memoranda, specifications, plans, manufacturing procedures, data, drawings, descriptions, documents, discussions, contract pricing, or other information developed or received by or for the Team or the Authority related to the sale of the SBLs (other than Marketing Materials)) and all other written information submitted to the Team in connection with the performance of this Agreement shall be held as confidential information as required by

Applicable Law, including laws of privacy and trade secrets, and shall not be used for any purposes other than the performance of the obligations of the Parties under this Agreement or the Senior Secured Facility Loan Documents, nor be disclosed to any Party not associated with performance and consummation of such obligations unless required by Applicable Law, or the information that would otherwise be deemed confidential has otherwise (a) been previously publicly disclosed, without the benefit of an agreement of confidentiality, by the disclosing Person, (b) become public knowledge without the breach of the receiving Party hereunder, or (c) been independently developed by the receiving Party without use of the other Party's confidential information. The Parties acknowledge that the Authority is subject to the Minnesota Government Data Practices Act, Minnesota Statutes, Chapter 13 (the "Data Practices Act"). If the Team creates, collects, receives, stores, uses, maintains or disseminates data because it performs government functions of the Authority under this Agreement, then the Team must comply with the requirements of the Data Practices Act as if it were a government entity, and may be held liable under the Data Practices Act for noncompliance. Upon receipt by the Authority of a Data Practices Act request relating to such data, the Authority shall designate in writing to the Team when and to what extent the Team is required to comply with the Data Practices Act. The Team shall promptly notify the Authority if it becomes aware of any potential claims, or facts giving rise to potential claims, under the Data Practices Act. The Team agrees to require its subagents to comply with this provision as required by law.

## **ARTICLE IX**

### **USE OF AUTHORITY MARKS AND ARCHITECTURE IMAGES**

Section 9.1. Certain Definitions. The capitalized terms used in this Article IX and not otherwise defined in this Agreement shall have the meanings given to them in the Stadium Use Agreement.

Section 9.2. License of Authority Marks and Architecture Images to SBL Agent. Subject to the terms and conditions of this Agreement, during the Sales Term, the Authority hereby grants to the SBL Agent, and the SBL Agent hereby accepts, a non-exclusive, nontransferable (subject to the terms of Section 7.1), royalty-free, sublicensable right to (a) use the Authority Marks for any lawful purpose for the sole purpose of executing the SBL Agent's rights and responsibilities under this Agreement and (b) use and exploit, including the right to reproduce, prepare derivative works, distribute, perform, display, and publish, the Architecture Images for any lawful purpose for the sole purpose of executing the SBL Agent's rights and responsibilities under this Agreement. The Authority shall not, and is not granting, any right or license herein to the SBL Agent for which it does not have the right to do so.

Section 9.3. Trademark Use Guidelines. The SBL Agent shall comply with all Applicable Law pertaining to the proper use and designation of Trademarks and with the Trademark Guidelines set forth from time to time by the Authority with respect to the appearance and manner of use of the Trademarks licensed by the Authority hereunder (the "**Licensed Trademarks**"), which rules and practices are provided or otherwise made available to the SBL Agent in written or electronic form.

Section 9.4. Modification of Licensed Trademarks. The SBL Agent shall not be permitted to modify or alter the Licensed Trademarks without prior written approval of the



Authority. In using any Licensed Trademarks of the Authority, the SBL Agent shall indicate that such Licensed Trademarks are Licensed Trademarks of the Authority and shall cause to appear such legends, markings and notices as may be reasonably requested by the Authority in order to give appropriate notice that such Licensed Trademarks are owned by the Authority and licensed hereunder. Any use of such Licensed Trademarks not specifically provided for by the Trademark Guidelines (including any uses not contemplated by the Trademark Guidelines, any uses in contravention of such rules and practices, and any clarifications of the Trademark Guidelines) shall be utilized by the SBL Agent only upon the prior written approval of the Authority.

Section 9.5. Request for Licensed Trademark Usage Documentation. At the Authority's reasonable request, the SBL Agent agrees to furnish from time to time to the Authority for the Authority's inspection and judgment of quality and design, true, representative samples of any written or other graphic matter bearing any of the Licensed Trademarks. On written notification by the Authority, the SBL Agent shall promptly correct any use of such Licensed Trademarks that the Authority determines does not comply with the Trademark Guidelines and/or proper trademark usage as set forth herein or which, in the good faith opinion of the Authority, detracts from the goodwill and reputation of such Licensed Trademarks, contributes to such Licensed Trademarks losing trademark significance, or impairs the Authority's right to use such Licensed Trademarks. The Authority cannot require the SBL Agent to modify previously approved uses or materials, except: (a) pursuant to changes in Applicable Law, as required by a court or other authority in a decision regarding the Licensed Trademarks, or as part of a settlement of a dispute involving the Licensed Trademarks, in which case the SBL Agent shall have a reasonable work out period to exhaust then-current materials using the Licensed Trademark and the SBL Agent's costs in making changes necessary to comply with the change in Applicable Law shall form part of the SBL Budget (unless such work out period would violate Applicable Law, decision, or settlement, in which case the SBL Agent shall modify such materials and the SBL Agent's costs in modifying such materials and in making changes necessary to comply with the change in Applicable Law, decision, or settlement shall form part of the SBL Budget); and (b) pursuant to changes in the Trademark Guidelines (other than as a result of a change in Applicable Law, decisions, or settlements in which case the SBL Agent shall have a reasonable work out period to exhaust then-current materials using the Licensed Trademarks and the SBL Agent's costs in making changes necessary to comply with the new Trademark Guidelines shall form part of the SBL Budget.

Section 9.6. Confirmation of Licensorsip. The Team acknowledges and agrees that all rights accruing from the use of the Authority Marks and Architecture Images, including any goodwill, inures to the benefit of the Authority and will be the exclusive property of the Authority. To the extent any right in or to any Authority Marks or Architecture Images or in the goodwill associated therewith is deemed to accrue to the Team, including as a result of any joint development, the Team hereby assigns such right and goodwill to the Authority for no additional consideration, subject to all rights, obligations and interests of the Parties set forth herein. At the request of the Authority, the Team will take all actions and execute and deliver all documents necessary or desirable to secure or preserve the Authority's right, title and interest in and to the Authority Marks and Architecture Images. Statements herein regarding the ownership of any Authority Marks and Architecture Images or with respect to the right, title or interest in or to any

Authority Marks and Architecture Images are intended to allocate and confirm rights among the Parties and are not a representation or warranty with respect to any Authority Marks and Architecture Images.

Section 9.7. Registrations; Notices; Enforcement. The registration, notice and enforcement sections of the Stadium Use Agreement applicable to Authority Marks and Architecture Images shall apply to this Agreement, mutatis mutandis.

## **ARTICLE X SUBLICENSING**

**EXCEPT AS OTHERWISE AGREED UPON BY THE PARTIES IN WRITING, THE TEAM SHALL BE LIABLE FOR ALL ACTIONS OR INACTIONS OF EACH OF ITS SUBCONTRACTORS, SUBAGENTS AND SUBLICENSEES HEREUNDER. THE SBL AGENT SHALL CAUSE EACH SUBCONTRACTOR, SUBAGENT AND SUBLICENSEE, BEFORE SUCH SUBCONTRACTOR, SUBAGENT AND SUBLICENSEE HEREUNDER EXERCISES ANY SUBCONTRACT, SUBAGENT OR SUBLICENSE RIGHTS, TO EXECUTE A WRITTEN AGREEMENT AGREEING TO BE BOUND BY THE APPLICABLE TERMS AND CONDITIONS OF THIS AGREEMENT APPLICABLE TO THE SBL AGENT. EACH SUCH SUBCONTRACT, SUBAGENT OR SUBLICENSE SHALL SPECIFY THAT IT SHALL TERMINATE UPON THE EXPIRATION OR TERMINATION OF THIS AGREEMENT.**

## **ARTICLE XI RIGHT TO INSPECT RECORDS OF THE SBL AGENT**

Section 11.1. Right to Inspect. The Authority, through its authorized employees, representatives or agents, including any legislative auditor, shall have the right during the Sales Term and for three (3) years from the date of the termination or expiration of this Agreement, to audit the books and records of the SBL Agent relating to the revenues, costs and expenses of the SBLs and the program associated therewith. The SBL Agent agrees to maintain books and records in accordance with generally accepted accounting principles. In the event any amounts are found to be due and owing by the SBL Agent, the SBL Agent shall promptly pay such amounts.

## **ARTICLE XII NON-DISCRIMINATION**

Section 12.1. Employee Non-Discrimination. The SBL Agent shall not discriminate against any employee or applicant for employment because of race, color, creed, national origin, gender, sexual orientation, age, disability, religion, ethnic background, or marital status, in violation of Applicable Law.

Section 12.2. SBL Purchaser Non-Discrimination. Furthermore, the SBL Agent shall not discriminate against any prospective SBL Licensee because of race, color, creed, national origin, gender, sexual orientation, age, disability, religion, ethnic background, or marital status, in violation of Applicable Law.

Section 12.3. SBL Agent Covenants Regarding Women and Minorities. The SBL Agent covenants and agrees that it will make commercially reasonable efforts to employ women and members of minority communities when hiring employees with respect to the SBL program in accordance with applicable law.

### **ARTICLE XIII INDEMNIFICATION**

Section 13.1. Indemnification and Payment of Damages by Team. To the fullest extent permitted by Applicable Law, the Team agrees to protect, defend, hold harmless and indemnify the Authority Indemnified Persons from and against any and all Damages resulting from a Claim for which the Authority may become liable, excluding, however, Damages to the extent resulting from gross negligence or willful misconduct on the part of such Authority Indemnified Person. All amounts due or to become due under this **Section 13.1** shall be reimbursable to the Team as SBL Costs, except to the extent resulting from the gross negligence or willful misconduct of the Team.

### **ARTICLE XIV INSURANCE**

Section 14.1. Insurance. During the Sales Term and for six (6) years thereafter (or for the longest term for which such insurance is available at a commercially reasonable rate), the Team shall purchase and maintain in full force and effect insurance policies with respect to employees, subcontractors and subagents and vehicles assigned to the performance of services under this Agreement with coverage amounts, required endorsements, certificates of insurance, and coverage verifications as defined in **Exhibit B**. All premiums and other costs, expenses and other amounts incurred by the Team in connection with obtaining and maintaining such coverage shall be reimbursable to the Team as SBL Costs.

### **ARTICLE XV MISCELLANEOUS**

Section 15.1. Amendments. No amendment or modification of this Agreement shall be valid unless in writing and duly executed by the Parties.

Section 15.2. Entire Agreement. This Agreement represents the entire agreement between the Authority and the Team with respect to the subject matter set forth herein. Nothing in this Agreement is intended to supersede, modify or terminate the Development Agreement or Stadium Use Agreement. No other understanding, agreements, conversations, or otherwise, with any representative of the Authority or the Team prior to execution of this Agreement shall affect or modify any of the terms or obligations of this Agreement. Any verbal agreement shall be considered unofficial information and is not binding upon the Parties.

Section 15.3. No Presumption Against Drafter. This Agreement has been negotiated at arm's length and between Persons sophisticated and knowledgeable in the matters dealt with herein. In addition, each Party had been represented by experienced and knowledgeable legal

counsel. Accordingly, this Agreement shall be interpreted to achieve the intents and purposes of the Parties, without any presumption against the Party responsible for drafting any part of this Agreement.

Section 15.4. Severability. If any term or provision of this Agreement or the application thereof to any Person or circumstance shall, to any extent, be inconsistent with, invalid or unenforceable under the Act or any Applicable Laws, the remainder of this Agreement, or the application of such term or provision to Persons or circumstances other than those as to which it was held invalid or unenforceable, shall not be affected thereby, and each term or provision of this Agreement shall be valid and enforceable to the fullest extent permitted by the Act or any Applicable Laws.

Section 15.5. Relationship of Parties. It is agreed that nothing contained in this Agreement shall be deemed or construed as creating a partnership or joint venture among the Parties.

Section 15.6. Incorporation by Reference. All exhibits, schedules or other attachments referenced in this Agreement are hereby incorporated into this Agreement by such reference and are deemed to be an integral part of this Agreement.

Section 15.7. Waiver. No action taken pursuant to or related to this Agreement, including, without limitation, any investigation by or on behalf of a Party, shall be deemed to constitute a waiver by the Party taking such action of compliance with any representation, warranty, condition or agreement in this Agreement. A Party's exercise of or failure to exercise any such right or remedy shall not prevent the concurrent or subsequent exercise of any other right or remedy. A Party's delay or failure to exercise or enforce any rights or remedies shall not constitute a waiver of any such rights, remedies or obligations. No Party shall be deemed to have waived any default unless such waiver is expressly set forth in an instrument signed by such Party. If a Party waives in writing any default, then such waiver shall not be construed as a waiver of any covenant or condition set forth in this Agreement, except as to the specific circumstances described in such written waiver. Neither payment of a lesser amount than the sum due hereunder nor endorsement or statement on any check or letter accompanying such payment shall be deemed an accord and satisfaction, and the other Party may accept the same without prejudice to the right to recover the balance of such sum or to pursue any other remedy.

Section 15.8. Notice of Matters. In the event that any Party receives knowledge about any matter that may constitute a breach of any of its warranties or covenants set forth in this Agreement that arises after the date of this Agreement, it shall promptly notify the other Party of the same in writing.

Section 15.9. Form of Notices; Addresses. All notices, requests, consents or other communications required under this Agreement shall be in writing and shall be deemed to have been properly given if served personally, or if sent by United States registered or certified mail, or overnight delivery service to the Parties as follows (or at such other address as a Party may from time to time designate by notice given pursuant to this **Section 14.9**):

**EXECUTION COPY**

**To the Team:** Minnesota Vikings Football, LLC  
9520 Viking Drive  
Eden Prairie, MN 55344  
Attn.: Kevin Warren  
Vice President of Legal Affairs &  
Chief Administrative Officer

**with copies to:** Briggs and Morgan, Professional Association  
2200 IDS Center  
80 South Eighth Street  
Minneapolis, MN 55402  
Attn.: Michael J. Grimes  
Brian Wenger

Minnesota Vikings Football, LLC  
9520 Viking Drive  
Eden Prairie, MN 55344  
Attn.: Lester Bagley  
Vice President of Public Affairs &  
Stadium Development  
Attn.: Steven D. Poppen  
Vice President of Finance &  
Chief Financial Officer

Garden Homes Development  
820 Morris Turnpike  
Short Hills, NJ 07078  
Attn.: Donald Becker  
Stadium Project Executive

**To the Authority:** Minnesota Sports Facilities Authority  
Mall of America Field  
900 South Fifth Street  
Minneapolis, MN 55415  
Attn.: Michele Kelm-Helgen, Chair  
Attn.: Ted Mondale, CEO/Executive Director

**with copies to:** Dorsey & Whitney LLP  
50 South 6<sup>th</sup> Street, Suite 1500  
Minneapolis, MN 55402  
Attn.: Robert Hensley  
Attn.: Jay Lindgren

Fabyanske Westra Hart & Thomson PA  
800 LaSalle Avenue, Suite 1900  
Minneapolis, MN 55402  
Attn.: Mark W. Westra  
Attn.: Dean B. Thomson

Until payment in full and termination of the Initial Senior Secured Facility, a copy of each notice provided hereunder shall also be provided to:

U.S. Bank National Association, as trustee  
425 Walnut Street  
Cincinnati, OH 45202  
Attn.: William Mulvihill

**with a copy to:** DLA Piper LLP  
1251 Avenue of the Americas  
New York, New York 10020-1104  
Attn.: Peter M. White

Each notice shall be deemed received upon the earlier of receipt or three (3) days after the date of deposit with the United States Postal Service if sent by certified mail as provided above, or one (1) Business Day after deposit with the overnight courier specifying “next Business Day” delivery, or upon the date delivery is made; provided, however, that any refusal to accept delivery shall be deemed to constitute receipt.

Section 15.10. Calculation of Time. Unless otherwise stated, all references to “day” or “days” shall mean calendar days. If any time period set forth in this Agreement expires on other than a Business Day, such period shall be extended to and through the next succeeding Business Day.

Section 15.11. Headings. The headings of the various sections, paragraphs and subparagraphs of this Agreement are for convenience only and shall not be considered or referred to in resolving questions of interpretation.

Section 15.12. Additional Documents and Approval. The Parties, whenever and as often as each shall be reasonably requested to do so by the other Party, shall execute or cause to be executed any further documents and take any further actions as may be reasonably necessary or expedient and within their lawful obligation in order to consummate the transactions provided for in, and to carry out the purpose and intent of, this Agreement. Furthermore, the Authority shall take all ministerial actions and proceedings reasonably necessary or appropriate to remedy

any apparent invalidity, lack or defect in authorization, or illegality, or to cure any other defect that has been asserted or threatened.

Section 15.13. Governing Law. This Agreement shall be governed by and construed in accordance with the laws of the State of Minnesota, without giving effect to the principles of conflicts of law thereof.

Section 15.14. Third Party Beneficiaries. This Agreement is solely for the benefit of the Parties hereto and, to the extent provided herein, their respective Affiliates, successors and permitted assigns, and no provision of this Agreement shall be deemed to confer upon other Persons any remedy, claim, liability, reimbursement, cause of action or other right. Notwithstanding the foregoing to the contrary, Stadium Funding Trust and any lenders providing financing for SBL revenues shall be considered third party beneficiaries of this Agreement.

Section 15.15. No Waiver of Authority Immunity or Liability. Nothing contained in this Agreement shall in any way affect or impair the Authority's immunity or the immunity of the Authority's employees or consultants or independent contractors, whether on account of official immunity, legislative immunity, statutory immunity, discretionary immunity or otherwise. Nothing contained in this Agreement shall in any way affect or impair the limitations on the Authority's liability or the liability of the Authority's employees or consultants or independent contractors, set forth in Minnesota Statutes Chapter 466. By entering into this Agreement, the Authority does not waive any rights, protections or limitations provided for the Authority or its employees or consultants or independent contractors under the various rules of governmental immunity or under Minnesota Statutes Chapter 466.

Section 15.16. Conformity with the Act. The Authority and the Team intend that this Agreement and all provisions in this Agreement conform to the Act and its requirements.

Section 15.17. Execution in Counterparts and Delivery of Electronic Signatures. This Agreement may be executed in any number of counterparts. All such counterparts will be deemed to be originals and will together constitute but one and the same instrument. The executed counterparts of this Agreement may be delivered by electronic means, such as email and/or facsimile, and the receiving Party may rely on the receipt of such executed counterpart as if the original had been received

Section 15.18. Conflicts of Interest. To prevent a conflict of interest, the Parties certify that to the best of their knowledge, no Authority officer, employee or authorized representative has any financial interest in the business of the Team and that no person associated with the Team has any interest, direct or indirect, which could conflict with the faithful performance of this Agreement. The Parties are familiar with the provisions of Minnesota Statutes Section 471.87 and following, and certifies that it does not know of any facts which would violate these code provisions. The Parties will advise each other if a conflict arises.

**ARTICLE XVI  
DISPUTE RESOLUTION**

Section 16.1. Mediation. Unless otherwise mutually agreed to by the Parties any controversies between the Team and the Authority regarding the construction or application of this Agreement, and Claims arising out of this Agreement or its breach, shall be submitted to mediation within thirty (30) days of the written request of one Party after the service of that request on the other Party. If the Parties are unable to resolve the dispute through mediation, either Party may bring disputes to a State Court sitting in Minneapolis, Minnesota (Fourth Judicial District).

Section 16.2. Mediation Rules. The Parties may agree on one mediator. The mediation meeting shall not exceed one day (eight (8) hours). The Parties may agree to extend the time allowed for mediation under this Agreement.

Section 16.3. Cost of Mediation. The costs of mediation shall be borne by the Parties equally.

Section 16.4. Mediation as Condition Precedent. For any contract dispute other than those requiring specific performance or injunctive relief, mediation under this **Section 16.4** is a condition precedent to filing an action in any court. In the event of mediation which arises out of any dispute related to this Agreement, the Parties shall each pay their respective attorneys' fees, expert witness costs and cost of suit, through mediation only. In the event of litigation, the prevailing Party shall recover its reasonable costs of suit, expert's fees and attorneys' fees.

Section 16.5. Forum Selection; Waiver of Jury Trial. Any disagreement, dispute or Claim relating to, arising out of or in connection with this Agreement, or the relationship between the Parties, shall be subject to the exclusive jurisdiction of the State Courts sitting in Minneapolis, Minnesota (Fourth Judicial District), and both Parties expressly consent to such exclusive jurisdiction, including personal jurisdiction, and agree that venue in such court is proper. THE AUTHORITY AND TEAM HEREBY IRREVOCABLY WAIVE THE RIGHT TO TRIAL BY JURY OF ANY DISPUTE BETWEEN THEM AND ACKNOWLEDGE THAT ANY DISPUTE BETWEEN THEM SHALL BE TRIED TO THAT COURT.

Section 16.6. Injunctive Relief; Specific Performance. The Parties acknowledge that the rights conveyed by this Agreement and the covenants of the Parties are of a unique and special nature, and that any violation of this Agreement shall result in immediate and irreparable harm to the Authority or the Team, as applicable, and that in the event of any actual or threatened breach or violation of any of the provisions of this Agreement each Party shall be entitled as a matter of right to seek injunctive relief or a decree of specific performance from any court of competent jurisdiction. The alleged breaching Party waives the right to assert the defense that such breach or violation can be compensated adequately in Damages in an action at law

Section 16.7. Remedies Cumulative. All rights and remedies set forth in this Agreement are cumulative and in addition to the Parties' rights and remedies at law or in equity. A Party's exercise of any such right or remedy shall not prevent the concurrent or subsequent exercise of any other right or remedy.



**[SIGNATURE PAGE FOLLOWS;  
REMAINDER OF PAGE INTENTIONALLY LEFT BLANK]**

**EXECUTION COPY**

**IN WITNESS WHEREOF**, the Parties have executed this Agreement as of the date stated in the first paragraph of this Agreement.

**TEAM:**

**MINNESOTA VIKINGS FOOTBALL, LLC**,  
a Delaware limited liability company

By: \_\_\_\_\_

Name: Mark Wilf

Title: President

**[SIGNATURE PAGE TO STADIUM BUILDER'S LICENSE  
MARKETING AND SALES AGREEMENT]**

M-2-23

**EXECUTION COPY**

**AUTHORITY:**

**MINNESOTA SPORTS FACILITIES**

**AUTHORITY,**

a public body and political subdivision of the  
State of Minnesota

By: \_\_\_\_\_

Name: Michele Kelm-Helgen

Title: Chair

By: \_\_\_\_\_

Name: Ted Mondale

Title: CEO / Executive Director

**[SIGNATURE PAGE TO STADIUM BUILDER'S LICENSE  
MARKETING AND SALES AGREEMENT]**

M-2-24

**SCHEDULE 1**

**DEFINITIONS**

“**Act**” shall have the meaning set forth in the Recitals.

“**Affiliate**” of a specified Person shall mean any corporation, partnership, limited liability company, sole proprietorship or other Person that directly or indirectly, through one or more intermediaries controls, is controlled by, or is under common control with the Person specified. For purposes of this definition, the terms “controls,” “controlled by,” or “under common control” mean the possession, direct or indirect, of the power to direct or cause the direction of the management and policies of a Person.

“**Agreement**” shall have the meaning set forth in the Preamble, as the same may be amended, modified or supplemented from time to time.

“**Applicable Law**” or “**Applicable Laws**” shall mean any and all laws (including all statutory enactments and common law), ordinances, constitutions, regulations, treaties, rules, codes, standards, permits, requirements and orders that (i) have been adopted, enacted, implemented, promulgated, ordered, issued, entered or deemed applicable by or under the authority of any Governmental Authority or arbitrator having jurisdiction over a specified Person (or the properties or assets of such Person), and (ii) are applicable to this Agreement or the performance of the obligations of the Parties under this Agreement, including, without limitation, any bulk sales act and consumer laws of the jurisdictions in which they are offered.

“**Authority**” shall have the meaning set forth in the Preamble.

“**Authority Indemnified Persons**” shall mean the Authority and its elected officials, appointed officials, board members, volunteers, officers, employees, agents and attorneys.

“**Business Day**” shall mean any day other than a Saturday, Sunday or other day on which banks are required or authorized to close in Minneapolis, Minnesota.

“**City**” shall have the meaning set forth in the Recitals.

“**Claim**” shall mean any claim, demand or dispute relating to this Agreement or any SBL Sales Agreement.

“**Collateral Account**” shall have the meaning set forth in **Section 4.1**.

“**Commissions**” shall have the meaning set forth in **Section 6.2**.

“**Consent**” shall mean prior consent or approval of a Party in writing which shall not be unreasonably withheld, conditioned or delayed.

**“Damages”** shall mean any loss, liability, damage, cost and expense, including costs of investigation and defense and reasonable attorneys’ fees, whether for money damages, or for equitable or declaratory relief, and may include incidental, consequential, exemplary, punitive and similar Damages when asserted in connection with a third party Claim.

**“Development Agreement”** shall have the meaning set forth in the Recitals.

**“Effective Date”** shall have the meaning set forth in **Section 3.1**.

**“Initial Senior Secured Facility”** shall have the meaning set forth in the Recitals.

**“Initial Senior Secured Loan Documents”** shall have the meaning set forth in the Recitals.

**“Governmental Authority”** shall mean any federal, state, county, city, local or other government or political subdivision or any agency, authority, board, bureau, commission, department or instrumentality thereof.

**“Lien”** shall mean any mortgage, pledge, hypothecation, assignment, encumbrance, lien (statutory or other), charge, or preference, priority or other security interest or preferential arrangement in the nature of a security interest of any kind or nature whatsoever (including any conditional sale or other title retention agreement and any financing lease having substantially the same economic effect as any of the foregoing).

**“Marketing Materials”** shall have the meaning set forth in Section 2.5.

**“Marketing Plan”** shall have the meaning set forth in **Section 2.2(a)**.

**“NFL”** shall have the meaning set forth in the Recitals.

**“Party”** or **“Parties”** shall mean either or both of the Authority and the SBL Agent.

**“Person”** shall mean any natural person, sole proprietorship, corporation, partnership, trust, limited liability company, limited liability association, unincorporated association, joint venture, joint-stock company, Governmental Authority, or any other entity.

**“Sales Center”** shall have the meaning set forth in **Section 5.1**.

**“Sales Term”** shall have the meaning set forth in **Section 3.1**.

**“SBL Agent”** shall have the meaning set forth in **Section 2.1**.

**“SBL Budget”** shall have the meaning set forth in **Section 5.1**.

**“SBL Costs”** shall have the meaning set forth in **Section 5.1**.

**“SBL Licensee”** shall mean the licensee under an SBL, and such licensee’s guests utilizing the licensee’s SBL.

**“SBL Sales Agreements”** shall have the meaning set forth in **Section 2.4**.

**“SBLs”** shall have the meaning set forth in the Recitals.

**“Senior Secured Facility”** shall mean, initially, the Initial Senior Secured Facility and, upon payment in full and termination of the Initial Senior Secured Facility, any loan or purchase facility (including the SBL Purchase Facility) established pursuant to or in connection with the Senior Secured Facility Loan Documents.

**“Senior Secured Facility Loan Documents”** shall mean, initially, the Initial Senior Secured Facility Loan Documents, and upon payment in full and termination of the Initial Senior Secured Facility, the documents, instruments and agreements evidencing any loan or purchase facility established by the Authority to finance or sell SBLs or revenues associated therewith.

**“Stadium”** shall have the meaning set forth in the Recitals.

**“Stadium Funding Trust”** shall have the meaning set forth in the Recitals.

**“Stadium Use Agreement”** shall have the meaning set forth in the Recitals.

**“Subagent”** shall have the meaning set forth in Section 2.1.

**“Team”** shall have the meaning set forth in the Preamble.

**“Team IP”** shall have the meaning given to it in the Stadium Use Agreement.

EXHIBIT A

**Authority Stadium Builder License Program**

The general terms of the Authority Stadium Builder License Program (the "**Program**") are as follows:

1. Gross Amount of Program – \$125,000,000 (One Hundred Twenty-Five Million Dollars).
2. Estimated Construction Fund Deposit - (Gross Amount of Program less estimated cost of SBL sales and interest costs) - Approximately \$100,000,000 (One Hundred Million Dollars).
2. Non-Stadium Builder License Percentage of Stadium Seating – 25% (Twenty-five Percent).
3. Stadium Builder License ("SBL") Percentage of Stadium Seating – 75% (Seventy-five Percent).
4. Maximum SBL Price Per Seat – Less than \$10,000.
5. Average SBL will be approximately - \$2,500.
6. Payment Opportunities – At least two (2) forms:
  - (a) On an Interest Free basis with three (3) equal installments beginning in 2014 (if purchased in 2014) with one-third (1/3) of the amount due paid at signing, one-third (1/3) of the amount due paid by July 1, 2015, and one-third (1/3) of the amount due paid by July 1, 2016.
  - (b) Financing options will be available for purchasers. Currently considering offering financing terms as follows:
    - Down payment at purchase
    - Two additional installments prior to stadium opening in 2015 and 2016
    - Financing will initially be interest free prior to stadium opening
    - Upon stadium opening, financing will be provided for remaining balance due at market interest rates, for up to a period of five years.
    - Purchasers can elect to pre-pay anytime
7. Commencement of SBL Program – Upon the Effective Date of the Stadium Development Agreement.
8. Statutory and Contractual SBL Agent for the Authority – Minnesota Vikings Football, LLC (with right to sublicense).

**EXHIBIT B**

**INSURANCE COVERAGE REQUIREMENTS**

Without limiting the SBL Agent's indemnification of the Authority, and within 30 days of the Effective Date of this Agreement, the SBL Agent shall purchase and maintain in full force and effect, at its sole cost and expense, the following insurance policies with at least the indicated coverages, provisions and endorsements:

**A. COMMERCIAL GENERAL LIABILITY INSURANCE**

1. Commercial General Liability Insurance. Policy limits are subject to review, but shall in no event be less than, the following:  
  
\$2,000,000 Each occurrence  
  
\$2,000,000 General aggregate  
  
\$2,000,000 Products/Completed Operations aggregate  
  
\$2,000,000 Personal Injury
2. Exact structure and layering of the coverage shall be left to the discretion of the SBL Agent; however, any excess or umbrella policies used to meet the required limits shall be at least as broad as the underlying coverage and shall otherwise follow form.
3. The following provisions shall apply to the Commercial Liability policy as well as any umbrella policy maintained by the SBL Agent to comply with the insurance requirements of this Agreement:
  - a. Coverage shall be on a "pay on behalf" basis with defense costs payable in addition to policy limits;
  - b. There shall be no cross liability exclusion which precludes coverage for claims or suits by one insured against another; and
  - c. Coverage shall apply separately to each insured against whom a claim is made or a suit is brought, except with respect to the limits of liability.
4. The Authority shall be included as an additional insured under the CGL policy.
5. This insurance shall apply as primary insurance with respect to any other insurance or self-insurance programs afforded to the Authority. There shall be no endorsement or modification of the commercial general liability to make it excess over other available insurance; alternatively, if the commercial general liability states it is excess or pro rata, the policy shall be endorsed to be primary with respect to the additional insureds.



**B. BUSINESS AUTOMOBILE LIABILITY INSURANCE**

1. Business automobile liability insurance policy with a minimum limit of not less than one million dollars (\$1,000,000) each accident. Liability coverage shall apply to any auto, including all owned, non-owned and hired autos.
2. Coverage as required by this section shall be written on a standard ISO business auto, garage, truckers, or motor carrier policy form. The Team shall effect additional insured status for the Authority under auto liability coverage required by this section.
3. The SBL Agent waives all rights against the Authority, their agents, officers, employees, and volunteers for recovery of damages to the extent such damages are covered by the business automobile liability or commercial excess liability insurance obtained by the SBL Agent pursuant to this Agreement.

**C. WORKERS' COMPENSATION**

1. Workers' Compensation Insurance Policy as required by statute and employer's liability with limits of at least one million dollars (\$1,000,000) policy limit Bodily Injury by disease, one million dollars (\$1,000,000) each accident/Bodily Injury and one million dollars (\$1,000,000) each employee Bodily Injury by disease.
2. The indemnification and hold harmless obligations of the SBL Agent included in this Agreement shall not be limited in any way by any limitation on the amount or type of damage, compensation or benefit payable by or for the SBL Agent or any subcontractor under any Workers' Compensation Act(s), Disability Benefits Act(s) or other employee benefits act(s).
3. This policy must include a Waiver of Subrogation in favor of the Authority Indemnified Persons.
4. The SBL Agent waives all rights against the Authority, and their employees, officers, directors and agents for recovery of damages to the extent these damages are covered by the workers' compensation and employer's liability or commercial umbrella liability insurance obtained by the SBL Agent pursuant to this section. The SBL Agent shall obtain an endorsement equivalent to WC 00 03 13 to affect this waiver.
5. The SBL Agent certifies that it is in compliance with Minn. Stat. § 176.181, subd. 2, pertaining to workers' compensation insurance coverage. The SBL Agent's employees and agents will not be considered Authority employees. Any claims that may arise under the Minnesota Workers' Compensation Act on behalf of these employees and any claims made by any third party as a consequence of any act or omission on the part of these employees are in no way the Authority's obligation or responsibility.

D. Professional Liability (Errors and Omissions Coverage)

1. Minimum limits of insurance under this section shall be \$2,000,000 per claim, \$2,000,000 aggregate.

E. COMPLIANCE WITH REQUIREMENTS

All of the following clauses and/or endorsements, or similar provisions, must be part of each commercial general liability policy, and each umbrella or excess policy.

1. Additional Insureds. The Authority Indemnified Persons are hereby added as additional insureds in respect to liability arising out of the SBL Agent's work for the Authority.
2. Primary and non-contributing. Each insurance policy provided by the SBL Agent shall contain language or be endorsed to contain wording making it primary insurance as respects to, and not requiring contribution from, any other insurance which the indemnities may possess, including any self-insurance or self-insured retention they may have. Any other insurance indemnities may possess shall be considered excess insurance only and shall not be called upon to contribute with the SBL Agent's insurance.
3. General Aggregate. The general aggregate limits shall apply separately to the SBL Agent's work under this Agreement.
4. Cancellation.
  - a. Each insurance policy shall contain language or be endorsed to reflect that no cancellation or modification of the coverage provided due to non-payment of premiums shall be effective until written notice has been given to the Authority at least thirty (30) days prior to the effective date of such modification or cancellation. In the event of non-renewal, written notice shall be given at least thirty (30) days prior to the effective date of non-renewal. Cancellation shall not relieve the SBL Agent of its obligations hereunder.
  - b. Each insurance policy shall contain language or be endorsed to reflect that no cancellation or modification of the coverage provided for any cause save and except non-payment of premiums shall be effective until written notice has been given to the Authority at least thirty (30) days prior to the effective date of such modification or cancellation. In the event of non-renewal, written notice shall be given at least thirty (30) days prior to the effective date of non-renewal.
5. Other Endorsements. Other endorsements may be required for policies other than the commercial general liability policy if specified in the description of required insurance set forth in **Sections A through E** of this **Exhibit B**, above.

**F. ADDITIONAL INSURANCE RELATED PROVISIONS**

The SBL Agent and the Authority agree as follows:

1. The SBL Agent agrees to ensure that subcontractors and subagents and any other party involved with fulfilling the SBL Agent's obligations under this Agreement, provide the same minimum insurance coverage required of the SBL Agent. The SBL Agent agrees to monitor and review all such coverage and assumes all responsibility for ensuring that such coverage is provided in conformity with the requirements of this Agreement. The SBL Agent agrees that upon request by the Authority, all agreements with, and insurance compliance documents provided by, such subcontractors, subagents and other involved party or parties will be submitted to the Authority for review.
2. The SBL Agent agrees to be responsible for ensuring that no contract used by any party involved in any way with the Agreement reserves the right to charge the Authority or the SBL Agent for the cost of additional insurance coverage required by this Agreement. Any such provisions are to be deleted with reference to the Authority. It is not the intent of the Authority to reimburse the SBL Agent or any third party for the cost of complying with these requirements. There shall be no recourse against the Authority for payment of premiums or other amounts with respect thereto.

**G. EVIDENCE OF COVERAGE**

Within 30 days of the Effective Date of this Agreement, the SBL Agent, and each and every subagent (of every tier) shall, at its sole cost and expense, purchase and maintain not less than the minimum insurance coverage with the endorsements and deductibles indicated in this Agreement. Such insurance coverage shall be maintained with insurers, and under forms of policies, satisfactory to the Authority and as described in this Agreement. The SBL Agent shall file with the Authority all certificates and endorsements for the required insurance policies for the Authority's approval as to adequacy of the insurance protection. Upon the Authority's request, the SBL Agent shall submit to the Authority copies of the actual insurance policies or renewals or replacements.

**H. QUALIFYING INSURERS**

All of the insurance companies providing insurance for the SBL Agent shall have, and provide written proof of, an A. M. Best rating of at least A minus 6 (A- VI) or shall be an insurance company of equal financial stability that is approved by the Authority or its insurance compliance representatives.

**EXHIBIT N**

**SBL PURCHASE AND SALE AGREEMENT**

**SEE ATTACHED**

**PURCHASE AND SALE AGREEMENT**

**among**

**MINNESOTA STADIUM FUNDING TRUST,  
as Purchaser,**

**MINNESOTA SPORTS FACILITIES AUTHORITY,  
as Seller,**

**and**

**VAN WAGNER TEAM SERVICES, LLC,  
as Servicer**

**Dated as of November 22, 2013**

This PURCHASE AND SALE AGREEMENT, dated as of November 22, 2013 (this “**Agreement**”), among MINNESOTA STADIUM FUNDING TRUST, a Delaware statutory trust (the “**Purchaser**”), MINNESOTA SPORTS FACILITIES AUTHORITY, a public body and political subdivision of the State of Minnesota (the “**Seller**”) and VAN WAGNER TEAM SERVICES, LLC, a Delaware limited liability company (in its capacity as servicer hereunder, the “**Servicer**”).

**WITNESSETH:**

WHEREAS, the Seller intends to develop, finance and construct the Stadium (as defined herein) and in connection therewith intends to sell stadium builders licenses pursuant to SBL Contracts (as defined herein);

WHEREAS, the Purchaser desires from time to time to purchase from the Seller interests in SBL Revenues (as defined herein) arising under SBL Contracts and certain related rights;

WHEREAS, the Seller is willing from time to time to sell such SBL Revenues to the Purchaser;

WHEREAS, the Purchaser will finance the purchases of SBL Revenues by borrowing funds and pledging the SBL Revenues as security therefor pursuant to the Credit Agreement (as defined herein);

WHEREAS, Servicer has been or expects to be engaged to provide certain sales representative services for SBLs (as defined herein) in the Stadium (as defined herein) and in connection therewith is willing to provide additional services related to the servicing, administration and collection of the SBL Revenues in accordance with the terms hereof;

NOW, THEREFORE, in consideration of the premises and the mutual covenants herein contained, other good and valuable consideration, receipt and sufficiency of which are hereby acknowledged, the parties hereto agree as follows:

**ARTICLE I**  
**DEFINITIONS**

Section 1.01 Definitions. Whenever used in this Agreement, the following words and phrases, unless the context otherwise requires, shall have the following meanings:

“**Adverse Claim**” means a Lien on any Person’s assets or properties in favor of any other Person, other than any Lien created under the Transaction Documents.

“**Agreement**” means this agreement, as the same may be amended or supplemented from time to time.

“**Authority Contribution**” shall have the meaning given to such term in the Development Agreement.

“**Authority SBL Account Agreement**” means that certain Authority SBL Account Agreement, dated as of the Closing Date, among the Seller, the Purchaser, the Calculation Agent, the

Collateral Trustee and the depository bank thereunder, as it may be amended, restated, supplemented or otherwise modified from time to time.

**“Authority SBL-Sourced Proceeds Account”** shall have the meaning given to such term in Section 3.03.

**“Bankruptcy Code”** means the Bankruptcy Reform Act of 1978, 11 U.S.C. §§101 et seq., as now in effect or hereafter amended.

**“Calculation Agency Agreement”** means that certain Calculation Agency Agreement dated or about the date hereof by and among the Seller, the Purchaser and the Calculation Agent, pursuant to which the Calculation Agent shall calculate the amount of funds require to be transferred from the Authority SBL-Sourced Proceeds Account to the Trust SBL-Sourced Proceeds on each Purchase Date and provide related instructions to the depository bank under the Authority SBL Account Agreement.

**“Calculation Agent”** means Minnesota Vikings Football, LLC, a Delaware limited liability company, or its successors, as calculation agent under the Calculation Agency Agreement.

**“Closing Date”** means November 22, 2013.

**“Collateral Trustee”** means U.S. Bank National Association, in its capacity as collateral trustee under the Credit Agreement.

**“Credit Agreement”** means that certain credit agreement, dated as of the date hereof, among Purchaser, various lenders party thereto, U.S. Bank National Association, Goldman Sachs Bank USA, Merrill Lynch, Pierce, Fenner & Smith Incorporated, and Sumitomo Mitsui Banking Corporation, as co-lead arrangers and joint bookrunners, Goldman Sachs Bank USA, Bank of America, N.A. and Sumitomo Mitsui Banking Corporation, as syndication agents, and U.S. Bank National Association, as administrative agent and collateral trustee thereunder, as the same may be amended, restated or supplemented from time to time.

**“DD Agreement”** means that certain Deposit and Disbursement Agreement dated as of November 22, 2013, by and among the Purchaser, the Seller, StadCo and the depository banks named therein, as amended from time to time.

**“Debtor Relief Laws”** means any applicable liquidation, conservatorship, bankruptcy, moratorium, rearrangement, insolvency, fraudulent conveyance, reorganization, or similar Laws affecting the rights, remedies, or recourse of creditors generally, including the Bankruptcy Code and all amendments thereto, as are in effect from time to time.

**“Development Agreement”** means that certain Development Agreement, dated as of October 3, 2013, by and between the Seller and the Team, as amended from time to time.

**“ERISA”** means the U.S. Employee Retirement Income Security Act of 1974 and any regulations promulgated and rulings issued thereunder.

**“Event of Bankruptcy”** means, with respect to any Person, (a) that such Person becomes unable or admits in writing its inability or fails generally to pay its debts as they become due; (b) that any writ or warrant of attachment or execution or similar process is issued or levied against all or any material part of the property of any such Person and is not released, vacated or fully bonded within sixty (60) days after its issue or levy; (c) that such Person institutes or consents to the institution of any proceeding under any Debtor Relief Law, or makes an assignment for the benefit of creditors, or applies for or consents to the appointment of any receiver, trustee, custodian, conservator, liquidator, rehabilitator or similar officer for it or for all or any material part of its property; or (d) that any receiver, trustee, custodian, conservator, liquidator, rehabilitator or similar officer is appointed without the application or consent of such Person and the appointment continues undischarged or unstayed for sixty (60) calendar days; or (e) that any proceeding under any Debtor Relief Law relating to any such Person or to all or any material part of its property is instituted without the consent of such Person and continues undismissed or unstayed for sixty (60) calendar days, or an order for relief is entered in any such proceeding.

**“Event of Default”** means the occurrence of any one or more of the following events:

- (a) the Seller or the Purchaser shall fail to make any payment or deposit required to be made by it hereunder or under any other Transaction Document when due hereunder or thereunder and such failure shall continue for two (2) Business Days;
- (b) any representation, warranty, certification or statement made by the Seller or the Purchaser in this Agreement, any other Transaction Document to which it is a party or in any other information, report or document delivered pursuant hereto or thereto shall prove to have been incorrect in any material respect (except any representation or warranty qualified by materiality or by reference to a material adverse effect, which shall prove to have been incorrect in any respect when made or confirmed);
- (c) the Seller or the Purchaser shall fail to perform or observe in any material respect any term, covenant or agreement contained in this Agreement required on its part to be performed or observed and any such failure remains unremedied for thirty (30) days after the earlier to occur of (i) written notice thereof has been given to the Seller or Purchaser or (ii) knowledge thereof by a Responsible Officer;
- (d) any Event of Bankruptcy shall occur with respect to the Seller or the Purchaser;
- (e) the Purchaser or the Collateral Trustee, on behalf of the Secured Parties, shall for any reason fail or cease to, with respect to Purchaser, own, or, with respect to the Collateral Trustee, have a perfected first priority security interest in the SBL Revenues, free and clear of any Adverse Claim;
- (f) a Servicer Default shall have occurred and be continuing;
- (g) the occurrence of an Event of Default under the Credit Agreement; or
- (h) any material provision of this Agreement or any other Transaction Document to which the Seller, the Servicer or the Purchaser is a party shall cease to be in full force and effect.



“**Final Purchase**” shall have the meaning set forth in Section 2.01(b).

“**Final Purchase Date**” shall have the meaning set forth in Section 2.01(b).

“**Governmental Authority**” means any government or political subdivision or any agency, authority, bureau, central bank, commission, department or instrumentality of any such government or political subdivision, or any court, tribunal, grand jury or arbitrator, or any accounting board or authority (whether or not a part of government) which is responsible for the establishment or interpretation of national or international accounting principles, in each case whether foreign or domestic, other than the Seller.

“**Holding Account**” shall have the meaning given to such term in Section 3.03.

“**Initial Purchase**” is defined in Section 2.01(a).

“**Initial Purchase Date**” shall mean the first date on which the Seller has sold an SBL Tranche to the Purchaser pursuant to this Agreement.

“**Law**” means any law (including common law), constitution, statute, treaty, regulation, rule, ordinance, order, injunction, writ, decree, judgment or award of any government or political subdivision or any agency, authority, bureau, central bank, commission, department or instrumentality of any such government or political subdivision, or any court, tribunal, grand jury or arbitrator, or any accounting board or authority (whether or not a part of government) which is responsible for the establishment or interpretation of national or international accounting principles, in each case whether foreign or domestic.

“**Lien**” means any mortgage, pledge, hypothecation, assignment, encumbrance, lien (statutory or other), charge, or preference, priority or other security interest or preferential arrangement in the nature of a security interest of any kind or nature whatsoever (including any conditional sale or other title retention agreement and any financing lease having substantially the same economic effect as any of the foregoing).

“**Loan(s)**” means the loans or other extensions of credit provided to the Purchaser under the Credit Agreement.

“**Material Adverse Effect**” means any change, effect, event, occurrence, state of facts or development that materially and adversely affects (a) the collectability of a material portion of the SBL Revenues, (b) the operations, business, properties, liabilities (actual or contingent), or condition (financial or otherwise) of the Purchaser, (c) the ability of the Purchaser, the Servicer or the Seller to perform its or their, as applicable, respective obligations under the Transaction Documents to which it is a party, or (d) the material rights of or benefits available to the Collateral Trustee or the Lenders under the Transaction Documents.

“**Maximum Amount**” means \$125,000,000, such amount being the aggregate “face” amount of license fees, not including any finance charges or installment fees paid or to be paid by SBL Licensees, relating to the total SBL Contracts available to be entered into by the Seller, counting only one SBL Contract per SBL Seat. The Maximum Amount will be reduced dollar for dollar

for any SBL Revenues related to the Unsold SBL Tranche which are used by the Seller to directly fund the Private Contribution pursuant to Section 3.03.

**“Minimum Monthly SBL Tranche”** means an SBL Tranche of SBL Revenues determined by the Purchaser to be sufficient to cover the Purchaser’s monthly debt service under the portion of the Credit Agreement used to fund the purchase of the SBL Tranches of SBL Revenues and related costs.

**“Notice of Sale”** means the written notice delivered by the Seller to the Purchaser before the applicable Purchase Date pursuant to Section 2.01(b), in substantially the form attached hereto as Exhibit A.

**“Opinion of Counsel”** means one or more written opinions of counsel, which counsel shall be acceptable to the Collateral Trustee.

**“Person”** means an individual, partnership, limited liability company, corporation, joint stock company, trust (including a business trust), unincorporated association, joint venture, firm, enterprise, Governmental Authority or any other entity.

**“Private Contribution”** shall have the meaning given to such term in the Development Agreement.

**“Project”** shall mean the Stadium and Stadium Infrastructure (as defined in the Development Agreement), including, without limitation, all activities relating to the planning, development, design and construction of the Stadium and Stadium Infrastructure.

**“Purchase”** shall mean, as the context may require, the Initial Purchase or a Subsequent Purchase.

**“Purchase Consideration”** means the consideration required to be given to the Seller as set forth in Section 2.06.

**“Purchase Date”** shall mean, as the context may require, the Initial Purchase Date or a Subsequent Purchase Date.

**“Purchase Price”** means, with respect to any SBL Tranche sold hereunder, the percentage of the SBL Revenues then being sold multiplied by the Maximum Amount, less any discounts relating to the fees, costs or expenses of the Purchaser and any set asides for capitalized interest and/or debt service reserves under the Credit Agreement.

**“Release Date”** means the date on which \$260,000,000 of GMP (as defined in the Development Agreement) have been spent and the foundation for the Stadium is in the ground.

**“Replacement SBL”** shall have the meaning set forth in Section 5.01(e).

**“Residual Certificate”** means one or more bonds, notes or other instruments of the Purchaser which together evidence the right of the holder to be paid any amounts representing SBL Revenues following the repayment in full of the Purchaser’s obligations under a specified

portion of the Credit Agreement and certain replacement debt as more particularly described in such Residual Certificate.

**“Responsible Officer”** means, (i) with respect to the Seller, any executive or attorney of the Seller, or any other official of the Seller customarily performing functions similar to those performed by either of the above designated officials, and also with respect to a particular matter, any other official to whom such matter is referred because of such official’s knowledge of and familiarity with the particular subject, and (ii) with respect to the Purchaser, the President, any Vice President, Assistant Vice President, Secretary, any Assistant Secretary, Treasurer, any trust officer or any other officer of Wilmington Trust Company (in its capacity as Trustee of the Purchaser) customarily performing functions similar to those performed by any of the above designated officers and also, with respect to a particular matter, any other officer of Wilmington Trust Company (in its capacity as Trustee of the Purchaser) to whom such matter is referred because of such officer’s knowledge of and familiarity with the particular subject, (iii) with respect to the Servicer, the President, any Vice President, Secretary, or Treasurer of the Servicer, and (iv) with respect to any of the Seller or the Servicer, any official thereof so designated by the governing board.

**“SBL”** means a stadium builders license that entitles the SBL Licensee to, among other things, buy season tickets to certain Team games and for certain other events held at the Stadium for a certain seat in the Stadium.

**“SBL Contract”** means the license agreement relating to an SBL.

**“SBL Licensee”** means the licensee under an SBL.

**“SBL Marketing and Sales Agreement”** means that certain Stadium Builder’s License Marketing and Sales Agreement dated on or about the date hereof by and between the Seller and the Team.

**“SBL Revenues”** means, collectively: (i) all payments, revenues, rents, royalties, issues, profits, fees, proceeds and other amounts paid or payable to the Seller under or relating to an SBL Contract (including any Replacement SBLs) sold, or caused to be sold, by the Seller, including any financing fees and interest relating to the financing of an SBL Contract, (ii) all other rights (but not any obligations) of the Seller under the related SBL Contracts, (iii) any and all proceeds related to the foregoing, and (iv) all insurance or condemnation proceeds payable to the Seller in the event of a casualty event with respect to all or any portion of the Stadium or in the event of a condemnation of all or any portion of the Stadium and allocated to the Private Contribution in accordance with the Development Agreement and the Stadium Use Agreement.

**“SBL Seat”** means a seat in the Stadium which has been designated by the Seller as having an SBL associated with it.

**“SBL Tranche”** means the percentage of SBL Revenues sold pursuant to this Agreement on a Purchase Date as set forth in the applicable Notice of Sale or, with respect to the Initial Purchase Date, the percentage set forth in Section 2.01(a).

**“Servicer Default”** shall have the meaning set forth in Section 3.04.

**“Servicer Indemnified Parties”** shall have the meaning set forth in Section 3.08.

**“Servicing Agreement Supplement”** shall have the meaning set forth in Section 3.01(a).

**“Servicing Fee”** means \$0 per annum, which amount takes into account other valuable consideration received by the Servicer in connection with related services provided with respect to the SBLs, or such other amount as may be agreed to in writing by the Servicer, the Purchaser and the Collateral Trustee.

**“Solvent”** means, with respect to any Person at any time, a condition under which (i) the fair value and present fair saleable value of such Person’s total assets is, on the date of determination, greater than such Person’s total liabilities (including contingent and unliquidated liabilities) at such time; (ii) such Person is and shall continue to be able to pay all of its liabilities as such liabilities mature; and (iii) such Person does not have unreasonably small capital with which to engage in its current and in its anticipated business.

For purposes of this definition, (a) the amount of a Person’s contingent or unliquidated liabilities at any time shall be that amount which, in light of all the facts and circumstances then existing, represents the amount which can reasonably be expected to become an actual or matured liability; (b) the “fair value” of an asset shall be the amount which may be realized within a reasonable time either through collection or sale of such asset at its regular market value; (c) the “regular market value” of an asset shall be the amount which a capable and diligent business person could obtain for such asset from an interested buyer who is willing to purchase such asset under ordinary selling conditions; and (d) the “present fair saleable value” of an asset means the amount which can be obtained if such asset is sold with reasonable promptness in an arm’s length transaction in an existing and not theoretical market.

**“StadCo”** means Minnesota Vikings Football Stadium, LLC.

**“Stadium”** means a new approximately 1.5 million square foot, 65,000 seat professional football stadium and all related facilities and improvements which the Seller intends to develop, finance and construct on a site consisting of all or portions of the current site of the Hubert H. Humphrey Metrodome and the adjacent areas as more fully described in the Development Agreement.

**“Stadium Use Agreement”** means that certain Stadium Use Agreement, dated as of the October 3, 2013, between the Seller and the Team, as the same may be amended, restated, supplemented and otherwise modified from time to time.

**“Subsequent Purchase”** shall mean each Purchase (including the Final Purchase) other than the Initial Purchase.

**“Subsequent Purchase Date”** shall mean any date (other than the Initial Purchase Date) on which the Seller has sold an SBL Tranche pursuant to this Agreement. For the avoidance of doubt, the term Subsequent Purchase Date includes the Final Purchase Date. Except for the Final Purchase Date, each Subsequent Purchase Date shall occur on the twenty-fifth (25) of the

calendar month in which a Notice of Sale is delivered or deemed delivered pursuant to Section 2.01(b).

“**Subservicer**” shall have the meaning set forth in Section 3.01(d).

“**Team**” means Minnesota Vikings Football, LLC, a Delaware limited liability company.

“**Team Contribution**” shall have the meaning given to such term in the Development Agreement.

“**Transaction Documents**” means this Agreement, the Credit Agreement and all of the other instruments, documents and other agreements executed and delivered by the Seller, the Purchaser or the Servicer in connection with any of the foregoing.

“**Trust SBL-Sourced Proceeds Account**” shall have the meaning given to such term in Section 3.03.

“**UCC**” means the Uniform Commercial Code as in effect in the applicable jurisdiction or jurisdictions.

“**Unsold SBL Tranche**” means the percentage of SBL Revenues not sold pursuant to this Agreement as of any date of measurement.

Section 1.02 Other Definitional Provisions.

(a) Capitalized terms used herein and not otherwise defined herein have the meanings assigned to them in the Credit Agreement.

(b) All terms defined in this Agreement shall have the defined meanings when used in any certificate or other document made or delivered pursuant hereto unless otherwise defined therein.

(c) As used in this Agreement and in any certificate or other document made or delivered pursuant hereto or thereto, accounting terms not defined in this Agreement or in any such certificate or other document, and accounting terms partly defined in this Agreement or in any such certificate or other document to the extent not defined, shall have the respective meanings given to them under generally accepted accounting principles. To the extent that the definitions of accounting terms in this Agreement or in any such certificate or other document are inconsistent with the meanings of such terms under generally accepted accounting principles, the definitions contained in this Agreement or in any such certificate or other document shall control.

(d) The words “hereof”, “herein”, “hereunder” and words of similar import when used in this Agreement shall refer to this Agreement as a whole and not to any particular provision of this Agreement; Article and Section references contained in this Agreement are references to Articles and Sections in or to this Agreement unless otherwise specified; and the term “including” shall mean “including without limitation.”

(e) The definitions contained in this Agreement are applicable to the singular as well as the plural forms of such terms and to the masculine as well as to the feminine and neuter genders of such terms.

(f) Any agreement, instrument or statute defined or referred to herein or in any instrument or certificate delivered in connection herewith means such agreement, instrument or statute as from time to time amended, modified or supplemented and includes (in the case of agreements or instruments) references to all attachments thereto and instruments incorporated therein; references to a person are also to its permitted successors and assigns.

(g) The phrases “to the knowledge of the Seller,” “to the Seller’s knowledge,” “to the best knowledge of the Seller” or other similar phrase used herein or in any certificate delivered pursuant hereto, shall mean that a Responsible Officer had actual knowledge with respect to the information referred to in connection with such phrase.

## **ARTICLE II**

### **CONVEYANCE OF SBL REVENUES**

#### **Section 2.01 Conveyance of SBL Revenues.**

(a) On the terms and subject to the conditions set forth herein, the Seller hereby sells to the Purchaser on the Initial Purchase Date, and the Purchaser hereby purchases from the Seller on the Initial Purchase Date, all of Seller’s right, title and interest, in, to and under 2.342% of the SBL Revenues whether such SBL Revenues exist on the Initial Purchase Date or come into existence thereafter. The foregoing purchase and sale is herein sometimes referred to as the “**Initial Purchase.**”

(b) On the terms and subject to the conditions set forth herein, the Seller hereby sells to the Purchaser effective as of each Subsequent Purchase Date, and the Purchaser hereby purchases from the Seller effective as of each Subsequent Purchase Date, all of Seller’s right, title and interest, in, to and under the percentage of the SBL Revenues set forth in the Notice of Sale delivered by the Seller to the Purchaser (with a copy thereof delivered to the Calculation Agent and the Collateral Trustee) at least five (5) days before each such Subsequent Purchase Date, whether such SBL Revenues exist on the date of such sale or come into existence thereafter. The Notice of Sale shall also set forth the total percentage (including the percentage then being sold) of SBL Revenues sold as of the date of each Subsequent Purchase Date. For the avoidance of doubt, no more than 100% of the SBL Revenues may be sold hereunder. The Seller agrees to deliver to the Purchaser (with a copy thereof delivered to the Calculation Agent and the Collateral Trustee) a Notice of Sale once per calendar month and, pursuant to such monthly Notice of Sale, the Seller shall sell to the Purchaser an SBL Tranche equal to or greater than the Minimum Monthly SBL Tranche. In the event that the Seller fails to deliver such monthly Notice of Sale on or before the twentieth (20th) calendar day of any month, the Seller shall be deemed to have sold to the Purchaser the Minimum Monthly SBL Tranche on such date. The Purchaser shall provide to the Seller on or before the tenth (10th) calendar day of each month, the Minimum Monthly SBL Tranche required

for the current month. In addition to the foregoing, on the date which is 365 days after the date of Substantial Completion (as defined in the Development Agreement) (the “**Final Purchase Date**”), the Seller shall be deemed to have sold the remaining Unsold SBL Tranche to the Purchaser hereunder (the “**Final Purchase**”) so that 100% of the SBL Revenues shall have been sold hereunder. The Seller shall deliver a Notice of Sale with respect to such Final Purchase at least five (5) days prior to the Final Purchase Date; provided, however, that the Final Purchase shall be deemed to occur on the Final Purchase Date notwithstanding the failure of the Seller to deliver such Notice of Sale.

(c) The Purchaser, by purchasing each SBL Tranche hereunder, shall be entitled to receive SBL Revenues relating to each such SBL Tranche as such SBL Revenues are collected as more fully set forth herein. The Purchaser’s interest in such SBL Revenues is an undivided legal and equitable interest and Purchaser shall be entitled to receive its percentage interest in the SBL Revenues on a *pari passu* basis with any other Person holding an interest therein (including, without limitation, the Seller’s interest in the Unsold SBL Tranche).

(d) The Seller hereby acknowledges and consents to any pledge, assignment and grant of a security interest by the Purchaser to the Collateral Trustee pursuant to the Credit Agreement for the benefit of the Lenders (and any other creditors or assignees of Purchaser) of any or all right, title and interest of the Purchaser in, to and under the SBL Revenues or the assignment of any or all of the Purchaser’s rights and obligations hereunder to the Collateral Trustee for the benefit of the Lenders.

Section 2.02 Intent of the Parties; Grant of Security Interest. The Seller and the Purchaser intend that the sale, assignment and transfer of SBL Tranches of SBL Revenues to the Purchaser hereunder shall be treated as a true sale and not a loan. If notwithstanding the intent of the parties, the sale, assignment and transfer of SBL Tranches of SBL Revenues to the Purchaser is not treated as a true sale, then (i) this Agreement also is intended by the parties to be, and hereby is, a security agreement within the meaning of the UCC, and (ii) the sale, assignment and transfer of SBL Tranches of SBL Revenues provided for in this Agreement shall be treated as the grant of, and the Seller hereby grants to the Purchaser, a security interest in the SBL Revenues to secure the payment and performance of the Seller’s obligations to the Purchaser hereunder and under the other Transaction Documents or as may be determined in connection therewith by applicable Law. The Seller and the Purchaser shall, to the extent consistent with this Agreement, take such actions as may be necessary to ensure that, if this Agreement were deemed to create a security interest in, and not to constitute a sale of, the SBL Tranches of SBL Revenues, such security interest would be deemed to be a perfected security interest in favor of the Purchaser under applicable Law and shall be maintained as such throughout the term of this Agreement.

Section 2.03 No Recourse. Except as specifically provided in this Agreement, the purchase and sale of SBL Tranches under this Agreement shall be without recourse to the Seller.

Section 2.04 No Assumption of Obligations. Except as described in Section 3.03 below, the Purchaser shall not have any obligation or liability with respect to any SBL Revenues or the SBL Contracts, nor shall the Purchaser have any obligation or liability to any SBL Licensee (including, without limitation, any obligation to perform any of the obligations of the

Seller under the SBL Contracts). The exercise of Purchaser of any rights under this Agreement shall not release the Seller from any of its duties or obligations under any such SBL Revenues or SBL Contracts.

Section 2.05 UCC Filing; Other Actions. The Seller shall record and file, at its own expense, any financing statements (and continuation statements with respect to such financing statements when applicable) with respect to the SBL Revenues then existing and thereafter created (and, in any case, conveyed to the Purchaser hereunder) for the transfer and grant, as applicable, of accounts, instruments, chattel paper and general intangibles (as defined in the UCC) meeting the requirements of applicable state law in such manner and in such jurisdictions as are reasonably requested by the Purchaser or the Collateral Trustee and necessary to perfect the transfer and assignment of such SBL Revenues to the Purchaser (and to the Collateral Trustee (for the benefit of the Secured Parties) as assignee thereof). The Seller has delivered or shall, within two (2) Business Days following the Purchase Date of any SBL Revenues, deliver a file-stamped copy of such financing statements to the Purchaser and the Collateral Trustee, and has taken, or shall take, at the Seller's own expense (which expenses may be funded using proceeds received by the Seller from sales of SBL Tranches to the Purchaser hereunder), all other steps as are necessary under applicable Law (including the filing of any additional financing statements in connection with any Subsequent Purchase) to perfect such transfers and assignments and has delivered to the Purchaser and the Collateral Trustee, or shall deliver, confirmation of such steps including any assignments, as are necessary or are reasonably requested by the Purchaser or the Collateral Trustee. The Seller further agrees, at its own expense, with respect to the SBL Revenues conveyed by it to the Purchaser hereunder, that it will not make any indication on its computer files that suggests such SBL Revenues have not been conveyed pursuant to this Agreement.

Section 2.06 Purchase Consideration. The Purchaser agrees to pay the Seller with respect to any SBL Tranche of SBL Revenues purchased by the Purchaser from the Seller on each Purchase Date, the Purchase Price. As additional consideration for the purchases of SBL Tranches hereunder, the Purchaser shall by appropriate instrument or instruments sell, transfer, assign, set over and otherwise convey, or cause to be sold, transferred, assigned, set over or otherwise conveyed or issued, to the Seller the Residual Certificate.

### **ARTICLE III** **SERVICING**

#### **Section 3.01 Appointment of Servicer**

(a) Notwithstanding the sale of SBL Tranches of SBL Revenues pursuant to this Agreement, each of the Seller and the Purchaser hereby appoints Van Wagner Team Services, LLC as Servicer and authorizes Van Wagner Team Services, LLC, in its capacity as Servicer, to be responsible for the servicing, administration and collection of the SBL Revenues upon the terms and conditions set forth in this Article III. It is acknowledged and agreed that terms and conditions set forth in this Article III may be supplemented and/or modified pursuant to a separate servicing agreement executed by each of the Seller, the Purchaser and the Servicer (the "Servicing Agreement Supplement"). To the extent permitted by applicable Law, the Seller and the Purchaser



hereby grant to the Servicer appointed hereunder an irrevocable power of attorney to take any and all steps in the their respective names and on their behalf as necessary or desirable, in the reasonable determination of the Servicer, to collect all amounts due under any and all SBL Revenues, including endorsing the Seller's and the Purchaser's name on checks and other instruments representing collections and enforcing such SBL Revenues and the related SBL Contracts and to take all such other actions set forth in this Article III or any Servicing Agreement Supplement. Until the Purchaser or the Collateral Trustee gives notice to the existing Servicer of the designation of a new Servicer, the existing Servicer is hereby designated as, and hereby agrees to perform the duties and obligations of, the Servicer pursuant to the terms hereof. At any time following the resignation of the existing Servicer or occurrence and during the continuation of an Event of Default, the Purchaser or the Collateral Trustee may designate as Servicer any Person (including the Collateral Trustee) to succeed the initial Servicer or any successor Servicer, on the condition in each case that any such Person so designated shall agree to perform the duties and obligations of the Servicer pursuant to the terms hereof and any Servicing Agreement Supplement.

(b) Upon the designation of a successor Servicer as set forth above, the existing Servicer agrees that it will terminate its activities as Servicer hereunder in a manner which the Collateral Trustee determines will facilitate the transition of the performance of such activities to the new Servicer, and the existing Servicer shall cooperate with and assist such new Servicer. Such cooperation shall include access to and transfer of records and use by the new Servicer of all records, licenses, hardware or software necessary or desirable to collect the SBL Revenues.

(c) The existing Servicer acknowledges that the Seller, the Purchaser and the Collateral Trustee have relied on the existing Servicer's agreement to act as Servicer hereunder in making their decision to execute and deliver this Agreement and the other Transaction Documents. Accordingly, the existing Servicer agrees that it will not voluntarily resign as Servicer without giving the Seller, the Purchaser and the Collateral Trustee at least ninety (90) days prior written notice.

(d) Subject to the prior written consent of the Seller, the Purchaser and the Collateral Trustee, the Servicer may delegate its duties or obligations hereunder to a subservicer (the "**Subservicer**"); provided that, in connection with such delegation, (i) the Subservicer agrees in writing to perform the duties and obligations of the Servicer pursuant to the terms hereof, (ii) the Servicer shall remain primarily liable for the performance of the duties and obligations so delegated, and (iii) the terms of any agreement with the Subservicer shall provide that the Purchaser or the Collateral Trustee may terminate such agreement upon the termination of the Servicer hereunder by giving notice of its desire to terminate such agreement to the Servicer (and the Servicer shall provide appropriate notice to the Subservicer).

Section 3.02 Duties of Servicer and Related Matters.

(a) The Servicer shall take or cause to be taken all reasonable action as may be necessary or advisable to collect all SBL Revenues from time to time, all in

accordance with this Agreement, any Servicing Agreement Supplement and all applicable Law, with reasonable care and diligence. To the extent not otherwise paid directly to the Holding Account by the applicable SBL Licensees, the Servicer shall set aside (and, if applicable, segregate) and hold in trust for the accounts of the Purchaser and the Seller, as applicable, the amount of the collections with respect to the SBL Revenues to which the Purchaser and the Seller are entitled. The Servicer shall not commingle any SBL Revenues received by it with any of its own assets. The Servicer shall not amend, modify or waive any term or condition of any SBL Contract related to the SBL Revenues without the prior written consent of the Purchaser and the Collateral Trustee. The Seller and the Purchaser shall deliver to the Servicer and the Servicer shall hold in trust for the Seller, the Purchaser and the Collateral Trustee, on behalf of the Lenders, in accordance with their respective interests, all records which evidence or relate to any SBL Revenues. Notwithstanding anything to the contrary contained herein, at any time when an Event of Default is continuing, the Purchaser or the Collateral Trustee shall have the right to direct the Servicer to commence or settle any legal action to enforce collection of any SBL Revenue; provided, however, that the Servicer shall not be required to pursue any such enforcement action unless and until it has received, to its reasonable satisfaction, assurances that its costs and expenses in connection with such enforcement action will be reimbursed. The Servicer shall not make the Purchaser or the Collateral Trustee a party to any litigation without the prior written consent of such Person. The Servicer acknowledges that at any time when an Event of Default exists and is continuing, the Purchaser or the Collateral Trustee may notify any SBL Licensee of its interest in the SBL Revenues.

(b) The Servicer shall employ procedures (including collection procedures) and exercise the same degree of care that it customarily employs and exercises in servicing and administering receivables and any other assets similar to the SBL Revenues and shall act in accordance with the standards of practice, diligence, prudence and competence generally maintained by companies that are in the business of servicing and administering receivables.

Section 3.03 Holding Account; Authority SBL Account Agreement and DD Agreement. Prior to the Closing Date the Purchaser shall establish an account with the Collateral Trustee, which account shall be maintained under the Authority SBL Account Agreement for the benefit of the Seller and the Purchaser (the “**Holding Account**”). The Seller, the Servicer and the Purchaser shall direct all SBL Licensees to pay all SBL Revenues directly to the Holding Account. To the extent not otherwise paid directly to the Holding Account by the applicable SBL Licensees, any SBL Revenues received by any of the Seller, the Servicer or the Purchaser shall be sent promptly (but in any event within two (2) Business Days following receipt thereof) to the Holding Account. Pursuant to the Authority SBL Account Agreement, an additional account (the “**Authority SBL-Sourced Proceeds Account**”) shall be established. Pursuant to the DD Agreement, an additional account (the “**Trust SBL-Sourced Proceeds Account**”) shall be established. The Trust SBL-Sourced Proceeds Account shall consist of the following subaccounts: (i) the Restricted Subaccount and (ii) the Unrestricted Subaccount. As set forth in the Authority SBL Account Agreement, the Collateral Trustee shall transfer from the Holding Account to the Authority SBL-Sourced Proceeds Account all SBL Revenues related to the

Unsold SBL Tranche. The Collateral Trustee shall maintain the Authority SBL-Sourced Proceeds Account as a fiduciary in trust on behalf of the Seller. The Collateral Trustee shall transfer from the Holding Account to the Trust SBL-Sourced Proceeds Account the percentage of SBL Revenues that has been sold pursuant to this Agreement. Upon each Subsequent Purchase Date, the Collateral Trustee shall transfer from the Authority SBL-Sourced Proceeds Account to the Trust SBL-Sourced Proceeds Account, that percentage of the SBL Revenues therein that have been sold to the Purchaser as a part of the SBL Tranche then sold. For purposes of making the transfer described in the immediately preceding sentence, the Collateral Trustee shall rely on a certificate of the Calculation Agent (which shall be acknowledged by the Seller and the Purchaser) setting forth the amount then on deposit in the Authority SBL-Sourced Proceeds Account and the amount needed to be transferred to the Trust SBL-Sourced Proceeds Account so that after such transfer the amount on deposit in the Trust SBL-Sourced Proceeds Account represents the total percentage (including the percentage then being sold) of SBL Revenues sold as of the date of each Subsequent Purchase Date. Prior to the Release Date, the Collateral Trustee shall transfer to the Restricted Subaccount of the Trust SBL-Sourced Proceeds Account all SBL Revenues transferred to the Trust SBL-Sourced Proceeds Account. The Purchaser acknowledges that if the Seller defaults under the Development Agreement and abandons the Project prior to the Release Date, the SBL Revenues on deposit in the Restricted Subaccount of the Trust SBL-Sourced Proceeds Account are subject to return to the Seller solely for the purpose of making refunds to SBL Licensees under the terms of the SBL Contracts. Until the Release Date, the Purchaser agrees to maintain all SBL Revenues purchased hereunder on deposit in the Restricted Subaccount for the purpose of satisfying such refund obligations and, if such refunds are required, Purchaser shall direct the Servicer to make such refunds using the SBL Revenues on deposit in the Restricted Subaccount pursuant to the terms and conditions of the applicable SBL Contracts. Notwithstanding the foregoing, the Purchaser shall also be entitled to use funds in the Restricted Subaccount for the purpose of paying any Servicing Fee which may be due and payable hereunder and any such funds shall be released in accordance with the terms of the Authority SBL Account Agreement. Upon the Release Date, the Collateral Trustee shall transfer all SBL Revenues on deposit in the Restricted Subaccount to the Unrestricted Subaccount and thereafter, all SBL Revenues sold and received pursuant to this Agreement shall be deposited directly into the Unrestricted Subaccount. The Seller agrees that prior to the Release Date the Seller shall maintain all SBL Revenues related to the Unsold SBL Tranche on deposit in the Authority SBL-Sourced Proceeds Account for the purpose of making additional sales of SBL Tranches to the Purchaser hereunder. Upon the Release Date, the SBL Revenues related to the Unsold SBL Tranche on deposit in the Authority SBL-Sourced Proceeds Account may be used, at the option of the Seller, to directly fund the Private Contribution and any such payments to fund the Private Contribution shall reduce the Maximum Amount; provided, however, that on the Final Purchase Date the Seller shall be deemed to have sold the Unsold SBL Tranche (which includes any SBL Revenues in the Authority SBL-Sourced Proceeds Account) to the Purchaser as provided in Section 2.01(b) hereof. The SBL Revenues on deposit in the Unrestricted Subaccount will be used to pay debt service on the Loans made to the Purchaser to fund the purchase of SBL Revenues hereunder.

Section 3.04 Servicer Default. The occurrence of any one or more of the following events shall constitute a "Servicer Default":

(a) The Servicer (i) shall fail to make any payment or deposit required to be made by it hereunder or under any Servicing Agreement Supplement when due and such failure continues for two (2) Business Days, or (ii) shall fail to observe or perform any other term, covenant or agreement hereunder or under any Servicing Agreement Supplement and such failure continues past the earlier of five (5) Business Days following notice by Purchaser or Collateral Trustee or actual knowledge of a Responsible Officer of the Servicer or Purchaser; or

(b) any representation, warranty, certification or statement made by the Servicer in this Agreement or in any Servicing Agreement Supplement or in any certificate or report delivered by it pursuant to any of the foregoing shall prove to have been incorrect in any material respect when made or deemed made (except any representation or warranty qualified by materiality or by reference to a material adverse effect, which shall prove to have been incorrect in any respect when made or confirmed); or

(c) any Event of Bankruptcy shall occur with respect to the Servicer.

Section 3.05 Servicing Fee. The Servicer shall be paid the Servicing Fee. The Servicing Fee shall be paid by the Purchaser from available funds in accordance with the Credit Agreement.

Section 3.06 Representations and Warranties of the Servicer. As of the date hereof, the Servicer hereby makes the following representations and warranties for the benefit of the Seller and the Purchaser and their respective successors and assigns.

(a) Organization and Good Standing. The Servicer is duly organized, validly existing and in good standing under the laws of the jurisdiction of its organization, and has the organizational power and authority to execute, deliver and perform its obligations under this Agreement and, in all material respects, to own its property and conduct its business as such properties are presently owned and as such business is presently conducted.

(b) Due Qualification. The Servicer is validly existing, is duly qualified to do business, is in good standing and has obtained all necessary licenses and approvals in each jurisdiction in which the failure to so qualify or to obtain such license or approval would be reasonably likely to have a Material Adverse Effect.

(c) Due Authorization. The execution, delivery, and performance of this Agreement have been duly authorized by the Servicer by all necessary organizational action on the part of the Servicer.

(d) Binding Obligation. This Agreement has been duly executed and delivered by the Servicer and constitutes a legal, valid and binding obligation of the Servicer enforceable in accordance with its terms except as enforcement thereof may be limited by bankruptcy, insolvency, reorganization, moratorium or other similar laws affecting

enforcement of creditor's rights generally and by general principles of equity (regardless of whether enforcement is sought in a proceeding in law or at equity).

(e) No Violation. To the Servicer's knowledge, the consummation of this Agreement by the Servicer and the fulfillment of the terms hereof by the Servicer do not in any material way conflict with, result in any material breach by the Servicer of any of the material terms and provisions of, nor constitute (with or without notice or lapse of time) a material default by the Servicer under any indenture, agreement or other instrument to which the Servicer is a party or by which it shall be bound; nor, to the Servicer's knowledge, without investigation, violate any law or any order, rule or regulation applicable to the Servicer of any court or of any federal or state regulatory body, administrative agency or other federal or state instrumentality having jurisdiction over the Servicer that would reasonably be expected to have a Material Adverse Effect.

(f) No Proceedings. There are no material proceedings or investigations pending or, to the Servicer's knowledge, threatened against the Servicer, before any court, regulatory body, administrative agency or other governmental instrumentality having jurisdiction over the Servicer: (i) asserting the invalidity of this Agreement, (ii) seeking to prevent the consummation of any of the transactions contemplated by this Agreement with respect to the Servicer, or (iii) seeking any determination or ruling that would materially and adversely affect the validity or enforceability of this Agreement with respect to the Servicer.

(g) No Consents. To the Servicer's knowledge, without investigation, no consent, approval, authorization, order, registration or qualification of or with any court or governmental agency or body is required for the consummation of the transactions contemplated by this Agreement by the Servicer, except for those which have been obtained and are in full force and effect.

Section 3.07 Covenants of the Servicer. The Servicer covenants and agrees that:

(a) Compliance with Law. The Servicer shall duly satisfy all obligations on its part to be fulfilled under or in connection with the SBL Revenues set forth herein and the related SBL Contracts, will maintain in effect all qualifications required on its part under applicable Law in order to properly service the SBL Revenues and will comply in all material respects with all applicable Law in connection with servicing the SBL Revenues the failure to comply with which would reasonably be expected to have a Material Adverse Effect.

(b) Collections. The Servicer shall direct all SBL Licensees to pay all SBL Revenues directly to the Holding Account. The Servicer shall hold in trust, and deposit, promptly, but in any event not later than two (2) Business Days following its receipt thereof, to the Holding Account all collections with respect to the SBL Revenues and the related SBL Contracts received by it from time to time. The Servicer shall not commingle any SBL Revenues received by it with any of its own assets.

(c) Conduct of Business. The Servicer will do all things necessary to remain duly formed, validly existing and in good standing as a limited liability company in its jurisdiction of formation and the Servicer shall maintain all requisite authority to conduct its business in each jurisdiction in which its business is conducted to the extent that the failure to maintain such would reasonably be expected to have a Material Adverse Effect.

(d) Notice of Events of Default or Servicer Default. Immediately, and in any event within one (1) Business Day after the Servicer obtains knowledge or receives notice of the occurrence of each Servicer Default, the Servicer will furnish to the Seller and the Purchaser a statement of a Responsible Officer of the Servicer, setting forth details of such Servicer Default, and the action which the Servicer or the Seller proposes to take with respect thereto.

(e) Furnishing of Information and Inspection of Records. To the extent permitted by law, the Servicer will furnish to the Seller, the Purchaser and the Collateral Trustee from time to time such information with respect to the SBL Revenues as the Seller, the Purchaser and the Collateral Trustee may reasonably request, including, without limitation, listings identifying the outstanding principal balance for each of the SBL Revenues. To the extent permitted by law, the Servicer will, at any time and from time to time during regular business hours and, upon reasonable notice, permit the Seller, the Purchaser and the Collateral Trustee, or their respective agents or representatives, (i) to examine and make copies of and abstracts from all records relating to the SBL Revenues and (ii) to visit the offices and properties of the Servicer for the purpose of examining such records, and to discuss matters relating to SBL Revenues or the Servicer's performance hereunder with any of the officers of the Servicer having knowledge of such matters. Upon a Servicer Default, the Seller, the Purchaser and the Collateral Trustee may have, without notice, immediate access to all records and the offices and properties of the Servicer.

(f) Further Information. The Servicer shall furnish or cause to be furnished to the Seller, the Purchaser and the Collateral Trustee such other information relating to the SBL Revenues, as soon as reasonably practicable, and in such form and detail, as the Seller, the Purchaser and the Collateral Trustee may reasonably request.

Section 3.08 Servicer Indemnification of Indemnified Parties. Without limiting any other rights which the Servicer Indemnified Parties (as defined below) may have hereunder or under applicable Law, the Servicer hereby agrees to indemnify the Seller, the Purchaser, the Collateral Trustee and their respective successors, transferees and assigns and all officers, directors, shareholders, controlling persons, employees, counsel and other agents of any of the foregoing (collectively, "**Servicer Indemnified Parties**") from and against any loss, liability, expense, direct damage or injury suffered or sustained (including any judgment, award, settlement, reasonable attorneys' fees and other costs or expenses reasonably incurred in connection with the defense of any actual action, proceeding or claim) subject to the limitation set forth herein, to the extent as a result of or otherwise arising from the Servicer's willful misconduct, fraud, bad faith or gross negligence in the performance of its duties hereunder or any representation or warranty of the Servicer proving to be materially false or materially inaccurate as of the date hereof. The provisions of such indemnity shall run directly to and be

enforceable by such Servicer Indemnified Parties. Under no circumstances shall Servicer be liable for any consequential, incidental or indirect damages (including, but not limited to, lost profits, lost revenues or loss of business opportunity, whether or not Servicer was aware or should have been aware of possibility of those damages) or punitive, special, exemplary or other damages that are not direct damages. Servicer and any officer or employee or agent of Servicer may rely conclusively on the representations and warranties of the Purchaser and Seller hereunder and in good faith on the advice of counsel or on any document of any kind, prima facie properly executed and submitted by any person respecting any of the matters arising hereunder.

**ARTICLE IV**  
**REPRESENTATIONS AND WARRANTIES OF THE SELLER**

Section 4.01 Representations and Warranties of the Seller. The Seller makes the following representations and warranties on which the Purchaser is deemed to have relied in acquiring the SBL Tranches of SBL Revenues. The representations and warranties herein speak as of the Initial Purchase Date and on each Subsequent Purchase Date, and shall survive the sale of the SBL Tranches of SBL Revenues to the Purchaser and the pledge thereof to the Collateral Trustee pursuant to the Credit Agreement.

(a) Power and Authority. The Seller is validly existing as a public body and political subdivision of the State, including the constitution of the State, with full power and authority to execute and deliver this Agreement and to carry out its terms; the Seller has full power, authority and legal right to sell and assign the SBL Tranches of SBL Revenues to the Purchaser and the Seller has duly authorized such sale and assignment to the Purchaser by all necessary action; and the execution, delivery and performance of this Agreement has been duly authorized by the Seller by all necessary action.

(b) Binding Obligation. This Agreement has been duly executed and delivered by the Seller and, assuming the due authorization, execution and delivery of this Agreement by the Purchaser, constitutes a legal, valid and binding obligation of the Seller enforceable in accordance with its terms except as enforcement thereof may be limited by bankruptcy, insolvency, reorganization, moratorium or other similar laws affecting enforcement of creditor's rights generally and by general principles of equity (regardless of whether enforcement is sought in a proceeding in law or at equity).

(c) No Consents. No consent, approval, authorization, order, registration or qualification of or with any court or governmental agency or body is required for the consummation of the transactions contemplated by this Agreement, except for those which have been obtained and are in full force and effect.

(d) No Violation. The consummation of the transactions contemplated by this Agreement and the fulfillment of the terms hereof and thereof do not, to the Seller's knowledge, in any material way conflict with, result in any material breach by the Seller of any of the material terms and provisions of, nor constitute (with or without notice or lapse of time) a material default by the Seller under any indenture, agreement or other instrument to which the Seller is a party or by which it shall be bound; nor violate any

law or, to the Seller's knowledge, any order, rule or regulation applicable to the Seller of any court or of any federal or Minnesota state regulatory body, administrative agency or other federal or Minnesota instrumentality having jurisdiction over the Seller that would reasonably be expected to have a Material Adverse Effect.

(e) No Proceedings. There are no material proceedings or investigations pending or, to the Seller's knowledge, threatened against the Seller or the Purchaser, before any court, regulatory body, administrative agency or other governmental instrumentality having jurisdiction over the Seller: (i) asserting the invalidity of this Agreement, (ii) seeking to prevent the consummation of any of the transactions contemplated by this Agreement, or (iii) seeking any determination or ruling that would materially and adversely affect the validity or enforceability of this Agreement.

(f) Solvent. Both before and after giving effect to the transactions contemplated by this Agreement, including each sale of an SBL Tranche of SBL Revenues hereunder, the Seller is and will be Solvent.

(g) Perfection; Good Title. Immediately preceding each Purchase hereunder, the Seller shall be the owner of the SBL Tranche of SBL Revenues, as such SBL Revenues may be in existence from time to time, to be sold by it pursuant to such Purchase, free and clear of all Adverse Claims (other than any Adverse Claim arising hereunder or under the Credit Agreement). This Agreement constitutes a valid sale, transfer and assignment of the SBL Tranches of SBL Revenues to the Purchaser and, upon each Purchase, the Purchaser shall acquire a valid and enforceable perfected first priority ownership interest or a first priority perfected continuing security interest in the SBL Tranche of SBL Revenues sold on the date of such Purchase, free and clear of any Adverse Claim (other than pursuant to this Agreement or the Credit Agreement) and enforceable as against creditors of and purchasers from the Seller. The SBL Revenues constitute "general intangibles," "accounts" or "payment intangibles" within the meaning of UCC Section 9-102. Upon each Purchase, the transfer or security interest in the SBL Tranche of SBL Revenues sold to the Purchaser will be perfected under the UCC. The Seller has not taken any action to convey any right to any Person that would result in such Person having a right to payments due under the SBL Revenues, except as contemplated by this Agreement. Other than the transfer of SBL Tranches of SBL Revenues under this Agreement, the Seller has not pledged, assigned, sold, granted a security interest in, or otherwise conveyed any of the SBL Revenues. The representations contained in this Section 4.01(g) shall continue and remain in full force and effect until such time as all obligations under this Agreement have been finally and fully paid and performed.

(h) Financing Statements. The Seller has taken or will have taken all steps reasonably necessary to assist the Purchaser to cause, within nine (9) days after the effective date of this Agreement, the filing of all appropriate financing statements in the proper filing office in the appropriate jurisdictions under applicable law in order to perfect the sale of, or security interest in, each SBL Tranche of SBL Revenues sold hereunder.



(i) Fair Value. With respect to each SBL Tranche of SBL Revenues sold hereunder, (i) the consideration received from the Purchaser in respect of such SBL Tranche of SBL Revenues represents adequate consideration and fair and reasonably equivalent value for such SBL Tranche as of the applicable Purchase Date, and (ii) based upon the terms of the SBL Marketing and Sales Agreement, such consideration, together with the benefit to the Seller from the transactions contemplated by the Transaction Documents, is not less than the fair market value of such SBL Tranche of SBL Revenues, in each case, as of the applicable Purchase Date. No transfer of a SBL Tranche of SBL Revenues was or is made for or on account of an antecedent debt owed by the Seller to the Purchaser, and no such transfer was and is voidable or subject to avoidance under any Debtor Relief Law.

(j) Margin Stock; Use of Proceeds. The Seller is not engaged in the business of extending credit for the purpose of purchasing or carrying margin stock (within the meaning of Regulations T, U, and X, as issued by the Board of Governors of the Federal Reserve System), and no proceeds of any Purchase hereunder shall be used by the Seller (i) to acquire any security in any transaction which is subject to Section 13 or 14 of the Securities Exchange Act of 1934, (ii) to acquire any equity security of a class which is registered pursuant to Section 12 of such Act or (iii) for any other purpose that violates applicable Law, including Regulation U of the Board of Governors of the Federal Reserve System.

(k) Principal Place of Business; Chief Executive Office; Location of Records. The principal place of business, chief executive office and the offices where the Seller keeps all its books and records are located at the address described in Section 8.02.

(l) SBLs; SBL Revenues; SBL Contracts. Seventy-five percent (75%) of the seats in the Stadium will consist of SBL Seats. The face value of the SBLs related to such SBL Seats will be \$125 million in the aggregate. On the Purchase Date of any SBL Tranche of SBL Revenues purchased by the Purchaser hereunder, the Seller has no knowledge of any fact that would cause it or should have caused it to expect any payments on the SBL Revenues not to be paid in full when due. All SBL Revenues are (or will be at the time of the sale of the underlying SBL) evidenced by a SBL Contract the form of which (and any modifications thereto) shall be approved by the Purchaser and the Collateral Trustee in writing prior to any sale of SBLs and which shall be substantially consistent with the summary of terms set forth in Exhibit D attached hereto, subject to such modifications to the form of SBL Contract as may be approved in advance by the Purchaser and the Collateral Trustee in writing. Each SBL Contract constitutes a legal, valid and binding obligation of the Seller and, to the Seller's knowledge, the applicable SBL Licensee enforceable in accordance with its terms except as enforcement thereof may be limited by bankruptcy, insolvency, reorganization, moratorium or other similar laws affecting enforcement of creditor's rights generally and by general principles of equity (regardless of whether enforcement is sought in a proceeding in law or at equity). Each SBL was sold in compliance applicable Law.

(m) Material Adverse Effect. To the Seller's knowledge after due inquiry and investigation, on and since the Closing Date, no event has occurred that alone or together

with other events could reasonably be expected to have a Material Adverse Effect. The Seller has no knowledge of any judgment, ERISA or tax lien filings against it which would reasonably be expected to have a Material Adverse Effect.

(n) No Event of Default. To the Seller's knowledge after due inquiry and investigation, no event has occurred and is continuing and no condition exists which constitutes an Event of Default.

(o) Holding Account. All SBL Licensees have been instructed pursuant to the terms of the SBL Contracts or otherwise to make payment to the Holding Account.

(p) Bulk Sales/Consumer Laws. No transaction contemplated hereby or any of the other Transaction Documents requires compliance with any bulk sales act or similar law. The SBL Contracts and the offering of the SBL's to potential SBL Licensees complies with the consumer laws of the jurisdictions in which they are offered.

(q) Lack of Intent to Hinder, Delay or Defraud. The Seller has not sold, and will not sell, any interest in any SBL Revenues with any intent to hinder, delay or defraud any of its creditors.

(r) Patriot Act. The Seller is in compliance, in all material respects, with (i) the Trading with the Enemy Act, as amended, and each of the foreign assets control regulations of the United States Treasury Department (31 C.F.R., Subtitle B, Chapter V, as amended) and any other enabling legislation or executive order relating thereto, and (ii) the Uniting and Strengthening America by Providing Appropriate Tools Required to Intercept and Obstruct Terrorism Act (Title III of Pub. L. 107-56 (signed into law October 26, 2001) (the "**PATRIOT Act**"). No part of the consideration paid to the Seller hereunder will be used, directly or indirectly, for any payments to any governmental official or employee, political party, official of a political party, candidate for political office, or anyone else acting in an official capacity, in order to obtain, retain or direct business or obtain any improper advantage, in violation of the United States Foreign Corrupt Practices Act of 1977, as amended.

Section 4.02 Reliance; Notice of Breach. The Seller acknowledges that the Purchaser will assign to the Collateral Trustee for the benefit of the Lenders all of its rights and remedies with respect to the breach of any representations and warranties of the Seller under this Agreement. Upon discovery by the Seller, or the Purchaser of a breach of any of the foregoing representations and warranties that materially and adversely affects the value of the SBL Revenues, the party discovering such breach shall give prompt written notice to the other party and to the Collateral Trustee.

Section 4.03 Limitation on Liability. The Seller and any officer or employee or agent of the Seller may rely in good faith on the advice of counsel or on any document of any kind, prima facie properly executed and submitted by any person respecting any matters arising hereunder. The Seller shall not be under any obligation to appear in, prosecute or defend any legal action that shall not be related to its obligations under this Agreement, and that in its opinion may involve it in any expense or liability. Neither the Seller nor any of the officers or

employees or agents of the Seller shall be under any liability to the Purchaser, except as provided under this Agreement, for any action taken or for refraining from the taking of any action pursuant to this Agreement or for errors in judgment; but this sentence shall not protect the Seller or any such person against any liability that would otherwise be imposed by reason of willful misfeasance, bad faith or gross negligence in the performance of duties or by reason of reckless disregard of obligations and duties under this Agreement.

**ARTICLE V**  
**COVENANTS**

Section 5.01 Covenants of the Seller. The Seller covenants and agrees that:

(a) Protection of Title. The Seller shall take all commercially reasonable actions as may be required by law fully to preserve, maintain, defend, protect and confirm the interests of the Purchaser and the interests of the Collateral Trustee on behalf of the Lenders in the SBL Revenues and in the proceeds thereof. The Seller will not take any action that will materially adversely affect the Purchaser's or the Collateral Trustee's ability to receive payments with respect to the SBL Revenues.

(b) Non-Impairment Covenant. The Seller hereby pledges and agrees with the Purchaser and with the Lenders that the Seller will not materially alter, limit or impair the rights of the Purchaser to fulfill the terms of its agreements with such Lenders, or in any way impair the rights and remedies of such Lenders or the security for the Loan, until the Loan, together with the interest thereon, and all reasonable costs and expenses in connection with any action or proceeding by or on behalf of such Lenders, are fully met and discharged and such agreements are fully performed on the part of the Purchaser.

(c) Furnishing of Information and Inspection of Records. The Seller shall furnish to the Purchaser and the Collateral Trustee from time to time such information with respect to the SBL Revenues as the Purchaser or the Collateral Trustee may reasonably request, including listings identifying the SBL Licensees and the unpaid balance of each SBL Revenue and copies of the SBL Contracts. The Seller shall, at any time and from time to time during regular business hours upon reasonable notice, as requested by the Purchaser or the Collateral Trustee, permit the Purchaser or the Collateral Trustee, or their respective agents or representatives, (i) to examine and make copies of and take abstracts from all books, records and documents (including computer tapes and disks) relating to the SBL Revenues, including the related SBL Contracts and (ii) to visit the offices and properties of the Seller for the purpose of examining such materials described in clause (i), and to discuss matters relating to the SBL Revenues, or the Seller's performance hereunder, under the SBL Contracts and under the other Transaction Documents to which such Person is a party with any of the officers, employees or independent public accountants of the Seller having knowledge of such matters which are reasonably selected for such purpose by the Seller; provided that unless an Event of Default caused by the Seller shall have occurred and be continuing, the Seller shall not be required to reimburse expenses with respect to such visits.

(d) Keeping of Records and Books of Account. The Seller shall maintain and implement administrative and operating procedures (including an ability to recreate records evidencing SBL Revenues and SBL Contracts in the event of the destruction of the originals thereof), and keep and maintain all documents, books, computer tapes, disks, records and other information reasonably necessary or advisable for the collection of all SBL Revenues (including records adequate to permit the daily identification of each SBL Revenue and all collections with respect to each SBL Revenue). The Seller shall give the Purchaser and the Collateral Trustee prompt notice of any material change in its administrative and operating procedures referred to in the previous sentence.

(e) Sale of SBLs. The Seller shall use its best efforts to sell, or cause to be sold, all of the SBLs for an aggregate purchase price of \$125 million in accordance with the SBL Marketing and Sales Agreement. It is acknowledged and agreed that the SBLs will be sold pursuant to the SBL Marketing and Sales Agreement and that the Seller's compliance with its obligations under the SBL Marketing and Sales Agreement shall be evidence that the Seller has used its best efforts to sell the SBLs in compliance with the immediately preceding sentence. The Seller agrees that it will not amend, modify or waive any term or condition of the SBL Marketing and Sales Agreement without the prior written consent of the Purchaser and the Collateral Trustee. Each sale of SBLs shall be evidenced by an SBL Contract in the form approved by the Purchaser and the Collateral Trustee in writing. In the event that an SBL shall terminate due to a default by the SBL Licensee under the applicable SBL Contract, the Seller shall use its best efforts to sell, or cause to be sold, a new SBL with respect to the applicable SBL Seat (each such new SBL, a "**Replacement SBL**"). It is acknowledged and agreed that the Replacement SBLs may be sold pursuant to the SBL Marketing and Sales Agreement and that the Seller's compliance with its obligations under the SBL Marketing and Sales Agreement shall be evidence that the Seller has used its best efforts to sell the Replacement SBLs in compliance with the immediately preceding sentence.

(f) Performance and Compliance with SBL Contracts. The Seller shall (i) at its own expense, timely and fully perform and comply with all material provisions, covenants and other promises required to be observed by it under the SBL Contracts related to the SBL Revenues in accordance with commercially reasonable standards; and (ii) timely and fully comply in all material respects with commercially reasonable standards in regard to all SBL Revenues and the related SBL Contracts. The Seller shall not extend, amend, forgive, discharge, compromise, cancel or otherwise materially adversely modify the terms of any SBL Revenue or the related SBL Contract without the prior written consent of the Purchaser and the Collateral Trustee.

(g) Notice of Collateral Trustee's Interest. In the event that the Seller shall sell or otherwise transfer any interest in accounts receivable or any other financial assets (other than as contemplated by the Transaction Documents), any computer tapes or files or other documents or instruments provided by the Seller in connection with any such sale or transfer shall disclose the Purchaser's ownership of the applicable percentage of the SBL Revenues and the Collateral Trustee's security interest therein.

(h) Collections. The Seller has instructed, or shall instruct, all SBL Licensees to cause all payments with respect to the SBL Contracts to be deposited directly to the Holding Account. The Seller shall not commingle any collections related to any SBL Tranche of SBL Revenues sold hereunder at any time with any other funds, except with respect to funds received in the Holding Account in accordance with the terms hereof and in the Authority SBL Account Agreement.

(i) Collections Received. The Seller shall hold in trust, and deposit, promptly, but in any event not later than two (2) Business Days following its receipt thereof, to the Holding Account all collections with respect to the SBL Revenues and the related SBL Contracts received by it from time to time.

(j) Sale Treatment. The Seller shall not treat the transactions contemplated by this Agreement in any manner other than as a sale of SBL Tranches of SBL Revenues by the Seller to the Purchaser. In addition, the Seller shall disclose (in a footnote or otherwise) in all of its financial statements (including any such financial statements consolidated with any other Person's financial statements) the existence and nature of the transaction contemplated hereby and the interest of the Purchaser in the SBL Revenues consistent with generally accepted accounting principles applicable to the Seller.

(k) Ownership Interest, Etc. The Seller shall, at its expense, take all action necessary or desirable to establish and maintain a valid and enforceable ownership or first priority perfected security interest in the SBL Tranches of SBL Revenues sold pursuant hereto, and proceeds with respect thereto, in each case free and clear of any Adverse Claim, in favor of the Purchaser, including taking such action to perfect, protect or more fully evidence the interest of the Purchaser and the Collateral Trustee, as the Collateral Trustee may reasonably request.

(l) Perfection Covenants. In order to evidence the interests of the Purchaser under this Agreement, the Seller shall, from time to time, take such action, or execute and deliver such instruments (other than filing financing statements) as may be reasonably necessary and reasonably requested in writing by the Collateral Trustee to maintain the Purchaser's ownership interest and to maintain and perfect, as a first-priority interest, the Purchaser's security interest in the SBL Tranches of SBL Revenues sold hereunder. The Seller shall, upon the reasonable request of the Collateral Trustee, from time to time and within the time limits established by Law, prepare and present to the Collateral Trustee for the Collateral Trustee's authorization and approval all financing statements, amendments, continuations or other filings necessary to continue, maintain and perfect as a first-priority interest the Purchaser's interest in the SBL Tranches of SBL Revenues sold hereunder. The Collateral Trustee's approval of such filings shall authorize the Seller to file such financing statements under the UCC. Notwithstanding anything else in the Transaction Documents to the contrary, the Seller shall not have any authority to file a termination, partial termination, release, partial release, or any amendment that deletes the name of a debtor or excludes collateral of any such financing statements, without the prior written consent of the Collateral Trustee.

(m) Information for Reports; Financial Statements. The Seller shall promptly deliver any information, documents, records or reports with respect to the SBL Revenues and the SBL Contracts that the Purchaser shall require to complete any reports required to be delivered by the Purchaser under the Credit Agreement. The Seller shall provide on an annual basis its audited comprehensive annual financial report and, on a quarterly basis, copies of interim revenue and expense statements of the Seller, relating to the Stadium, the SBL Revenues and the SBL Contracts.

(n) No Sales, Liens, Etc. Except as otherwise provided herein, the Seller shall not sell, assign (by operation of law or otherwise) or otherwise dispose of, or create or suffer to exist any Adverse Claim upon (or grant the right to file any financing statement) or with respect to any SBL Revenues, or assign any right to receive income in respect thereof.

(o) Change of Name, Etc. The Seller shall not change its name, identity or structure (including pursuant to a merger) or the location of its jurisdiction or formation or any other change which could render any UCC financing statement filed in connection with this Agreement or any other Transaction Document to become “seriously misleading” under the UCC, unless at least fifteen (15) days prior to the effective date of any such change the Seller delivers to the Purchaser and the Collateral Trustee such documents, instruments or agreements, executed by the Seller as are necessary to reflect such change and to continue the perfection of the Purchaser’s and the Collateral Trustee’s ownership interests or security interests in the SBL Tranche of SBL Revenues.

(p) Amendment of this Agreement. The Seller shall not amend, modify or supplement this Agreement or waive any provision hereof, in each case except with the prior written consent of the Collateral Trustee. The Seller shall not take any other action under this Agreement that would reasonably be expected to result in a Material Adverse Effect.

(q) PATRIOT Act. The Seller shall, promptly following a request by the Purchaser or the Collateral Trustee, provide all documentation and other information that the Purchaser or the Collateral Trustee requests in order to comply with applicable “know your customer” and anti-money laundering rules and regulations, including the PATRIOT Act.

(r) Construction of Stadium. The Seller will comply with its obligations under the Development Agreement to complete the construction of the Stadium on or before the Scheduled Completion Date (as defined and set forth in the Development Agreement). The Seller shall provide to the Purchaser and the Collateral Trustee periodic reports related to the construction of the Stadium. As security for the obligations of the Seller under this Section 5.01(r) the Seller will provide conditional assignments of the Development Agreement Documents (as defined in the Development Agreement) in accordance with the summary of the “step-in” provisions set forth in Exhibit C.

(s) Compliance with Related Agreements. The Seller will comply with its obligations under the Calculation Agency Agreement, the Development Agreement and the SBL Marketing and Sales Agreement.

Section 5.02 Covenants of the Purchaser.

(a) Issuance of Residual Certificate. In accordance with Section 2.06 hereof, the Purchaser shall take all steps reasonably necessary to cause the Residual Certificate to be issued to the Seller in the form attached hereto as Exhibit B.

(b) Credit Agreement not a Debt of the Seller. The Purchaser acknowledges and agrees that the Seller is not a borrower under the Credit Agreement and that the Seller is not liable for any of the Purchaser's obligations thereunder.

Section 5.03 Further Actions of Seller. Upon request of the Purchaser or the Collateral Trustee, the Seller will execute and deliver such further instruments and do such further acts as may be reasonably necessary or proper to carry out more effectively the purposes of this Agreement.

**ARTICLE VI**  
**EFFECT OF EVENT OF DEFAULT**

Section 6.01 Effect of Event of Default. Following the occurrence of an Event of Default, the Seller shall not sell to, and the Purchaser shall not purchase from the Seller, any interests in SBL Revenues. Notwithstanding the foregoing, the occurrence of an Event of Default shall not discharge any Person from any obligations incurred prior to the occurrence of such Event of Default, including any obligations to make any payments with respect to the interest of the Purchaser in the SBL Revenues sold prior to such date; and provided further that (i) the rights and remedies of the Purchaser with respect to any representation and warranty made or deemed to be made by the Seller pursuant to this Agreement, (ii) the indemnification and payment provisions of Article VII, and (iii) the agreements set forth in Sections 2.02, 2.03, 2.04 and 8.08 shall expressly survive the occurrence of any Event of Default. At any time when an Event of Default exists and is continuing, the Purchaser or the Collateral Trustee may notify any SBL Licensee of its interest in the SBL Revenues.

**ARTICLE VII**  
**INDEMNIFICATION**

Section 7.01 Liability of Seller; Indemnities. Without limiting any other rights which the Seller Indemnified Parties (as defined below) may have hereunder or under applicable Law, the Seller hereby agrees to indemnify the Purchaser and its successors, transferees and assigns and all officers, directors, shareholders, controlling persons, employees, counsel and other agents of any of the foregoing (collectively, "**Seller Indemnified Parties**") from and against any and all damages, losses, claims, liabilities, costs and expenses, including reasonable attorneys' fees (which attorneys may be employees of any Seller Indemnified Party) and disbursements (all of the foregoing being collectively referred to as "**Seller Indemnified Amounts**") awarded against or incurred by any of them in any action or proceeding between the Seller and any of the Seller

Indemnified Parties or between any of the Seller Indemnified Parties and any third party, in each case arising out of or as a result of this Agreement, the ownership or maintenance, either directly or indirectly, by the Purchaser or any other Seller Indemnified Party of any interest in any SBL Revenues or any of the other transactions contemplated hereby, excluding, however, (i) Seller Indemnified Amounts to the extent resulting from gross negligence or willful misconduct on the part of such Seller Indemnified Party as determined by a court of competent authority in a final non-appealable order or (ii) recourse for uncollectible SBL Revenues. Without limiting the generality of the foregoing, the Seller shall indemnify each Seller Indemnified Party for Seller Indemnified Amounts relating to or resulting from:

- (a) any representation or warranty made by the Seller or any officers of the Seller under or in connection with this Agreement, any of the other Transaction Documents, any report or any other information delivered by the Seller pursuant hereto, or pursuant to any of the other Transaction Documents which shall have been incomplete, false or incorrect in any respect when made or deemed made;
- (b) the failure by the Seller to comply with any applicable Law with respect to any SBL Revenue or the related SBL Contract, or the nonconformity of any SBL Revenue or the related SBL Contract with any such applicable Law;
- (c) to the extent any sale hereunder does not constitute a true sale, the failure to vest and maintain vested in the Purchaser a first priority, perfected security interest in the SBL Tranche of SBL Revenues sold hereunder, free and clear of any Adverse Claim;
- (d) the failure by the Seller, following a request from the Collateral Trustee, to file, or any delay in filing, financing statements, continuation statements, or other similar instruments or documents under the UCC of any applicable jurisdiction or other applicable laws with respect to any SBL Tranche of SBL Revenues sold hereunder;
- (e) any dispute, claim, offset or defense (other than discharge in bankruptcy) of the SBL Licensee to the payment of any SBL Revenue (including a defense based on such SBL Revenue or the related SBL Contract not being the legal, valid and binding obligation of such SBL Licensee enforceable against it in accordance with its terms), or from any breach or alleged breach of any provision of the SBL Revenue or the related SBL Contract restricting assignment of any SBL Revenues;
- (f) any products liability claim or personal injury or property damage suit or other similar or related claim or action of whatever sort arising out of or in connection with merchandise or services which are the subject of any SBL Revenue or the related SBL Contract;
- (g) the failure by the Seller to comply with any term, provision or covenant contained in this Agreement or any of the other Transaction Documents to which it is a party or to perform any of its respective duties or obligations under the SBL Revenue or the related SBL Contract;



- (h) the failure of the Seller to pay when due any sales, excise or personal property taxes payable in connection with any of the SBL Revenues or the related SBL Contracts;
- (i) except as contemplated by the Authority SBL Account Agreement, the commingling by the Seller of collections related to any SBL Tranche of SBL Revenues sold hereunder at any time with any other funds;
- (j) any investigation, litigation or proceeding related to this Agreement, any of the other Transaction Documents, or any SBL Revenues or the related SBL Contracts;
- (k) any inability to obtain any judgment in or utilize the court or other adjudication system of, any state in which an SBL Licensee may be located as a result of the failure of the Seller to qualify to do business or file any notice of business activity report or any similar report;
- (l) any attempt by any Person to void, rescind or set-aside any transfer by the Seller to the Purchaser of any SBL Tranche of SBL Revenues under statutory provisions or common law or equitable action, including any provision of the Bankruptcy Code or other insolvency law;
- (m) any action taken by the Seller or the Servicer (if the Servicer is the Seller) in the enforcement or collection of any SBL Revenues or the related SBL Contracts;
- (n) the use of the proceeds of any Purchase hereunder; or
- (o) any and all amounts paid or payable by the Purchaser pursuant to the indemnification provisions set forth in the Credit Agreement.

**ARTICLE VIII**  
**MISCELLANEOUS**

Section 8.01 Amendment. Subject to Section 5.01(p), no agreement or other instrument purporting to amend, modify, supersede or retract or otherwise alter this Agreement or any provision hereof shall have any force or effect unless approved by the governing board of and executed and delivered under seal by a Responsible Officer of the party against whom asserted; nor, so long as the Loan remains outstanding, except as provided hereinafter in this Section. Further, with the prior written consent of the Collateral Trustee (which shall be subject to Collateral Trustee's sole discretion) this Agreement may be amended from time to time by the Seller and the Purchaser: (a) to cure any ambiguity or patent defect; (b) to correct or amplify the description of the SBL Revenues; or (c) to add additional covenants for the benefit of the Purchaser and the Lenders.

Promptly after the execution of any such amendment, the Purchaser shall furnish an executed counterpart of such amendment to the Collateral Trustee.

Prior to the execution of any amendment to this Agreement, the Collateral Trustee shall be entitled to receive and rely upon an Opinion of Counsel stating that the execution of such

amendment is authorized or permitted by this Agreement. The Collateral Trustee may, but shall not be obligated to, enter into any such amendment which affects the Collateral Trustee's own rights, duties or immunities under this Agreement or otherwise.

Section 8.02 Notices. All demands, notices and communications upon or to the Seller, the Purchaser or the Collateral Trustee under this Agreement shall be in writing, personally delivered or mailed by certified mail, return receipt requested, and shall be deemed to have been duly given upon receipt (a) in the case of the Seller, to Minnesota Sports Facilities Authority, Attention: Ted Mondale, Executive Director, 900 South Fifth Street, Minneapolis, Minnesota 55415, with a copy to Dorsey & Whitney LLP, Attention Jay R. Lindgren, 50 South Sixth Street, Minneapolis, Minnesota 55402; (b) in the case of the Purchaser, to Minnesota Stadium Funding Trust, c/o Wilmington Trust, National Association, Rodney Square North, 1100 North Market Street, Wilmington, Delaware 19890-0001, Attention: Corporate Trust Administration; (c) in the case of the Collateral Trustee, at U.S. Bank National Association, EP-MN-WS3C, 60 Livingston Avenue, St. Paul, MN 55107, Attention: Christine Robinette; or (d) in the case of the Servicer, to Van Wagner Team Services, LLC, 800 Third Avenue, 28th Floor, New York, NY 10022 Attention: Jeffrey S. Knapple, with a copy to Van Wagner Team Services, LLC, 800 Third Avenue, 28th Floor, New York, NY 10022 Attention: Steven S. Pretsfelder, Esq.; or, as to each of the foregoing, at such other address as shall be designated by written notice to the other parties.

Section 8.03 Assignment. This Agreement may not be assigned by the Seller and any such purported assignment shall be of no effect. This Agreement may not be assigned by the Purchaser except pursuant to the Credit Agreement.

Section 8.04 Limitations on Rights of Others. The provisions of this Agreement are solely for the benefit of the Seller, the Purchaser, the owner of the Residual Certificate, Collateral Trustee, and the Lenders, and nothing in this Agreement, whether express or implied, shall be construed to give to any other person any legal or equitable right, remedy or claim under or in respect of this Agreement or any covenants, conditions or provisions contained herein.

Section 8.05 Separate Counterparts. This Agreement may be executed by the parties hereto in separate counterparts, each of which when so executed and delivered shall be an original, but all such counterparts shall together constitute but one and the same instrument.

Section 8.06 Headings. The headings of the various Articles and Sections herein are for convenience of reference only and shall not define or limit any of the terms or provisions hereof.

Section 8.07 Governing Law. THIS AGREEMENT SHALL BE GOVERNED BY AND CONSTRUED IN ACCORDANCE WITH THE LAWS OF THE STATE OF MINNESOTA.

Section 8.08 Nonpetition Covenant; Limited Recourse. The Seller shall not, prior to the date which is one year and one day after the date on which the principal of and interest on all Loans have been paid in full, acquiesce, petition or otherwise invoke or cause the Purchaser to invoke the process of any court or government authority for the purpose of commencing or

sustaining a case against the Purchaser under any Federal or state bankruptcy, insolvency or similar law or appointing a receiver, liquidator, assignee, trustee, custodian, sequestrator or other similar official of the Purchaser or any substantial part of its property, or ordering the winding up or liquidation of the affairs of the Purchaser. In addition, all amounts payable by the Purchaser to the Seller pursuant to this Agreement shall be payable solely from funds available for that purpose pursuant to the terms of the Credit Agreement.

Section 8.09 Limitation of Liability of the Seller. Notwithstanding anything contained herein to the contrary, no officer, employee or agent of the Seller shall have any liability for the representations, warranties, covenants, agreements or other obligations of the Seller hereunder or in any of the certificates, notices or agreements delivered pursuant hereto, as to all of which recourse shall be had solely to the Seller.

Section 8.10 No Setoff. The Seller's obligations under this Agreement shall not be affected by any right of setoff, counterclaim, recoupment, defense or other right the Seller might have against the Purchaser, all of which are hereby expressly waived by the Seller.

Section 8.11 Termination of Certain Provisions. To the extent any covenant, representation, obligation or consent requirement herein is said to be for the benefit of the Lenders or of the Collateral Trustee, such provision shall, with respect to the Lenders or the Collateral Trustee, be deemed to terminate upon the payment of all outstanding Loans and the termination of the Credit Agreement.

Section 8.12 Severability of Provisions. If any one or more of the provisions of this Agreement shall for any reason whatsoever be held invalid, then such provisions shall be deemed severable from the remaining provisions of this Agreement and shall in no way affect the validity or enforceability of such other provisions.

Section 8.13 Limitation of Liability of Trustee. It is expressly understood and agreed by the parties hereto that (a) this Agreement is executed and delivered by Wilmington Trust, National Association, not individually or personally but solely as Trustee of the Purchaser, in the exercise of the powers and authority conferred and vested in it under the Trust Agreement (as defined in the Credit Agreement), (b) each of the representations, undertaking and agreements herein made on the part of the Purchaser is made and intended not as personal representations, undertaking and agreements by Wilmington Trust, National Association but is made and intended for the purposes for binding only the Purchaser, (c) nothing herein contained shall be construed as creating any liability on Wilmington Trust, National Association, individually or personally, to perform any covenant either express or implied contained herein, all such liability, if any, being expressly waived by the parties hereto and any Person claiming by, through or under the parties hereto, and (d) under no circumstances shall Wilmington Trust, National Association be personally liable for the breach or failure of any obligation, representation, warranty or covenant made or undertaken by the Purchaser under this Agreement.

Section 8.14 NFL Requirements. The parties hereto acknowledge that the Trust, StadCo, the Administrative Agent and the Collateral Trustee are entering into a separate letter agreement with, inter alia, the NFL, Minnesota Vikings Football Company, LLC, Minnesota Vikings Football Stadium Company, LLC and their respective Affiliates party thereto (as the

same may hereafter be amended, the “NFL Letter Agreement”; all capitalized terms used in this Section and not defined in this Section are defined in the NFL Letter Agreement), and that so long as the NFL Letter Agreement is in effect and notwithstanding anything in this Agreement or any other Operative Document to the contrary, (a) the exercise by the Secured Parties of their rights and remedies under any Operative Document will be made in accordance with the terms and provisions of the NFL Letter Agreement, and (b) in the event of any conflict or inconsistency between the terms of the NFL Letter Agreement and the terms of any Operative Document (including without limitation this Agreement) relating to the rights and remedies of the Secured Parties under such Operative Document, the terms of the NFL Letter Agreement will control as among the parties thereto. Although, as described above, the NFL Letter Agreement may affect the exercise by the Secured Parties of their rights and remedies under any Operative Documents, the parties acknowledge that the Authority is not a party to the NFL Letter Agreement, and that nothing in the NFL Letter Agreement controls the exercise by the Authority of its rights, or the performance by the Authority of its obligations, hereunder.

[Signatures follow on next page]

**EXECUTION COPY**

IN WITNESS WHEREOF, the parties hereto have caused this Agreement to be duly executed by their respective officers as of the day and year first above written.

MINNESOTA STADIUM FUNDING  
TRUST, as Purchaser

By: Wilmington Trust, National Association,  
not in its individual capacity but solely as  
Trustee

By: \_\_\_\_\_  
Name:  
Title:

MINNESOTA SPORTS FACILITIES  
AUTHORITY, as Seller

By: \_\_\_\_\_  
Name:  
Title:

VAN WAGNER TEAM SERVICES, LLC,  
as Servicer

By: \_\_\_\_\_  
Name:  
Title:

**Exhibit A**

**Form of Notice of Sale**

[Attached]

## FORM NOTICE OF SALE

[DATE]

Minnesota Stadium Funding Trust  
 c/o Wilmington Trust, National Association  
 Rodney Square North  
 1100 North Market Street  
 Wilmington, Delaware 19890-0001  
 Attention: Corporate Trust Administration

U.S. Bank National Association, as Collateral Trustee  
 EP-MN-WS3C  
 60 Livingston Avenue  
 St. Paul, MN 55107  
 Attention: Christine Robinette

Ladies and Gentlemen:

Reference is made to that certain Purchase and Sale Agreement (the “Agreement”), dated as of November 22, 2013, by and between Minnesota Stadium Funding Trust, as purchaser (the “Purchaser”) and Minnesota Sports Facilities Authority, as seller (the “Seller”). Capitalized terms used but not otherwise defined herein shall have the meanings set forth in the Agreement.

The Seller hereby delivers this Notice of Sale pursuant to Section 2.01(b) of the Agreement and further provides for the sale of SBL Revenues as follows:

1. SBL Tranche.

		Percentage (%)	Dollar Equivalent
A	SBL Tranche to be sold to fund current Private Contribution	[ ]%	\$( )
B	Plus SBL Tranche to be sold to fund Seller’s costs, fees and expenses	[ ]%	\$( )
C	Plus SBL Tranche to be sold and representing Minimum Monthly SBL Tranche	[ ]%	\$( )
D	Plus SBL Tranche to be sold to fund Purchaser’s costs, fees and expenses	[ ]%	\$( )
E	Total SBL Tranche to be sold on Purchase Date	[ ]%	\$( )
F	Total SBL Tranche sold to date (inclusive of % stated above)	[ ]% (not to exceed 100%)	\$( )
G	Total Unsold SBL Tranche	[ ]% (100% minus amount set forth above)	\$( )

The Seller has been informed by the Purchaser or the Collateral Trustee that the Purchaser's next monthly debt service payment under the portion of the Credit Agreement used to fund the purchase of SBL Tranches (the "SBL Revenue Purchase Tranche") is \$\_\_\_\_\_ and, therefore, the Minimum Monthly SBL Tranche as stated above is [\_\_]%. The Seller hereby represents that, based on the information provided by the Purchaser or the Collateral Trustee, that the total SBL Tranche to be sold to the Purchaser on the Purchase Date is equal to or greater than such Minimum Monthly SBL Tranche.

The Seller has also been informed by the Purchaser or the Collateral Trustee that prior to the date hereof the Purchaser has borrowed an aggregate cumulative principal amount of \$\_\_\_\_\_ under the SBL Revenue Purchase Tranche of the Credit Agreement. The Seller hereby represents that the Purchaser or the Collateral Trustee has advised the Seller that following the sale of the SBL Tranche contemplated by this Notice of Sale, the aggregate cumulative principal amount borrowed by the Purchaser under the SBL Revenue Purchase Tranche of the Credit Agreement will be \$\_\_\_\_\_[Not to exceed \$125 million].

2. Purchase Date.

The Purchase Date for the SBL Tranche described in paragraph 1 above shall be: [notice needs to be ten (10)] days in advance].

3. Purchase Price.

The Purchase Price for the SBL Tranche described in paragraph 1 above shall be [\$\_\_\_\_\_][Paragraphs 1(A) and 1(B)], determined as follows:

[__]% (SBL Tranche %) [Paragraph 1(E)] * \$125,000,000 (Maximum Amount)	\$_____
<i>Less</i> fees, costs and expenses of Purchaser [Paragraph 1(D)]	\$(_____)
<i>Less</i> the amount of the Minimum Monthly SBL Tranche [Paragraph 1(C)]	\$(_____)
Purchase Price [Paragraphs 1(A) and 1(B)] [To be wired in accordance with the instructions in Paragraph 4]	\$_____



4. Disbursement Instruction.

You are hereby authorized and instructed to disburse the Purchase Price as follows:

\$\_\_\_\_\_ (Private Contribution) [Paragraph 1(A)], to be wired to the following account:

ABA:  
Acct#:  
Bank Name:  
Facsimile:  
REF:

\$\_\_\_\_\_ (Seller's costs, fees and expenses) [Paragraph 1(B)], to be wired to the following account:

ABA:  
Acct#:  
Bank Name:  
Facsimile:  
REF:

The Seller hereby represents and warrants as of the date hereof and as of the Purchase Date referenced above that (a) the representations and warranties of the Seller set forth in the Agreement are true and correct in all material respects, and (b) to the Seller's knowledge, no event has occurred and is continuing or would result from the consummation of the sale contemplated hereby that would constitute an Event of Default.

[The Remainder Of This Page Is Intentionally Left Blank]

**EXECUTION COPY**

IN WITNESS WHEREOF, the undersigned has executed this Notice of Sale as of  
[\_\_\_\_\_], 201[ ].

**MINNESOTA SPORTS FACILITIES  
AUTHORITY**

By: \_\_\_\_\_

Name:

Title:

[Signature Page to Notice of Sale]

**Exhibit B**

**Form of Residual Certificate**

[Attached]

**REGISTERED  
NUMBER: 1**

MINNESOTA STADIUM FUNDING TRUST  
RESIDUAL CERTIFICATE  
REGISTERED OWNER: MINNESOTA SPORTS FACILITIES AUTHORITY

The **MINNESOTA STADIUM FUNDING TRUST** (the “**Trust**”), a Delaware statutory trust, for value received, promises to pay to the registered owner of this Residual Certificate, all SBL Revenues (as defined in the Purchase and Sale Agreement (defined below)) owned by the Trust following the repayment in full of the Trust’s obligations under the following (collectively, the “**Obligations**”): (i) the SBL Revenue Purchase Tranche (as defined in the Credit Agreement) of that certain Credit Agreement, dated as of November 22, 2013 (as amended, restated or supplemented from time to time, as “**Credit Agreement**”), among the Trust, the lenders party thereto from time to time, U.S. Bank National Association (“**U.S. Bank**”), Goldman Sachs Bank USA, Merrill Lynch, Pierce, Fenner & Smith Incorporated and Sumitomo Mitsui Banking Corporation, as co-lead arrangers and joint bookrunners, Goldman Sachs Bank USA, Bank of America, N.A. and Sumitomo Mitsui Banking Corporation, as syndication agents, and U.S. Bank, as administrative agent and collateral trustee (in such capacity, the “**Collateral Trustee**”) and (ii) (a) any other obligations or indebtedness incurred by the Trust to replace or refinance the SBL Revenue Purchase Tranche or any commitment in respect thereof which are secured by all or any portion of the SBL Revenues and (b) any obligations or indebtedness incurred by the Trust to repay all or any portion of the SBL Revenue Purchase Tranche of the Credit Agreement, including, without limitation, pursuant to any financing provided by Minnesota Vikings Football Stadium, LLC (“**StadCo**”) pursuant to that certain Stadco Obligations Agreement dated as of November 22, 2013, among StadCo, the Trust (clauses (ii)(a) and (b) are collectively referred to as the “**Replacement Debt**”). All obligations or indebtedness constituting Replacement Debt shall, if entered into with creditor parties who are affiliates of StadCo or the Minnesota Vikings Football Club, LLC, bear interest and other financing charges at commercially reasonable rates and terms. The Trust covenants not to borrow more than an aggregate cumulative principal amount of \$125,000,000 under (A) the SBL Revenue Purchase Tranche (as defined in the Credit Agreement) of the Credit Agreement and (B) under any Replacement Debt. The SBL Revenues shall be paid to the owner of this Residual Certificate by wire transfer as promptly as practicable following repayment in full of the Obligations and, with respect to SBL Revenues received after such date, as promptly as practicable following the actual receipt thereof by the Trust or the Collateral Trustee. The Trust’s interest in the SBL Revenues is set forth in that certain Purchase and Sale Agreement, dated as of November 22, 2013 (as amended, restated or supplemented from time to time, the “**Purchase and Sale Agreement**”) between the Trust and the Minnesota Sports Facilities Authority (the “**Authority**”).

Payments with respect to this Residual Certificate shall be payable solely from the SBL Revenues and not from any other assets of the Trust. Neither the trustee of the Trust nor any other person executing this Residual Certificate shall be liable personally thereon or be subject to any personal liability or accountability solely by reasons of the issuance hereof.

This Residual Certificate is issuable only in fully registered form and may not be converted into bearer form. The Trust and the Collateral Trustee may treat the registered owner as the absolute owner of this Residual Certificate for all purposes, notwithstanding any, notice to the contrary.

This Residual Certificate is not transferrable or assignable (except by operation of law to a successor to the Authority) and any attempt to transfer or assign the rights granted hereunder shall be null and void.

**THIS RESIDUAL CERTIFICATE SHALL BE GOVERNED BY AND CONSTRUED IN ACCORDANCE WITH THE LAWS OF THE STATE OF MINNESOTA.**

It is expressly understood and agreed by the parties hereto that (a) this Residual Certificate is executed and delivered by Wilmington Trust, National Association, not individually or personally but solely as Trustee of the Trust, in the exercise of the powers and authority conferred and vested in it under that certain Amended and Restated Trust Agreement dated as of November 22, 2013 by and among, Minnesota Vikings Football Stadium, LLC, as trust depositor, Minnesota Stadium Funding Trust Beneficiary, LLC, a Delaware limited liability company, as beneficiary and Wilmington Trust, National Association, as trustee, (b) each of the representations, undertaking and agreements herein made on the part of the Trust is made and intended not as personal representations, undertaking and agreements by Wilmington Trust, National Association, but is made and intended for the purposes for binding only the Trust, (c) nothing herein contained shall be construed as creating any liability on Wilmington Trust, National Association, individually or personally, to perform any covenant either express or implied contained herein, all such liability, if any, being expressly waived by the parties hereto and any Person claiming by, through or under the parties hereto, and (d) under no circumstances shall Wilmington Trust, National Association be personally liable for the breach or failure of any obligation, representation, warranty or covenant made or undertaken by the Trust under this Residual Certificate.

**EXECUTION COPY**

**IN WITNESS WHEREOF**, the MINNESOTA STADIUM FUNDING TRUST has caused this Residual Certificate to be executed as of the 22nd day of November, 2013.

**MINNESOTA STADIUM FUNDING  
TRUST**

By: Wilmington Trust, National  
Association, not in its individual capacity  
but solely as Trustee

By: \_\_\_\_\_  
Name:  
Title:

**Exhibit C**

**Construction ‘Step-In’ Rights**

1. Triggered by a ‘material’ default under Articles V, VI and VIII of the Development Agreement
2. 30 day notice and opportunity to cure under Development Agreement, followed by 20 day notice of exercise of rights under conditional assignment
3. 10 day ADR adjudication procedure to determine whether or not the alleged default is, in fact, a ‘material default’ and determine what action is required to cure. Five days for the hearing and five days for the decision.
4. Loser pays attorneys’ fees on adjudication as to whether or not a ‘material default’ has occurred.
5. If ADR determines that a ‘material default’ has occurred and the Seller has failed to cure within the required time period, the Purchaser may exercise ‘step-in’ rights.
6. The Seller must pay all direct costs associated with exercise of the step-in rights and cure
7. The Seller will have a one-time right to reassert control of the conditionally assigned agreements subject to the following conditions:
  - a. The Seller has cured the default
  - b. All direct costs relating to the exercise of step-in rights have been reimbursed
  - c. Project is in balance
  - d. The Seller has provided sufficient evidence to an independent, third-party construction expert that it has remedied any deficiencies in its operational capacities that gave rise to the default and has the ability to perform on a going-forward basis
  - e. The Purchaser consents to reassertion of control, which consent the Purchaser shall grant or withhold in its sole discretion based on the Purchaser’s good faith consideration of the Seller’s proposal to reassert such control

**Exhibit D**

**Summary of Terms of SBL Contracts**

The general terms of the Authority Stadium Builder License Program (the "**Program**") are as follows:

1. Gross Amount of Program – \$125,000,000 (One Hundred Twenty-Five Million Dollars).
2. Estimated Construction Fund Deposit - (Gross Amount of Program less estimated cost of SBL sales and interest costs) - Approximately \$100,000,000 (One Hundred Million Dollars).
2. Non-Stadium Builder License Percentage of Stadium Seating – 25% (Twenty-five Percent).
3. Stadium Builder License ("SBL") Percentage of Stadium Seating – 75% (Seventy-five Percent).
4. Maximum SBL Price Per Seat – Less than \$10,000.
5. Average SBL will be approximately - \$2,500.
6. Payment Opportunities – At least two (2) forms:
  - (a) On an Interest Free basis with three (3) equal installments beginning in 2014 (if purchased in 2014) with one-third (1/3) of the amount due paid at signing, one-third (1/3) of the amount due paid by July 1, 2015, and one-third (1/3) of the amount due paid by July 1, 2016.
  - (b) Financing options will be available for purchasers. Currently considering offering financing terms as follows:
    - Down payment at purchase
    - Two additional installments prior to stadium opening in 2015 and 2016
    - Financing will initially be interest free prior to stadium opening
    - Upon stadium opening, financing will be provided for remaining balance due at market interest rates, for up to a period of five years.
    - Purchasers can elect to pre-pay anytime
7. Commencement of SBL Program – Upon the Effective Date of the Stadium Development Agreement.
8. Statutory and Contractual SBL Agent for the Authority – Minnesota Vikings Football, LLC (with right to sublicense).



**EXHIBIT O-1**

**CONDITIONAL ASSIGNMENT OF CONSTRUCTION SERVICES AGREEMENT**

**SEE ATTACHED**

CONDITIONAL ASSIGNMENT

OF CONSTRUCTION SERVICES AGREEMENT

A. FOR VALUE RECEIVED, the sufficiency of which is hereby acknowledged, MINNESOTA SPORTS FACILITIES AUTHORITY, a public body and political subdivision of the State of Minnesota (hereinafter referred to as the “*Authority*”), hereby collaterally assigns, transfers, sets over and grants a security interest to MINNESOTA STADIUM FUNDING TRUST, a Delaware statutory trust (hereinafter referred to as the “*Purchaser*”, and collectively with the Authority, the “*Parties*”), in all of its right, title and interest in and to:

- (a) the Construction Services Agreement dated February 15, 2013 and all addenda, modifications and amendments thereto (the “*Agreement*”), between the Authority and M.A. Mortenson Company, a Minnesota corporation (hereinafter referred to as the “*Construction Manager*”), pertaining to the construction of the Project, as defined in the Agreement; and
- (b) any and all permits, licenses, allocations, approvals, certificates and consents heretofore or hereafter issued by any governmental or private authority or agency relating to the Project, naming the Authority or in which the Authority has an interest, and any other contracts, subcontracts or agreements for services, labor or materials pertaining to the Project, and all claims and rights with respect to nonperformance or breach thereof (hereinafter referred to as the “*Additional Interests*”).

B. This Assignment (this “*Assignment*”) is made as additional collateral and security for the Authority’s obligations under that certain Purchase and Sale Agreement dated November 22, 2013 by and between Purchaser and the Authority relating to the purchase by Purchaser of certain stadium builder licenses (the “*Sale Agreement*”). Reference is hereby made to that certain Amended and Restated Development Agreement dated November 22, 2013, effective as of October 3, 2013 by and between Minnesota Vikings Football Stadium, LLC, a Delaware limited liability company (“*Stadco*”) and the Authority and joined in by Minnesota Vikings Football, LLC, a Delaware limited liability company (hereinafter “*Team*”) (together with all addenda, modifications and amendments thereto, the “*Development Agreement*”). Capitalized terms used herein and not otherwise defined herein shall have the meanings given to them in the Development Agreement.

C. U.S. Bank National Association is the administrative agent and collateral agent “*Collateral Agent*”) under that certain Credit Agreement dated as of November [ ], 2013 by and between Purchaser, the Collateral Agent and the lenders party thereto. Notwithstanding the terms of this Assignment to the contrary, the grant by the Purchaser to the Collateral Agent of a security interest in this Assignment or the rights or interests of the Purchaser under this Assignment, or the making of a collateral assignment by the Purchaser to the Collateral Agent of this Assignment or the rights or interests of the Purchaser under this Assignment, are expressly permitted hereunder provided, the Purchaser agrees that thereafter neither it, nor any of its other successors or assigns or the Collateral Agent may re-assign its rights and remedies under this Assignment to Stadco, the Team or any of Stadco’s or the Team’s affiliates. The rights and

remedies of the Purchaser under this Assignment and the Consent and Agreement of Construction Manager are all expressly subject to the terms and conditions of this Section C.

The Authority represents and warrants and agrees as follows:

1. The copy of the Agreement heretofore delivered to Purchaser is a true, correct and complete copy thereof; there have been no prior assignments of the Agreement; the Agreement is valid, enforceable and in full force and effect as to the Authority, and the Agreement, as amended, has not been otherwise amended or modified in any manner as of the date of this Assignment; neither party, to the best of the Authority's knowledge, is in default under the terms of the Agreement; and all material covenants, conditions and agreements of the Authority contained in the Agreement have been substantially performed as required therein, except those not due to be performed until after the date hereof.
2. So long as this Assignment is in effect, the Authority agrees not to further assign, sell, pledge, mortgage or otherwise transfer or encumber its interest in the Agreement or any Additional Interests, or amend, restate or otherwise modify the Agreement or any Additional Interests except in accordance with the provisions of the Development Agreement, in each case, without the consent of Purchaser and Purchaser's assignees.
3. This Assignment shall constitute an absolute and present assignment, provided that Purchaser shall have no right under this Assignment to enforce the provisions of the Agreement or the Additional Interests until: (i)(a) an Event of Default has occurred pursuant to Section 12.1(d) of the Development Agreement (an "*Authority Insolvency Default*") or (b) Stadco or Purchaser has given the Authority written notice (hereinafter a "*Notice of Material Default*") in the manner described in Section 16.6 of the Development Agreement that the Authority has violated or failed to perform or observe a covenant or condition under the Development Agreement for which it is responsible (so long as Authority is otherwise diligently enforcing its contractual rights against third parties in a commercially reasonable manner) or a representation or warranty of the Authority was incorrect when made in any material respect as contemplated under Section 12.1(a) or 12.1(b) of the Development Agreement, and that such violation, failure or incorrect statement reflects a material impairment of the Authority's ability to fulfill its obligations under the Development Agreement (hereinafter "*Material Default*"), (ii) the Authority has not cured the Material Default within thirty (30) days or longer as may be allowed under Section 12.1(a) of the Development Agreement following receipt of the Notice of Material Default (the "*First Cure Period*"), (iii) the Authority has not cured the Material Default within twenty (20) days following receipt of notice (the "*Enforcement Notice*") from the Purchaser that it is exercising its rights under this Agreement (the "*Second Cure Period*"), provided that the Second Cure Period shall not commence until expiration of the First Cure Period, and (iv) if the Authority disputes that a Material Default has occurred in the manner described in Section 5 below, the Authority has been adjudicated to have caused a Material Default that is continuing pursuant to the expedited dispute resolution provisions in this Agreement (the "*ADR Provisions*").
4. A Notice of Material Default must list in reasonable detail the material facts then known that support and describe the allegation of a Material Default, the Section(s) of the Development

Agreement and related agreements (including but not limited to the Construction Services Agreement) that are claimed to be in Material Default, and the specific actions that Purchaser believes would constitute a cure of the alleged Material Default. Notwithstanding anything herein to the contrary, the Authority shall have no right to cure an Authority Insolvency Default.

5. In the event that Authority disputes (i) the alleged Material Default or (ii) that it has failed to timely cure such Material Default within the First Cure Period, the Authority shall so notify Purchaser and Stadco on or before the expiration of the First Cure Period by giving a notice (hereinafter, a “*Material Default Dispute Notice*”), and failure of Authority to provide said Material Default Dispute Notice on or before the expiration of the First Cure Period shall constitute a conclusive determination that a Material Default has occurred and remains uncured. If Authority provides such Material Default Dispute Notice, the Parties must adjudicate the alleged Material Default pursuant to the following ADR Provisions:

- (a) Agreement to Arbitrate. All disputes between the Parties solely with respect to an alleged Material Default are each subject to expedited arbitration (each, an “*Expedited ADR Dispute*”) and shall be submitted to expedited alternative dispute resolution (“*Expedited ADR*”) under this Section 5. One or more disputes over alleged Material Defaults if alleged in close proximity to each other shall be part of one (1) Expedited ADR Dispute. No other disputes between the Parties shall be subject to Expedited ADR under this Assignment, unless the Parties mutually agree to submit to Expedited ADR.
- (b) Initiation of Arbitration and Selection of Neutral.
  - (i) In order to initiate Expedited ADR, a Party shall simultaneously deliver a notice of an alleged Material Default (“*Notice of Material Default*”) to other Party and to the highest ranked eligible potential neutral on the roster (each such neutral a “*Potential Neutral*” and collectively, the “*Potential Neutrals*”) attached as Exhibit 1 to this Assignment (“*Roster of Potential Neutrals*”). The Potential Neutral receiving a Notice of Material Default shall respond to the Parties within two (2) Business Days whether the Potential Neutral is available to serve. If the Potential Neutral is unavailable or otherwise unable to serve, or fails to respond within two (2) Business Days, either Party may deliver the Notice of Material Default to the next highest ranked Potential Neutral on the Roster of Potential Neutrals and may proceed in this same manner until a Potential Neutral is able to serve and accepts appointment as the Neutral (“*Neutral*”) to hear and decide the dispute. If no Potential Neutral on the Roster of Potential Neutrals is able to serve, then either Party may request the Chief Judge of the United States District Court for the District of Minnesota to appoint a Neutral, and the Parties agree to request such appointment as soon as practicable, but no later than five (5) calendar days after the Chief Judge receives such a request. The fees and costs of the Neutral shall be borne equally by the Parties, but the prevailing Party shall be entitled to reimbursement for its share of such fees and costs from the non-prevailing Party in accordance with Section 5(d)(vii) below.

- (ii) After appointment of the Neutral, each Party shall have three (3) Business Days to prepare and deliver to the other Party and the Neutral a detailed and specific written statement outlining the nature of the alleged Material Default (each a “*Statement of Dispute*”).
  - (iii) The delivery of a Statement of Dispute by either Party to the Neutral shall initiate the Expedited ADR provisions of this Assignment and the matter covered by the Statement of Dispute shall be considered submitted to the Neutral for determination.
  - (iv) The timelines established for the expedited arbitration shall be strictly followed by the Neutral unless extended by mutual agreement of Parties.
- (c) Qualifications of Neutral. The Parties shall obtain disclosures from each Potential Neutral and confirm that each Potential Neutral is independent of the Authority, Purchaser, Trust, Stadco, Collateral Agent and lenders party to the Credit Agreement, and Team (and their respective Affiliates and agents) and holds no financial interest in, and has no material financial or material personal relationship with the Authority, Purchaser or Team (or their respective Affiliates).
- (d) Location and Conduct.
- (i) Location. The Expedited ADR proceeding shall be conducted by the Neutral at a time and location in Hennepin County, Minnesota selected by the Neutral. Subject to Section 5(b)(iv) hereof, the Neutral shall give the Authority and Purchaser reasonable notice of the Expedited ADR proceeding, which shall be within two (2) Business Days after submission the Statements of Dispute. The Neutral shall conduct the Expedited ADR proceeding in such manner as the Neutral deems appropriate, consistent with the provisions of this Section 5.
  - (ii) Presentation of Information. Each Party shall present its position with respect to the issue(s) to be determined in the Expedited ADR proceeding through evidence and oral presentation to the Neutral. Each Party shall be given the opportunity to hear and orally respond to the other Party’s presentation to the Neutral, and to present documents and evidence to the Neutral in support of such Party’s position. The Neutral shall have the right to limit the time allowed for oral presentations, testimony, and the evidence presented to the Neutral to assure that the hearing does not exceed its allowed length and assure a prompt resolution of the issue(s) to be determined by the Neutral. The Neutral may require the participation of the Architect, the Construction Manager and other Project Consultants that have knowledge of the subject matter in the Statements of Dispute. At the conclusion of the Expedited ADR proceeding each Party shall submit its proposed written decision to the Neutral.

- (iii) Authority of Neutral. The Authority and Purchaser intend that the Neutral shall have the sole and exclusive authority and power to resolve Expedited ADR Disputes.
- (iv) Discovery. There shall be no discovery permitted with respect to any Expedited ADR proceeding other than that required by the Neutral or as may be necessary to fully understand the alleged Material Default.
- (v) Cooperation/Duration. The Authority and Purchaser shall cooperate in good faith to permit the start of the Expedited ADR proceeding within two (2) Business Days following the submission of each Party's Statement of Dispute to the Neutral. The Expedited ADR proceeding shall last no longer than five (5) Business Days unless the Neutral determines, in its sole discretion, that additional time is required to properly conduct the proceeding in a manner contemplated to provide sufficient information on which to form and issue an informed and fair decision.
- (vi) Post-Hearing Mediation. After the Expedited ADR proceeding concludes and after each Party submits its proposed written decision(s), but before the Neutral issues its written decision, the Neutral shall conduct a 180-minute mediation session and attempt to facilitate resolution of the issue(s) by settlement.
- (vii) Decision of the Neutral. The Neutral shall render the arbitration decision within five (5) Business Days after the conclusion of the Expedited ADR proceeding, subject to the decision of the Neutral to expand such time for decision. First, the Neutral must render a written decision determining whether or not a Material Default has occurred, and if so, what actions the Authority must take to cure the Material Default. Nothing herein or in the Neutral's decision shall extend or otherwise grant the Authority additional time to cure any Material Default. Second, the Neutral must award the reasonable attorneys fees, costs (including the fees and costs of the Neutral), and disbursements to the prevailing Party. Third, the Neutral must prepare, at a minimum, a written memorandum with an explanation of the basis for the decision. Fourth, the Neutral's written memorandum and decision shall be addressed and simultaneously sent to each of the Parties as set forth in the notice provision of this Assignment. The decision of the Neutral shall be binding upon the Parties for the purposes of determining whether or not Purchaser has the right to exercise the assignment of the Agreement as described in this Assignment.
- (viii) Exclusive Remedy. The Authority and Purchaser shall use Expedited ADR exclusively, rather than litigation, as a means of resolving the merits of each Expedited ADR Dispute for the sole purposes of this Assignment. Subject to the provisions of applicable law, the written decision of the Neutral shall be the binding, final determination on the merits of the Expedited ADR Dispute for the sole purposes of this Assignment, and

shall preclude any subsequent litigation or other proceeding on such merits. The Authority or Purchaser may institute legal proceedings in a court of competent jurisdiction to enforce judgment upon the decision of a Neutral in regard to this Assignment. Notwithstanding anything to the contrary contained herein, the Purchaser may seek other legal and equitable remedies and relief in regard to an Authority Insolvency Default.

- (ix) Other Remedies. While the Expedited ADR procedures set forth herein are final and binding for purposes of this Assignment, nothing in this Agreement shall limit or impair the right of the Authority to seek other legal and equitable relief in regard to an alleged or actual Material Default as between the Team or its assignee and the Authority, including without limitation, the equitable remedies allowed in the Development Agreement. Notwithstanding anything to the contrary contained herein, except as provided in subsection (viii) above, the Purchaser may seek other legal and equitable remedies and relief in regard to an Authority Insolvency Default.

6. If the Authority cures the alleged Material Default before the expiration of the Second Cure Period, the Notice of Material Default and Material Default Dispute Notice shall be of no further force or effect. If the Authority receives a decision from a Neutral holding that a Material Default has occurred and the Authority has not cured the Material Default before the expiration of the Second Cure Period, Purchaser may proceed to exercise all of its rights and remedies under this Assignment (the “*Purchaser Step-In Date*”).

7. The Authority shall have a one-time right to reassume its rights and duties under the Agreement upon satisfaction of the following conditions: (i) the Authority has cured the Material Default; (ii) the Authority has reimbursed the Purchaser for all direct costs and expenses incurred by Purchaser during the time Purchaser exercised the Authority’s rights and obligations under the Agreement; (iii) the Project budget is in balance; (iv) a neutral, independent third party construction expert unaffiliated with the Project or the Authority, Purchaser, the Collateral Agent and lenders party to the Credit Agreement, and Stadco determines that the Authority has remedied any deficiencies in its operational capacities that gave rise to the Material Default and has the ability to perform its duties under the Agreement on an ongoing basis; and (v) the Purchaser consents to the Authority’s re-assumption of its rights and duties under the Agreement, which consent the Purchaser shall grant or withhold in its sole discretion based on the Purchaser’s good faith consideration of the Authority’s proposal to reassume such rights and duties under the Agreement.

8. At any time after (i) the occurrence of an Authority Insolvency Default or (ii) in the case of a Material Default, after the cure periods (if any) referenced in Section 3 have expired and, if the Notice of Material Default has been contested by the Authority, after the Authority has been adjudicated to be in Material Default pursuant to Section 5, Purchaser may, without affecting any of its rights or remedies against the Authority under any other instrument, document or agreement, exercise its rights under this Assignment, and in addition, Purchaser shall have the right to exercise and enforce any or all rights and remedies available to a secured party under the Uniform Commercial Code with respect to the Agreement and the Additional Interests.

9. At all times after Purchaser shall have exercised its rights pursuant to Section 3 above, Purchaser shall be entitled to demand, receive and enforce the Authority's rights with respect to the Agreement and the Additional Interests, to make payments under the Agreement and to give appropriate receipts, releases and satisfactions for and on behalf of and in the name of the Authority or, at the option of Purchaser, in the name of Purchaser, with the same force and effect as if Purchaser had originally executed the Agreement; provided, however, that the Purchaser may not amend the Agreement or any Additional Interests in a manner which would expand the obligations of the Authority under the Agreement or any Additional Interests beyond that which is in effect as of the date of the Material Default Dispute Notice.

10. Purchaser does not assume any of the obligations or duties of the Authority under or with respect to the Agreement unless and until Purchaser shall have given the Construction Manager written notice that it is exercising its right hereunder. If Purchaser does not provide such notice to the Construction Manager, Purchaser shall have no liability whatsoever for the performance of any of the obligations or duties under the Agreement. Purchaser may collaterally assign its right to and interest in the Agreement and this Assignment to any party (other than Team, Stadco or their respective affiliates) providing financing to Purchaser and in addition, Purchaser may reassign, in its sole discretion, and for the purpose of completing the Project, its right, title and interest in the Agreement (other than to the Team, Stadco or their respective affiliates) upon notice to the Construction Manager, but without any requirement for the consent of the Authority or Construction Manager.

11. Nothing herein shall affect the rights or obligations of the Authority, the Team or the Purchaser under the Development Agreement.

12. The Authority agrees to make, execute and deliver all such further or additional instruments as may be reasonably necessary to perfect the assignment made hereby.

13. Authority acknowledges and agrees that it has entered into this Agreement for good and adequate consideration, the sufficiency of which is hereby acknowledged by the Authority. This Assignment and the agreements and undertaking of the Authority hereunder shall be binding upon the Authority and its successors and assigns and shall inure to the benefit of Purchaser and its successors and assigns. Neither this Assignment nor any provision hereof may be changed, waived, discharged or terminated orally, rather only by an instrument in writing signed by the Authority and Purchaser.

14. This Assignment shall be governed by the laws of the State of Minnesota.

15. Any notice or other communication to be given to the Authority, Stadco or the Purchaser (each, a "*Notice Party*") hereunder shall be given in the manner set forth in the Development Agreement (i) to the Authority at Minnesota Sports Facilities Authority, Mall of America Field, 900 South Fifth Street, Minneapolis, MN 55415, Attn.: Chair and CEO / Executive Director, (ii) to Stadco at Minnesota Vikings Football, LLC, 9520 Viking Drive, Eden Prairie, MN 55344, Attn.: CFO, and (iii) to the Purchaser at Minnesota Stadium Funding Trust, c/o Wilmington Trust, National Association, as Trustee, Rodney Square North, 1100 North Market Street, Wilmington, DE 19890, Attn: Corporate Trust Administration, or to such other address as may be designated by such party in a written notice to each other Notice Party.



16. This Assignment shall expire upon the later to occur of (i) the payment in full of the Purchaser's obligations under that certain credit agreement, dated as of the date hereof, among Purchaser and U.S. Bank National Association, as administrative agent and collateral trustee thereunder, as the same may be amended, restated or supplemented from time to time and (ii) Substantial Completion of the Project.

**EXECUTION COPY**

IN WITNESS WHEREOF, the Authority has executed this Assignment as of the day and year first written above.

MINNESOTA SPORTS FACILITIES AUTHORITY  
a public body and political subdivision of the State of  
Minnesota

By: \_\_\_\_\_

Name: Michele Kelm-Helgen

Title: Chair

By: \_\_\_\_\_

Name: Ted Mondale

Title: CEO / Executive Director

The undersigned parties, Federal Insurance Company, Travelers Casualty and Surety Company of America and The Travelers Indemnity Company, each acknowledge receipt of notice of the foregoing Assignment and each agree that, upon satisfaction of any conditions to the assignment contained in such Assignment, each beneficiary of such assignment shall constitute a successor, grantee or assignee of the Authority under the terms of Bonds 82293944/105842847.

FEDERAL INSURANCE COMPANY

By: \_\_\_\_\_

Printed Name: \_\_\_\_\_

Its: \_\_\_\_\_

Dated: \_\_\_\_\_

TRAVELERS CASUALTY AND SURETY COMPANY OF AMERICA

By: \_\_\_\_\_

Printed Name: \_\_\_\_\_

Its: \_\_\_\_\_

Dated: \_\_\_\_\_

THE TRAVELERS INDEMNITY COMPANY

By: \_\_\_\_\_

Printed Name: \_\_\_\_\_

Its: \_\_\_\_\_

Dated: \_\_\_\_\_

**SIGNATURE PAGE 1 OF 2 TO  
CONDITIONAL ASSIGNMENT OF CONSTRUCTION SERVICES AGREEMENT**

O-1-10

Acknowledged and consented to as of the day and year first written above:

MINNESOTA STADIUM FUNDING TRUST,  
a Delaware statutory trust

By: Wilmington Trust, National Association, not in its  
individual capacity but solely as Trustee

By: \_\_\_\_\_

Printed Name: \_\_\_\_\_

Its: \_\_\_\_\_

It is expressly understood and agreed by the parties hereto that (a) this Assignment is acknowledged and consented to by Wilmington Trust, National Association, not individually or personally but solely as Trustee of Purchaser, in the exercise of the powers and authority conferred and vested in it under the Trust Agreement of the Purchaser, (b) each of the representations, undertaking and agreements herein made on the part of Purchaser is made and intended not as personal representations, undertaking and agreements by Wilmington Trust, National Association but is made and intended for the purposes for binding only Purchaser, (c) nothing herein contained shall be construed as creating any liability on Wilmington Trust, National Association, individually or personally, to perform any covenant either express or implied contained herein, all such liability, if any, being expressly waived by the parties hereto and any Person claiming by, through or under the parties hereto, and (d) under no circumstances shall Wilmington Trust, National Association be personally liable for the breach or failure of any obligation, representation, warranty or covenant made or undertaken by Purchaser under this Consent and Agreement.

**SIGNATURE PAGE 2 OF 2 TO  
CONDITIONAL ASSIGNMENT OF CONSTRUCTION SERVICES AGREEMENT**

O-1-11

**CONSENT AND AGREEMENT OF CONSTRUCTION MANAGER**

Reference is made to the foregoing Conditional Assignment of Construction Services Agreement. All capitalized terms below shall have the same meaning as set forth therein.

1. The Agreement is valid, enforceable (subject to applicable law) and in full force and effect as to the Construction Manager, and the Agreement, as amended, has not been otherwise amended or modified in any manner as of the date of this Assignment; neither party, to the best of the Construction Manager's knowledge, is in default under the terms of the Agreement.

2. The Construction Manager hereby consents to the assignment of the Agreement by the Authority to Purchaser as collateral for the Authority's obligations under the Sale Agreement relating to the purchase by Purchaser of certain stadium builder licenses under the terms of the Assignment. Any reference in this Consent and Agreement of Construction Manager to Purchaser or its assignee shall be subject to Section C of the Assignment.

3. Following the occurrence and during the continuance of a Material Default, and Purchaser's (or its assignee's) fulfillment of any outstanding obligations that the Authority has to the Construction Manager, including but not limited to payment of outstanding fees and expenses, the Construction Manager shall, at Purchaser's (or its assignee's) written request, continue performance on Purchaser's (or its assignee's) behalf under the Agreement in accordance with the terms of the Agreement, conditioned only upon receipt by the Construction Manager of payment on account of its compensation in accordance with the terms and provisions of the Agreement.

4. Following the occurrence and during the continuance of a Material Default, Purchaser (or its assignee) may enforce the obligations of the Construction Manager under the Agreement with the same force and effect as if enforced by the Authority and may perform the obligations of the Authority. The Construction Manager will accept such performance in lieu of performance by the Authority in satisfaction of the Authority's obligations thereunder.

5. The Construction Manager will give Purchaser (or its assignee) written notice of any default by Purchaser (or its assignee) under the Agreement which notice shall be given concurrently with any notice to the Authority. The Construction Manager will not terminate the Agreement on account of any default of the Authority thereunder without written notice of such default to Purchaser (or its assignee) giving Purchaser (or its assignee) the opportunity to cure such default for a period of twenty (20) Business Days after expiration of the Authority's right to cure. In the event Purchaser (or its assignee) elects to cure the default and does, in fact, cure the default within the time period set forth herein, the Construction Manager agrees not to terminate the Agreement. If, however, Purchaser (or its assignee) elects not to enforce the Agreement against the Construction Manager, Purchaser (or its assignee) shall have no obligation to cure any default of the Authority under the Agreement.

6. Notwithstanding anything herein to the contrary, the Construction Manager shall remain entitled to any change order or other amendment under the Agreement to which the Construction Manager is entitled under the Agreement for causes which are not the responsibility of the Construction Manager.

7. It is expressly understood and agreed by the parties hereto that (a) this Consent and Agreement is executed and delivered by Wilmington Trust, National Association, not individually or personally but solely as Trustee of Purchaser, in the exercise of the powers and authority conferred and vested in it under the Trust Agreement of the Purchaser, (b) each of the representations, undertaking and agreements herein made on the part of Purchaser is made and intended not as personal representations, undertaking and agreements by Wilmington Trust, National Association but is made and intended for the purposes for binding only Purchaser, (c) nothing herein contained shall be construed as creating any liability on Wilmington Trust, National Association, individually or personally, to perform any covenant either express or implied contained herein, all such liability, if any, being expressly waived by the parties hereto and any Person claiming by, through or under the parties hereto, and (d) under no circumstances shall Wilmington Trust, National Association be personally liable for the breach or failure of any obligation, representation, warranty or covenant made or undertaken by Purchaser under this Consent and Agreement.

**EXECUTION COPY**

M.A. MORTENSON COMPANY, a Minnesota  
corporation

By: \_\_\_\_\_

Printed Name: \_\_\_\_\_

Its: \_\_\_\_\_

Dated: \_\_\_\_\_

Acknowledged and agreed to by:

MINNESOTA SPORTS FACILITIES AUTHORITY  
a public body and political subdivision of the State of  
Minnesota

By: \_\_\_\_\_

Name: Michele Kelm-Helgen

Title: Chair

By: \_\_\_\_\_

Name: Ted Mondale

Title: CEO / Executive Director

Dated: \_\_\_\_\_

MINNESOTA STADIUM FUNDING TRUST,  
a Delaware statutory trust

By: Wilmington Trust, National Association, not in its  
individual capacity but solely as Trustee

By: \_\_\_\_\_

Printed Name:

Its:

Dated: \_\_\_\_\_

MINNESOTA VIKINGS FOOTBALL STADIUM,  
LLC, a Delaware limited liability company

By: \_\_\_\_\_

Printed Name: Mark Wilf

Its: President

Dated: \_\_\_\_\_

**SIGNATURE PAGE TO CONSENT TO  
CONDITIONAL ASSIGNMENT OF CONSTRUCTION SERVICES AGREEMENT**

O-1-14

Exhibit 1  
Eligible Potential Neutrals

1. Hon. James M. Rosenbaum (Ret.)
2. John M. Harnes
3. Hon. Robert G. Schiefelbein (Ret.)
4. Mark J. Heley
5. Hon. Gary R. Larson (Ret.)
6. Hon. H. Peter Albrecht (Ret.)
7. Hon. Steven Z. Lange (Ret.)

**EXHIBIT O-2**

**CONDITIONAL ASSIGNMENT OF DESIGN SERVICES AGREEMENT AND PLANS**

**SEE ATTACHED**



**CONDITIONAL ASSIGNMENT  
OF DESIGN SERVICES AGREEMENT AND PLANS**

A. FOR VALUE RECEIVED, the sufficiency of which is hereby acknowledged, MINNESOTA SPORTS FACILITIES AUTHORITY, a public body and political subdivision of the State of Minnesota (hereinafter referred to as the “*Authority*”), hereby collaterally assigns, transfers, sets over and grants a security interest to MINNESOTA STADIUM FUNDING TRUST, a Delaware statutory trust (hereinafter referred to as the “*Purchaser*”, and collectively with the Authority, the “*Parties*”), in all of its right, title and interest in and to:

- (a) the Design Services Agreement dated September 28, 2012 and all addenda, modifications and amendments thereto (the “*Agreement*”), between the Authority and HKS, Inc., a Texas corporation (hereinafter referred to as the “*Architect*”) pertaining to the construction of the Project, as defined in the Agreement; and
- (b) all plans, drawings, specifications and other documents, and all amendments, modifications, supplements, general conditions and addenda thereto, prepared by the Architect for the Team (as defined below) in connection with the construction of the Project (hereinafter referred to as the “*Plans*”).

B. This Assignment (this “*Assignment*”) is made as additional collateral and security for the Authority’s obligations under that certain Purchase and Sale Agreement dated November 22, 2013, 2013 by and between Purchaser and the Authority relating to the purchase by Purchaser of certain stadium builder licenses (the “*Sale Agreement*”). Reference is hereby made to that certain Amended and Restated Development Agreement dated November 22, 2013, effective as of October 3, 2013 by and between Minnesota Vikings Football Stadium, LLC, a Delaware limited liability company (“*Stadco*”) and the Authority and joined in by Minnesota Vikings Football, LLC, a Delaware limited liability company (hereinafter “*Team*”) (together with all addenda, modifications and amendments thereto, the “*Development Agreement*”). Capitalized terms used herein and not otherwise defined herein shall have the meanings given to them in the Development Agreement.

C. U.S. Bank National Association is the administrative agent and collateral agent “*Collateral Agent*”) under that certain Credit Agreement dated as of November [ ], 2013 by and between Purchaser, the Collateral Agent and the lenders party thereto. Notwithstanding the terms of this Assignment to the contrary, the grant by the Purchaser to the Collateral Agent of a security interest in this Assignment or the rights or interests of the Purchaser under this Assignment, or the making of a collateral assignment by the Purchaser to the Collateral Agent of this Assignment or the rights or interests of the Purchaser under this Assignment, are expressly permitted hereunder provided, the Purchaser agrees that thereafter neither it, nor any of its other successors or assigns or the Collateral Agent, may re-assign its rights and remedies under this Assignment to Stadco, the Team or any of Stadco’s or the Team’s affiliates. The rights and remedies of the Purchaser under this Assignment and the Consent and Agreement of Architect are all expressly subject to the terms and conditions of this Section C.

The Authority represents and warrants and agrees as follows:

1. The copy of the Agreement and the copies of the Plans heretofore delivered to Purchaser are true, correct and complete copies thereof; there have been no prior assignments of the Agreement; the Agreement is valid, enforceable and in full force and effect as to the Authority, and the Agreement, as amended, has not been otherwise amended or modified in any manner as of the date of this Assignment; neither party, to the best of the Authority's knowledge, is in default under the terms of the Agreement; and all material covenants, conditions and agreements of the Authority contained in the Agreement have been substantially performed as required therein, except those not due to be performed until after the date hereof.
2. So long as this Assignment is in effect, the Authority agrees not to further assign, sell, pledge, mortgage or otherwise transfer or encumber its interest in the Agreement or the Plans, or amend, restate or otherwise modify the Plans or the Agreement except in accordance with the provisions of the Development Agreement, in each case, without the consent of Purchaser and Purchaser's assignees.
3. This Assignment shall constitute an absolute and present assignment, provided that Purchaser shall have no right under this Assignment to enforce the provisions of the Agreement or to use the Plans until: (i)(a) an Event of Default has occurred pursuant to Section 12.1(d) of the Development Agreement (an "*Authority Insolvency Default*") or (b) StadCo or Purchaser has given the Authority written notice (hereinafter a "*Notice of Material Default*") in the manner described in Section 16.6 of the Development Agreement that the Authority has violated or failed to perform or observe a covenant or condition under the Development Agreement for which it is responsible (so long as Authority is otherwise diligently enforcing its contractual rights against third parties in a commercially reasonable manner) or a representation or warranty of the Authority was incorrect when made in any material respect as contemplated under Section 12.1(a) or 12.1(b) of the Development Agreement, and that such violation, failure or incorrect statement reflects a material impairment of the Authority's ability to fulfill its obligations under the Development Agreement (hereinafter "*Material Default*"), (ii) the Authority has not cured the Material Default within thirty (30) days or longer as may be allowed under Section 12.1(a) of the Development Agreement following receipt of the Notice of Material Default (the "*First Cure Period*"), (iii) the Authority has not cured the Material Default within twenty (20) days following receipt of notice (the "*Enforcement Notice*") from the Purchaser that it is exercising its rights under this Agreement (the "*Second Cure Period*"), provided that the Second Cure Period shall not commence until expiration of the First Cure Period, and (iv) if the Authority disputes that a Material Default has occurred in the manner described in Section 5 below, the Authority has been adjudicated to have caused a Material Default that is continuing pursuant to the expedited dispute resolution provisions in this Agreement (the "*ADR Provisions*").
4. A Notice of Material Default must list in reasonable detail the material facts then known that support and describe the allegation of a Material Default, the Section(s) of the Development Agreement and related agreements (including but not limited to the Construction Services Agreement) that are claimed to be in Material Default, and the specific actions that Purchaser believes would constitute a cure of the alleged Material Default. Notwithstanding anything herein to the contrary, the Authority shall have no right to cure an Authority Insolvency Default.

5. In the event that Authority disputes (i) the alleged Material Default or (ii) that it has failed to timely cure such Material Default within the First Cure Period, the Authority shall so notify Purchaser and Stadco on or before the expiration of the First Cure Period by giving a notice (hereinafter, a “*Material Default Dispute Notice*”), and failure of Authority to provide said Material Default Dispute Notice on or before the expiration of the First Cure Period shall constitute a conclusive determination that a Material Default has occurred and remains uncured. If Authority provides such Material Default Dispute Notice, the Parties must adjudicate the alleged Material Default pursuant to the following ADR Provisions:

- (a) Agreement to Arbitrate. All disputes between the Parties solely with respect to an alleged Material Default are each subject to expedited arbitration (each, an “*Expedited ADR Dispute*”) and shall be submitted to expedited alternative dispute resolution (“*Expedited ADR*”) under this Section 5. One or more disputes over alleged Material Defaults if alleged in close proximity to each other shall be part of one (1) Expedited ADR Dispute. No other disputes between the Parties shall be subject to Expedited ADR under this Assignment, unless the Parties mutually agree to submit to Expedited ADR.
- (b) Initiation of Arbitration and Selection of Neutral.
  - (i) In order to initiate Expedited ADR, a Party shall simultaneously deliver a notice of an alleged Material Default (“*Notice of Material Default*”) to other Party and to the highest ranked eligible potential neutral on the roster (each such neutral a “*Potential Neutral*” and collectively, the “*Potential Neutrals*”) attached as Exhibit 1 to this Assignment (“*Roster of Potential Neutrals*”). The Potential Neutral receiving a Notice of Material Default shall respond to the Parties within two (2) Business Days whether the Potential Neutral is available to serve. If the Potential Neutral is unavailable or otherwise unable to serve, or fails to respond within two (2) Business Days, either Party may deliver the Notice of Material Default to the next highest ranked Potential Neutral on the Roster of Potential Neutrals and may proceed in this same manner until a Potential Neutral is able to serve and accepts appointment as the Neutral (“*Neutral*”) to hear and decide the dispute. If no Potential Neutral on the Roster of Potential Neutrals is able to serve, then either Party may request the Chief Judge of the United States District Court for the District of Minnesota to appoint a Neutral, and the Parties agree to request such appointment as soon as practicable, but no later than five (5) calendar days after the Chief Judge receives such a request. The fees and costs of the Neutral shall be borne equally by the Parties, but the prevailing Party shall be entitled to reimbursement for its share of such fees and costs from the non-prevailing Party in accordance with Section 5(d)(vii) below.
  - (ii) After appointment of the Neutral, each Party shall have three (3) Business Days to prepare and deliver to the other Party and the Neutral a detailed and specific written statement outlining the nature of the alleged Material Default (each a “*Statement of Dispute*”).

- (iii) The delivery of a Statement of Dispute by either Party to the Neutral shall initiate the Expedited ADR provisions of this Assignment and the matter covered by the Statement of Dispute shall be considered submitted to the Neutral for determination.
  - (iv) The timelines established for the expedited arbitration shall be strictly followed by the Neutral unless extended by mutual agreement of Parties.
- (c) Qualifications of Neutral. The Parties shall obtain disclosures from each Potential Neutral and confirm that each Potential Neutral is independent of the Authority, Purchaser, Trust, Stadco, Collateral Agent and lenders party to the Credit Agreement, and Team (and their respective Affiliates and agents) and holds no financial interest in, and has no material financial or material personal relationship with the Authority, Purchaser or Team (or their respective Affiliates).
- (d) Location and Conduct.
  - (i) Location. The Expedited ADR proceeding shall be conducted by the Neutral at a time and location in Hennepin County, Minnesota selected by the Neutral. Subject to Section 5(b)(iv) hereof, the Neutral shall give the Authority and Purchaser reasonable notice of the Expedited ADR proceeding, which shall be within two (2) Business Days after submission the Statements of Dispute. The Neutral shall conduct the Expedited ADR proceeding in such manner as the Neutral deems appropriate, consistent with the provisions of this Section 5.
  - (ii) Presentation of Information. Each Party shall present its position with respect to the issue(s) to be determined in the Expedited ADR proceeding through evidence and oral presentation to the Neutral. Each Party shall be given the opportunity to hear and orally respond to the other Party's presentation to the Neutral, and to present documents and evidence to the Neutral in support of such Party's position. The Neutral shall have the right to limit the time allowed for oral presentations, testimony, and the evidence presented to the Neutral to assure that the hearing does not exceed its allowed length and assure a prompt resolution of the issue(s) to be determined by the Neutral. The Neutral may require the participation of the Architect, the Construction Manager and other Project Consultants that have knowledge of the subject matter in the Statements of Dispute. At the conclusion of the Expedited ADR proceeding each Party shall submit its proposed written decision to the Neutral.
  - (iii) Authority of Neutral. The Authority and Purchaser intend that the Neutral shall have the sole and exclusive authority and power to resolve Expedited ADR Disputes.

- (iv) **Discovery.** There shall be no discovery permitted with respect to any Expedited ADR proceeding other than that required by the Neutral or as may be necessary to fully understand the alleged Material Default.
- (v) **Cooperation/Duration.** The Authority and Purchaser shall cooperate in good faith to permit the start of the Expedited ADR proceeding within two (2) Business Days following the submission of each Party's Statement of Dispute to the Neutral. The Expedited ADR proceeding shall last no longer than five (5) Business Days unless the Neutral determines, in its sole discretion, that additional time is required to properly conduct the proceeding in a manner contemplated to provide sufficient information on which to form and issue an informed and fair decision.
- (vi) **Post-Hearing Mediation.** After the Expedited ADR proceeding concludes and after each Party submits its proposed written decision(s), but before the Neutral issues its written decision, the Neutral shall conduct a 180-minute mediation session and attempt to facilitate resolution of the issue(s) by settlement.
- (vii) **Decision of the Neutral.** The Neutral shall render the arbitration decision within five (5) Business Days after the conclusion of the Expedited ADR proceeding, subject to the decision of the Neutral to expand such time for decision. First, the Neutral must render a written decision determining whether or not a Material Default has occurred, and if so, what actions the Authority must take to cure the Material Default. Nothing herein or in the Neutral's decision shall extend or otherwise grant the Authority additional time to cure any Material Default. Second, the Neutral must award the reasonable attorneys fees, costs (including the fees and costs of the Neutral), and disbursements to the prevailing Party. Third, the Neutral must prepare, at a minimum, a written memorandum with an explanation of the basis for the decision. Fourth, the Neutral's written memorandum and decision shall be addressed and simultaneously sent to each of the Parties as set forth in the notice provision of this Assignment. The decision of the Neutral shall be binding upon the Parties for the purposes of determining whether or not Purchaser has the right to exercise the assignment of the Agreement as described in this Assignment.
- (viii) **Exclusive Remedy.** The Authority and Purchaser shall use Expedited ADR exclusively, rather than litigation, as a means of resolving the merits of each Expedited ADR Dispute for the sole purposes of this Assignment. Subject to the provisions of applicable law, the written decision of the Neutral shall be the binding, final determination on the merits of the Expedited ADR Dispute for the sole purposes of this Assignment, and shall preclude any subsequent litigation or other proceeding on such merits. The Authority or Purchaser may institute legal proceedings in a court of competent jurisdiction to enforce judgment upon the decision of a Neutral in regard to this Assignment. Notwithstanding anything to the

contrary contained herein, the Purchaser may seek other legal and equitable remedies and relief in regard to an Authority Insolvency Default.

- (ix) Other Remedies. While the Expedited ADR procedures set forth herein are final and binding for purposes of this Assignment, nothing in this Agreement shall limit or impair the right of the Authority to seek other legal and equitable relief in regard to an alleged or actual Material Default as between the Team or its assignee and the Authority, including without limitation, the equitable remedies allowed in the Development Agreement. Notwithstanding anything to the contrary contained herein, except as provided in subsection (viii) above, the Purchaser may seek other legal and equitable remedies and relief in regard to an Authority Insolvency Default.

6. If the Authority cures the alleged Material Default before the expiration of the Second Cure Period, the Notice of Material Default and Material Default Dispute Notice shall be of no further force or effect. If the Authority receives a decision from a Neutral holding that a Material Default has occurred and the Authority has not cured the Material Default before the expiration of the Second Cure Period, Purchaser may proceed to exercise all of its rights and remedies under this Assignment (the “*Purchaser Step-In Date*”).

7. The Authority shall have a one-time right to reassume its rights and duties under the Agreement upon satisfaction of the following conditions: (i) the Authority has cured the Material Default; (ii) the Authority has reimbursed the Purchaser for all direct costs and expenses incurred by Purchaser during the time Purchaser exercised the Authority’s rights and obligations under the Agreement; (iii) the Project budget is in balance; (iv) a neutral, independent third party construction expert unaffiliated with the Project or the Authority, Purchaser, the Collateral Agent and lenders party to the Credit Agreement, and Stadco determines that the Authority has remedied any deficiencies in its operational capacities that gave rise to the Material Default and has the ability to perform its duties under the Agreement on an ongoing basis; and (v) the Purchaser consents to the Authority’s re-assumption of its rights and duties under the Agreement, which consent the Purchaser shall grant or withhold in its sole discretion based on the Purchaser’s good faith consideration of the Authority’s proposal to reassume such rights and duties under the Agreement.

8. At any time after (i) the occurrence of an Authority Insolvency Default or (ii) in the case of a Material Default, after the cure periods (if any) referenced in Section 3 have expired and, if the Notice of Material Default has been contested by the Authority, after the Authority has been adjudicated to be in Material Default pursuant to Section 5, Purchaser may, without affecting any of its rights or remedies against the Authority under any other instrument, document or agreement, exercise its rights under this Assignment, and in addition, Purchaser shall have the right to exercise and enforce any or all rights and remedies available to a secured party under the Uniform Commercial Code with respect to the Agreement and the Plans.

9. At all times after Purchaser shall have exercised its rights pursuant to Section 3 above, Purchaser shall be entitled to demand, receive and enforce the Authority’s rights with respect to the Agreement and the Plans, to make payments under the Agreement and to give appropriate

receipts, releases and satisfactions for and on behalf of and in the name of the Authority or, at the option of Purchaser, in the name of Purchaser, with the same force and effect as if Purchaser had originally executed the Agreement; provided, however, that the Purchaser may not amend the Agreement or the Plans in a manner which would expand the obligations of the Authority under the Plans or the Agreement beyond that which is in effect as of the date of the Material Default Dispute Notice.

10. Purchaser does not assume any of the obligations or duties of the Authority under or with respect to the Agreement unless and until Purchaser shall have given the Architect written notice that it is exercising its right hereunder. If Purchaser does not provide such notice to the Architect, Purchaser shall have no liability whatsoever for the performance of any of the obligations or duties under the Agreement. Purchaser may collaterally assign its right to and interest in the Agreement and this Assignment to any party (other than Team, Stadco or their respective affiliates) providing financing to Purchaser and in addition, Purchaser may reassign, in its sole discretion, and for the purpose of completing the Project, its right, title and interest in the Agreement (other than to the Team, Stadco or their respective affiliates) upon notice to the Architect, but without any requirement for the consent of the Authority or Architect.

11. Nothing herein shall affect the rights or obligations of the Authority, the Team or the Purchaser under the Development Agreement.

12. The Authority agrees to make, execute and deliver all such further or additional instruments as may be reasonably necessary to perfect the assignment made hereby.

13. Authority acknowledges and agrees that it has entered into this Agreement for good and adequate consideration, the sufficiency of which is hereby acknowledged by the Authority. This Assignment and the agreements and undertaking of the Authority hereunder shall be binding upon the Authority and its successors and assigns and shall inure to the benefit of Purchaser and its successors and assigns. Neither this Assignment nor any provision hereof may be changed, waived, discharged or terminated orally, rather only by an instrument in writing signed by the Authority and Purchaser.

14. This Assignment shall be governed by the laws of the State of Minnesota.

15. Any notice or other communication to be given to the Authority, Stadco or the Purchaser (each, a "*Notice Party*") hereunder shall be given in the manner set forth in the Development Agreement (i) to the Authority at Minnesota Sports Facilities Authority, Mall of America Field, 900 South Fifth Street, Minneapolis, MN 55415, Attn.: Chair and CEO / Executive Director, (ii) to Stadco at Minnesota Vikings Football, LLC, 9520 Viking Drive, Eden Prairie, MN 55344, Attn.: CFO, and (iii) to the Purchaser at Minnesota Stadium Funding Trust, c/o Wilmington Trust, National Association, as Trustee, Rodney Square North, 1100 North Market Street, Wilmington, DE 19890, Attn: Corporate Trust Administration, or to such other address as may be designated by such party in a written notice to each other Notice Party.

16. This Assignment shall expire upon the later to occur of (i) the payment in full of the Purchaser's obligations under that certain credit agreement, dated as of the date hereof, among Purchaser and U.S. Bank National Association, as administrative agent and collateral trustee

thereunder, as the same may be amended, restated or supplemented from time to time and (ii) Substantial Completion of the Project.



IN WITNESS WHEREOF, the Authority has executed this Assignment as of the day and year first written above.

MINNESOTA SPORTS FACILITIES AUTHORITY  
a public body and political subdivision of the State of  
Minnesota

By: \_\_\_\_\_

Name: Michele Kelm-Helgen

Title: Chair

By: \_\_\_\_\_

Name: Ted Mondale

Title: CEO / Executive Director

Acknowledged and consented to as of the day and year first written above:

MINNESOTA STADIUM FUNDING TRUST,  
a Delaware statutory trust

By: Wilmington Trust, National Association, not in its  
individual capacity but solely as Trustee

By: \_\_\_\_\_

Printed Name: \_\_\_\_\_

Its: \_\_\_\_\_

It is expressly understood and agreed by the parties hereto that (a) this Assignment is acknowledged and consented to by Wilmington Trust, National Association, not individually or personally but solely as Trustee of Purchaser, in the exercise of the powers and authority conferred and vested in it under the Trust Agreement of the Purchaser, (b) each of the representations, undertaking and agreements herein made on the part of Purchaser is made and intended not as personal representations, undertaking and agreements by Wilmington Trust, National Association but is made and intended for the purposes for binding only Purchaser, (c) nothing herein contained shall be construed as creating any liability on Wilmington Trust, National Association, individually or personally, to perform any covenant either express or implied contained herein, all such liability, if any, being expressly waived by the parties hereto and any Person claiming by, through or under the parties hereto, and (d) under no circumstances shall Wilmington Trust, National Association be personally liable for the breach or failure of any obligation, representation, warranty or covenant made or undertaken by Purchaser under this Consent and Agreement.

**SIGNATURE PAGE TO CONDITIONAL ASSIGNMENT  
OF DESIGN SERVICES AGREEMENT AND PLANS**

**CONSENT AND AGREEMENT OF ARCHITECT**

Reference is made to the foregoing Conditional Assignment of Design Services Agreement and Plans. All capitalized terms below shall have the same meaning as set forth therein.

17. The Agreement is valid, enforceable and in full force and effect as to the Architect, and the Agreement, as amended, has not been otherwise amended or modified in any manner as of the date of this Assignment; neither party, to the best of the Architect's knowledge, is in default under the terms of the Agreement.

18. The Architect hereby consents to the assignment of the Agreement by the Authority to Purchaser as collateral for the Authority's obligations under the Sale Agreement relating to the purchase by Purchaser of certain stadium builder licenses under the terms of the Assignment. Any reference in this Consent and Agreement of Architect to Purchaser or its assignee shall be subject to Section C of the Assignment.

19. Following the occurrence and during the continuance of a Material Default, and Purchaser's (or its assignee's) fulfillment of any outstanding obligations that the Authority has to Architect, including but not limited to payment of outstanding fees and expenses, Purchaser (or its assignee) shall have the right to use the Plans (subject to Purchaser (or its assignee) paying all fees and charges provided for in the Agreement) and the Architect shall, at Purchaser's (or its assignee's) written request, continue performance on Purchaser's (or its assignee's) behalf under the Agreement in accordance with the terms of the Agreement, conditioned only upon receipt by the Architect of payment on account of its compensation in accordance with the terms and provisions of the Agreement.

20. Following the occurrence and during the continuance of a Material Default, Purchaser (or its assignee) may enforce the obligations of the Architect under the Agreement with the same force and effect as if enforced by the Authority and may perform the obligations of the Authority. The Architect will accept such performance in lieu of performance by the Authority in satisfaction of the Authority's obligations thereunder.

21. The Architect will give Purchaser (or its assignee) written notice of any default by Purchaser (or its assignee) under the Agreement which notice shall be given concurrently with any notice to the Authority. The Architect will not terminate the Agreement on account of any default of the Authority thereunder without written notice of such default to Purchaser (or its assignee) giving Purchaser (or its assignee) the opportunity to cure such default for a period of twenty (20) Business Days after expiration of the Authority's right to cure. In the event Purchaser (or its assignee) elects to cure the default and does, in fact, cure the default within the time period set forth herein, the Architect agrees not to terminate the Agreement. If, however, Purchaser (or its assignee) elects not to enforce the Agreement against the Architect, Purchaser (or its assignee) shall have no obligation to cure any default of the Authority under the Agreement.

22. It is expressly understood and agreed by the parties hereto that (a) this Consent and Agreement is executed and delivered by Wilmington Trust, National Association, not

individually or personally but solely as Trustee of Purchaser, in the exercise of the powers and authority conferred and vested in it under the Trust Agreement of the Purchaser, (b) each of the representations, undertaking and agreements herein made on the part of Purchaser is made and intended not as personal representations, undertaking and agreements by Wilmington Trust, National Association but is made and intended for the purposes for binding only Purchaser, (c) nothing herein contained shall be construed as creating any liability on Wilmington Trust, National Association, individually or personally, to perform any covenant either express or implied contained herein, all such liability, if any, being expressly waived by the parties hereto and any Person claiming by, through or under the parties hereto, and (d) under no circumstances shall Wilmington Trust, National Association be personally liable for the breach or failure of any obligation, representation, warranty or covenant made or undertaken by Purchaser under this Consent and Agreement.

**EXECUTION COPY**

HKS, INC., a Texas corporation

By: \_\_\_\_\_

Printed Name: \_\_\_\_\_

Its: \_\_\_\_\_

Dated: \_\_\_\_\_

Acknowledged and agreed to by:

MINNESOTA SPORTS FACILITIES AUTHORITY  
a public body and political subdivision of the State of  
Minnesota

By: \_\_\_\_\_

Name: Michele Kelm-Helgen

Title: Chair

By: \_\_\_\_\_

Name: Ted Mondale

Title: CEO / Executive Director

Dated: \_\_\_\_\_

MINNESOTA STADIUM FUNDING TRUST,  
a Delaware statutory trust

By: Wilmington Trust, National Association, not in its  
individual capacity but solely as Trustee

By: \_\_\_\_\_

Printed Name:

Its:

Dated: \_\_\_\_\_

MINNESOTA VIKINGS FOOTBALL STADIUM,  
LLC, a Delaware limited liability company

By: \_\_\_\_\_

Printed Name: Mark Wilf

Its: President

Dated: \_\_\_\_\_

**SIGNATURE PAGE TO CONSENT TO CONDITIONAL ASSIGNMENT OF DESIGN SERVICES  
AGREEMENT AND PLANS**

O-2-13

Exhibit 1  
Eligible Potential Neutrals

1. Hon. James M. Rosenbaum (Ret.)
2. John M. Harnes
3. Hon. Robert G. Schiefelbein (Ret.)
4. Mark J. Heley
5. Hon. Gary R. Larson (Ret.)
6. Hon. H. Peter Albrecht (Ret.)
7. Hon. Steven Z. Lange (Ret.)

**EXHIBIT P**


**FINAL TEAM'S STADIUM PROPERTY SCHEDULE**

**[TO BE AFFIXED BY THE PARTIES AFTER THE EFFECTIVE DATE.]**

**EXHIBIT Q**

**ROSTER OF POTENTIAL NEUTRALS**

1. Hon. James M. Rosenbaum (Ret.)
2. John M. Harnes
3. Hon. Robert G. Schiefelbein (Ret.)
4. Mark J. Heley
5. Hon. Gary R. Larson (Ret.)
6. Hon. H. Peter Albrecht (Ret.)
7. Hon. Steven Z. Lange (Ret.)

**EXHIBIT R-1****PRELIMINARY PROJECT SCHEDULE**


R-1-1




**EXHIBIT R-2**


**MASTER PROJECT SCHEDULE**


**SEE ATTACHED.**











**EXHIBIT S**

**FORM OF CONSTRUCTION MONITOR CERTIFICATION**

**SEE ATTACHED**

CONSTRUCTION CERTIFICATE

Merritt & Harris, Inc. (“**Construction Monitor**”), Construction Monitor under that certain Credit Agreement (the “**Credit Agreement**”), dated as of November 22, 2013, entered into by and among **MINNESOTA VIKINGS FOOTBALL STADIUM, LLC**, a special purpose entity (“**Borrower**”), **MINNESOTA STADIUM FUNDING TRUST**, a statutory trust established under the laws of the state of Delaware (“**Lender**”), and **U.S. BANK NATIONAL ASSOCIATION**, as administrative agent (together with its permitted successors in such capacity, “**Administrative Agent**”), delivers this Construction Certificate pursuant to Section 3 of the Credit Agreement. All terms used in this Certificate shall have the meanings given to such terms in the Credit Agreement. Construction Monitor hereby certifies to Borrower, Administrative Agent, Lender and the reliance parties listed in Section 15 below:

1. Master Application for Payment. Attached hereto as Annex I is the Master Application for Payment prepared by Hammes Company Sports Development, Inc. for submission to the Authority, which the Construction Monitor has been provided with and approved.
2. Adequate Construction Funds. Attached hereto as Annex II is a report to the Administrative Agent and Lender stating that the monies held by the Construction Funds Trustee on the Credit Extension Date, together with all monies available from and under the Upper Tier Credit Agreement, the NFL G-4 Facility, the Authority Contribution, any Qualified Letter of Credit and any other construction financing source reasonably satisfactory to each of the Co-Lead Arrangers are sufficient to complete construction of the Stadium Project by the Scheduled Completion Date.
3. Construction Progress. Attached hereto as Annex III are all progress reports delivered under the Construction Services Agreement for the period covered for this [Initial][Construction Costs][Substantial Completion] Credit Extension.
4. Satisfactory Title. Attached hereto as Annex IV is an endorsement issued by the Title Company in respect of the Title Policy indicating that since the most recent endorsement issued by the Title Company, there have been no changes in the state of title, and no additional survey exceptions not theretofore specifically approved in writing by Upper Tier Collateral Trustee and insuring the priority of the StadCo Leasehold Mortgage.
5. No Liens. The Construction Monitor has no knowledge of any vendor’s lien, mechanic’s lien or security interest which should be satisfied or discharged before the payment herein requested is made or which will not be discharged by such payment.
6. No Liens at Completion. Construction of the Improvements has been completed, free and clear of mechanics’ liens and security interests (excluding such liens and security interests (i) arising in the ordinary course of business

and securing obligations that are not overdue by more than thirty (30) days or are being contested in compliance with the requirements under Section 5.3 of the Credit Agreement or (ii) that will be paid in full with the proceeds of the payment herein requested), and any necessary utilities and roads have been finished and made available for use, in accordance with the Construction Services Agreement. Construction Monitor has received satisfactory evidence of the approval by all Governmental Authorities of the Improvements in their entirety for temporary or permanent occupancy, and of the contemplated uses thereof, to the extent any such approval is a condition of the lawful use and occupancy thereof.<sup>1</sup>

7. Construction Draw.

(a) The Construction Monitor authorizes a draw in furtherance of construction (a “**Construction Draw**”) in the amount of \$[\_\_\_\_\_] (the “**Current Construction Draw**”). \$[\_\_\_\_\_] of such Current Construction Draw will be from the [Initial Credit Extension][Construction Costs][Substantial Completion] Credit Extension (the “**Current Term Loan Facility Draw**”) and \$[\_\_\_\_\_] of such Current Construction Draw will be from proceeds of the NFL G-4 Facility (the “**Current NFL G-4 Draw**”). Details of the Current Construction Draw are set forth on Annex V attached hereto.

(b) The Current Construction Draw, when added to all prior Construction Draws in the aggregate amount of \$[\_\_\_\_\_] , will result in aggregate Construction Draws of \$[\_\_\_\_\_]. The Current NFL G-4 Draw, when added to all prior NFL G-4 Draws in the aggregate amount of \$[\_\_\_\_\_] , will result in aggregate NFL G-4 Draws of \$[\_\_\_\_\_].

8. Each of the Construction Services Agreement and the construction agreements is in full force and effect on the date hereof and has not been modified or amended, except as permitted by the terms thereof. Except for notices, if any, relating to matters which have been cured or waived, or except as may be stated on Annex VI attached hereto, the Construction Monitor has no knowledge of receipt by Borrower, StadCo, or the Authority, nor has the Construction Monitor received any notice of default from a contractor under any construction agreements or substitute construction agreement.

9. Except as may be stated on Annex VII attached hereto, construction of the Stadium Project has not materially deviated from the Construction Services Agreement and the construction agreements.

---

<sup>1</sup> To be delivered in connection with the Substantial Completion Credit Extension only.



**EXECUTION COPY**

10. Except as may be stated on Annex VIII attached hereto, all permits required to construct the Stadium Project at this stage of construction have been issued and are in full force and effect, and the Construction Monitor has no notice or knowledge as of the date hereof of any actions pending to revoke any such permits.
11. The Current Construction Draw is for costs that constitute Project Costs. The Current Construction Draw contains no items representing payment on account of any amounts not otherwise permitted to be paid as of the date hereof.
12. To the best of the Construction Monitor's knowledge, except as may be stated in Annex IX attached hereto, (a) construction of the Stadium Project is proceeding on schedule and (b) the Stadium Project will be completed by the Scheduled Completion Date.
13. The proceeds of all prior Construction Draws have been expended solely for the purpose for which they were requisitioned.
14. There have been no Material Change Orders other than those permitted by the Construction Services Agreement.
15. This Certificate and the accompanying supporting documentation are submitted to the Administrative Agent and Lender pursuant to the terms of the Credit Agreement and may be relied upon by Minnesota Vikings Football, LLC, a Delaware limited liability company, Minnesota Vikings Football Stadium, LLC, a Delaware limited liability company, NFL Ventures, L.P., the Upper Tier Co-Lead Arrangers and the Upper Tier Lenders.

Dated: \_\_\_\_\_, \_\_\_\_.

MERRITT & HARRIS, INC.

By: \_\_\_\_\_  
Name:  
Title:

Master Application for Payment

Adequate Construction Funds Report

Construction Progress Reports

Endorsement With Respect to Title Policy

Current Construction Draw Detail Report

Notice of Default from Contractors  
Under any Construction Agreements

Annex VII

Exceptions to the Construction Services  
Agreement Relating to Construction



Construction Permits Report

Construction Schedule Report

**EXHIBIT T**

**FORM OF AMENDMENT OF CONTINGENCY LETTER OF CREDIT**

U.S. Bank National Association  
Standby Letters of Credit: BC-MN-H20G  
800 Nicollet Mall  
Minneapolis, Minnesota 55402

SWIFT: USBKUS44  
TELEX:  
Phone: 503-464-3611  
612-303-7395  
Fax : 612-303-5226

(AMENDMENT DATE)

Letter of Credit Number: SLCMMSP07102

Amendment Number: 1

Applicant: Zygmunt Wilf, Mark Wilf and Leonard Wilf (individually and collectively, the "Applicant")

Beneficiary: U.S. Bank National Association  
EP-MN-WS3C  
60 Livingston Avenue  
St. Paul, MN 55107

---

The above mentioned credit is amended as follows:

---

Annex A (Reduction Certificate), Annex B (Sight Draft) and Annex C (Draw Certificate) are replaced in their entirety with the attached Annex A, Annex B and Annex C and are incorporated herein.

---

This amendment is to be considered as part of the above credit and must be attached thereto.

All other terms and conditions remain unchanged.

U.S. Bank National Association

***Draft***

---

Authorized Signature

---

Authorized Signature, Applicant  
as authorization to issue in this form

ANNEX A

REDUCTION CERTIFICATE

Re: U.S. Bank National Association  
Letter of Credit No. SLCMMSP07102

The undersigned, a duly authorized officer of U.S. Bank National Association, a national banking association, as trustee (the "Trustee") under that certain Amended and Restated Construction Funds Trust Agreement dated as of November 22, 2013, as amended by Amendments dated as of January 1, 2014, April 18, 2014 and August \_\_, 2014 (as so amended and as thereafter amended or supplemented, the "Agreement"), by and among the Trustee, Minnesota Sports Facilities Authority (the "Authority") and Minnesota Vikings Football Stadium, LLC ("StadCo"), hereby certifies to U.S. Bank National Association, a national banking association, in its capacity as letter of credit issuer (the "Bank"), with reference to the Letter of Credit identified above, issued by the Bank in favor of the Trustee as beneficiary (the "Letter of Credit"), that:

1. Check either (a) or (b) (and not both) as applicable:

\_\_\_\_ (a) On or about the date hereof \$[\_\_\_\_\_] has been deposited in the Contingency Direct Contribution Subaccount (as defined in the Agreement).

\_\_\_\_ (b) The Trustee is in receipt of a certificate dated on or about the date hereof, in the form attached as Exhibit A-2 to the Agreement (a "Reduction Certificate"), duly completed and executed by StadCo and Authority, instructing the Trustee to cause a reduction in the Stated Amount (as defined in the Letter of Credit) by an amount equal to \$\_\_\_\_\_.

2. Pursuant to the Letter of Credit, upon receipt by the Bank of this Certificate, the Stated Amount of the Letter of Credit shall be reduced by the amount set forth in paragraph 1 to a new total of \_\_\_\_\_ DOLLARS (\$\_\_\_\_\_).

IN WITNESS WHEREOF, the Trustee has executed and delivered this Certificate as of the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_.

U.S. Bank National Association,  
as trustee

By: \_\_\_\_\_  
Name: \_\_\_\_\_  
Title: \_\_\_\_\_

ANNEX B

SIGHT DRAFT

\_\_\_\_\_, 20\_\_

Drawn Under U.S. Bank National Association Letter of Credit No. SLCMMSP07102, dated as of November 22, 2013

At Sight

Pay to: U.S. Bank National Association, as Trustee, under the Amended and Restated Construction Funds Trust Agreement, dated as of November 22, 2013, as amended by Amendments dated as of January 1, 2014, April 18, 2014 and August \_\_, 2014, and as thereafter amended or supplemented, by an among Minnesota Vikings Football Stadium, LLC, Minnesota Sports Facilities Authority, and U.S. Bank National Association, as Trustee, the amount of:

\_\_\_\_\_ DOLLARS (\$\_\_\_\_\_)

U.S. Bank National Association,  
as Trustee

By: \_\_\_\_\_  
Name: \_\_\_\_\_  
Title: \_\_\_\_\_

ANNEX C  
DRAW CERTIFICATE

Re: U.S. Bank National Association  
Letter of Credit No. SLCMMSP07102

The undersigned, a duly authorized officer of U.S. Bank National Association, a national banking association, as trustee (the "Trustee") under that certain Amended and Restated Construction Funds Trust Agreement dated as of November 22, 2013, as amended by Amendments dated as of January 1, 2014, April 18, 2014 and August \_\_, 2014 (as so amended and as thereafter amended or supplemented, the "Agreement"), by and among the Trustee, Minnesota Sports Facilities Authority (the "Authority"), and Minnesota Vikings Football Stadium, LLC ("StadCo"), hereby certifies to U.S. Bank National Association, a national banking association, in its capacity as letter of credit issuer (the "Bank"), with reference to the Letter of Credit identified above, issued by the Bank in favor of the Trustee as beneficiary (the "Letter of Credit"), that:

1. The Trustee is the Trustee under the Agreement.
2. Check either (a) or (b) (and not both) as applicable:
  1. \_\_\_\_ (a) The Trustee is in receipt of a certificate dated on or about the date hereof, duly executed by an authorized officer of the Authority and duly notarized, in the form attached as Exhibit A-3 to the Agreement (the "Authority Certificate"). Funds drawn under this paragraph (a) will be credited by the Trustee to the Contingency Letter of Credit Subaccount under the Agreement.
  2. \_\_\_\_ (b) The Letter of Credit expires within fifteen (15) days after the date of this certificate and the sight draft presented herewith and has not been extended or replaced by a Substitute Letter of Credit under the terms of the Agreement. Funds drawn under this paragraph (b) will be credited by the Trustee to the Contingency Letter of Credit Termination Subaccount under the Agreement.
3. The amount of the sight draft accompanying this Certificate is \$\_\_\_\_\_, which is equal to the lesser of:
  - (a) either (i) the applicable amount described in paragraph 6 of the Authority Certificate if 2(a) above is checked, or (ii) the Stated Amount of the Letter of Credit if 2(b) above is checked, and
  - (b) the Stated Amount of the Letter of Credit as of the date hereof, *minus* the sum of (i) any amounts deposited in the Contingency Direct Contribution Subaccount (as defined in the Agreement) that would have caused the Trustee to deliver a certificate in the form of Annex A to the Letter of Credit, but for which such a certificate has not yet been delivered by the Trustee or processed by the Bank, plus (ii) the amount of any reduction of the Letter of Credit permitted by a Reduction Certificate (as defined in Annex A to the Letter of Credit) the Trustee has received but for which reduction a certificate in the form of Annex A to the Letter of Credit has not yet been delivered by the Trustee or processed by the Bank.

**EXECUTION COPY**

4. Pursuant to the Letter of Credit, upon the honoring by the Bank of the sight draft accompanying this Certificate, the Stated Amount of the Letter of Credit shall be reduced by the amount set forth in Paragraph 3 to a new total of \_\_\_\_\_ Dollars (\$\_\_\_\_\_).
5. The amount of the sight draft accompanying this Certificate shall be paid to the Trustee, by wire transfer to: [ \_\_\_\_\_ ]

IN WITNESS WHEREOF, the Trustee has executed and delivered this Certificate as of the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_.

U.S. Bank National Association,  
as trustee

By: \_\_\_\_\_

Name: \_\_\_\_\_

Title: \_\_\_\_\_

**EXHIBIT U**

**EAST EVENT LEVEL LOCKER ROOM BUILDOUT**






**EXHIBIT V****COST LIST**

<u>Costs</u>	<u>(\$millions)**</u>
Plaza (including Lighting)	8.5
Club Purple Deck	1.0
Food Service	2.6
Water Pumps	0.8
Toilet Partitions	0.3
Sink and Electrical Panel	0.1
Frames/Doors/Hardware/Readers	0.2
Retractable Seating	1.0
Laundry Equipment	0.1
High Roof Wash	0.6
Field Floor Drains	0.4
East Event Buildout (Locker Room)	2.0
Six (6) Foot Metal Panels	0.5
Nanawall	0.4
Seating Option 2/Nanawall Press	0.1
Completion Allowance*	0.2

\* Office Relocation Design (\$30,000), Plaza, Club Purple Deck & Retractable Seating.


\*\* Any cost savings realized within the specific line items identified in this **Exhibit V** will be reallocated to Project Costs as mutually approved by the Parties.

**EXHIBIT W****STADIUM PLAZA DESIGN AREA**

W-1








**EXHIBIT Y**


**TENTING PLANS SUBMITTED TO HENNEPIN COUNTY**



FAIR/MARKET

\*The above drawing is not to scale.






PRE-EVENT PARTY

\*The above drawing is not to scale.






**LARGE HOSPITALITY EVENT**

\*\*Hospitality tent may be temporary, seasonal or permanent structure and vary in size.

\*The above drawing is not to scale.



## HIGHSCHOOL PEP RALLY

\*The above drawing is not to scale.



MONSTER TRUCK SHOW

\*The above drawing is not to scale.